MILITARY SPECIFICATION

MOUNT, RESILIENT

1. SCOPE

1.1 This specification covers requirements, quality assurance provisions, and the preparation for delivery criteria for one type of mount entitled Mount, Resilient which is used in the Honest John warhead section.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein:

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-810	- Environmental Test Methods.
MIL-STD-1168	- Lot Numbering of Ammunition.
MIL-STD-1169	- Packaging, Packing and Marking for Shipment of Inert Ammunition Components.

DRAWINGS

ORDNANCE CORPS

8826392	- Mount, Resilient.
EL-8842569	- Equipment List.

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Materials. The contractor shall furnish objedtive evidence (see 6.2) that the material complies with the specifications listed on the applicable drawing.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:29Z
Check the source to verify that this is the current version before use.

3.2 Assembly. The mount shall comply with all requirements specified on the drawing (dwg) 8826392, with all requirements specified herein, and with the requirements of all applicable specifications to the extent specified on the drawing and herein.

3.3 First article testing. Requirements for the submission of first article samples by the contractor shall be as specified in the contract (see 4.2).

3.4 Serialization. The contractor shall assign serial numbers as required by drawings. The contractor may select any number which complies with the drawing requirement. These numbers shall not be duplicated.

3.5 Performance characteristics. After completing any or all of the tests specified in 4.4, the set of the unit shall not exceed 0.5 inches, measured not sooner than 1 hour after testing.

3.6 Load deflection. The mount shall exhibit deflections for the various loads at temperatures specified on dwg 8826392, when tested as specified in 4.4.1.

3.7 Pull test. The mount shall exhibit neither cracks on the elastomer surface nor separation of the elastomer to the metal bond at a deflection of 3 inches minus 0,125 inch when tested as prescribed in 4.4.2.

3.8 Environmental testing. The mount shall comply with MIL-STD-810, visual inspection and failure criteria, section 3. The mount shall also comply with 3.5 before and after each environmental test. Testing shall be as specified in 4.4.3. Tests shall be conducted in the order specified.

3.8.1 Drop test. The mount shall transmit neither shock acceleration nor deflect greater than the limits spcified on dwg 8826392. Testing shall be conducted as prescribed in 4.4.3.1.

3.8.2 High temperature. The mount shall withstand a high temperature of 160 ± 5°F when tested as specified in 4.4.3.1. Upon completion of this test the mount shall comply with 3.5.

3.8.3 Low temperature. The mount shall withstand exposure to a temperature of -80 ± 5°F without damage and while at -65 ± 5°F shall comply with 3.6, 3.7 and 3.8.1 when tested as specified in 4.4.3.3. Upon completion of this test the mount shall comply with 3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:29Z
Check the source to verify that this is the current version before use.

3.9 Workmanship.

3.9.1 Plastic and metal characteristics. All components shall be free from cracks, splits, cold flow, shrinkage, cold shuts, inclusions, porosity, or any similar characteristic.

3.9.2 Threads. Threads shall be full and undamaged for the entire minimum length or depth as required on the applicable drawing.

3.9.3 Burrs. Parts shall be free from burrs.

3.9.4 Foreign matter. Parts shall be free from chips, dirt, grease, rust, corrosion, or any embedded foreign material.

3.9.5 Cleaning. The cleaning method shall not be injurious to any of the parts, nor shall the parts be contaminated by the cleaning agent.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplies may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 First article inspection.

4.2.1 Quantity to be submitted. When the contract requires first article inspection, the contractor shall submit 4 complete assemblies (see dwg 8826392) for first article testing to the testing facility designated in the invitation for bids or request for proposal.

4.2.2 Inspection and testing to be performed. The first article inspection sample shall be subjected to the inspections and tests specified in Table I. Tests shall be conducted in order specified in Table I.

Table I
First article inspection and tests

Inspection or Test	Dest	Non Dest
1. Classification of characteristics (see 4.3.2.1)		X
2. Performance characteristics (see 3.5)		X
3. Load deflection (see 3.6)		X
4. Pull test (see 3.7)		X
5. Drop test (see 3.8.1)		X

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:29Z
Check the source to verify that this is the current version before use.

6. High temperature (see 3.8.2)	X
7. Low temperature (see 3.8.3)	X

4.2.3 Inspection equipment. The inspection and testing specified in 4.2.2 shall be accomplished by using the gages and test equipment specified in 4.3.4.1.

4.2.4 Rejection. If any item fails to comply with any of the applicable requirements, the first article sample shall be rejected.

4.3 Quality conformance inspection.

4.3.1 Lot formation.

4.3.1.1 Production lot. A lot shall consist of parts and assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision. Drawing, specification and process changes not affecting safety, performance, storage, or interchangeability, as determined by the Government, shall not necessitate changing the lot interfix number. The criteria and procedures for the assignment of lot numbers shall be in accordance with MIL-STD-1168.

4.3.1.2 Inspection lot. A lot or batch and its formation, size, and presentation is described in MIL-STD-105, Section 5. Accordingly, a lot shall mean an inspection lot and a batch shall mean an inspection batch for the purpose of this specification. The manner in which each inspection lot or batch is to be presented and identified by the contractor, shall be designated or approved by the Government representative.

4.3.2 Product inspection examination. A sample shall be selected at random from each inspection lot in accordance with the applicable major or minor characteristic table (see Table II and Table III), and inspected for all characteristics in the applicable classification. Any characteristics in the sample found to be defective shall reject the inspection lot. Sequence for the inspection of characteristics in each classification need not be followed as long as all characteristic inspections are performed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:29Z
Check the source to verify that this is the current version before use.

Table II
Major Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-72	all	140-141	124	256-259	177	541-549	230
73	72	142	125	260-262	178	550-559	231
74	73	143-144	126	263-265	179	560-569	232
75	74	145	127	266-268	180	570-579	233
76	75	146-147	128	269-271	181	580-590	234
77	76	148-149	129	272-275	182	591-601	235
78	77	150	130	276-278	183	602-613	236
79	78	151-152	131	279-282	184	614-625	237
80	79	153-154	132	283-285	185	626-637	238
81-82	80	155-156	133	286-289	186	638-649	239
83	81	157	134	290-293	187	650-662	240
84	82	158-159	135	294-296	188	663-676	241
85	83	160-161	136	297-300	189	677-690	242
86	84	162-163	137	301-304	190	691-704	243
87	85	164-165	138	305-308	191	705-719	244
88-89	86	166-167	139	309-312	192	720-735	245
90	87	168	140	313-316	193	736-751	246
91	88	169-170	141	317-320	194	752-768	247
92	89	171-172	142	321-324	195	769-785	248
93	90	173-174	143	325-329	196	786-804	249
94-95	91	175-176	144	330-333	197	805-823	250
96	92	177-178	145	334-338	198	824-842	251
97	93	179-180	146	339-342	199	843-863	252
98	94	181-182	147	343-347	200	864-884	253
99-100	95	183-184	148	348-352	201	885-907	254
101	96	185-187	149	353-356	202	908-930	255
102	97	188-189	150	357-361	203	931-955	256
103	98	190-191	151	362-366	204	956-981	257
104-105	99	192-193	152	367-372	205	982-1008	258
106	100	194-195	153	373-377	206	1009-1036	259
107	101	196-197	154	378-382	207	1037-1066	260
108-109	102	198-200	155	383-388	208	1067-1098	261
110	103	201-202	156	389-393	209	1099-1131	262
111	104	203-204	157	394-399	210	1132-1166	263
112-113	105	205-207	158	400-405	211	1167-1204	264
114	106	208-209	159	406-411	212	1205-1243	265
115	107	210-212	160	412-417	213	1244-1285	266
116-117	108	213-214	161	418-424	214	1286-1330	267
118	109	215-217	162	425-430	215	1331-1378	268
119	110	218-219	163	431-437	216	1379-1429	269
120-121	111	220-222	164	438-443	217	1430-1483	270
122	112	223-224	165	444-450	218	1484-1542	271
123-124	113	225-227	166	451-457	219	1543-1605	272
125	114	228-230	167	458-465	220	1606-1673	273
126-127	115	231-232	168	466-472	221	1674-1747	274
128	116	233-235	169	473-480	222	1748-1827	275
129-130	117	236-238	170	481-488	223	1828-1914	276
131	118	239-241	171	489-496	224	1915-2010	277
132-133	119	242-243	172	497-504	225	2011-2115	278
134	120	244-246	173	505-513	226	2116-2232	279
135-136	121	247-249	174	514-521	227	2233-2361	280
137	122	250-252	175	522-530	228	over 2361	298
138-139	123	253-255	176	531-540	229		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:29Z
Check the source to verify that this is the current version before use.

Table III
Minor Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-16	all	28-29	23	52-56	31	132-156	39
17	16	30-31	24	57-62	32	157-191	40
18	17	32-34	25	63-69	33	192-244	41
19-20	18	35-36	26	70-76	34	245-334	42
21	19	37-40	27	77-86	35	335-519	43
22-23	20	41-43	28	87-97	36	520-1120	44
24-25	21	44-47	29	98-112	37	over 1120	45
26-27	22	48-51	30	113-131	38		

4.3.2.1 Classification of characteristics (see 3.2). Critical, major and minor characteristics are defined in MIL-STD-105. Inspection shall be conducted as follows:

4.3.2.1.1 Resilient mount (see dwg 8826392).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Incorrect height of stud (3)	Gage
	102. Mislocation of mounting hole (4)	Gage
	103. Mislocation of stud	Gage
	104. Incorrect diameter (min) of mounting hole	Gage
	105. Incorrect major diameter (min) of stud thread	Gage
	106. Improper or missing counterbore	Visual
	107. Incorrect pitch diameter (min) of stud thread	Gage
	108. Marking missing, improper or illegible	Visual
	109. Incorrect vertical set	Gage
	110. Objective evidence relative to material missing or improper (see 3.1)	Visual
Minor:		
	201. Evidence of flashing -- except areas around holes permissable	Visual
	202. Evidence of poor workmanship (see 3.9)	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:29Z
Check the source to verify that this is the current version before use.

4.3.2.1.2 Container, sealed (see 5).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:	None defined.	
Minor:		
	201. Container damaged exposing contents	Visual
	202. Contents loose when container shaken	Manual
	203. Marking missing, illegible or improper	Visual
	204. Evidence of poor workmanship (see 3.9)	Visual

4.3.3 Testing. All tests shall be performed. Tests shall be performed in the order specified below:

Test	Test classification
a. Pull	Major
b. Load deflection	Major

None of these tests are considered destructive and samples so tested may be returned to the lot.

4.3.3.1 Pull test. Each mount shall be tested in accordance with 4.4.2. If any item fails to comply with 3.7, the item shall be rejected and removed from the lot.

4.3.3.2 Drop test A sample shall be selected at random in accordance with Table IV. The sample shall be tested in accordance with 4.4.1. If any item fails to comply with 3.6, the lot shall be rejected.

Table IV
Sample sizes for non - destructive testing

Lot Size	Sample Size
2-8	1
9-15	2
16-25	3
26-40	5
41-65	8
66-110	13
111-180	22
181-300	36
301 and over	MIL-STD-105 (AQL 0.25%)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:29Z
Check the source to verify that this is the current version before use.

4.3.4 Acceptance inspection equipment.

4.3.4.1 Major characteristics and tests. Inspection and testing shall be performed with the acceptance inspection equipment, operating instructions, and calibration instructions specified on the Equipment Lists (EL) (see EL-8842569). When either of the conditions listed below exist, the contractor shall design required equipment or specify suitable commercial equipment and obtain approval prior to use on the contract.

a. Any deviation from equipment or procedures specified on the EL is desired (see 6.3).
b. The code "CD" is listed in the "Part or Identifying Number" column on the EL (see 6.1.2).

4.3.4.2 Minor characteristics and tests. Acceptance inspection equipment for minor characteristics is not specified on ELs. The acceptance inspection equipment, operating instructions and calibration instructions used by the contractor for minor classification inspection shall be approved by the Government representative authorized by the procuring agency.

4.4 Test methods. The tolerances specified herein are absolute with no allowance for test equipment inaccuracy. The tolerances used by the manufacturer shall be equal to the absolute tolerances less the accuracy tolerances of the test equipment used.

4.4.1 Load deflection. Two mounts shall be firmly attached to a testing fixture by which the mounts can be preflexed twice to the maximum limits specified on dwg 8826392 by applying and relieving the load at a rate of 0.6 to 1.0 inch per minute. The required load shall be applied continuously to the suspended load. To facilitate ease of handling, but with prior Government approval, a lightweight rigid yoke or bar may be used in lieu of the heavier weight (suspended mass). In this event, a preload of 100 pounds (including the weight of yoke) shall be applied to the two mounts prior to the third flexing. In either event, the load scale and deflection indicator shall be zeroed to the preload value (or suspended mass) and deflection position. The required load shall be applied at a rate of 0.6 to 1.0 inch per minute. Load reading shall be taken at 0.6 inch deflection without interruption of the load application and shall agree with the load values specified in dwg 8826392. All the mounts constituting the sample shall be tested accordingly. Upon completion of test, mount shall meet the requirements of 3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:29Z
Check the source to verify that this is the current version before use.

4.4.2 Pull test. Two mounts shall be firmly attached to a testing fixture by which the mounts can be deflected to the limits specified on dwg 8826392. However the lighter yoke or bar specified in 4.4.1 may be used in lieu of the heavier weight when permitted by the Government. This test may be performed as a continuation of 4.4.1 All the mounts constituting the lot shall be tested accordingly. Upon completion of test, mount shall meet the requirements of 3.5.

4.4.3 Environmental testing(see 3.8).

4.4.3.1 Drop test Two mounts shall be attached to a test fixture and with an accelerometer having applicable ranges, shall be installed on top of the suspended mass directly above the mass center of gravity. The entire assembly then shall be raised to the height specified on drawing 8826392 and allowed to fall freely and flat on its base upon a concrete or equally hard surface. Deceleration shall be measured and recorded. This test shall be performed a minimum of three times. The deceleration loads or shock level, measured in gravity unity (g), shall meet the requirements specified on dwg 8826392. All the mounts constituting the sample shall be tested accordingly. Upon completion of test, mount shall meet the requirements of 3.5

4.4.3.2 High temperature The mounts shall be placed within a chamber and the internal temperature of the chamber raised to 160 ± 5°F. The mounts shall be maintained at 160 ± 5°F for a period of 2 hours. While still at this temperature, the mounts shall be tested as specified in 4.4.3.1.

4.4.3.3 Low temperature The mounts shall be placed within a chamber and the chamber stabilized (see 6.4), and maintained at -80 ± 5°F for a period of 4 hours. The temperature of the chamber shall then be raised to -65 ± 5°F and maintained for an additional 2 hours. While still at this temperature, the mounts shall be tested as specified in 4.4.3.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:29Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging. Preservation and packaging shall be level A or C as specified (see 6.1).

5.1.1 Level A. The mounts shall be preserved and packaged in accordance with instructions contained in MIL-STD-1169(MU).

5.1.2 Level C. The mounts shall be preserved and packaged in accordance with instructions contained in MIL-STD-1169(MU).

5.2 Packing.

5.2.1 Levels A and C. The mounts shall be packed in accordance with the applicable instructions contained in MIL-STD-1169(MU).

5.3 Marking. Marking shall be in accordance with MIL-STD-1169(MU).

6. NOTES

6.1 Ordering data. Procurement documents should specify the following:

6.1.1 Procurement requirements.

a. Title, number, and date of this specification.
b. Selection of applicable level of packaging and packing required (see 5.1 and 5.2).

6.1.2 Contract data requirements (see 4.3.4.1). Data specified in 4.3.4.1 will be delivered as identified on a numbered DD Form 1664 when required on a DD Form 1423 incorporated in the contract.

6.2 Objective evidence. Records of contractor quality control and inspections which can be verified.

6.3 Acceptance inspection equipment (see 4.3.4.1). The contractor shall obtain approval from the Commander, Picatinny Arsenal, Dover, New Jersey 07801, ATTN: SARPA-QA-N-I.

6.4 Temperature stabilization. The temperature is considered stabilized when the greatest peaks (both highest and lowest) continually observed over 5 minutes min. do not exceed the nominal temperature plus tolerance specified.

6.5 Supersession data. This specification supersedes the requirements of Purchase Description PA-PD-1693 (Rev. 1) Amendment 2 dated 7 September 1965.

Custodian:
Army - PA

Preparing activity:
Army - PA

Project No. NUOR-A018

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:29Z
Check the source to verify that this is the current version before use.