MILITARY SPECIFICATION

TELESCOPE, ELBOW, M11A2

This specification is approved for use by the U.S. Army Armament Research and Development Command, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers an instrument designated as Telescope, Elbow: M118A2.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-O-13830	Optical Components for Fire Control Instruments, General Specification Governing the Manufacture, Assembly, and Inspection of
MIL-F-13926	Fire Control Materiel: General Specification Governing the Manufacture and Inspection of
MIL-P-14232	Parts, Equipment and Tools for Army Materiel, Packaging and Packing of
MIL-I-45607	Inspection Equipment, Supply and Maintenance of

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commander, US Armament Research and Develppment Command, Attn. DRDAR-QA, Dover, New Jersey 07801 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 202610-23T02:43Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105	Sampling procedures and Tables for for Inspection by Attributes
MIL-STD-109	Quality Assurance Terms and Definitions
MIL-STD-202	Test Methods for Electronic and Electrical Component Parts

DRAWINGS

U.S. ARMY ARMAMENT RESEARCH AND DEVELOPMENT COMMAND (ARRADCOM)

F11829207	Telescopes, Elbow: M118A2

PACKAGING DATA SHEET

10512082	Packaging of Telescope, Elbow: M118A2

(Copies of specifications, standards, drawomgs and publicaitons required by suppliers in connection with specified procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Fabrication. - The telescope shall be manufactured in accordance with all drawings applicable to the telescope specified in the contract or order and drawings pertaining thereto.

3.2 General specifications. - The contractor shall be responsible for adherence to, and compliance with, the following requirements of Specifications MIL-O-13830 and MIL-F-13926.

3.2.1 MIL-O-13830.

a. Illuminated reticle

b. Cleanliness

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:43Z
Check the source to verify that this is the current version before use.

3.2.2 MIL-F-13926.

a. Order of precedence
b. Dimensions and tolerances
c. Inorganic protective surface finishes
d. Electrical and electronic assemblies
e. Part identification and marking
f. Workmanship

3.3 Environmental.

3.3.1 Storage temperatures. - The telescope shall show no evidence of physical failure at room temperature (60° to 90°F) after having been thermally stabilized at -70°F and +160°F.

3.3.2 Standard ambient temperatures. - Subsequent to meeting the requirements of 3.3.1, the telescope shall meet all the requirements of this specification except 3.3.3 at a standard ambient temperature between 60°F and 90°F.

3.3.3 Operating temperatures. - The telescope shall show no evidence of physical failure and shall meet the applicable requirements of 3.9 while thermally stabilized at -40°F and +150°F.

3.3.4 Vibration. - The telescope shall show no evidence of physical failure (loose, missing or broken parts) after having been vibrated at a frequency of 30 cycles per second at an amplitude of 1/16 inch (1/8 inch total excursion) for a period of 5 minutes ± 15 seconds. Vibration shall not have caused the eyepiece are to disengage from the initially engaged position. Subsequent to vibration, the telescope shall meet the requirements of 3.4 to 3.10 inclusive.

3.4 Cleanliness. - The telescope shall meet the cleanliness requirements of Specification MIL-O-13830. There shall be no more than 2 particles of dirt visible in the center zone (.614 inch diameter) of the reticle, and the area of each particle shall not be in excess of the area equivalent to a size 10 dig. There shall be no more than 5 particles of dirt visible in the outer zone of the reticle, and the area of each particle shall not be in excess of the area equivalent to a size 20 dig.

3.5 Sealing. - The telescope shall maintain an internal pressure of dry nitrogen at 5 pounds per square inch (psig) for a minimum period of 2 hours without loss of pressure in excess

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:43Z
Check the source to verify that this is the current version before use.

of 0.2 psig. The interior atmosphere of the accepted telescope shall contain nitrogen having a dew point of at least as low as - 2 5 %

3.6 Orientaiton. - The telescope shall meet the requirements of 3.7 with the tapered holes vertical, the level vial bubble centered, the mechanical cant index line indicating zero, and the eyepiece arm horizontal.

3.7 Accuracy.

3.7.1 Collimation. - The line of sight through the boresight point of the reticle shall be 20 mils ± 1.0 mil above the geometric axis and within 1.0 mil of a plumb line passing through the geometric axis.

3.7.2 Parallelism of reticle and image. - The horizontal reticle line nearest the goemetric axis of the reticle shall be parallel to a horizontal target line within thirty minutes of arc.

3.4.3 Reticle accuracy. - The angular value between the zero range mark and the maximum range mark (in the finished telescope) shall be as indicated on the reticle drawing within 0.25 mil.

3.7.4 Eyepiece focus. - The eyepiece focus shall be fixed between the limits of -0.75 and -1.0 diopter.

3.7.5 Resolution. - The resolution at the optical axis shall be 12 seconds of arc or less.

3.7.6 Parallax. - Parallax at the geometric axis shall not exceed 0.15 mil when viewing a target at 600 meters ± 25 meters.

3.8 Illumination.

3.8.1 Level vial. - The lamp for level vial illumination, when energized with 18 VDC and 28 VDC, shall provide sufficient illumination at each voltage for the level vial markings to be clearly defined when observed in a darkened area.

3.8.2 Reticle. - The lamp for reticle illumination, when energized with 19 VDC and then 28 VDC, shall provide sufficient illumination at each voltage for the reticle markings to be clearly defined when observed in a darkened area. Rotation of the rheostat knob shall cause a change in illumination of the reticle only.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:43Z
Check the source to verify that this is the current version before use.

3.9 Operability. - The torque required to operate the following controls shall be within the values specified when the controls are rotated at a standard ambient temperature of 60° to 90°F. The torque values obtained when the telescope is exposed to the extreme temperatures of 3.3.3 shall not exceed the values obtained at standard ambient temperature by more than 100 percent.

3.9.1 Cant correction knob. - With the level vial bubble centered and the tapered holes and eyepiece arm vertical, the running torque required to rotate the cant correction knob shall be 7 inch-pounds ± 1.0 inch-pound.

3.9.2 Mirror, plunger arm and rheostat.- The level Vial mirror (pivotal type only), plunger, eyepiece arm and the rheostat knob shall be mechanically operable when exposed to the operating temperatures of 3.3.3.

3.10 Insulation resistance. - Insulation resistance shall not be less than 10 megohms with a potential of 100 volts direct current applied.

4. QUALITY ASSURANCE PROVISIONS

4.1 Resposibility for inspection. - Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 General provisions. - The component and subassembly inspection requirements of MIL-F-13926 form a part of the Quality Assurance Provisions of this specification. Definitions of inspection terms shall be as listed in MIL-STD-109.

4.2 First Article (Initial Production) Approval. - The requirement for first article approval and the responsibility (Government or Contractor) for first article testing shall be as specified in the contract. The sample for first article approval tests shall consist of 3 Elbow Telescopes plus three (3) each of all item covered by SQAP. The sample shall be

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:43Z
Check the source to verify that this is the current version before use.

manufactured in the same manner, using the same materials, equipment, processes and procedures as used in regular production. All parts and materials, including packaging and packing, shall be obtained from the same source of supply as used in regular production.

4.2.1 Government testing. - When the Government is responsible for conducting first article approval tests, the contractor, prior to submitting the sample to the Government, shall inspect the sample to insure that-it conforms to all the requirements of the contract and submit a record of this inspection with the sample, including certificates of conformance for materials.

4.2.2 Contractor testing. - When the contractor is responsible for conducting first article approval tests, the sample shall be inspected-by the contractor for all the requirements of the contract. The sample and a record of this inspection, including certificates of conformance for materials, shall be submitted to the Government for approval. The Government reserves the right to witness the contractor’s inspection.

4.3 Inspection provisions.

4.3.1 Submission of product. - Unless otherwise specified by the contracting officer, inspection lot size, lot formation and presentation of lots shall be in accordance with “Submission of Product" provisions of MIL-STD-105.

4.3.2 Examination and tests.

4.3.2.1 Components and subassemblies. - All components and subassemblies shall be inspected in accordance with the inspection provisions contained in Supplementary Quality Assurance Provisions (SQAP) when provided with the Technical Data Package (TDP). In the absence of SQAP’S, the applicable Quality Assurance Provisions of MIL-F-13926 shall apply.

4.3.2.2 Final acceptance inspection. - Subsequent to first article approval, examination and tests related to Section 3 herein shall be performed on a single defect (individual characteristic) basis in accordance with MIL-STD-105 and the sampling plans specified in Table I herein. Examination and tests for Packaging, Packing and Marking shall be in accordance

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:43Z
Check the source to verify that this is the current version before use.

with MIL-P-14232 and Section 5 herein. The tbulated classification of defects in Table I shall constitute the minimum inspection to be performed by the supplier after first article approval and prior to Government acceptance or rejection by item or lot.

TABLE I - CLASSIFICATIONS

CHARACTERISTICS	REQUIREMENT	TEST PROCEDURE
CRITICAL: 100%		
1. Sealing	3.5	4.7.2.10
2. Internal pressure	3.5	4.7.2.10.1
MAJOR 1.5% DEFECTIVE		
101. Collimation	3.7.1	4.7.2.1
102. Cleanliness	3.4	4.7.2.1
103. Vibration	3.3.4	4.7.2.2
104. Post Collimation	3.7.1	4.7.2.3
105. Cleanliness (Post vibration)	3.4	4.7.2.3
106. Eyepiece focus	3.7.5	4.7.2.4
107. Parallax	3.7.7	4.7.2.6
108. Parallelism of image and reticle	3.7.2	4.7.2.5
109. Resolution	3.7.6	4.7.2.8
110. Reticle accuracy	3.7.3	4.7.2.7
111. Torque (Cant correction knob 60° - 90°)	3.9.1	4.7.2.10
112. Torque mirror, plunger arm and rheostat 60° - 90°	3.9.2	4.7.2.10
113. Illumination (level vial)	3.8.1	4.7.1
114. Illumination (reticle)	3.8.2	4.7.1
115. Insulation Resistance	3.10	4.7.2.11
MINOR: NONE		

4.3.3 Acceptance and rejection. - Rejected lots shall be screened for all defective characteristics. Removal or correction of defective units and resubittance of rejected lots shall be in accordance with "Acceptance and Rejection" as specified in MIL-STD-105.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:43Z
Check the source to verify that this is the current version before use.

4.4 Special sampling for environmental testing.

4.4.1 Samples shall be selected from lots at random using inspection Level S-3 Table I of MIL-STD-105. Acceptance or rejection of the lot shall be in accordance with AQL 2.5 of Table II-A of MIL-STD-105. The samples shall have met all the requirements and tests outlined in Table I prior to being subjected to the following examination and test.

TABLE II

CHARACTERISTIC	REQUIREMENT	TEST PROCEDURE
301. Fabrication	3.1	Certification
302. General specification	3.2	Certification
303. Temperature storage	3.3.1	4.6.1.1
304. Temperature operating	3.3.3	4.6.1.1
305. Torque (Cant correction knob -40° + 150°)	3.9.1	4.7.2.10
306. Torque, (Mirror, plunger, arm and rheostat (-40° + 150°)	3.9.3	4.7.2.10

4.4.2 Failure of sample. - Should any one item of a special sampling fail to meet the specified test requirements, acceptante of the represented inspection lot will be suspended by the Government until necessary corrections have been made by the contractor and the resubmitted samples have been approved (see 4.3.3).

4.5 Inspection equipment. - Requirements for inspection equipment to perform examinations and tests are specified herein and in specific contract clauses as applicable. See Section 6 of this specification for general provisions applicable to inspection designs.

4.5.1 Government furnished inspection equipment. - Where the contract provided for Government furnished test equipment, supply and maintenance of test equipment shall be in accordance with the applicable requirements specified in MIL-I-45607.

4.5.2 Contractor furnished inspection equipment.

4.5.2.1 Governmant design. - Unless otherwise specified in the contract, all inspection equipment specified by drawing number in specification or SQAP forming a part of the contract shall be supplied by the contractor in accordance with technical data listed in the List of Inspection Documents when provided with the Technical Data Package (TDP).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:43Z
Check the source to verify that this is the current version before use.

4.5.2.2 Contractor design. - The contractor shall design and supply inspection equipment compatible with the "Test Methods and Procedures" specified in 4.6 of this specification and with the component inspection procedures specified in "Examination" and "Test Facilities" requirements of MIL-F-13926. Since tolerance of test equipment is normally considered to within 10% of the product tolerance for which it is intended, this inherent error in the test equipment design must be considered as part of the prescribed product tolerance limit. Thus, concept, construction, materials, dimensions and tolerance used in the design of test equipment shall be so selected and controlled as to insure that the test equipment will reliably indicate acceptability of a product which does not exceed 90% of the prescribed tolerance limit, and permit positive rejection when non-conforming. Construciton shall be such as to facilitate routine calibration of test equipment.

4.5.3 Test equipment. - In conjunction with 4.5.2.2 the following standard test equipment shall be utilized in the performance of the applicable tests as specified in 4.6 and 4.7.

NOMENCLATURE	DESCRIPTION
1. Hot and Cold Chamber	Standard type conforming to the accuracies outlined in test facilities specified under test facilities of MIL-F-13926.
2. Insulation Resistance Checker	Standard shop type conforming to the accuracies outlined in 4.5.2.2
3. Power Supply	0 to 100 VDC output within 10% accuracy
4. Torque Wrench, Scales and Adapters	Standard shop type accurate to within 10% of specification requirements
5. Pressure Gage	Standard shop type accurate to within 10% of specification requirement

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:43Z
Check the source to verify that this is the current version before use.

4.6 Test methods and procedures.

4.6.1 Environmental.

4.6.1.1 Temperature test. - The telescope shall be subjected to test Procedure I of MIL-F-13926; however, the temperatures specified in 3.3.1, 3.3.2 and 3.3.3 shall apply. When the telescope has been stabilized at the temperature specified, the result of the specified test shall conform to the limits outlined in 3.3.1, 3.3.2 and 3.3.3.

4.7 Performance testing.

4.7.1 Orientation. - Proper orientation is assured when the telescope is properly mounted and secured to a testing device, the accuracy of which shall be equal to or exceed the accuracy depicted in Drawing F8599924, and when aligned as outlined in set-up instructions outlined on Drawing F8599924. When the telescope is aligned as outlined above, set the mechanical cant index line, and observe that the level vial position is as specified in 3.6. During acceptance inspection, energize the telescope's electrical system and observe that the illumination of the level vial when energized with the voltage specified is in conformance with 3.8.1. With the voltages specified in 3.8.2, observe that the reticle markings are in conformance with 3.8.2 and also observe that a rotation of the rheostat will cause illumination to increase from low to bright. Prior Prior to performing acceptance inspection, remove image tilt by unlocking the eyepiece portion of the telescope and rotating the eyepiece until the longest reticle line is positioned parallel to the comparable collimator target line. Lock in this position.

4.7.2 Collimation.

4.7.2.1 Previbration. - With the telescope positioned as outlined in 4.7.1, observe coincidence between the intersecting point of the vertical reticle line designated as the normal line for boresighting (N), to a comparable projector reticle mark. This coincidence must be within the limits outlined in 3.7.1. Record this position, and observe coincidence for conformance with 3.7.2. Inspect telescope for cleanliness using techniques outlined in MIL-O-13830 for conformance with 3.4. Exercise care not to move telescope settings.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:43Z
Check the source to verify that this is the current version before use.

4.7.2.2 Vibration. - This test shall be performed using a testing device, the accuracy of which shall be equal to or exceed the accuracy depicted on Fixture Drawing F7560085. The The test shall be performed as outlined in Procedure V of MIL-F-13926; however, the duration shall be as specified in 3.3. At the conclusion of the test, the telescope shall be subjected to a visual and tactile examination and shall be subjected to the following performance test to determine conformance with 3.3. Repeat test for cleanliness.

4.7.2.3 Post vibration. - Immediately after completing the vibration test and test for cleanliness, reassemble the telescope to the testing fixture or medium without disturbing any previous settings. Observe where the intersecting point of the telescopes reticle fall upon the collimator projector retcile with respect to the recorded position observed in 4.7.2.1. They must coincide within the limits of 3.7.1.

4.7.2.4 Eyepiece focus. - This test is to be accomplished by placing a white background in front of the telescope’s objective lens. Eyepiece focus is to be measured using a 3 power dioptometer conforming to the accuracies depicted on Drawing 7680631. Adjust the dioptometer eyepiece assembly to the dioptometer’s optical axis. Next direct the dioptometer's line of sight toward a 500 feet distance target such as a smoke stack, edge of a building, or some other well defined target image. Adjust the objective assembly until parallax is removed. Set the dioptometer scale to zero diopters. The telescope reticle and image shall remain clear and distinguishable throughout the permissible diopter range specified in paragraph 3.7.6.

4.7.2.5 Parallelism of image and reticle. - With the telescope positioned as outlined in 4.7.1, observe coincidence between one end of the instrument’s horizontal reticle line with respect to the comparable projector collimator’s horizontal reticle line and observe where the opposite end of the telescope horizontal reticle line falls with respect to the projector collimator horizontal line, both lines must coincide within the limits specified in 3.7.3.

4.7.2.7 Parallax. - Using set-up outlines in 4.7.1, parallax will be checked after the distances specified in 3.7.8 have been set into the projector collimator. The test is performed by aligning the reticle line or mark near or on the optical axis of the projector collimator reticle. Observe this positioning,

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:43Z
Check the source to verify that this is the current version before use.

there shall be no apparent movement between the selected lines or mark when the observer moves his head from side to side or up and down. Reticle displacement shall not exceed the limits outline in 3.7.8. Use the thickness of the elbow telescope reticle line to estimate any apparent movement.

4.7.2.7 Reticle accuracy. - Reticle accuracy may be assured by aligning the normal line for boresighting of the telescope under test to the corresponding reticle line of the projector collimator. Adjustments may be made by means of loosening the telescopes in the test fixture to obtain coincidence. When the coincidence has been established, observe where the maximum range graduation of telescope's reticle falls with respect to the corresponding reticle line of the projector collimator. They must coincide within the limits of the reticle tolerance mark to assure compliance with 3.7.4.

4.7.2.8 Resolution. - This test may be performed after directing the line of sight toward a target similar to that specified in MIL-O-13830. The actual test is performed as outlined in MIL-O-13830. Observe the definition pattern on the target. The patterns must be resolved in the four meridians within the limits outlined in 3.7.7.

4.7.2.9 Sealing. - This test shall be performed on a 100% basis using testing equipment the accuracy of which shall conform to the fixture depicted on Drawing F8565556. When using pressure test fixture, the fixture shall be set-up as outlined-in set-up instructions shown on Drawing F8565556, Sheet 1. The gas used shall be dry nitrogen having a dew point of -20°F. After connecting the test equipment to the telescope, adjust the pressure to the pressure specified in 3.5 and maintain the pressure for the time specified in 3.5. Pressure gage shall remain constant to assure compliance with 3.5. At the completion of this test, connect a dew point tester to the exit port and purge the telescope until -20°F is recorded and seal the unit containing the pressure specified in 3.5.

4.7.9.1 Internal pressure. - This test to be performed using standard shop type pressure gage using standard inspection techniques. This test to be performed on a 100% inspection basis just prior to packaging for shipment. Any telescope found not to contain an internal pressure in accordance with 3.5 shall be rejected and repressurized and

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:43Z
Check the source to verify that this is the current version before use.

retested in accordance with 4.7.2.10. All retested telescopes shall be aside for a minimum of 12 hours and then retested for internal pressure in accordance with 3.5. Should the telescope fail second test, the telescope shall be rejected.

4.7.2.10 Torque. - Torque to be measured using appropriate adapters and torque measuring devices (scales, weights or wrench). Torque measurements to be considered as running torque and are to be performed under temperature conditions outlined in 3.9 and shall conform to the requirements' of 3.9.1, 3.9.2 and 3.9.3.

4.7.2.11 Insulation resistance. - This test shall be conducted in accordance with Method 302 of MIL-STD-202, using test condition "A". Insulation resistance measurements shall be made between insulated points and ground. Insulation resistance shall not be less than the value specified in 3.10.

5. PREPARATION FOR DELIVERY

5.1 Packaging, packing and marking. - Packaging, packing and marking shall be in accordance with MIL-P-14232 and the applicable packaging data sheet as follows:

10512082 Telescope, Elbow: M118A2

The level of protection shall be as specified in the procurement document.

6. NOTES

6.1 Intended use. - Elbow Telescope M118A2 is intended for use as components of the primary direct fire control systems on self-propelled howitzers.

6.2 Ordering data. - Procurement documents should specify the following:

a. Title, number, and date of this specification.
b. Selection of applicable levels of preservation, packaging, and packing.
c. Applicable stock numbers.
d. Applicable packaging data sheet number (see 5.1).
e. Selection of applicable level of preservation, packaging and packing.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:43Z
Check the source to verify that this is the current version before use.

f. Quanity required and delivery schedule
g. Requirements for First Article Submission, including data requirements for certificates of conformance for materials.

6.3 Inspection equipment design.

6.3.1 Government design. - Unless otherwise specified in the contract, all inspection equipment specified by drawing number in specifications or SQAP forming a part of the contract shall be supplied by the contractor in accordance with the technical data listed in the Technical Data Package (TDP).

6.3.2 Contractor design. - The contractor shall design and supply inspection equipment compatible with the "Methods of Inspection" specified in 4.6 of this specification and with the "Test Conditions" and "Test Facilities and Apparatus" specified in the "General Requirements" of MIL-STD-810. Since tolerance of test equipment is normally considered to be within 10% of the product tolerance for which it is intended, this inherent error in the test equipment design must be considered as part of the prescribed product tolerance limit. Thus,m concept, construction, materials and dimensions shall be so selected and controlled as to insure that the test equipment will reliably indicate acceptability of a product which does not exceed 90% of the prescribed tolerance limit and permit positive rejection when non-conforming. Construction shall be such as to facilitate routine calibration of test equipment.

6.3.3 Submission of designs for approval. - Contractor designs shall be approved by the Government prior to fabrication or procuring the equipment. Partial submission of inspection equipment designs is permissible and encouraged. However, the completion date for design review will be based on the date of the final submission of designs and the required delivery schedule as stipulated in the contract. Submit designs as required to : Commander, U.S. Army Armament Research and Development Command, ATTN: DRDAR-QAF-Q, Dover, NJ 07801. When the contractor submits inspection inspection equipment designs to the government for approval, he shall give the following information in his letter of transmittal:

a. The contract number.
b. The contract item (name, model number, etc).
c. The designs remaining to be submitted and the expected date of submittal.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:43Z
Check the source to verify that this is the current version before use.

6.4 Drawings. - Drawings listed in Section 2 of this specification under the heading of U.S. Army Armament Research and Development Command (ARRADCOM) may also indicate drawings prepared by, and identified as Edgewood Arsenal, Frankford Arsenal, Rock Island Arsenal or Picatinny Arsenal drawings. Technical data originally perpared by these activities is now under the cognizance of ARRADCOM.

Custodian:

Army - AR

Preparing Activity:

Army - AR

Project No: 1240-A729

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:43Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS: This form is provided to solicit beneficial comments which may improve this document and enhance its use. DoD contractors, government activities, manufacturers, vendors, or other prospective users of the document are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity. A response will be provided to the submitter, when name and address is provided, within 30 days indicating that the 1426 was received and when any appropriate action on it will be completed.
NOTE: This form shall not be used to submit requests for waivers, deviations or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

DOCUMENT IDENTIFIER *(Number)* AND TITLE

MIL-T-63359 Telescope, Elbow, M11A2

NAME OF ORGANIZATION AND ADDRESS OF SUBMITTER

☐ VENDOR ☐ USER ☐ MANUFACTURER

1. ☐ HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE? ☐ IS ANY PART OF IT TOO RIGID, RESTRICTIVE, LOOSE OR AMBIGUOUS? PLEASE EXPLAIN BELOW.

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDED WORDING CHANGE

C. REASON FOR RECOMMENDED CHANGE(S)

2. REMARKS

SUBMITTED BY *(Printed or typed name and address — Optional)*	TELEPHONE NO.
	DATE

DD FORM 1 OCT 76 1426 EDITION OF 1 JAN 72 WILL BE USED UNTIL EXHAUSTED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:43Z
Check the source to verify that this is the current version before use.