MILITARY SPECIFICATION

PROJECTILE ASSEMBLY FOR CARTRIDGE, H.E., 81MM, M374

This amendment forms a part of Military Specification MIL-P-60626B(MU) dated 14 August 1967.

Paragraph 4.3.2.4 under Critical Defect, Line 4; change "(Alternative body design No. II only)" to "(as applicable)" Line 5; add "(all bodies)"
Paragraph 4.3.2.5 Delete MAJOR Characteristic 112, in its entirety.
Add Paragraph 4.3.3.3.2.1.3 (Applies to body, body altenative I, III and IV).

"4.3.3.3.2.1.3 After final heat treatment or stress relief and prior to painting, bodies shall be inspected visually and by magnetic particle inspection technique approved by the Responsible Technical Agency.

(a) Visual inspection shall be 100% with a 4X magnification on all bodies.
(b) 100% magnetic particle inspection will be in effect until 2500 consecutive items have been inspected and found to be free of defects.
(c) Reduced sampling may then be instituted for magnetic particle inspection consisting of 30 items for each hours production for ten consecutive working days.
(d) If no defectives are found during the ten days the magnetic particle sample may be reduced to 15 items for each hours production for five consecutive days.
(e) If no defects are encountered during the five day's the magnetic particle sample may be reduced to 5 items per hour.
(f) If a defect is encountered either by visual or magnetic particle inspection during reduced sampling, (c thru e) the magnetic particle inspection shall revert to (b) above, in addition a 100% back screening to the last acceptable hours production will be performed.
(g) For requalification for reduced sampling the manufacturer must follow the same steps as outlined in the paragraph b thru e above.
(h) Should a controversy arise as to the validity of an indication the contractor shall use metallographic test method or an approved non-destructive method for proof of acceptability.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:51Z
Check the source to verify that this is the current version before use.

4.3.3.3.2.1.3 Cont'd

(i) Continual application of 100% magnetic particle inspection by paragraph (b) above shall not be used as an alternative procedure in lieu of corrective manufacturing process action to eliminate a continuing process induced defect. If corrective action is not instituted and the cause eliminated, the government reserves the right to withdraw acceptance inspection until the contractor can prove his process is capable of producing suspect free projectiles. Bodies that have passed the magnetic particle inspection shall have the letter "M" stamped approximately 4.50 inches from rear of body.

Custodian

Army - MU

Preparing Activity

Army - MU

Project No. 1315 - A641

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:51Z
Check the source to verify that this is the current version before use.