MIL-N-60195(MU)
AMENDMENT 4
15 December 1969
SUPERSEDING
AMENDMENT 3
12 July 1968

MILITARY SPECIFICATION

NEON DRIVER CIRCUIT BOARD: 8623298

This amendment forms a part of Military Specification MIL-N-60195(MU), datef 24 February 1965.

Paragraph 3.4.3.1: Change "0.6 volts" to "0.7 volts".

Paragraph 3.5.3 delete and substitute: "The forward voltage drop shall not exceed 0.8 volts at a current of 6 ± 0.3ma and the reverse leakage shall not exceed 10 microamps with a reverse bias of 6 ± 0.5 volts".

Paragraph 3.5.4.1(a): Delete "plus 0.2" and "plus 0.15" and substitute "minus 0.2" and "minus 0.15".

* Paragraph 3.5.4.2(a): Change "15.3 plus or minus 0.6 volts" to "15.9 plus or minus 1.2 volts".

Following paragraph 4.1.1: Add paragraphs 4.1.2, 4.1.2.1 and 4.1.2.2 as follows:

"4.1.2 First Article (Initial Production) Approval.- The requirement for first article approval and the responsibility (Government or contractor) for first article testing shall be as specified in the contract. The sample for first article tests shall consist of three (3) neon drivers manufactured in the same manner using the same materials, equipment, processes, and procedures as used in regular production. All parts and materials, including packaging and packing, shall be obtained from the same source of supply as used in regular production.

4.1.2.1 Government Testing.- When the Government is responsible for conducting first article approval tests, the contractor, prior to submitting the sample to the Government, shall inspect the sample to insure that it conforms to all the requirements of the contract and submit a record of this inspection with the sample, including certificates of conformance for materials.

4.1.2.2 Contractor Testing.- When the contractor is responsible for conducting first article approval tests, the sample shall be inspected by the contractor for all the requirements of the contract. The sample and a record of this inspection, including certificates of conformance for materials, shall be submitted to the Government for approval. The Government reserves the right to witness the contractor's inspection."

FSC 1220

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:17Z
Check the source to verify that this is the current version before use.

Paragraph 4.2.3: Add the following sentence: "No lots shall be accepted until control samples have been satisfactorily tested".

Paragraph 4.3.2: Delete first sentence and substitute: "Neon driver units shall be selected at random by a government representative as control samples from each three (3) months production or portion thereof as follows:

3	units per first 100 produced
5	units per 200 "
7	units per 300 "
9	units per 400 "
10	units per 500 "
12	units per 700 "
15	units per 1000 "

and 2 units for each 100 items produced in excess of 1000".

Delete paragraph 4.5.1.3.2 and substitute the following:

"4.5.1.3.2 Operating.- This test shall be conducted in accordance with the humidity test defined in Procedure III of MIL-F-13926, except that the humidity shall be maintained at 92 to 97 percent for the 24-hour period and the test shall cease at the end of that period (Method 106 of MIL-STD-202 shall be excluded). Throughout the test period, the board shall be capable of performing the tests of 4.5.3 to determine compliance with 3.3.4.1. In order to demonstrate this capability, the tests of 4.5.3 shall be performed a minimum of once each 6 hours of the 24-hour period. The final test shall be conducted during the final portion of the 24-hour period. Between tests, the board shall be electrically de-energized."

Delete paragraph 4.5.1.4 and substitute the following:

"4.5.1.4 Salt Spray.- This test shall be conducted in accordance with the salt spray test defined in Method 101, Condition B of MIL-STD-202 using a 5 percent salt solution. At the end of the exposure period, salt deposits shall be removed from the board by a gentle wash, not exceeding 30 minutes, in running water not warmer than 100°F, using a soft-hair brush or plastic-bristle brush. The board shall then be air dried in a controlled environment at 72°F ± 5°F and a relative humidity of 30 to 50 percent for a period of 24 hours. The board shall be inspected visually for any physical damage, then tested in accordance with 4.5.2 for compliance with 3.3.6."

Paragraph 4.5.2.3.1(c), (e), (g): Change "0.6 volts" to "0.7 volts".

* Paragraph 4.5.3.3: Change "1.2 volts" to "0.8 volts"; change "12 millivolts" to "60 millivolts".

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:17Z
Check the source to verify that this is the current version before use.

*The outside margins have been marked to indicate where additions to the previous amendment have been made. This has been done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in this notation. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content as written irrespective of the marginal notation and relationship to the last previous amendment.

Custodian:

Army - MU

Preparing activity:

Army - MU

Project No. 1220-A238

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:17Z
Check the source to verify that this is the current version before use.