MILITARY SPECIFICATION

CABLE ASSEMBLIES, POWER, ELECTRICAL: W2-H, W3-H, W4-H, W6-H, W7-H, W8-HA, and W20-H

1. SCOPE

1.1 This specification covers requirements, quality assurance provisions, and the preparation for delivery criteria for one type of cable entitled Cables W2-H, W3-H, W4-H, W6-H, W7-H, W8-HA and W20-H which are used in the Nike Hercules warhead section.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein:

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-810	- Environmental Test Methods.
MIL-STD-1168	- Lot Numbering of Ammunition.
MIL-STD-1169	- Packaging, Packing and Marking for Shipment of Inert Ammunition Components.
MIL-STD-1460	- Soldering of Electrical Connections and Printed Wiring Assemblies, Procedure For.

DRAWINGS

ORDNANCE CORPS

8785761 - Cable Assembly W7-H.
8785789 - Cable Assembly W2-H.
8785790 - Cable Assembly W3-H.
8785791 - Cable Assembly W4-H.
8785894 - Cable Assembly W6-H.
8804182 - Cable Assembly W20-H.
EL-8817196 - Equipment Lists.
8826747 - Cable Assembly W8-HA.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:06Z
Check the source to verify that this is the current version before use.

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Materials. The contractor shall furnish objective evidence (see 6.2) that the material complies with the specifications listed on the applicable drawing.

3.2 Assembly. The cable assemblies shall comply with all requirements specified on the drawing (dwg) 8785761, 8785789, 8785790, 8785791, 8785894,8804182 and 8826747, with all requirements specified herein, and with the requirements of all applicable specifications to the extent specified on the drawing and herein.

3.3 First article testing. Requirements for the submission of first article samples by the contractor shall be as specified in the contract (see 4.2).

3.4 Continuity. The cable assembly shall exhibit point-to-point continuity as indicated on applicable drawing when tested as specified in 4.4.1.

3.5 Insulation resistance. The insulation resistance between electrically isolated wires and between ungrounded wires and the connector shells shall be not less than 20 megohms when a direct current (dc) potential of 500 plus or minus (+) 50 volts is applied as specified in 4.4.2.

3.6 Environmental testing. The cable assemblies shall comply with MIL-STD-810, visual inspection and failure criteria, section 3. The cable assemblies shall also comply with 3.4 and 3.5 before and after each environmental test. Testing shall be as specified in 4.4.3. Tests shall be conducted in the order specified.

3.6.1 High temperature. The cable assemblies shall comply with the requirements of 3.4 and 3.5 at high temperature. After completion of the test, the cable shall show no evidence of deterioration or damage such as obliterated marking; embrittled, distorted, cracked, chipped, peeled, swollen, or eroded components; or fail to comply with the requirements of 3.4 and 3.5 when tested as specified in 4.4.3.1.

3.6.2 Low temperature. The cable assemblies shall comply with the requirements of 3.4 and 3.5 at low temperature. After completion of test, the cable shall show no evidence of deterioration or damage such as obliterated markings; embrittled, distorted, cracked, chipped, peeled, swollen, or eroded components; or fail to comply with the requirements of 3.4 and 3.5 when tested as specified in 4.4.3.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:06Z
Check the source to verify that this is the current version before use.

3.7 Soldering. All soldering shall comply with the requirements specified in MIL-STD-1460.

3.8 Workmanship.

3.8.1 Plastic and metal characteristics. All components shall be free from cracks, splits, cold flow, shrinkage, cold shuts, inclusions, porosity, or any similar characteristic.

3.8.2 Threads. Threads shall be full and undamaged for the entire minimum length or depth as required on the applicable drawing.

3.8.3 Burrs. Parts shall be free from burrs.

3.8.4 Foreign matter. Parts shall be free from chips, dirt, grease, rust, corrosion, or any embedded foreign material.

3.8.5 Cleaning. The cleaning method shall not be injurious to any of the parts, nor shall the parts be contaminated by the cleaning agent.

3.8.6 Electrical. Cable assemblies and wires shall be dressed in such a manner as to prevent pinching or chafing of the wire insulation. Ends of wires shall be free from burrs, sharp edges, or points. All parts shall be free from flux, chips, dirt, grease, rust or foreign material.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 First article inspection.

4.2.1 Quantity to be submitted. When the contract requires first article inspection, the contractor shall submit 3 complete assemblies (see dwg 8785761, 8785789, 8785790, 8785791, 8785894, 8804182 and 8826747) for first article testing to the testing facility designated in the invitation for bids or request for proposal.

4.2.2 Inspection and testing to be performed. The first article inspection sample shall be subjected to the inspections and tests specified in Table I. Tests shall be conducted in order specified in Table I.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:06Z
Check the source to verify that this is the current version before use.

Table I
First article inspection and tests

Inspection or Test	Dest	Non Dest
1. Classification of characteristics (see 4.3.2.1)		X
2. Continuity (see 3.4)		X
3. Insulation resistance (see 3.5)		X
4. High temperature (see 3.6.1)		X
5. Low temperature (see 3.6.2)		X

4.2.3 Inspection equipment. The inspection and testing specified in 4.2.2 shall be accomplished by using the gages and test equipment specified in 4.3.4.1.

4.2.4 Rejection. If any item fails to comply with any of the applicable requirements, the first article sample shall be rejected.

4.3 Quality conformance inspection.

4.3.1 Lot formation.

4.3.1.1 Production lot. A lot shall consist of parts and assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision. Drawing, specification and process changes not affecting safety, performance, storage, or interchangeability, as determined by the Government, shall not necessitate changing the lot interfix number. The criteria and procedures for the assignment of lot numbers shall be in accordance with MIL-STD-1168.

4.3.1.2 Inspection lot. A lot or batch and its formation, size, and presentation is described in MIL-STD-105, Section 5. Accordingly, a lot shall mean an inspection lot and a batch shall mean an inspection batch for the purpose of this specification. The manner in which each inspection lot or batch is to be presented and identified by the contractor, shall be designated or approved by the Government representative.

4.3.2 Product inspection examination. A sample shall be selected at random from each inspection lot in accordance with the applicable major or minor characteristic table (see Table II and Table III), and inspected for all characteristics in the applicable classification. Any characteristics in the sample found to be defective shall reject the inspection lot. Sequence for the inspection of characteristics in each classification need not be followed as long as all characteristic inspections are performed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:06Z
Check the source to verify that this is the current version before use.

Table II
Major Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-72	all	140-141	124	256-259	177	541-549	230
73	72	142	125	260-262	178	550-559	231
74	73	143-144	126	263-265	179	560-569	232
75	74	145	127	266-268	180	570-579	233
76	75	146-147	128	269-271	181	580-590	234
77	76	148-149	129	272-275	182	591-601	235
78	77	150	130	276-278	183	602-613	236
79	78	151-152	131	279-282	184	614-625	237
80	79	153-154	132	283-285	185	626-637	238
81-82	80	155-156	133	286-289	186	638-649	239
83	81	157	134	290-293	187	650-662	240
84	82	158-159	135	294-296	188	663-676	241
85	83	160-161	136	297-300	189	677-690	242
86	84	162-163	137	301-304	190	691-704	243
87	85	164-165	138	305-308	191	705-719	244
88-89	86	166-167	139	309-312	192	720-735	245
90	87	168	140	313-316	193	736-751	246
91	88	169-170	141	317-320	194	752-768	247
92	89	171-172	142	321-324	195	769-785	248
93	90	173-174	143	325-329	196	786-804	249
94-95	91	175-176	144	330-333	197	805-823	250
96	92	177-178	145	334-338	198	824-842	251
97	93	179-180	146	339-342	199	843-863	252
98	94	181-182	147	343-347	200	864-884	253
99-100	95	183-184	148	348-352	201	885-907	254
101	96	185-187	149	353-356	202	908-930	255
102	97	188-189	150	357-361	203	931-955	256
103	98	190-191	151	362-366	204	956-981	257
104-105	99	192-193	152	367-372	205	982-1008	258
106	100	194-195	153	373-377	206	1009-1036	259
107	101	196-197	154	378-382	207	1037-1066	260
108-109	102	198-200	155	383-388	208	1067-1098	261
110	103	201-202	156	389-393	209	1099-1131	262
111	104	203-204	157	394-399	210	1132-1166	263
112-113	105	205-207	158	400-405	211	1167-1204	264
114	106	208-209	159	406-411	212	1205-1243	265
115	107	210-212	160	412-417	213	1244-1285	266
116-117	108	213-214	161	418-424	214	1286-1330	267
118	109	215-217	162	425-430	215	1331-1378	268
119	110	218-219	163	431-437	216	1379-1429	269
120-121	111	220-222	164	438-443	217	1430-1483	270
122	112	223-224	165	444-450	218	1484-1542	271
123-124	113	225-227	166	451-457	219	1543-1605	272
125	114	228-230	167	458-465	220	1606-1673	273
126-127	115	231-232	168	466-472	221	1674-1747	274
128	116	233-235	169	473-480	222	1748-1827	275
129-130	117	236-238	170	481-488	223	1828-1914	276
131	118	239-241	171	489-496	224	1915-2010	277
132-133	119	242-243	172	497-504	225	2011-2115	278
134	120	244-246	173	505-513	226	2116-2232	279
135-136	121	247-249	174	514-521	227	2233-2361	280
137	122	250-252	175	522-530	228	over 2361	298
138-139	123	253-255	176	531-540	229		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:06Z
Check the source to verify that this is the current version before use.

Table III
Minor Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-16	all	28-29	23	52-56	31	132-156	39
17	16	30-31	24	57-62	32	157-191	40
18	17	32-34	25	63-69	33	192-244	41
19-20	18	35-36	26	70-76	34	245-334	42
21	19	37-40	27	77-86	35	335-519	43
22-23	20	41-43	28	87-97	36	520-1120	44
24-25	21	44-47	29	98-112	37	over 1120	45
26-27	22	48-51	30	113-131	38		

4.3.2.1 Classification of characteristics (see 3.2). Critical, major and minor characteristics are defined in MIL-STD-105. Inspection shall be conducted as follows:

4.3.2.1.1 Assembly prior to insulating the soldered connections and assembling the adapters (see dwg 8785761, 8785789, 8785790, 8785791, 8785894, 8826747, and 8804182).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Improper stripping of wire	Visual
	102. Improper soldering (see 3.9)	Visual
	103. Objective evidence relating to material missing or improper (see 3.1)	Visual
Minor:		
	201. Evidence of poor workmanship (see 3.7)	Visual

4.3.2.1.2 Assembly prior to securing connectors and cable clamp adapters (see dwg 8785761, 8785789, 8785790,8785791, 8785894, 8826747, and 8804182).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Torn or damaged insulating sleeving	Visual
	102. Loose insulating sleeving	visual/Manual
	103. Objective evidence relating to material missing or improper (see 3.1)	Visual
Minor:		
	201. Protective coating damaged to the extent of exposing base metal	Visual
	202. Evidence of poor workmanship (see 3.8)	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:06Z
Check the source to verify that this is the current version before use.

4.3.2.1.3 Cable assemblies W2-H, W3-H, and W7-H (see dwgs 8785789, 8785790, and 8785761).

Categories		Characteristics	Method of Inspection
Critical:		None defined.	
Major:			
	101.	Total length, min	Gage
	102.	Marking missing, incorrect, or unidentifiable	Visual
	103.	Connector pin bent	Visual
	104.	Torn or split insulating sleeving	Visual
	105.	Any identification tape improperly located	Visual
	106.	Cable clamp loose	Visual/Manual
	107.	Any component loose or missing	Visual/Manual
	108.	Solder loose, inadequate, or cold solder joint (see 3.7)	Visual
	109.	Coupling ring missing or damaged	Visual
	*110.	Height of pin(s) (pins of the same diameter must all appear to be within 1/16 inch in height relative to adjacent pins)	Visual/Gage
	**111.	Depth of socket(s) (female sockets of the same diameter must all appear to be within 1/16 inch in height relative to adjacent pins)	Visual/Gage
	112.	Objective evidence relating to material missing or improper (see 3.1)	Visual

*In the event pin(s) do not appear to be within 1/16 inch in height relative to the adjacent pins, Gage (see 4.3.4) shall be used to determine the variation from the normal height. Reject any pin that varies by more than 0.063 inch max. from the normal pin height of the individual connector. The normal height of the individual connector pins shall be determined by calculating the average height from measurements taken of pins adjacent to the pin that appears to be defective. The forward metal edge of the connector shall be utilized as the reference surface of all measurements of pin heights.

**In the event socket inserts do not appear to be within 1/16 inch in depth relative to the adjacent socket, Gage (see 4.3.4) shall be used to determine the variation from the normal depth. Reject any insert that varies by more than 0.063 inch max. from the normal socket insert depth of the individual connector. The normal depth of the individual connector sockets shall be determined by calculating the average depth

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:06Z
Check the source to verify that this is the current version before use.

from measurements taken of sockets adjacent to the socket that appears to be defective. The forward edge of the connector insert shall be utilized as the reference surface for all measurements of socket depths.

Minor:

201. Evidence of poor workmanship (see 3.8).Visual

4.3.2.1.4 Cable assembly W8-HA (see dwg 8826747).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
101.	Distance from P2 and P3 cable junction to end of P2 connector, min.	Gage
102.	Distance from P2 and P3 cable junction to end of P3 connector, min.	Gage
103.	Total length, min.	Gage
104.	Marking missing, incorrect, or unidentifiable.	Visual
105.	Connector pin bent.	Visual
106.	Torn or split insulating sleeving.	Visual
107.	Any identification tape improperly located.	Visual
108.	Cable clamp loose.	Visual/Manual
109.	Any component loose or missing.	Visual/Manual
110.	Solder loose, inadequate, or cold solder joint.	Visual
*111.	Height of pin(s) (pins of the same diameter must all appear to be within 1/16 inch in height relative to adjacent pins).	Visual/Gage
**112.	Depth of socket(s) (female sockets of the same diameter must all appear to be within 1/16 inch in height relative to adjacent pins).	Visual/Gage
113.	Objective evidence relating to material missing or improper (see 3.1).	Visual

*In the event pin(s) do not appear to be within 1/16 inch in height relative to the adjacent pins, Gage (see 4.3.4) shall be used to determine the variation from the normal height. Reject any pin that varies by more than 0.063 inch max. from the normal pin height of the individual connector. The normal height of the individual connector pins shall be determined by calculating the average height from measurements taken of pins adjacent to the pin that appears to be defective.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:06Z
Check the source to verify that this is the current version before use.

The forward metal edge of the connector shall be utilized as the reference surface of all measurements of pin heights.

**In the event socket inserts do not appear to be within 1/16 inch in depth relative to the adjacent socket, Gage (see 4.3.4) shall be used to determine the variation from the normal depth. Reject any insert that varies by more than 0.063 inch max. from the normal socket insert depth of the individual connector. The normal depth of the individual connector sockets shall be determined by calculating the average depth from measurements taken of sockets adjacent to the socket that appears to be defective. The forward edge of the connector insert shall be utilized as the reference surface for all measurements of socket depths.

Minor:
201. Evidence of poor workmanship (see 3.8).Visual

4.3.2.1.5 Cable assemblies W4-H, W6-H, and W20-H (see dwgs 8785791, 8785894, and 8804182).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
101.	Distance from P1 and P2 cable junction to end of P1 connector, min.	Gage
102.	Distance from P1 and P2 cable junction to end of P2 connector, min.	Gage
103.	Distance from P3 and P4 cable junction to end of P3 connector, min.	Gage
104.	Distance from P3 and P4 cable junction to end of P4 connector, min.	Gage
105.	Total length, min.	Gage
106.	Marking missing, incorrect, or unidentifiable.	Visual
107.	Connector pin bent.	Visual
108.	Torn or split insulating sleeving.	Visual
109.	Any identification tape improperly located.	Visual
110.	Cable clamp loose.	Visual/Manual
111.	Any component loose or missing.	Visual/Manual
112.	Solder loose, inadequate, or cold solder joint (see 3.7).	Visual
*113.	Height of pin(s) (pins of the same diameter must all appear to be within 1/16 inch in height relative to adjacent pins).	Visual/Gage

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:06Z
Check the source to verify that this is the current version before use.

**114. Depth of socket(s) (female sockets of the same diameter must all appear to be within 1/16 inch in height relative to adjacent pins).....Visual/Gage

115. Objective evidence relating to material missing or improper (see 3.1).....Visual

*In the event pin(s) do not appear to be within 1/16 inch in height relative to the adjacent pins, Gage (see 4.3.4) shall be used to determine the variation from the normal height. Reject any pin that varies by more than 0.063 inch max. from the normal pin height of the individual connector. The normal height of the individual connector pins shall be determined by calculating the average height from measurements taken of pins adjacent to the pin that appears to be defective. The forward metal edge of the connector shall be utilized as the reference surface of all measurements of pin heights.

**In the event socket inserts do not appear to be within 1/16 inch in depth relative to the adjacent socket, Gage (see 4.3.4) shall be used to determine the variation from the normal depth. Reject any insert that varies by more than 0.063 inch max. from the normal socket insert depth of the individual connector. The normal depth of the individual connector sockets shall be determined by calculating the average depth from measurements taken of sockets adjacent to the socket that appears to be defective. The forward edge of the connector insert shall be utilized as the reference surface for all measurements of socket depths.

Minor:

201. Evidence of poor workmanship (see 3.8).Visual

4.3.2.1.6 Preparation for delivery (see 5).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Preservation, packing, and packaging not in accordance with MIL-STD-1169	Visual
	102. Marking not in accordance with MIL-STD-1169	Visual
Minor:		
	201. Evidence of poor workmanship (see 3.8)	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:06Z
Check the source to verify that this is the current version before use.

4.3.3 Testing. All tests shall be performed. Tests shall be performed in the order specified below:

Test	Test Classification
a. Continuity	Major
b. Insulation resistance	Major
c. High temperature	Major
d. Low temperature	Major

None of these tests are considered destructive and samples so tested may be returned to the lot.

4.3.3.1 Continuity and insulation resistance. Each cable assembly shall be tested in accordance with 4.4.1 and 4.4.2. If any item fails to comply with 3.4 and 3.5, the item shall be rejected and removed from the lot.

4.3.3.2 High temperature and low temperature. A sample shall be selected at random in accordance with Table IV. The sample shall be tested in accordance with 4.4.3.1 and 4.4.3.2. If any item fails to comply with 3.6.1 and 3.6.2, the lot shall be rejected.

Table IV
Sample sizes for non-destructive testing

Lot Size	Sample Size
2-8	1
9-15	2
16-25	3
26-40	5
41-65	8
66-110	13
111-180	22
181-300	36
301 and over	MIL-STD-105(AQL 0.25 percent)

4.3.4 Acceptance inspection equipment.

4.3.4.1 Major characteristics and tests. Inspection and testing shall be performed with the acceptance inspection equipment, operating instructions, and calibration instructions specified on the Equipment Lists (EL) (see EL-8817196). When either of the conditions listed below exist, the contractor shall design required equipment or specify suitable commercial equipment and obtain approval prior to use on the contract.

a. Any deviation from equipment or procedures specified on the EL is desired (see 6.3).
b. The code "CD" is listed in the "Part or Identifying Number" column on the EL (see 6.1.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:06Z
Check the source to verify that this is the current version before use.

4.3.4.2 Minor characteristics and tests. Acceptance inspection equipment for minor characteristics is not specified on ELs. The acceptance inspection equipment, operating instructions and calibration instructions used by the contractor for minor classification inspection shall be approved by the Government representative authorized by the procuring agency.

4.4 Test methods. The tolerances specified herein are absolute with no allowance for test equipment inaccuracy. The tolerances used by the manufacturer shall be equal to the absolute tolerances less the accuracy tolerances of the test equipment used.

4.4.1 Continuity. Each conductor of each assembly shall be tested for continuity and correct connections between its terminations, using a potential of not more than 6 volts. A suitable indicator such as a flashlight bulb shall be placed in the circuit. The continuity tests shall be made in accordance with the applicable cable assembly schematic drawing.

4.4.2 Insulation resistance. Apply 500 ± 50 volts between all ungrounded wires and the connector shells utilizing an insulation tester having a direct reading scale in megohms.

4.4.3 Environmental testing (see 3.6).

4.4.3.1 High temperature. The cable shall be placed in a test chamber with the electrical circuits made externally available through appropriate electrical cabling. The temperature within the chamber shall be raised to 165 ± 2 degrees Fahrenheit (°F) and maintained at that level unitl the cable has stabilized at this temperature (see 6.4). Stabilization shall be determined by an appropriate thermal device in direct contact with the cable. After temperature stabilization, the cable shall be tested as specified in 4.4.1 and 4.4.2. The temperature in the chamber shall then be reduced to ambient room temperature. This may be accomplished by discontinuing the chamber heating, opening the chamber doors, and carefully removing the plate from the chamber thus permitting the cable to be bathed by the surrounding ambient room temperature. No forced cooling shall be employed, such as directing air on the cable by means of a fan or placing the cable in refrigerated air. Upon return to ambient room temperature, the cable shall be visually and manually examined and then tested as specified in 4.4.1 and 4.4.2.

4.4.3.2 Low temperature. The cables shall be tested as specified in 4.4.3.1, except that the chamber temperature shall be reduced to -65 ± 2°F before starting the test. No forced warming, such as directing warm air on the cable by means of a fan or placing the cable in warmed air, shall be used in returning the cable to ambient room temperature. Upon return to ambient room temperature, the cable shall be visually and manually examined and then tested as specified in 4.4.1 and 4.4.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:06Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging. Preservation and packaging shall be level A or C as specified (see 6.1).

5.1.1 Level A. The cable assemblies shall be preserved and packaged in accordance with instructions contained in MIL-STD-1169(MU).

5.1.2 Level C. The cable assemblies shall be preserved and packaged in accordance with instructions contained in MIL-STD-1169(MU).

5.2 Packing.

5.2.1 Levels A and C. The cable assemblies shall be packed in accordance with the applicable instructions contained in MIL-STD-1169(MU).

5.3 Marking. Marking shall be in accordance with MIL-STD-1169(MU).

6. NOTES

6.1 Ordering data. Procurement documents should specify the following:

6.1.1 Procurement requirements.

a. Title, number, and date of this specification.

b. Selection of applicable level of packaging and packing required (see 5.1 and 5.2).

6.1.2 Contract data requirements (see 4.3.4.1). Data specified in 4.3.4.1 will be delivered as identified on a numbered DD Form 1664 when required on a DD Form 1423 incorporated in the contract.

6.2 Objective evidence. Records of contractor quality control and inspections which can be verified.

6.3 Acceptance inspection equipment (see 4.3.4.1). The contractor shall obtain approval from the Commander, Picatinny Arsenal, Dover, New Jersey 07801, ATTN: SARPA-QA-T.

6.4 Temperature stabilization. The temperature is considered stabilized when the greatest peaks (both highest and lowest) continually observed over 5 minutes min. do not exceed the nominal temperature plus tolerance specified.

6.5 Supersession data. This specification supersedes the requirements of Purchase Description PA-PD-1411 Revision 2 dated 12 October 1962.

Custodian:
Army - PA

Preparing activity:
Army - PA

Project No. 1190-A088

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:06Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426 REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:06Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY
DOD – 314



OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

COMMANDER
Picatinny Arsenal
ATTN: SARPA-QA-N-Q
Dover, New Jersey 07801

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:06Z
Check the source to verify that this is the current version before use.