MIL-D-46688A(MU)
30 APRIL 1965
SUPERSEDING
MIL-D-46688 (Ord)
13 AUGUST 1962

MILITARY SPECIFICATION

DEMOLITION KIT, PROJECTED CHARGE, M173, AND PRACTICE, M174 LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers quality assurance requirements, and special requirements not covered by the drawings, pertaining to the loading and assembling of one type of mine clearing device designated as Demolition Kit, Projected Charge, M173 or Practice, M174.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 — Ammunition and Special Weapons; General Specification for.

MIL-I-45607 — Inspection Equipment, Supply and Maintenance of.

STANDARDS

MILITARY

MIL-STD-105 — Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105).

MIL-STD-109 — Quality Assurance Terms and Definitions.

MIL-STD-129 — Marking for Shipment and Storage.

MIL-STD-1167 — Ammunition Data Cards.

MIL-STD-1235 — Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes.

DRAWINGS

ORDNANCE CORPS

8846706 — Demolition Kit, Projected Charge, M173 and Demolition Kit, Projected Charge, Practice, M174, Marking and Packing Assembly.

FSC 1375

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:41Z
Check the source to verify that this is the current version before use.

8846709 — Demolition Kit, Projected Charge, M173 and Demolition Kit, Projected Charge, Practice, Loading Assembly.

PUBLICATIONS

Department of the Army Technical Manual—Demolition Kit, Projected Charge, M173 and Demolition Kit, Projected Charge, Practice, M174, TM9–1375–202–10.

ORDNANCE CORPS

IEL–8846709 — Index of Inspection Equipment Lists.

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Material. Materials and parts shall be in accordance with applicable drawings and specifications.

3.2 Demolition kits. The demolition kits shall comply with all requirements specified on Drawings (dwgs.) 8846706, and 8846709 and with all requirements specified in applicable specifications.

3.3 Electrical continuity of tow cable release assembly. The electrical resistance of the assembly, to evidence acceptable continuity, shall be 500 to 5,000 ohms when a current limited to 60 microampères, maximum, is applied between the contacts of the electrical connector.

3.4 Functioning. The Demolition Kit, Projected Charge, M173 and Practice, M174 shall be capable of performing the following sequence of operating functions when connected to an energy source of 24 volts D.C. and actuated by the firing control switch.

3.4.1 Firing control switch. The firing control switch, when indexed, shall be capable of electrically initiating the demolition kit through the proper sequence of functional operations.

3.4.1.1 *Tow 1 position.* Indexing to this position, shall cause the explosive bellows motors (T5E1) to function or detonate and electrically release the mechanical coupling from the towing vehicle, but leaving the electrical cable still connected.

3.4.1.2 *Electrical cable reel.* The 250 foot electrical cable shall be capable of being payed out of the cable reel, without fouling, being cut or damaged.

3.4.1.3 *Lid 2 position.* Indexing to this position shall cause the XM24 Thruster to function and fire, automatically removing the main cover and exposing the jato and line charge compartments, raising the launcher tube to the preset elevation and electrically closing the circuit.

3.4.1.4 *Jato 3 position.* Indexing to this position shall function and fire the Rocket Motor, M95, which shall be expelled, when the restraining screw breaks, pulling the linear demolition charge over the (mine) field along the target path, automatically arming the attached fuze and being halted by the nylon arresting cable attached to the hull. The jato shall come to a rest on the ground a minimum of 360 feet from the front bow of the M3 Skid. There shall be no damage or breakage to the nylon arresting cable or inert lined charge.

3.4.1.5 *Charge 4 position.* Indexing to this position shall function and detonate the Fuze, M1134 (M173) or simulate detonation of inert Fuze T1302E1 (M174), firing the linear charge (H.E.M96) or simulating firing of inert linear charge (M97).

3.4.2 *Propagation and crater.* The Demolition Kit, M173 shall, when operated and functioned in the sequence, as specified in 3.4.1, be capable of detonating and propa-

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:41Z
Check the source to verify that this is the current version before use.

gating completely the Linear Demolition Charge (H.E.M96) and creating a crater or clearing a path along the target path or (mine) field, which shall extend for a minimum length of 270 feet, starting at a minimum distance of 80 feet from the front of the M3 Skid.

3.5 Workmanship. Loading and assembling shall be accomplished in a thorough workmanlike manner. All parts and assemblies shall be free of dirt, grease, rust, corrosion products and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. Surface coatings on metal shall be continuous except for a few light scratches not exposing base material. All required marking shall be neat and sharply defined.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL–STD–109 in order to define terms used herein. The provisions of MIL–A–2550 shall apply.

4.1.1 *Submission of product.* At the time the completed lot of product is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

(a) A statement that the lot complies with all quality assurance provisions specified within this specification.

(b) Number of units of product inspected.

(c) Results obtained, by defect code, for all inspection performed.

(d) Drawing, specification number and date, together with an identification and date of changes.

(e) Statement of findings on all material purchased by the contractor when such material is controlled by the Government specifications referenced in any of the contractual documents.

(f) Number of items in the lot.

(g) Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agen't authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.2 *Government verification.* Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.1.3 *Production sample test.* After ac-

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:41Z
Check the source to verify that this is the current version before use.

ceptance of the initial production sample and at any time during the production of the first 100 demolition kits, the Government inspector shall select at random a demolition kit from any production lot for testing in accordance with the provisions of 4.2.2. The tests shall be performed at a Government-approved facility as designated by the contracting officer (see 6.4). The comparison tests will be performed to the extent necessary to conform the qualitative conformance of the various materials, items and components used in the production of the end item, the continued compliance of the production items with the applicable requirements relative to inter-changeability, functionability and design adequacy status of the demolition kit.

4.2 Initial Production Inspection.

4.2.1 *Submission.* Prior to the start of production, the contractor shall submit an initial production sample to a Government-approved facility as designated by the contracting officer (see 6.4) for inspection and testing in accordance with the provisions of 4.2.2. The initial production sample shall consist of one of each complete marked and packaged Demolition Kit, Projected Charge, which have been produced by the contractor or furnished by a supplier in accordance with the contractual documents and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same source of supply as will be used in regular production. The sample shall be accompanied by statements of findings for material. An initial production sample, or portion thereof, as directed by the contracting officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply such as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the contracting officer.

4.2.2 *Inspections to be performed.* Assemblies and components will be subjected by the Government to any or all of the examinations and tests specified in 4.3.2 and 4.3.3.1 of this specification and for any or all of the requirements specified in the applicable drawings.

4.2.3 *Rejection.* If any assembly or component fails to comply with any of the applicable requirements, the initial production sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new initial production sample, or portion thereof. Until an initial production sample is accepted, the contractor is, in no way, authorized by the Government to initiate regular production unless otherwise directed by the contracting officer.

4.3 Inspection Provisions.

4.3.1 *Lot formation.* A lot shall consist of demolition kits produced by one manufacturer in one unchanged process, in accordance with the same drawing revision, same specification and same specification revision. Drawing, specification, and process changes not affecting safety, performance or fit, as determined by the Government shall not necessitate changing the lot interfix number. Each lot shall contain—

(a) Launching skids from lots of the same lot interfix number from one manufacturer.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:41Z
Check the source to verify that this is the current version before use.

(b) Linear charges from lots of the same lot interfix number from one manufacturer.

(c) Rocket motors from lots of the same lot interfix number from one manufacturer.

(d) Thruster assemblies from lots of the same lot interfix number from one manufacturer.

(e) Bellows motors, from lots of the same lot interfix number from one manufacturer.

(f) Igniter assemblies, from lots of the same lot interfix number from one manufacturer.

(g) Fuze a ssemblies, from lots of the same lot interfix number from one manufacturer.

4.3.2 *Examination.* Sampling plans and procedures for the following classifications of defects, shall be in accordance with MIL–STD–105 (ABC–STD–105) except that inspection for critical defects, when listed, shall be 100 percent. Continuous sampling plans in accordance with MIL–STD–1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Launching skid, prior to assembling charge (see dwg. 8846713 covering a detail of dwg. 8846709).

Categories	*Defects*	*Method of inspection*	*Code No. (see 6.2)*
Critical: None defined			
Major:	AQL 1.0 percent		
101.	Kinks in rope	Visual	01001
102.	Rope coiled improperly	Visual	01002
103.	Electric plug, not connected	Visual	01003
104.	Component or assembly missing or improperly assembled	Visual	01004
105.	Control switch or circuits improperly assembled or wired	Visual	01005
106.	Desiccant omitted or not as specified	Visual	01006
Minor:	AQL 1.5 percent		
201.	Protective coating omitted or improper	Visual	01007
202.	Foreign matter, inside	Visual	01008
203.	Evidence of poor workmanship, (see 3.5)	Visual	01009

4.3.2.2 Demolition Kit, after faking first layer of charge (see dwg. 8846709).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:			
1.	Linear charge improper type	Visual	02001
Major:	AQL 1.0 percent		
101.	Relay position in fuze connector	Gage	02002
102.	Component or assembly missing	Visual	02003
103.	Component or assembly, connected or assembled improperly	Visual	02004
104.	Faking of first layer improper	Visual	02005
105.	Slack, improper on line charge	Visual	02006
106.	Slack, improper on arresting cable	Visual	02007
107.	Fuze connector and charge not assembled	Visual	02008
Minor: None defined			

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:41Z
Check the source to verify that this is the current version before use.

4.3.2.3 Demolition Kit, during faking of charge (see dwg. 8846709).

Categories	Defects	Method of inspection	Code No.
Critical: None defined			
Major:	AQL 0.65 percent		
101.	Stowage pattern, improper	Visual	03001
102.	Arresting cable, improperly assembled	Visual	03002
103.	Component, assembly or tools missing or improperly assembled	Visual	03003
104.	Wiring or connections improper	Visual-Manual	03004
Minor:	AQL 1.0 percent		
201.	Foreign matter present	Visual	03005
202.	Evidence of poor workmanship (see 3.5)	Visual	03006

4.3.2.4 Demolition Kit, prior to assembly of cover (see dwg. 8846709).

Categories	Defects	Method of inspection	Code No.
Critical: None defined			
Major:	AQL 1.00 percent		
101.	Charge above cover mating surface	Gage	04001
102.	Pick up cable not attached	Visual	04002
103.	Insufficient slack in pick up cable at rocket motor	Visual	04003
104.	Insufficient slack in electrical lead to launcher	Visual	04004
105.	Launcher elevation setting improper	Visual	04005
106.	Fuze type improper	Visual	04006
107.	Color coding of skid improper for charge	Visual	04007
108.	Foreign matter inside	Visual	04008
109.	Cover removal rocker or other component missing or insecure	Visual-Manual	04009
110.	Rocket motor restraining screw missing or loose	Visual-Manual	04010
Minor:	AQL 1.50 percent		
201.	Clearance of bolt head at rocket nose, maximum	Gage	04011
202.	Lubricant missing from cover seal	Visual	04012
203.	Evidence of poor workmanship, (see 3.5)	Visual	04013

4.3.2.5 Demolition Kit, prior to assembly of aft strap (see dwg. 8846709 and 8846713).

Categories	Defects	Method of inspection	Code No.
Critical: None defined			
Major:	AQL 0.65 percent		
101.	Component missing	Visual	05001
102.	Less desiccant than required or improperly distributed	Visual	05002
103.	Cover lock does not engage	Manual	05003
Minor: None defined			

4.3.2.6 Demolition Kit (see dwg. 8846706).

Categories	Defects	Method of inspection	Code No.
Critical: None defined			
Major:	AQL 1.0 percent		
101.	Serial numbers of covers and skid do not match	Visual	06001

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:41Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of inspection	Code No.
102.	Tape missing or improperly applied	Visual	06002
103.	Color stripe missing (when applicable)	Visual	06003
104.	Cover fails to lock	Manual	06004
105.	Strapping, wood skid, pallet or cross blocking missing, loose or broken	Visual-Manual	06005
106.	Pad on thruster guide missing or insecure	Visual-Manual	06006
Minor:	AQL 1.5 percent		
201.	Car seal missing or improperly applied	Visual	06007
202.	Marking missing, misleading or unidentifiable	Visual	06008
203.	Evidence of poor workmanship, (see 3.5)	Visual	06009

4.3.3 *Testing.*

4.3.3.1 *Initial production (see 4.2.1)—selected production sample (see 4.1.3).* The entire sample submitted as the initial production quantity or production sample shall be tested as specified herein, in accordance with 4.2.2. Rejection and resubmission shall be in accordance with 4.2.3.

4.3.3.1.1 Electrical continuity of tow cable release assembly (see 3.3)—Code No. 07001.

4.3.3.1.2 Functioning (see 3.4 and 4.4.2).

4.3.3.1.2.1 Fire control switch (see 3.4.1) —Code No. 08001.

4.3.3.1.2.2 Tow 1 position (see 3.4.1.1)— Code No. 08002.

4.3.3.1.2.3 Electrical cable reel (see 3.4.1.2)—Code No. 08003.

4.3.3.1.2.4 Lid 2 position (see 3.4.1.3)— Code No. 08004.

4.3.3.1.2.5 Jato 3 position (see 3.4.1.4)— Code No. 08005.

4.3.3.1.2.6 Charge 4 position (see 3.4.1.5) —Code No. 08006.

4.3.3.1.2.7 Propagation and crater (see 3.4.2)—Code No. 09001.

4.3.3.2 *Production testing.*

4.3.3.2.1 *Electrical continuity of tow cable release assembly—(see 3.3)—Major defect —Code No. 07001.* This test shall be performed 100 percent using the applicable test equipment of 4.3.4 as specified in 4.4.1. Any assembly exhibiting a resistance outside the permitted range shall be classed defective and removed from the lot.

4.3.4 *Inspection Equipment.* Index of Inspection Equipment Number IEL-8846709 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 *Government rights to documentation.* Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawigs are needed.

4.3.4.2 *Supply and maintenance.* Supply and maintenance of the equipment listed on the IEL shall be in accordance with MIL-I-45607.

4.3.4.3 *Government use of contractor's in-*

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:41Z
Check the source to verify that this is the current version before use.

spection and test equipment. The contractor shall make available to the Government all inspection and test equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment, and verification of it's accuracy, shall be supplied by the contractor for the performance of examination or test by the Government.

4.4 Test methods and procedures.

4.4.1 *Electrical continuity of tow cable release assembly.* The applicable test equipment shall be connected to the contacts of the electrical connector, the required limited current applied and the resistance observed and recorded. Any assembly exhibiting a resistance outside the permitted range shall be classed defective.

4.4.2 *Functioning.* This test shall be performed at a designated Government Proving Ground. This test must be performed in accordance with instructions as contained in "Department of the Army Technical Manual for Demolition Kit, Projected Charge, M173 and Demolition Kit, Projected Charge, Practice, M174, TM 9–1375–202–10". Motion pictures shall be taken during all phases of this test using a minimum of three motion picture cameras, which shall be so placed, as to be capable of photographing as much detail as possible during the actual functioning operations of the demolition kit. If any assembly or component fails to comply with any of the applicable requirements, the sample shall be classed defective and shall not be returned to the lot. One or more defectives shall reject the lot. In the event of a defective, a still camera shall also be used to photograph said malfunction or failure.

5. PREPARATION FOR DELIVERY

5.1 Preservation, strapping, marking and packing. The kits shall be preserved, strapped, marked and packaged in accordance with dwg. 8846706.

5.2 Data cards. Data card information shall be as specified in MIL–STD–1167.

5.3 Shipping. When component parts from more than one lot are shipped as a carload, each lot shall be kept separate and the division between lots clearly indicated.

6. NOTES

6.1 Ordering data. Procurement documents shall specify title, number and date of this specification.

6.2 Inspection code numbers. The five digit code numbers assigned to the inspections herein are to facilitate future data colection and analysis by the Government.

6.3 *Inspection equipment.* The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 *Inspection equipment lists.* Inspection equipment lists indicate the availability of inspection equipment designs by showing in the number column of the list of inspection equipment (00 Form 1242–3) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 *Inspection equipment list codes.* The

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:41Z
Check the source to verify that this is the current version before use.

inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5 and 6.3.6 will be designed in the IEL by the following codes:

CDAF — Contractor's design responsibility on Army format in accordance with MIL–D–45608.

CDCF — Contractor's design responsibility on contractor format.

AD — Army design.

ADMU — Army design, mandatory for use.

CE — Commercial equipment.

SCD — Specification control drawing.

6.3.3 *Army designs.* Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and non-mandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 *Specification control drawing.* Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 *Commercial equipment.* Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 *Contractor designs.* Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification wil not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL–D–45608, and in addition, contain the detail and information specified above. Final approved contractor designs identified as CDCF shall be suitable for microfilming.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:41Z
Check the source to verify that this is the current version before use.

They must be non-reproducible diazo or electrostatic full size prints of top quality with black lines on white background, and shall provide a legible print produced via the 35MM microfilm process. The contractor shall submit one rolled or flat set copy of the final approved design.

6.3.7 *Submission of contractor designs.* Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

6.4 Submission of initial production samples. Instructions, as to the location for the evaluation of the Initial Production Sample and Selected Production Sample shall be obtained from the contracting officer. Upon receipt of such request, the contracting officer shall advise Picatinny Arsenal and instructions will be issued accordingly. All inquiries should be forwarded to: Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–NI.

Custodian:

Army—MU

Preparing activity:

Army—MU

Project No. 1375–A910

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:41Z
Check the source to verify that this is the current version before use.

To detach this form, cut along this line

SPECIFICATION ANALYSIS SHEET

Form Approved Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity.

SPECIFICATION

ORGANIZATION	CITY AND STATE

CONTRACT NO.	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT
		$

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES" IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)*	DATE

DD FORM 1426
1 APR 63

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:41Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE ARMY
PICATINNY ARSENAL
DOVER, NEW JERSEY 07801

OFFICIAL BUSINESS

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY

COMMANDING OFFICER
United States Army
Picatinny Arsenal
ATTN: SMUPA-ND
Dover, New Jersey 07801

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:41Z
Check the source to verify that this is the current version before use.