MIL-D-51083C
INTERIM AMENDMENT 5(EA)
23 June 1988
USED IN LIEU OF
AMENDMENT 4
19 September 1984

MILITARY SPECIFICATION

DETECTOR TICKET, ANTICHOLINESTERASE AGENT

This interim amendment is approved for use within U.S. Army Chemical Research, Development and Engineering Center, Department of the Army, with MIL-D-51083C, dated 29 December 1967.

PAGE 1

2.1, Under "DRAWINGS": Add the following drawing numbers and titles in sequence:

"IL136-41-780 - Dilution Apparatus, Q5, Single and Double Dilution
136-41-1520 - Portable Gas Generator, Q219"

PAGE 2

2.2:

Lines 8 and 9: Delete "202 Union Station, 516 West Jackson Boulevard" and substitute "Room 1106, 222 South Riverside Plaza".

Line 16: Delete "56" following "D1193".

PAGE 4

3.7: Add "and poor heat seals."

4.1.1: Delete in its entirety and substitute the following:

"4.1.1 Contractor's responsibility. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the

AMSC N/A FSC 6665

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:49Z
Check the source to verify that this is the current version before use.

right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements."

PAGE 6

4.3.3.3: Delete and subsitute the following:

"4.3.3.3 Classification of defects.

(a) Belts, detector ticket, assembly and detail (Dwg 5-77-808).

Categories		Defects
Critical:		None defined
Major:	AQL 1.0 percent defective	
101		Perforations incorrectly located
Minor:	AQL 2.5 percent defective	
201		Retaining ring not properly sealed (bulging)
202		Glass fiber disc incorrectly located
203		Incorrect number of tickets per belt
204		Incorrect marking
205		Workmanship (3.7)"

4.3.4, line 1: Following "ASTM D1193" add "type III".

PAGE 7

4.3.4.2(a), line 2: Delete "Dilution Apparatus, Toxic Gas, Q5" and substitute "Dilution Apparatus, Toxic Gas, Q5 (IL136-41-780) or Portable Gas Generator, Q219 (136-41-1520)".

PAGE 8

4.3.4.2(b)(1): Add "The Munsell color shall be read using a 7400°K light source in an enclosure having a neutral gray-colored interior."

4.3.4.2(b)(2): Add "The Munsell color shall be read using a 7400°K light source in an enclosure having a neutral gray-colored interior."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:49Z
Check the source to verify that this is the current version before use.

6.5: Delete this paragraph in its entirety.

Preparing activity:

Army - EA

Project No. 6665-A555

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:49Z
Check the source to verify that this is the current version before use.