MILITARY SPECIFICATION

PROJECTILE, 81MM, H.E., M374A1 METAL PARTS ASSEMBLY
(PEARLITIC MALLEABLE IRON)

This amendment forms a part of Military Specification MIL-P-50649(MU) dated 16 February 1970.

Paragraph 4.3.2.3 Delete in its entirety.

* Paragraph 4.3.2.5 for CRITICAL 1. under "Defect" column Line 3 Add "(internal)".
Paragraph 4.3.2.6 for MAJOR characteristic 114. Delete "or not full".

Paragraphs 4.3.2.7 and 4.3.2.8 Add "Drawing F7548319" to heading.

* Paragraph 4.3.3.4.1 after paragraph identification "Braze metal.-" Add "(external)"
* Add Paragraph 4.3.4.2.

"4.3.4.2 Production lot sample.-The quantity listed in Table II shall be ballistically tested in the phase indicated.

Table II

Phase	Quantity
Excess pressure	10 each lot"

Paragraphs 4.3.4.3 and 4.3.4.4 line 2 Delete "and II", line 4 Delete "or the production lot represented by the sample".

* Paragraph 4.3.4.3 line 2 Add "and II", line 4 Add "or the production lot represented by the sample". (Previously deleted by prior amendment)

* Paragraph 4.3.6 Delete in its entirety. (Added by prior amendment).

* Paragraph 4.4.4.3 Delete in its entirety and substitute:

"4.4.4.3 Excess pressure.-The samples supplied in accordance with Tables I and II, inert loaded to the service weight and dummy fuzed, will

Source: https://assist.dla.mil -- Downloaded: 202610-22T20:31Z
Check the source to verify that this is the current version before use.

4.4.4.3 (Cont'd)

be assembled into complete rounds and fired for recovery in a mortar for which the round is standard, the tube of which will have a minimum of 25 percent life remaining based on current mortar tube condemnation criteria. A propellant charge adjusted to produce 109 to 117 percent of the upper pressure limit of the propellant used with the applicable projectile. Photographic equipment will be set up near the muzzle to record the flight of the projectile to determine compliance with 3.7. After three (3) consecutive production lots have been tested successfully the excess pressure phase may be eliminated, however implementation of the excess pressure phase can be instituted whenever directed by procuring contracting officer ."

* Paragraph 4.4.7.2 line 2 Delete "and II".

* Paragraph 4.4.8 Delete in its entirety. (Added by prior amendment).

Paragraph 5.1 Add to end of sentence "and Drawing F7548319".

* The margins of this amendment are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to last previous issue.

Custodian

Army - MU

Preparing activity

Army - MU(FA)

Project No. 1315-A227

Source: https://assist.dla.mil -- Downloaded: 202610-22T20:31Z
Check the source to verify that this is the current version before use.