MIL-G-11164A (MU)
7 August 1967
SUPERSEDING
MIL-G-11164 (ORD)
21 May 1951

MILITARY SPECIFICATION

GRENADE, RIFLE, SMOKE, COLORED, M22A2 METAL PARTS FOR

1. SCOPE

1.1 This specification covers the inspection of the parts for one type of smoke rifle grenade designated as Grenade, Rifle, Smoke, Colored, M22A2.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 — Ammunition and Special Weapons; General Specification for

MIL-I-45607 — Inspection Equipment, Supply and Maintenance of

STANDARDS

FEDERAL

FED-STD-151 — Metals; Test Methods

MILITARY

MIL-STD-105 — Sampling Procedures and Tables for Inspection by Attributes (ABC - STD - 105)

MIL-STD-109 — Quality Assurance Terms and Definitions

MIL-STD-1168 — Lot Numbering of Ammunition

MIL-STD-1169 — Packaging, Packing, and Marking for Shipment of Inert Ammunition Components

MIL-STD-1235 — Single and Mutli-level Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U. S. ARMY MUNITIONS COMMAND

FSC: 1330

Source: https://assist.dla.mil -- Downloaded: 2026l0-17T15:30Z
Check the source to verify that this is the currentversion before use.

82–2–44 — Grenade, Rifle, Smoke, Metal Parts Arrangement and Details

82–1–78 — Stabilizer, Grenade, Rifle, Metal Parts, Assembly and Details

9216145 — Clip, Launcher Positioning

PUBLICATIONS

U. S. ARMY MUNITIONS COMMAND

IEL–7298722 — Index of Inspection Equipment

(Copies of specifications, standards, drawings and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Material. The materials and parts shall be in accordance with applicable drawings and specifications.

3.2 Metal parts assemblies. The metal parts assemblies shall comply with all requirements specified on Drawings (dwgs.) 82–2–44, 82–1–78, and 9216145 as applicable, and with all requirements specified in this and other referenced specifications.

3.3 Strength of stabilizer tube brazed joint. The brazed joint of the stabilizer tube and the fuze body shall not crack or show evidence of separation when tested as specified in 4.4.1.

3.4 Strength of stabilizer tube and fin assembly welds. The spot welds shall leave a button of fin material on the stabilizer tube, which is the thickness of the fin material and has an area at the base of at least one-half the area of the specified weld diameter, when tested as specified in 4.4.2.

3.5 Safety band assembly attachment. The sealing washer and disc on the safety band assembly shall provide a complete seal for the safety pin holes as evidenced by visible noticeable compression of the entire circumference of the washer and disc on attachment of the safety band assembly to the stabilizer assembly, and the lever of the safety band assembly shall snap back in place under its own tension when raised 3/16 of an inch. The test shall be performed as specified in 4.4.3.

3.6 Workmanship. All parts shall be fabricated and finished in a thorough, workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, unblended radii, surface defects, dirt, grease, rust, corrosion products and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. All required markings shall be neat and sharply defined.

3.7 First article inspection. This specification makes provisions for first article inspection. Requirements for the submission of first article samples by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL–STD–109 in order to define the terms used herein. The provisions of Specification MIL–A–2550 shall apply.

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:30Z
Check the source to verify that this is the current version before use.

4.1.1 *Submission of product.* At the time of the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all quality assurance provisions specified within this specification.

b. Number of units of product inspected.

c. Results obtained, by defect code, for all inspections performed.

d. Drawing, specification number and date, together with an identification and date of changes.

e. Certificates of conformance on all material purchased by the contractor when such material is controlled by Government or commercial specifications referenced in any of the contractual documents.

f. Number of items in the lot.

g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.2 *Government verification.* Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be performed to the extent necessary to assure inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 First article inspection.

4.2.1 *Submission.* The contractor shall submit a first article sample as designated by the contracting officer for evaluation in accordance with the provisions of 4.2.2. The first article sample shall consist of 25 assemblies and 25 complete sets of parts (i.e. 25 each of every component and every subassembly) which have been produced by the contractor or furnished by a supplier and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same source of supply as will be used in regular production. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample, including certificates of conformance for materials, (see 4.1.1e). A sample containing known defects will not be submitted unless specifically authorized, by the Contracting Officer. A first article sample, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days or whenever a change occurs in manufacturing process, material used, drawing or specification such as to significantly affect product uniformity as determined by the Government.

4.2.2 *Inspections to be performed.* Assemblies and components will be subjected by the Government to any or all of the examinations or tests specified in 4.3.2 and 4.3.3 of this specification and any or all requirements of the applicable drawings.

Source: https://assist.dla.mil -- Downloaded: 2026l0-17T15:30Z
Check the source to verify that this is the currentversion before use.

4.2.3 *Rejection.* If any assembly or component fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component to comply with any of the stated requirements.

4.3 Inspection provisions.

4.1.3 *Lot formation.* The term "lot" as used throughout this specification refers to an inspection lot, which is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance of the lot with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, specification, or revision thereof. Changes to either the process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government inspector, shall not be deemed to alter the homogeneity of the lot. Each lot shall contain parts of one kind from one manufacturer.

Inspection lots shall comply with MIL–STD–105 and shall be numbered in accordance with MIL–STD–1168.

Unless otherwise approved by the contracting officer, the inspection lot size of end items deliverable under the contract shall be not less than the smallest weekly estimate of quantities contractually scheduled for production during the contract period nor more than the largest quantity contractually scheduled for delivery during any month of the contract period. Inspection lots for components or sub-assemblies, other than the items of delivery, shall be homogeneous and of a size convenient to the contractor.

4.3.2 *Examination.* Sampling plans and procedures for the following classification of defects shall be in accordance with Standard MIL–STD–105 except that inspection for critical defects (and Majors, when so specified) shall be 100 percent. Contractor's sampling plans, if used, shall be approved by the Government and shall provide as a minimum, the protection afforded the Government by the sampling plans in Standard MIL–STD–105. Continuous sampling plans in accordance with Standard MIL–STD–1235 for defects other than critical may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 *Body fuze (see dwg. 82–1–78).*

Categories	*Defects*	*Method of Inspection*	*Code No. (see 6.2)*
Critical: None defined			
Major:	AQL 1.50 percent		
101.	Concentricity of rear outside diameter with thread	Gage	01001
102.	Concentricity of external thread with internal thread	Gage	01002
103.	Perpendicularity of rear outside diameter with forward shoulder	Gage	01003
104.	Perpendicularity of external thread with forward shoulder	Gage	01004
105.	Concentricity of firing pin cavity with internal thread	Gage	01005
106.	Pitch diameter of male thread, min.	Gage	01006
107.	Pitch diameter of female thread, max.	Gage	01007

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:30Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection	Code No.
	108. Minor diameter of female thread, max.	Gage	01008
	109. Major diameter of male thread, min.	Gage	01009
	110. Length of female thread	Gage	01010
	111. Location of safety pin hole	Gage	01011
	112. Diameter of safety pin hole	Gage	01012
	113. Depth of firing pin cavity	Gage	01013
	114. Depth of detonator holder cavity	Gage	01014
Minor:	AQL 2.50 percent		
	201. Pitch diameter of female thread, min.	Gage	01015
	202. Pitch diameter of male thread, max.	Gage	01016
	203. Major diameter of male thread, max.	Gage	01017
	204. Diameter of firing pin cavity, min.	Gage	01018
	205. Evidence of poor workmanship (see 3.6)	Visual	01019

4.3.2.2 *Holder detonator (see dwg. 82–1–78).*

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 1.00 percent		
	101. Concentricity of firing pin hole with thread	Gage	02001
	102. Diameter of cavity, min.	Gage	02002
	103. Depth of cavity, min.	Gage	02003
	104. Pitch diameter of thread, min.	Gage	02004
	105. Major diameter of thread, min.	Gage	02005
	106. Diameter of firing pin hole	Gage	02006
	107. Length of threads	Gage	02007
	108. Small outside diameter, max.	Gage	02008
Minor:	AQL 2.50 percent		
	201. Concentricity of detonator cavity with thread	Gage	02009
	202. Diameter of cavity, max.	Gage	02010
	203. Pitch diameter of thread, max.	Gage	02011
	204. Major diameter of thread, max.	Gage	02012
	205. Wrench holes missing	Visual	02013
	206. Evidence of poor workmanship (see 3.6)	Visual	02014

4.3.2.3 *Spring, firing pin (see dwg. 82–1–78).*

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
	101. Load test failure	Gage	03001
Minor:	AQL 1.00 percent		
	201. Solid height, max.	Gage	03002
	202. Evidence of poor workmanship (see 3.6)	Visual	03003

4.3.2.4 *Pin, firing (see dwg. 82–1–78).*

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 1.00 percent		
	101. Profile of point	Gage	04001
	102. Concentricity of point with outside diameter	Gage	04002
	103. Total length	Gage	04003
	104. Height of firing pin point	Gage	04004
	105. Diameter of safety pin slot	Gage	04005

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:30Z
Check the source to verify that this is the currentversion before use.

Categories	Defects	Method of Inspection	Code No.
	106. Location of safety pin slot	Gage	04006
Minor:	AQL 1.00 percent		
	201. Large outside diameter, max.	Gage	04007
	202. Evidence of poor workmanship (see 3.6)	Visual	04008

4.3.2.5 *Tube stabilizer (see dwg. 9216144 covering a detail of dwg. 82–1–78)*

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
	101. Wall thickness, min.	Gage	05001
	102. Inside diameter	Gage	05002
Minor:	AQL 1.50 percent		
	201. Length	Gage	05003
	202. Flared flange missing	Visual	05004
	203. Evidence of poor workmanship (see 3.6)	Visual	05005

4.3.2.6 *Safety band assembly (see dwg. 82–1–105 covering a detail of dwg. 82–1–78).*

Categories	Defects	Method of Inspection	Code No.
Critical:			
	1. Pin missing	Visual	06001
Major:	AQL 0.40 percent		
	101. Any part missing or distorted	Visual	06002
Minor:	AQL 0.65 percent		
	201. Evidence of poor workmanship (see 3.6)	Visual	06003

4.3.2.7 *Fin (see dwg. 9216137 covering a detail of dwg. 82–1–78).*

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.65 percent		
	101. Thickness, min.	Gage	07001
	102. Crack or fracture	Visual	07002
	103. Spot weld missing (when applicable)	Visual	07003
Minor:	AQL 1.50 percent		
	201. Inside diameter, min.	Gage	07004
	202. Width of ring either side of formed section	Gage	07005
	203. Total length	Gage	07006
	204. Evidence of poor workmanship (see 3.6)	Visual	07007

4.3.2.8 *Clip, Launcher positioning (see dwg. 9216145).*

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
	101. Clip failure, functional	Gage	08001
Minor:	AQL 1.50 percent		
	201. Length after forming, max.	Gage	08002
	202. Width	Gage	08003
	203. Evidence of poor workmanship (see 3.6)	Visual	08004

4.3.2.9 *Stabilizer assembly (see dwg. 82–1–78).*

Categories	Defects	Method of Inspection	Code No.
Critical:			
	1. Firing pin spring missing	Visual	09001
	2. Safety band assembly missing or improperly assembled	Visual	09002

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:30Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection	Code No.
Major:	AQL 0.65 percent		
101.	Inside diameter of tube	Gage	09003
102.	Distance from inside bottom of detonator holder to firing pin, min.	Gage	09004
103.	Outside diameter of fin	Gage	09005
104.	Spot weld missing	Visual	09006
Minor:	AQL 1.50 percent		
201.	Total length	Gage	09007
202.	Marking missing or improper	Visual	09008
203.	Evidence of poor workmanship (see 8.6)	Visual	09009

4.3.2.10 *Body (see dwg. 82–2–44).*

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Inside diameter of flange	Gage	10001
102.	Inside diameter of forward hole	Gage	10002
Minor:	AQL 1.50 percent		
201.	Length of body to flange	Gage	10003
202.	Wall thickness	Gage	10004
203.	Evidence of poor workmanship (see 8.6)	Visual	10005

4.3.2.11 *Union, body (see dwg. 82–2–44).*

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Pitch diameter of thread	Gage	11001
102.	Outside diameter of flange	Gage	11002
Minor:	AQL 2.50 percent		
201.	Total length	Gage	11003
202.	Outside diameter of neck	Gage	11004
203.	Minor diameter of thread, max.	Gage	11005
204.	Perpendicularity of flange face with pitch diameter of thread including parallelism	Gage	11006
205.	Presence of smoke vents	Visual	11007
206.	Evidence of poor workmanship (see 8.6)	Visual	11008

4.3.2.12 *Plug, body (see dwg. 82–2–44).*

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Small outside diameter	Gage	12001
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 8.6)	Visual	12002

4.3.3 *Testing.*

4.3.3.1 *Strength of stabilizer tube brazed joint.*

4.3.3.1.1 *1000 pound load test (see 3.3)* — Major defect — Code No. 13001. — This test shall be performed one hundred percent. Any brazed joint which shows evidence of failure shall cause the assembly to be classed defective. The test shall be performed as specified in 4.4.1.1 using equipment in accordance with 4.3.4.

4.3.3.1.2 *7500 pound load test (see 3.3)* — Major defect — Code No. 13002. — The sampling plan for this test shall be in accordance

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:30Z
Check the source to verify that this is the current version before use.

with Standard MIL–STD–105 using code letter G and an AQL of 0.40 percent. Any stabilizer tube assembly which fails to comply with the applicable requirement shall be classed defective. The test shall be performed as specified in 4.4.1.2 using equipment in accordance with 4.3.4.

4.3.3.2 *Strength of stabilizer tube and fin assembly welds (see 3.4)* — Major defect — Code No. 09010.

4.3.3.2.1 Beginning with the first lot produced and continuing until three (3) consecutive lots have been found to be acceptable, eighty (80) assemblies shall be selected from each lot for test. If two (2) or more assemblies show evidence of failure, the lot shall be rejected. The test shall be performed as specified in 4.4.2 using equipment in accordance with 4.3.4.

4.3.3.2.2 After three (3) consecutive lots have complied with the criteria of 4.3.3.2.1, the sampling plan for this test shall be in accordance with Standard MIL–STD–105 using code letter G and an AQL of 0.40 percent. Any stabilizer tube and fin assembly spot weld which fails to comply with the applicable requirement shall be classed defective. The test shall be performed as specified in 4.4.2 using equipment in accordance with 4.3.4.

4.3.3.3 *Safety band assembly attachment. (see 3.5)* — Major defect. — Code No. 06004. The sampling plan for this test shall be in accordance with Standard MIL–STD–105 using code letter J and an AQL of 1.00 percent. Any assembly which fails to comply with the applicable requirement shall be classed defective. The test shall be performed as specified in 4.4.3 using equipment in accordance with 4.3.4.

4.3.3.4 *Hardness of launcher positioning clip (see dwg. 9216145)* — Major defect. — Code No. 08005. — Twenty (20) launcher positioning clips shall be selected from each heat treated batch for test. If any clip fails to comply with the applicable requirement, the heat treated batch represented by the sample shall be rejected. The test shall be performed as specified in 4.4.4 using equipment in accordance with 4.3.4.

4.3.3.5 *Hydrostatic test of stabilizer tube (see dwg. 9216144)* — Major defect — Code No. 05006. — This test shall be performed 100 percent (see 6.4). If any stabilizer tubing fails to comply with the applicable requirement, it shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.5 using equipment in accordance with 4.3.4.

4.3.4 *Inspection Equipment.* Index of Inspection Equipment Number IEL — 7298722 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 *Government rights to documentation.* Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.3.4.2 *Supply and maintenance.* Supply and maintenance of the equipment listed on the IEL shall be in accordance with Specification MIL–I–45607.

4.3.4.3 *Government use of contractor's inspection equipment.* The contractor shall make available to the Government all inspection equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment, and verification of its accuracy, shall be supplied by the contractor for the performance of examination or test by the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:30Z
Check the source to verify that this is the current version before use.

4.4 Test methods and procedures.

4.4.1 *Strength of stabilizer tube brazed joint.*

4..4.1.1 *1000 pound load test.* The brazed joint of the stabilizer tube assembly shall be tested by applying a load of 1000 pounds, minimum, to the inside of the brazed joint. The load shall be applied in a direction parallel to the axis of the tube at the rate of from 0.100 to 0.125 inch per minute, inclusive. Observation shall be made to determine compliance with the applicable requirement. Test equipment shall be in accordance with 4.3.4.

4..4.1.2 *7500 pound load test.* The stabilizer tube assembly shall be tested by applying a load in a direction parallel to the axis of the tube sufficient to cause failure in tension of the tube, or a load of 7,500 pounds (whichever is reached first). The load shall be applied at a rate of 0.100 to 0.125 inch per minute, inclusive. The sides of the tube may be flattened, if necessary, for attachment to the testing machine. Observation shall be made to determine compliance with the applicable requirement. Test equipment shall be as specified in 4.3.4.

4.4.2 Strength of stabilizer tube and fin assembly welds. The spot welded assemblies shall be pulled apart utilizing equipment in accordance with 4.3.4. Observation shall be made to determine compliance with the applicable requirement.

4.4.3 *Safety band assembly attachment.* The safety band shall be assembled to a simulated stabilizer assembly in accordance with 4.3.4 and tested to determine compliance with the applicable requirement.

4.4.4 *Hardness of launcher positioning clip.* The launcher positioning clip shall be tested for hardness as specified in Federal Standard No. 151, Method 243.

4.4.5 *Hydrostatic test of stabilizer tube.* Prior to machining, the stabilizer tubing shall be tested for not less than five (5) seconds at the minimum hydrostatic pressure specified on the drawing. Observation shall be made for rupture, indication of flaws as evidenced by leaks, and for permanent deformation beyond the drawing requirements. Test equipment shall be as specified in 4.3.4.

5. PREPARATION FOR DELIVERY

5.1 Packaging, packing and marking. Packaging, packing and marking shall be in accordance with Standard MIL-STD-1169.

6. NOTES

6.1 Ordering data. Procurement documents should specifiy the following:

a. Title, number and date of this specification.

b. Ammunition data cards shall be prepared for each lot in accordance with Standard MIL-STD-1167.

c. Submission of first article quantity.—Instructions as to the location of the facility at which the evaluation of the first article quantity shall be carried out, may be obtained from the contracting officer.

6.2 Inspection code numbers. The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment. The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 *Inspection equipment lists.* Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:30Z
Check the source to verify that this is the currentversion before use.

equipment (00 Form 1242–3) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Two copies of the designs shall be submitted for approval as specified in 6.3.7.

6.3.2 *Inspection equipment list codes.* The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5 and 6.3.6 will be designated in the IEL by the following codes:

CDAF — Contractor's design responsibility on Army format in accordance with MIL–D–45608.

CDCF — Contractor's design responsibility on contractor format.

AD — Army design.

ADMU — Army design, mandatory for use.

CE — Commercial equipment.

SCD — Specification control drawing.

6.3.3 *Army designs.* Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and non-mandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 *Specification control drawing.* Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagramatic or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 *Commercial equipment.* Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 *Contractor designs.* Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:30Z
Check the source to verify that this is the current version before use.

an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL-D-45608, and in addition, contain the detail and information specified above. Final approved contractor designs identified as CDCF shall be suitable for microfilming. They must be non-reproducible diazo or electro-static full size prints of top quality with black lines and white background, and shall provide a legible print produced via the 35MM microfilm process. The contractor shall submit one rolled of flat set copy of the final approved design.

6.3.7 *Submission of contractor designs.* Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

6.4 Hydrostatic test. If the stabilizer tubing procured under the specification has been previously subjected to the hydrostatic test specified in this specification, a second hydrostatic test will not be required.

Custodian:

Army—MU

Preparing activity:

Army—MU

Project No. 1330-A-075

Source: https://assist.dla.mil -- Downloaded: 202640-17T15:30Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity.

SPECIFICATION

ORGANIZATION	CITY AND STATE

CONTRACT NO.	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT
		$

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)*	DATE

DD FORM 1 OCT 64 1426

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:30Z
Check the source to verify that this is the current version before use.