MILITARY SPECIFICATION

ENGINE, DIESEL: 6 CYLINDER, IN-LINE
213 H.P. TURBO-SUPERCHARGED

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers Model 3306 Diesel 6 cylinder, in-line, liquid-cooled, 4 stroke-cycle, turbo-supercharged, internal-combustion engine as modified for use in 8 ton GOER military vehicles.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein.

SPECIFICATIONS

Federal

O-I-490	-	Inhibitor Corrosion, Liquid Cooling System.
P-C-437	-	Cleaning Compound, High Pressure (Steam) Cleaner.
VV-F-800	-	Fuel Oil, Diesel.

Military

MIL-P-514	-	Plates; Identification, Instruction and Marking Blank.
MIL-L-2104	-	Lubricating Oil, Internal-Combustion Engine, Tactical Service.
MIL-B-11188	-	Batteries, Storage: Lead-Acid.
MIL-C-11755	-	Compound Antifreeze, Arctic-Type.
MIL-S-13856	-	Electrical Components for Automotive Vehicles; Waterproofness Tests.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

MIL-A-46153 - Antifreeze, Ethylene Glycol, Inhibited, Heavy-Duty, Single Package.
MIL-L-46167 - Lubricating Oil, Internal-Combustion Engine, Artic.
MIL-T-62130 - Truck Tank: Fuel Servicing 2,500 Gallon, 4x4 M559.
MIL-T-62131 - Truck Wrecker: 10 Ton, 4x4 M553.
MIL-T-62132 - Truck Cargo: 8 Ton, 4x4 M520, M877.
MIL-T-62134 - Transmission, Power Shift, Commercial Modified.

STANDARDS
Military
MIL-STD-105 - Sampling Procedures and Table for Inspection by Attributes.
MIL-STD-130 - Identification Marking of U. S. Military Property.
MIL-STD-193 - Painting Procedures, Tactical Vehicles (Tracked and Wheeled).
MIL-STD-461 - Electromagnetic Interference Characteristics Requirements for Equipment.
MIL-STD-721 - Definitions of Effectiveness Terms for Reliability Maintainability, Human Factors, and Safety.
MIL-STD-882 - System Safety Program for Systems and Associated Subsystems and Equipment; Requirements for.

DRAWINGS
11681062 - Power Plant Assembly.
11614457 - Transmission Assembly.

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

ENVIRONMENTAL PROTECTION AGENCY
Control of Air Pollution From New Motor Vehicles and New Motor Vehicle Engines.

(Application for copies should reference "Federal Register Volume 35, Number 108, Part II, dated June 4, 1968" and should be addressed to the Superintendent of Documents, U. S. Government Printing Office, Washington, D. C. 20402.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Accessories and equipment. All electrical accessories and equipment shall conform to the applicable requirements of MIL-E-13856, and specifications shown on the accessory drawing. All accessories and equipment installed on the engine shall be properly adjusted as required for vehicle operation.

3.2 Assembly. The engine assembly including accessories shall be in accordance with drawing 11681062. The engine shall interface and be compatible with transmission 11614457 procured under MIL-T-62134. The engine shall provide the necessary performance and durability to meet the requirements of this specification and vehicle specifications, MIL-T-62130, MIL-T-62131, and MIL-T-62132. The engine shall be identified in accordance with MIL-STD-130. Spare parts, assemblies, and subassemblies shall be identified in accordance with MIL-STD-130 when specified on drawings. Definitions contained in MIL-STD-721 shall apply.

3.2.1 Interchangeability of parts. Component assemblies and parts of the engine, shall be so constructed that they may be installed, replaced, and adjusted without requiring modification among other engines provided under the same part number. If some parts must be furnished in matched sets, the contractor shall provide a list giving part number, part nomenclature, and tolerance range of sets involved. This list must be approved by the government prior to shipment of any engines.

3.2.2 Qualified products. When assemblies and parts requiring qualification are specified, the contractor shall be responsible for using items that are listed or approved for listing on the qualified products list (QPL). The contractors inspection records shall list all QPL items by part or drawing number, name, and supplier and date of qualification.

3.3 Reliability, durability, maintainability, and endurance requirements.

3.3.1 Reliability (minimum). The engine shall have a 1,000 hour Mean Time Between Failure (MTBF) when installed in either the M520, M553, M559 or M877 vehicle. Failure is defined as any malfunction which causes the engine to cease operation, produces a critical or catastrophic safety hazard as defined by MIL-STD-882.

3.3.2 Durability (minimum. Engine replacements in vehicles shall be used to measure durability and shall have probabilities of not requiring replacement as follows:

a. M520 68% in 25,000 miles of mission operation.
b. M553 82% in 12,500 miles of mission operation.
c. M559 77% in 18,000 miles of mission operation.
d. M877 68% in 25,000 miles of mission operation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

3.3.3 Maintainability. When maintenance procedures shown in the technical manuals are followed and the engine is operated in the vehicles, as defined in the vehicle mission statements, the demonstrated maintainability shall be as follows:

(a) Mean Operator Preventive Maintenance Time shall not exceed .25 manhours per mission. This time shall not be included in organizational preventive maintenance time.
(b) Maximum Operator Corrective Maintenance Time shall not exceed 1.00 manhours in vehicle per mission without being classified as a mission failure.
(c) The ratio of total corrective and organizational preventive maintenance manhours to operating hours shall not exceed .06.
(d) The ratio of total organizational preventive maintenance manhours to total operating hours shall not exceed .02.
(e) The ratio of total corrective maintenance manhours to operating hours shall not exceed .04.
(f) Mean manhours to perform a corrective maintenance action shall not exceed 4.00.
(g) The Mean Time Between Corrective Maintenance Actions shall not be less than 100 operating hours.

3.3.4 Endurance run. The bare engine (see 6.3) shall be subjected to an endurance run as specified. At the conclusion of the run, the engine shall conform to all the performance requirements of this specification with the exception that the power and torque shall be not less than 95% of initial readings without readjustment of the injection system. In addition, there shall be no evidence of abnormal wear, scuffing or galling of cylinder bores, pistons, piston rings, piston pins, bearings, bearing journals, gear teeth, cam surfaces, valves, tappets or other parts, burning of valves or pistons, sticking of valves or piston rings, leakage of gaskets or seals which may result in failure of a component or other malfunction.

3.3.4.1 Initial production engine(s). The engine(s) selected shall be fully representative of engines proposed to be furnished under the contract and shall be submitted to the Government for inspection to determine conformance to the requirements of this specification.

3.3.5 Performance requirements.

3.3.5.1 Speed range. The engine shall operate under all loads and conditions as specified herein throughout the entire speed range. The engine shall maintain an idle speed of 700 to 800 rpm when using fuel specified herein.

3.3.5.1.1 Governor. The governor shall limit the maximum engine speed as follows:

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

Full load operation	2175 to 2225 rpm
No load operation	2330 to 2380 rpm

The engine speed with no load on the engine shall stabilize within 3 seconds after full-throttle position is reached. The governor shall have been set and sealed prior to shipment.

3.3.5.2 Brake horsepower. At the completion of the production break-in run, the bare engine (see 6.3) at the full-rack (throttle) setting shall develop 213 minimum gross brake horsepower (see 6.4) at 2200 rpm when using fuel specified herein, air density of 0.070 pounds per cubic foot, a fuel temperature of 90°F, and fuel at specific gravity of 0.853 at 60°F.

3.3.5.3 Torque. At the completion of the production break-in run and with the full-rack setting specified herein, the bare engine (see 6.3) shall develop at the engine flywheel a minimum observed torque of 578 lb ft at 1550 rpm when using fuel specified herein.

3.3.5.3.1 Correction factors. Engine rating can be corrected as follows:

1.0 brake horsepower per each 1 change of API gravity.

3.3.5.4 Exhaust smoke density. The maximum exhaust smoke density at full rack position, through the speed range of 1550 to 2200 rpm when measured within three feet of the turbocharger outlet, shall not exceed a No. 3 visual or a No. 6 meter smoke condition as defined in 6.5 when using fuels specified herein.

3.3.5.4.1 Air pollution control. All vehicles shall comply with the Environmental Protection Agency Regulations governing control of air pollution from new motor vehicles and new motor vehicle engines in effect on the date of award of contract.

3.3.5.5 Fuel. The engine shall be capable of full performance when using fuel conforming to Grade DF-2 of VV-F-800. Using the specified fuels, the engine shall perform as specified with fuel inlet temperatures of up to 180°F measured at inlet to injection pump.

3.3.5.5.1 Fuel consumption. The fuel consumption in lbs per hour of a bare engine which meets the requirements of 3.3.5.2 and 3.3.5.3 (see 6.3) shall be not greater than the following when operating at full load, and full-rack setting and using fuel specified herein.

ENGINE - RPM	FUEL: POUND PER HOUR
1550	85.0
2200	100.0

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z.
Check the source to verify that this is the current version before use.

3.3.5.6 Oil. Engine shall perform as specified herein using lubricating oil in accordance with the seasonal requirements of MIL-L-2104 from -10 / 125°F, and MIL-L-46167 from -65 / 10°F. The manufacturer may use oil of his own selection during engine build-up and break-in run.

3.3.5.6.1 Oil consumption. The engine shall consume not more than 0.0035 lb of lubricating oil per observed brake horsepower per hour, when operated throughout the endurance run, with oil sump temperatures of 230 to 250°F, using oil as specified herein. During vehicle operation with full pay load over hard-surfaced roads, the oil consumption shall be not more than 1 quart per 100 miles.

3.3.5.6.2 Oil pressure. Under all operating conditions specified herein, including oil at the add oil mark and with the oil sump temperature of not less than 180°F, gallery oil pressure shall not be more than 80 pounds per square inch (psig) and not less than 32 psig when the engine is operating at 2200 rpm, using oil as specified herein and shall not be less than 5 psig when engine is idling as specified herein.

3.3.5.7 Supercharging. The turbo-supercharger shall develop a minimum compressor discharge pressure of 50 in. Hg. absolute when engine is operating at 2200 rpm with full load and using fuel conforming to VV-F-800.

3.3.5.7.1 Air induction restriction. The engine shall perform a specified with inlet restriction of 10 to 15 inches of water measured at inlet to turbo-supercharger.

3.3.5.7.2 Exhaust back pressure. The engine shall perform as specified with an exhaust back pressure of 1.5 to 2.0 inches of Hg. measured at the outlet of the turbo-supercharger.

3.3.5.8 Operating temperatures. The engine oil and coolant shall not exceed the following temperatures when operating at full load throughout the speed range of the engine under any of the conditions specified herein or vehicle operation.

(a)	Oil Sump	250°F. (measured at the drain plug)
(b)	Coolant	230°F. (measured at the engine outlet)

3.3.5.9 Cooling system. With a water pump inlet restriction of not more than 1" Hg vacuum and engine outlet restriction pressure of not more than 20.4" Hg (10 PSIG), the outlet thermostat in vide open position, and an inlet temperature of 195 to 210°F. the coolant temperature rise through the engine block and cylinder heads shall not exceed 18°F. when operating at 213 HP and 2,200 RPM in the vehicle. For bare engine testing, an inlet temperature of 165° to 175°F may be used, and the coolant temperature rise through the engine block, cylinder heads, and oil cooler shall not exceed 20°F. This requirement shall be met with all mixtures of water containing from 0 to 50% antifreeze compound conforming to MIL-C-11755.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

3.3.5.9.1 Coolant. The engine shall perform as specified herein using water and antifreeze compound conforming to type I of MIL-A-46153, arctic-type antifreeze compound conforming to MIL-C-11755, or water corrosion inhibitor compound conforming to O-I-490, without overheating and damage to engine.

3.3.5.10 Environmental requirements.

3.3.5.10.1 Starting. The engine shall start within 2 minutes after recommended use of starting aids under any of the following conditions or possible combination:

a. With integral cold starting aid glow plugs, and without external aids after being cold-soaked for a 24 hour period, and without benefit of solar radiation to an ambient temperature of -25°F. Electrical power shall be supplied by four (4) fully charged 6 TN batteries conforming to MIL-B-11188 that were cold-soaked for 24 hrs and with the wiring system same as used on the vehicle.
b. Without external aids, with cooling fan installed, and a fuel pressure of 5 psi at the inlet to the fuel transfer pump, and when operated at the following temperatures with exposure to maximum solar radiation:

Ambient air temperature	125°F
Intake air temperature (at air cleaner inlet)	125°F
Coolant, engine out temperature	230°F
Oil sump temperature	At maximum temperature attainable up to 250°F

c. With the transmission and all accessories when installed in the vehicle.
d. Humidity conditions. Under relative humidity conditions as low as 5 percent at temperature of 125°F. and as high as 100 percent at all temperatures from -25 to 85°F.

3.3.5.10.2 Elevation conditions. The power output of the engine shall remain unchanged at any elevation from sea level to 10,000 feet at ambient temperatures not greater than 60°F.

3.3.5.11 Grades and slopes. The engine shall start and demonstrate the performance characteristics specified herein when operated. The engine shall operate with full, and add oil, oil level conditions in the sump, on longitudinal grades up to 60 percent or lateral slopes up to 30 percent in all directions and combinations. As a result of said operation, no evidence of faulty lubrication, cooling, fuel supply leakage, or other malfunction shall be found.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

3.3.5.12 Steam and water jet cleaning. The engine and all its components shall withstand cleaning with high pressure steam and cleaner conforming to P-C-437 and water jet, without deterioration of seals or hose, water leakage past seals or gaskets, or other defects. Paint removal shall not be considered a deficiency. Steam and water jet cleaning is defined as follows:

> The jet is applied perpendicular to the surface being cleaned at a distance of not more than 1 ft. from the surface for steam cleaning, and not more than 5 feet from the surface for water jet cleaning, and cleaned at a rate of 1 square foot per minute. The jet pressure shall be not less than 100 psi, and not more than 110 psi.

3.4 Production engines. All engines procured under the production contract shall meet all the operational and performance requirements specified herein.

3.4.1 Production break-in run. Each engine shall be given a break-in run by the contractor. After successful completion of this run, the engine with no further break-in, shall be ready for use in the Goer vehicles and meet all performance requirements specified herein.

3.4.2 Fifty hour run. An engine selected during production shall be submitted to a 50 hour run using fuel conforming to Grade DF 2 of VV-F-800.

3.5 Exterior surface treatment. All exposed exterior surfaces of the engine and its components shall be cleaned, painted, or treated for corrosion resistance as specified in the applicable drawings, or if not so specified, shall be painted in accordance with the applicable provisions of MIL-STD-193.

3.6 Nameplate. Unless otherwise specified (see 6.2) on the applicable drawings, the nameplate, data and instruction plates shall conform to the applicable provisions of MIL-P-514.

3.7 Radio, interference suppression. The engine shall meet the tactical suppression requirements of MIL-STD-461.

3.8 Workmanship. The engine assembly shall be constructed and finished thoroughly in a workmanlike manner, particular attention shall be paid to thoroughness of painting, plating, bolted on assemblages, welding and brazing. Electric, fuel and lubrication lines shall be located in a manner so as to prevent possible damage by rubbing on adjacent lines or appendages. All parts and assemblages shall be free from burrs, sharp edges or any condition which may present a safety hazard to operating and maintenance personnel.

3.9 Leakage. During dynamometer operation or when installed in vehicle the engine shall show no evidence of leakage greater than seep as defined in 6.6.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Contractor's inspection or quality control system. Unless otherwise specified by the procuring activity, the contractor shall provide and maintain an effective inspection or quality assurance system acceptable to the Government covering the supplies under the contract. A current, written description of the system shall be submitted to the contracting officer prior to initiation of production. The contractor shall notify the Government of any change to the written procedure subsequent to submission of procedure to the contracting officer.

4.1.2 Government verification. All quality assurance operations performed by the contractor will be subject to Government verification at unscheduled intervals. Verification will consist of (a) surveillance of the operations to determine that practices, methods and procedures of the written inspection plan are being properly applied, and (b) Government inspection to measure quality of product offered for acceptance. Deviation from the prescribed or agreed upon procedures or instances of poor practices which might have an effect upon the quality of the product will be immediately called to the attention of the contractor. Failure of the contractor to promptly correct defects discovered shall be cause for suspension of acceptance until corrective action has been taken, or until conformance of product to specified criteria has been demonstrated.

4.1.3 Materials and qualified products. The contractor shall provide the Government with evidence that materials used are as specified in the applicable specifications and drawings (see 3.1, 3.2, 3.2.1, and 3.2.2).

4.1.4 Break-in. Under this contract, every engine shall be operated as specified (see 5.4.1) and any unsatisfactory engine operation or condition which requires correction shall be corrected by the contractor before the engine is presented for acceptance or additional testing.

4.1.5 Log sheet. The contractor shall maintain a log sheet of each engine run during all tests specified herein. The form of the log sheet and number of legible copies to be furnished to the Government shall be as approved by the procuring activity.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

4.2 Inspection provisions.

4.2.1 Lot size. An inspection lot shall consist of all engines of one type from one day's production, submitted at one time for acceptance inspection.

4.2.1.1 Sampling for inspection. For the purpose of visual, dimensional and primary functional inspection, a representative sample shall be selected from each inspection lot in accordance with inspection level II of MIL-STD-105. Before sampling may be accomplished by the contractor, the contractor shall 100% inspect the first 20 engines to establish a process average (see 6.9) to allow normal sampling in accordance with MIL-STD-105.

4.2.1.2 Examinations. Visual, dimensional, and primary functional examination shall consist of examination of the engines for conformance to the applicable drawings and this specification. Examination shall be performed against the classification of defects and with the acceptable quality levels shown in Table I. The following constitutes a part of the classification of defects (see 6.6 and 6.10).

(a) Any drip constitutes a major defect when the engine has been standing idle and the components are at ambient temperatures.
(b) Any droplet that occurs at a static fit metal to metal or gasket combination shall constitute a major defect.

Table I. Classification of quality defects

Defect No.	Defects	Method of Inspection
Major	A.Q.L. = 25 Defects/100 Units	
101	Valve tappet clearance (each valve): intake and exhaust valves improperly adjusted.	Visual and functional
102	Fuel, oil and coolant leaks: leakage (see 6.6).	Visual
103	Governor: malfunction; not sealed	Visual and functional
104	Torque on accessible cylinder head bolts, intake and exhaust manifold flange bolts that can be reached without breaking seals or removing cover: improper torque.	Visual and functional
105	Crankshaft: excessive or restrictive end play.	Visual and functional

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

Table I. Classification of quality defects (Cont'd)

Defect No.	Defects	Method of Inspection
106	Fuel system components: malfunction; damage; leaks (see 6.6).	Visual and functional
107	Fuel injection system timing and components: malfunction; improper adjustment.	Visual and functional
Minor	A.Q.L. = 150 Defects/100 Units	
201	Fuel lines: damaged; rubbing; improper support.	Visual
202	Injection pump support bracket: improperly installed.	Visual
203	Linkage: improper adjustment.	Visual and functional
204	Minor assemblies: omitted.	Visual
205	Engine: improper adjustment or installation of components.	Visual and functional
206	Fuel lines, hose, vents, shut-off valve: improperly assembled or installed	Visual and functional
207	Oil sump, fuel and oil filters: dirt, chips, and foreign particles, due to production.	Visual
208	Painting: spots missed; sags or runs.	Visual

4.2.1.3 Unclassified defects. All defects having no bearing on function, safety, interchangeability or life, but are considered departures from good workmanship will be noted in writing. Workmanship deficiencies falling within this category and recurring in 5 consecutive lots or ten lots or more within a thirty-day period will be added to the minor classification with no increase to A.Q.L.'s.

4.2.1.4 Recurring major deficiencies. A major deficiency (see 6.10) is recurring when the same defect occurs more than once in the same sample or when the defect occurs in two successive samples. A major defect may be considered

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

recurring when the historical inspection records ("P" chart or approved equivalent) reflect such a condition. Recurring major deficiencies shall be cause for the entire lot or lots to be inspected for the recurring deficiencies. The deficiencies shall be corrected when found.

4.2.2 Examination failure. If an engine fails to pass any acceptance examination specified herein, the government inspector shall stop acceptance of subsequent engines until evidence has been provided by the contractor that corrective action has been accomplished. Correction of any defect must be accomplished by the manufacturer at no cost to the Government on all engines accepted under the contract. Any defects found are considered prima facie evidence that engines already accepted are similarly defective unless evidence satisfactory to the contracting officer is furnished by the contractor that no defects exist.

4.3 Initial production test. One of the first ten production engines produced under contract will be selected by the Government and subjected to a 400 hour endurance run as specified in Table II. This test shall be conducted by the Government at a place designated by the Government to determine conformance to 3.3.4.1 and 3.3.4. With the engine, the contractor shall furnish a certified graph with performance curves showing horsepower, torque, and specific fuel consumption for the bare engine. The contractor shall support the dynamometer endurance test and the initial production vehicle tests by providing any components necessary for completion of such test. Delay in test completion caused by engine breakdown or failure of the contractor to adequately support the engine with parts during the tests shall not be the basis for adjustment of contract delivery schedule or contract price. In addition, the initial production test engine must be examined for all defects of Table I and all tests as required by Table III.

4.3.a In vehicle test. To determine conformance to 3.3.1 through 3.3.3 engines shall be installed in test vehicles (3.3.3) (quantities as specified in the contract) and shall be subjected to mileage specified for each vehicle type. These tests (3.3) shall be conducted in conjunction with the vehicle initial production test, comparison tests, or any other government vehicle tests.

4.3.b Failure. Any engine test failure found during the above test shall be reason for refusal by the Government to accept subsequent engines until evidence has been provided by the supplier that corrective action has been taken. Any test failures found during or as a result of these tests shall be prima facie evidence that all engines already accepted prior to completion of test are similarly defective unless evidence satisfactory to the Government is furnished by the contractor that they are not similarly defective. Such defects on all engines shall be corrected by the contractor at no cost to the Government.

4.3.1 Endurance tests. The bare engine (see 6.3) shall be operated in accordance with Table II to determine conformance to 3.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

Table II. Endurance five hour schedule

Period	% Rated Speed	% Load	Time, Hrs
1	Low Idle	0	1/2
2	Max. Torque	100	1
3	100	0	1/2
4	75	85	1
5	100	50	1/2
6	100	100	1
7	50	25	1/2
		TOTAL	5 hours

4.3.1.1 Performance tests.

4.3.1.1.1 Speed range and governor tests. To determine conformance to 3.3.5.1 and 3.3.5.1.1, the speed range and governor shall be checked for functional requirements.

4.3.1.1.2 Brake horsepower and torque test. To determine conformance to 3.3.5.2 and 3.3.5.3, the engine shall be operated, as specified, brake horsepower and torque checked for functional requirements.

4.3.1.1.3 Exhaust smoke density test. To determine conformance to 3.3.5.4, with the engine operating, as specified; the smoke shall be checked for density.

4.3.1.1.4 Fuel consumption test. To determine conformance to 3.3.5.5.1, with the engine operating as specified; the fuel consumption shall not exceed that specified.

4.3.1.1.5 Oil consumption and pressure tests. To determine conformance to 3.3.5.6.1 and 3.3.5.6.2, with the engine operating as specified; the oil consumption and oil pressure shall be not more than that specified.

4.3.1.1.6 Supercharging, air restriction, and exhaust back pressure test. To determine conformance to 3.3.5.7 through 3.3.5.7.2, with the turbo supercharger operating as specified; the discharge pressure, air induction restriction, and exhaust back pressure shall be measured. The engine shall be checked to assure it meets performance requirements under these conditions.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

4.3.1.1.7 Operating temperatures test. To determine conformance to 3.3.5.8, with engine operating as specified; the oil and coolant shall be measured at locations indicated and temperatures checked.

4.3.1.1.8 Cooling system test. To determine conformance to 3.3.5.9, the cooling system with specified restrictions shall not cause the coolant temperature rise through the engine more than specified.

4.3.1.1.9 Grades and slope test. To determine conformance to 3.3.5.11, the initial production engine shall be subjected to this test.

4.3.1.1.10 Steam and jet cleaning test. To determine conformance to 3.3.5.12 the initial production engine shall be subjected to cleaning as specified. The seals, hose, and gaskets shall be checked for damaged and leaks.

4.3.1.1.11 Air pollution test. To determine conformance to 3.3.5.4.1, the initial production engine shall be tested for compliance to specific standards.

4.3.1.1.12 Radio interference suppression test. To determine conformance to 3.7, the engine, as delivered, shall have met the requirements of the specified standard.

4.3.1.2 Environmental tests. To determine conformance to 3.3.5.10, the engine shall be subjected to the specified environment conditions and functional compliance verified.

4.3.1.2.1 Starting test. To determine conformance to 3.3.5.10.1, the engine shall be subjected to a starting test under specified conditions.

4.3.1.2.2 Elevation test. To determine conformance to 3.3.5.10.2, the engine power output shall be verified at specified altitudes. When actual altitude or altitude chamber is not available, the conditions shall be simulated by imposing restriction on inlet air and suction on engine exhaust.

4.3.1.2.3 Leakage test. To determine conformance to 3.9, with engine operating or installed in vehicle leakage shall be not more than a weep or seep as indicated in 6.6.

4.3.1.3 Endurance test. The endurance test shall consist of a total of 400 hours divided into four periods of 100 hours each. Each 100 hour period shall consist of twenty, five hour endurance schedules (see Table II). Procedures defined in 6.8 will be utilized.

4.3.1.3.1 Test hours. Any period of the schedule terminated due to equipment malfunction or minor test specimen failure must be repeated when time elapsed is less than half. The voided part of the period will not be accrued as endurance time.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

4.3.1.3.2 Power check tests. To insure engine compliance to performance requirements listed below, the engine shall be subjected to power checks before start of the endurance run and thereafter every 100 hours of endurance time:

Speed Range	(see 3.3.5.1)
Brake Horsepower	(see 3.3.5.2)
Torque	(see 3.3.5.3)
Exhaust Smoke Density	(see 3.3.5.4)
Fuel Consumption	(see 3.3.5.5.1)
Oil Pressure	(see 3.3.5.6.2)
Supercharger Pressure	(see 3.3.5.7)

The power checks will be performed with the throttle set in the wide open position (full load) and engine speeds of 1550, 1700, 1800, 1900, 2000, 2100, and 2200 RPM in both ascending and descending order. At each engine setting, the engine should be run for a sufficient time (approximately 20 minutes) for stabilization. In addition, following the pre-endurance power check, part load data will be obtained at each of the speeds above and 85%, 70%, 50%, and 25% of the full load for each speed.

4.3.1.3.3 Temperatures. The endurance test, including power checks, will be performed at an ambient cell temperature of 85 ± 5° F, except for the last 100 hour period which will be performed at an ambient cell temperature of 125 ± 5° F.

4.3.1.4 Tear down inspection. Prior to tear down inspection a compression check shall be made on all cylinders. Variation of compression between cylinders shall be not more than 50 psi at 400 rpm's. Each engine subjected to the tests shall be disassembled to the extent required to perform the following inspections:

a. Oil contamination.
b. Dirt, chips or foreign matter in the engine block, oil pan, filters, and accessory drive case.
c. Main bearings bolt torque.
d. Connecting rod bolt torque.
e. Cylinder bore scuffing, scoring, and galling.
f. Piston scuffing, scoring, and burning.
g. Excessive wear.

4.3.1.5 Endurance failure. Failure of an endurance engine to conform to any of the requirements specified or any major defect of a workmanship or material found as a result of the test shall be cause for rejection, and for refusal to continue acceptance of production engines until objective evidence has been provided by the manufacturer that corrective action has been taken to eliminate the defect. Correction of any defect must be accomplished by the manufacturer at no cost to the Government on engines accepted under the contract. Any defects found as a result of test is considered prima facie evidence that

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

engines already accepted are similarly defective unless evidence satisfactory to the contracting officer is furnished by the contractor that no defects exist.

4.3.1.5.1 A major failure. Is a failure to any component or part of the engine system that causes an engine stoppage or reduction of power in excess of 15 HP. All major failures shall be a basis for an endurance test termination. Subsequent retest will begin at 0 hours on the 400 hour schedule.

4.3.1.5.2 A minor failure. Is a defect leading to a reduction of power not exceeding 15 HP provided the defect can be rectified and 95% of full power restored within the scope of normal maintenance and adjustments permitted at the completion of the 100 hour period. Failure to attain 95% of full power after adjustment shall be a basis for termination. Subsequent retest will begin with 0 hours on the 400 hour schedule.

4.4 Acceptance tests. After successful completion of the break-in run, each engine shall be examined for defects in the acceptance tests listed in Table III.

4.4.1 Acceptance test failures. If an engine fails to pass any examinations or tests specified herein, the Government shall stop acceptance until evidence has been provided that the corrective action has been taken on all engines.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

Table III. Test schedule

Test No.	Name	Initial Production	Acceptance	Control
4.1.4	Break-in	X	X	
4.4	Acceptance	X	X	
4.3	Initial production (endurance)	X		
4.3.1.1.1	Speed range & governor	X	X	X
4.3.1.1.2	Brake horsepower & torque	X	X	X
4.3.1.1.3	Exhaust smoke density	X	X	X
4.3.1.1.4	Fuel consumption	X	X	X
4.3.1.1.5	Oil consumption	X		X
4.3.1.1.5	Oil pressure	X	X	X
4.3.1.1.6	Supercharging	X		X
4.3.1.1.6	Air restriction	X		X
4.3.1.1.6	Exhaust back pressure	X		X
4.3.1.1.7	Operating temperatures	X		X
4.3.1.1.8	Cooling system	X		X
4.3.1.2	Environment	X		
4.3.1.2.1	Cold starting	X		
4.3.1.2.2	Elevation	X		
4.3.1.2.3	Leakage	X	X	X

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

Table III. Test schedule (Cont'd)

Test No.	Name	Initial Production	Accept-ance	Contrc
4.3.1.1.9	Grades & slope	X		
4.3.1.1.10	Steam & jet cleaning	X		
4.3.1.1.11	Air pollution	X		
4.3.1.1.12	Radio interference sup-pression	X		

4.5 Fifty hour quality control test. The 50-hour quality control tests as referenced in 3.4.2 shall be conducted as specified herein for the purpose of determining the continuous quality of the engines. These tests are conducted at the contractor's plant.

4.5.1 Selection of test sample. Engines shall be selected by the Government at the rate of one per month when production is 100 units per month or less and at the rate of two per month when production is greater than 100 units per month. Engine shall be identified as to production period.

4.5.2 Test. Each engine selected shall be examined for defects in Table I and subjected to the tests in Table IV.

Table IV. 50 hour control test

Period	Time (hrs)	Speed (rpm)	Percent of full rack load at indicated speed
1	(Engine must have completed acceptance test)		
2	5	1550	50
3	5	1800	75
4	5	2000	75
5	5	2100	100
6	30	2200	100

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

Table IV. 50 hour control test (Cont'd)

Period	Time (hrs)	Speed (rpm)	Percent of full rack load at indicated speed
7	(Performance as required, see Table III.)		
8	(Disassembly & inspection)		
9	(Assembly)		
10	(Rerun acceptance test prior to shipment)		

4.5.3 Control test failure. Failure of engine selected for control tests to conform to the requirements specified or any major defect for workmanship or material found as a result of the test shall be cause for rejection and for refusal to accept subsequent engines. Also, defects found during or as a result of the test shall be prima facie evidence that engines accepted subsequent to the previous acceptable control test engine are similarly defective unless evidence satisfactory to the contracting officer is furnished by the contractor that they are not similarly defective. Defects on all engines shall be corrected by the contractor at no cost to the Government. Another engine, with corrective action implemented, shall be subjected to the control test.

4.5.4 Tear down inspection. Prior to tear down inspection, a compression check shall be made on all cylinders. Variation of compression shall be not more than 50 psi at 4000 rpm's. Each engine subjected to the control tests shall be disassembled to the extent required to perform the following inspection:

(a) Oil contamination.
(b) Dirt, chips or foreign matter in the engine block, oil pan, filters and accessory drive case.
(c) Main bearings bolt torque, head bolt torque, intake and exhaust manifold flange bolts, and vibrator damper.
(d) Connecting rod bolt torque.
(e) Cylinder bore scuffing, scoring, and galling.
(f) Piston scuffing, scoring, and burning.
(g) Excessive wear.

4.5.5 Corrections and reassembly. Should there be evidence of any condition of engine or parts requiring correction, such corrections shall be made by the contractor prior to reassembly of the engine and re-submission to the break-in run. In addition, the contractor shall submit evidence to the Government, that corrective action has been taken in production to eliminate any deficiency disclosed. Failure of the contractor to submit such evidence shall be

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

cause for refusal by the Government to continue acceptance of subsequent engines. Any engine not requiring replacement parts shall be reassembled and subjected to the acceptance power check test only.

4.5.6 Test results and recorded data. The contractor's report furnished to the Government shall include all data resulting from the control test. This data shall be obtained under stabilized operating conditions and during the last half hour of periods 2 through 5. For period 6, the data shall be obtained during the last half hour of each 10 hour increments. Oil consumption shall be measured during the last 25 hours of operation.

4.6 Preparation for delivery. Inspection of preservation packaging, packing and marking shall be performed on each engine to determine conformance to 5.1.

5. PREPARATION FOR DELIVERY

5.1 Preservation, packaging, packing, and marking. Preparation for deliver shall be in accordance with the technical requirements specified on the appropriate packaging data sheet (see 6.2).

6. NOTES

6.1 Intended use. The engines covered by this specification are intended for production use, as spares, or as replacements for the M520, M553, M559, and M60ER vehicles.

6.2 Ordering data. Procurement documents should specify the following:

a. Title, number, and date of this specification.
b. Additional data for nameplate, when required (see 3.6).
c. Quantity of initial production test engines required (see 4.3).
d. Selection of method and applicable level of preservation and packaging, and level or packing of the referenced specification (see 5.1).

6.3 Bare engine. The term bare engine assembly, without compressor, is defined as an engine depicted on 11681061.

6.4 Brake horsepower. Brake horsepower is defined as the horsepower output of the bare engine at the flywheel.

6.5 Exhaust smoke density. Exhaust smoke density shall be determined with a Robert R Bosch Model DPAW 68 Smoke Meter or equal (as approved by responsible engineering activity) and Model DPAW 65 Sampling Pump or equal (as approved by responsible engineering activity). The following table may be used to visually define the degree of exhaust smoke density in lieu of the smoke meter:

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

Description of exhaust smoke	Classification
Clear	1
Haze	2
Light Gray	3
Medium Gray	4
Dark Gray to Black	5

NOTE: Observation of exhaust smoke should be made against a white background within 3 feet of the turbocharger outlet.

6.6 The following definitions shall be used for the classification of defects for leaks:

(a) Weep: - Any non-recurring evidence of fluid beyond the seal.
(b) Seep: - Any recurring evidence of fluid beyond the seal that does not result in formation of a droplet.
(c) Droplet: - Any recurring evidence of fluid beyong the seal that results in formation of a non-falling droplet.
(d) Drip: - Any recurring evidence of fluid beyond the seal where droplet forms and falls.

6.7 Typical vehicle life operational profile

Model	Renewal life Miles - Hours	Avg M.P.H.	Total Missions	Mission Miles - Hours
M520	25000 - 1250	20.0	250	100 - 5
M559	18000 - 1250	14.4	182	100 - 6.9
M553	12500 - 1250	10.0	250	50 - 5
M877	25000 - 1250	20.0	250	100 - 5

In actual troop use, this will vary due to environmental, terrains, and troop mission differences.

6.8 The following procedures are provided for conduct of endurance testing:

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

6.8.1 Engine shut down. The engine test may be shut down after completion of any period in the five hour schedule. Planned shut down following test periods 2, 4, and 5 will include a cool down running of period no. 7. This cool down period will not be credited as endurance test time. This cool down period is not required after periods 1, 3, and 7.

6.8.2 Engine warm-up period. A one-half hour warm-up period is required prior to continuation of endurance run following any shut down. During this one-half hour period, the loads and speeds shall be progressively increased to the values required in period no. 5. Temperatures stabilization in period no. 5 is required. This warm-up period will not be credited as endurance time.

6.8.3 Data. The following data will be recorded during the last five minutes of each schedule periods and power check tests:

a. Engine speed (RPM).
b. Observed brake horsepower (OBHP) and/or torque (lb-ft).
c. Fuel flow (lbs/hour).
d. Test cell ambient temperature (^{o}F) and barometric pressure (in. Hg).
e. Engine oil gallery and sump temperature (^{o}F) and pressure (PSIG-Gallery only).
f. Fuel secondary filter out and spill back temperatures (^{o}F) and pressures (PSIG).
g. Air cleaner inlet temperature (^{o}F).
h. Air intake manifold pressure (in.Hg).
i. Air cleaner restriction (in. water).
j. Coolant engine inlet and outlet temperatures (^{o}F) and pressures (PSIG).
k. Exhaust port temperatures (^{o}F).
l. Exhaust manifold pressure (in. Hg).
m. Crankcase pressure (in. water).
n. Fuel, transfer pump, inlet pressure (PSIG).
o. Oil consumption (lb/hr) will be calculated on basis of oil added in lbs accumulating to the engine as necessary during the endurance run.
p. Exhaust smoke density (power check only).

6.8.4 Warning and shut downs. To guard against overstress caused by equipment malfunction or human error, the following automatic warning/shutdown provisions will be incorporated in each test cell:

a. Temperatures ^{o}F, maximum	WARNING	SHUT DOWN
(1) Coolant, engine out	225	235
(2) Oil, engine sump	245	255

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

	WARNING	SHUT DOWN
b. Pressure PSIG, minimum		
(1) Oil engine gallery 600-1400 RPM	8	5
(2) Oil engine gallery 1400-2200	18	10
c. Engine speed	2380	2500

6.8.5 Servicing. Prior to the power check test, the lubricating oil shall be changed, all filters serviced, valve clearance and injector rack linkage checked and adjusted to applicable requirements.

6.9 Process average. Sampling shall be initiated if the process average value of the first twenty engines inspected is less than the A.Q.L. specified in the classification of defects for major and minor defects. Process average shall be computed as follows:

$$\text{Process average} = \frac{\text{Number of defects}}{\text{Number of engines inspected}} \times 100$$

If the computed process average exceeds the specified A.Q.L., 100 percent inspection shall be performed and continued until such time that the process average for twenty consecutive engines is less than the specified A.Q.L.

6.10 Definitions of recurring major and minor defects. The Government Inspector shall verify that a thorough inspection of each engine is performed by the contractor not only for the listed characteristics, but also for any other departures from good workmanship. The Government Inspector shall assure that all deficiencies encountered during the inspection are enumerated on the Deficiency Sheet for the engine. The defects noted on the Deficiency Sheet shall contain sufficient description to enable the Government Inspector and the contractor's representative to classify the deficiency in accordance with the classification of defects of the engine specification and definitions contained in MIL-STD-105. Corrective action shall be taken for recurring deficiencies.

Custodian:
Army - AT

Preparing activity:
Army - AT

Project No. 2815-A130

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION

MIL-E-62133B(AT)

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO (If "yes", in what way?)

4. REMARKS (Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)

SUBMITTED BY (Printed or typed name and activity - Optional)

DATE

DD FORM 1 JAN 68 1426

REPLACES EDITION OF 1 OCT 58 WHICH MAY BE USED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID
DEFENSE SUPPLY AGENCY

DEFENSE SUPPLY AGENCY
OFFICIAL BUSINESS

Commander
US Army Tank-Automotive Command
DRSTA-GSES
Warren, MI 48090

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:19Z
Check the source to verify that this is the current version before use.