INCH-POUND

MIL-F-52569C(ME)
26 October 1992
SUPERSEDING
MIL-F-52569B(ME)
21 October 1980

MILITARY SPECIFICATION

FOOTWALK ASSEMBLY: ALUMINUM,

FOR BRIDGE, BAILEY

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers an aluminum footwalk for the Bailey fixed bridge.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DoDISS) and supplement thereto, cited in the solicitation (see 6.2).

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research, Development, and Engineering Center, ATTN: SATBE-TSE, Fort Belvoir, VA 22060-5606 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 5420

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:25Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

PPP-T-97	- Tape, Pressure-Sensitive Adhesive, Filament Reinforced.

MILITARY

MIL-T-704	- Treatment and Painting of Materiel.
MIL-C-16173	- Corrosion Preventive Compound, Solvent Cutback, Cold-Application.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-889	- Dissimilar Metals.

(Unless otherwise indicated, copies of Federal and military specifications, standards, and handbooks are available from the Standardization Documents Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Other Government drawings. The following other Government drawings form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those in effect on the date of the solicitation.

DRAWINGS

ME

TA13205E5395	- Footwalk Assembly: Aluminum, for Bridge, Bailey.

(Copies of drawings required by contractors in connection with specific acquisition functions should be obtained from the USA Belvoir Research, Development and Engineering Center, ATTN: SATBE-JBS, Fort Belvoir, VA 22060-5606.)

2.2 Non-Government publications. The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DoDISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DoDISS are the issues of the documents cited in the solicitation (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:25Z
Check the source to verify that this is the current version before use.

AMERICAN WELDING SOCIETY (AWS)

A 5.10	- Bare Aluminum and Aluminum Alloy Welding Electrodes and Rods.
D 1.2	- Structural Welding Code, Aluminum.

(Application for copies should be addressed to the American Welding Society, 550 N.W. LeJeune Road, P.O. Box 351040, Miami, FL 33135.)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Qualification Standard for Welding and Brazing Procedures, Welders, Brazers, and Welding and Brazing Operators.

(Application for copies should be addressed to the American Society of Mechanical Engineers, United Engineering Center, 345 East 47th Street, New York, NY 10017.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

D 3951	- Standard Practice for Commercial Packaging.
D 3953	- Strapping, Flat Steel and Seals.
D 4675	- Selection and Use of Flat Strapping Materials.

(Non-Government standards and other publications are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein (except for related associated detail specifications, specification sheets, or MS standards), the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained

3. REQUIREMENTS

3.1 Description. The footwalk assembly shall be as shown on TA13205E5395 and as specified herein.

3.1.1 Drawings. The drawings forming a part of this specification are engineering design drawings. No deviations from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Any data (e.g., shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:25Z
Check the source to verify that this is the current version before use.

3.2 First article. Unless otherwise specified (see 6.2), a sample shall be subjected to first article inspection (see 6.3) in accordance with 4.3.

3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Material not as specified shall be selected by the contractor and shall be subject to all provisions of this specification.

3.3.1 Material deterioration prevention and control. The item shall be fabricated from compatible materials, inherently corrosion resistant, or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable operating and storage environments to which the item may be exposed.

3.3.2 Dissimilar metals. Dissimilar metals shall not be used in intimate contact with each other unless protected against galvanic corrosion. Dissimilar metals and methods of protection are defined and detailed in MIL-STD-889.

3.3.3 Identification of materials and finishes. The contractor shall identify the specific materials, material finish, or treatment for use with component and subcomponent and shall make information available upon request to the contracting officer or designated representative.

3.3.4 Recovered materials. For the purpose of this requirement, recovered materials are those materials which have been collected from solid waste and reprocessed to become a source of raw materials, as distinguished from virgin raw materials. The components, pieces, and parts incorporated in the footwalk assembly may be newly fabricated from recovered materials to the maximum extent practicable, provided the footwalk assembly produced meets all other requirements of this specification. Used, rebuilt, or remanufactured components, pieces, and parts shall not be incorporated in the footwalk assembly.

3.4 Welding electrodes. Welding electrodes for aluminum shall conform to AWS A 5.10, classification ER4043, size as required.

3.5 Identification marking. The footwalk assembly shall be metal-die stamped as shown on the applicable drawing. Die stamping shall be legible after painting.

3.6 Treatment and painting. The footwalk assembly, except the bridge pin retainer, shall be cleaned, treated, and painted as specified on the drawings. The bridge pin retainer shall be coated with a corrosion-preventive solvent cutback coating, hard film type, conforming to MIL-C-16173, grade 1.

3.7 Stenciling. The nomenclature, national stock number, weight, and cube shall be stenciled on each component. The letters "NET WT" shall precede the numerals in the weight and the letters "CU" shall precede the cubic displacement. Marking shall be Gothic-type capitals and Arabic numerals 3/4 inch high. Stenciling shall conform to MIL-T-704.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:25Z
Check the source to verify that this is the current version before use.

3.8 Workmanship.

3.8.1 Aluminum fabrication. Aluminum used in the fabrication of the footwalk assembly shall be free from kinks and sharp bends. Straightening of material shall be done by methods that will not cause injury to the metal. Surfaces and edges of all finished members shall be smooth and free from kinks, bends, and winds. All bends of a major character shall be made with metal dies or "fixtures" to insure uniformity of size and shape. Sharp instruments shall not be used for marking bend lines. Aluminum shall not be cut by methods using heat. Aluminum less than 3/8 inch thick may be cut by shearing; aluminum 3/8 inch thick and over shall be cut by routing or by high-speed saws. Shearing and sawing shall be done neatly and accurately.

3.8.2 Jigs and fixtures. Components and parts of the assembly shall be assembled in jigs or fixtures and jointed while held in position. Jigs or fixtures shall be designed to prevent distortion or to limit the distortion to an amount that can be removed by straightening and stress relieving without changing the physical characteristics of the metal.

3.8.3 Welders and welding.

3.8.3.1 Welders or welding operator. Before assigning any welder or welding operator to manual welding work covered by this specification, the contractor shall obtain certification that the welder or welding operator has passed qualification tests as prescribed by either AWS D 1.2 or the ASME code for the materials joined and the type of welding operation to be performed and that such qualification is effective as defined. Contractors who only make horizontal welds need not qualify welders for "all position welding." The contractor is responsible for determining that automatic welding equipment operators are capable of producing quality welds in accordance with AWS and ASME codes. In the event of evidence of poor welds, the Government reserves the right to require retesting of any welder or welding operator (see 6.5).

3.8.3.2 Welding. The surfaces of parts to be welded shall be free from scale, paint, grease, and other foreign matter. Welding shall be done by the shielded metal-arc or gas metal-arc (MIG) process and shall conform to the provisions of ASME or AWS Code. All welded parts shall be free from cracks and other imperfections that may reduce the effectiveness of the part. Work shall be positioned for flat welding when practicable. Before welding over previously deposited weld metal, all traces of slag shall be removed and the deposit shall be preheated for welding to a temperature of not more than 400 °F. Aluminum welds may be filed with stainless steel, wire brushed, or chipped but shall not be hammered.

3.8.4 Interchangeability. Components and parts of like description shall be fabricated to be duplicates within the tolerances specified and shall be interchangeable.

3.8.5 Assembly. The footwalk assemblies shall be capable of being joined together by means of the brackets without any misfit.

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:25Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.2 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards.

4.1.3 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the Quality Assurance Provisions (QAP) shown on the drawings. The drawings specify the characteristics requiring QAP inspection, the sampling plan, and the basis for acceptance and rejection (see 6.4 and 6.6).

4.2 Classification of inspection. Inspection shall be classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Inspection of packaging (see 4.6).

4.3 First article inspection.

4.3.1 Examination. The first article footwalk assembly shall be examined for the defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Test. The first article footwalk assemblies shall be tested as specified in 4.5.2. Failure of the test shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.4.2 Examination. Samples selected in accordance with 4.4.1 shall be examined for the major and minor defects specified in 4.5.1. Presence of one or more defects shall constitute failure of this examination and shall be cause for rejection.

4.5 Inspection procedure.

4.5.1 Examination. The footwalk assembly shall be examined as specified herein for the following defects:

Major

101. Any part or component not in accordance with the QAP requirements as shown on the drawings (see 3.1.1).
102. Material not as specified (see 3.3).
103. Materials not resistant to corrosion and deterioration or treated to be resistant to corrosion and deterioration of the applicable storage and operating environments (see 3.3.2).
104. Dissimilar metals as defined in MIL-STD-889 are not effectively insulated from each other (see 3.3.3).
105. Contractor does not have documentation available for identification of materials, material finishes, or treatment (see 3.3.4).
106. Used, rebuilt, or remanufactured components, pieces, or parts incorporated in the footwalk assembly (see 3.3.5).
107. Welders and welding operators not certified as specified (see 3.8.3.1).
108. Welding and welds not as specified (see 3.8.3.2).
109. Components missing or not as specified (see 3.8.4).
110. Workmanship not as specified (see 3.8).
111. Weld defects such as flux inclusions, spatter, undercutting, porosity, incorrect size, or lack of fusion with parent metal (see 3.8.1).
112. Welding electrode not as specified (see 3.4).

Minor

201. Dimensions other than those identified by QAP data not as specified (see 3.1.1).
202. Identification marking incorrect, missing, or illegible (see 3.5).
203. Treatment and painting not as specified (see 3.6).

4.5.2 Test. The two footwalk assemblies shall be joined together by means of the brackets. Failure to assemble properly without any misfit shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:25Z
Check the source to verify that this is the current version before use.

4.6 Inspection of packaging.

4.6.1 Quality conformance inspection of pack.

4.6.1.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.6.1.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.6.1.3 Examination. Samples selected in accordance with 4.6.1.2 shall be examined for the following defects. Presence of one or more defects shall constitute failure of this examination and shall be cause for rejection.

113.	Bridge pin retainers and locking brackets not secured together and attached to footwalk as specified for level A (see 5.1.1.2).	
114.	Quantity per bundle not as specified for level A (see 5.2.1).	
115.	Bundling not as specified for level A (see 5.2.1).	
116.	Wood strings not as specified and placed under the two end straps on bundles for level A (see 5.2.1).	
117.	Strapping not as specified for level A (see 5.2.1).	
118.	Preservation and packing not as specified for commercial packaging in accordance with the referenced document (see 5.1.2 and 5.2.2).	
119.	Marking missing, illegible, incorrect, or incomplete for level A or commercial (see 5.3.1 and 5.3.2).	

5. PACKAGING

5.1 Preservation. Preservation shall be level A or commercial as specified (see 6.2).

5.1.1 Level A.

5.1.1.1 Preservation. The footwalk assembly, cleaned, treated, and painted as specified on the drawings and the bridge pin retainers coated as specified in 3.6 shall not require additional preservation.

5.1.1.2 Bridge pin retainers and locking brackets. Two bridge pin retainers shall be secured to each leg of the two locking brackets with tape conforming to PPP-T-97, type IV, size 3/4 inch. They shall then be secured to the underside of the end grating of the footwalk with soft annealed wire by passing the wire through the holes on the brackets and the grating.

5.1.2 Commercial. The component parts of the footwalk assemblies shall be preserved in accordance with ASTM D 3951.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

5.2 Packing. Packing shall be level A or commercial as specified (see 6.2).

5.2.1 Level A. Eight footwalk assemblies preserved as specified in 5.1, shall be bundled together using not less than four flat steel straps. The two end straps shall be placed adjacent to the end block and full 1-inch by 2-inch wood strips the same height as the bundle shall be placed under the straps. Two intermediate straps, without the wood strips, shall be placed equal distances between the end straps. The strapping shall conform to ASTM D 3953, type 1 or 2, zinc-coated, size 3/4 inch by .035 inches and ASTM D 4675.

5.2.2 Commercial. The footwalk assemblies, preserved as specified in 5.1, shall be packed in accordance with ASTM D 3951.

5.3 Marking.

5.3.1 Military. Marking for military levels of protection shall be in accordance with MIL-STD-129.

5.3.2 Commercial. Marking for commercial packaging shall be in accordance with ASTM D 3951. The gross weight and cube shall also be marked on the shipping container.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful but is not mandatory.)

6.1 Intended use. The footwalk assemblies are intended to be used outside the trusses on the Bailey bridge to provide a walkway for pedestrian traffic.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of the specification.
b. Issue of DoDISS to be cited in the solicitation and, if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
c. Time frame required for submission of first article model (see 3.2).
d. Degree of preservation and packing required (see 5.1 and 5.2).

6.3 First article. When a first article inspection is required, the item(s) should be a preproduction model. The first article should consist of one or more units. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, approval of the first article test results, and disposition of the first articles. Invitation for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:25Z
Check the source to verify that this is the current version before use.

Government approval is presently appropriate for the pending contract. Bidders should not submit alternate bids unless specifically requested to do so in the solicitation.

6.4 Consideration of data requirements. The following data requirements should be considered when this specification is applied on a contract. The applicable Data Item Description (DIDs) should be reviewed in conjunction with the specific acquisition to ensure that only essential data are requested/ provided and that the DIDs are tailored to reflect the requirements of the specific acquisition. To ensure correct contractual application of the data requirements, a Contract Data Requirements List (DD From 1423) must be prepared to obtain the data, except where DoD Far Supplement 27.475-1 exempts the requirements for a DD Form 1423.

Reference Paragraph	DID Number	DID Title
3.8.3.1	DI-MISC-80876	Welding Procedure Qualification Test Report

6.5 Definitions.

6.5.1 Quality assurance provisions (QAP). A QAP is a contractual requirement that supplements Section 4 of the specification. QAP indicates the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

6.6 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

6.7 Subject term (keyword) listing.

Aluminum footwalk
Bailey bridge
Trusses

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 5420-A404

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:25Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

RECOMMEND A CHANGE:	1. DOCUMENT NUMBER MIL-F-52569C(ME)	2. DOCUMENT DATE (YYMMDD) 921026

3. DOCUMENT TITLE
Footwalk, Assembly: Aluminum, For Bridge, Bailey

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (if applicable) (2) AUTOVON	7. DATE SUBMITTED

8. PREPARING ACTIVITY

a. NAME Geraldine F. Harlow	b. TELEPHONE (Include Area Code) (1) Commercial (703) 704-3469 (2) AUTOVON 654-3468
c. ADDRESS (Include Zip Code) Army Belvoir RDE Center ATTN: SATBE-TSE Fort Belvoir, VA 22060-5606	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.