MIL-B-13157C
1 May 1980
SUPERSEDING
MIL-B-13157B
2 May 1973

MILITARY SPECIFICATION

BRIDGE, FIXED: PANEL, SINGLE LANE, ALUMINUM

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers the components of a class 60, aluminum panel, single-lane, fixed bridge with a 13-foot, 6-1/2-inch roadway.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

FF-B-575	- Bolts, Hexagon and Square.
FF-N-836	- Nut: Square, Hexagon, Cap, Slotted, Castle, Knurled, Welding and Single Ball Seat.
FF-S-92	- Screws, Machine: Slotted, Cross-Recessed or Hexagon Head.
FF-T-791	- Turnbuckle.
FF-W-92	- Washers, Metal, Flat (Plain).
QQ-S-781	- Strapping, Steel, and Seals.
RR-C-271	- Chains and Attachments, Welded, Weldless and Roller Chain.
PPP-B-601	- Boxes, Wood, Cleated-Plywood.
PPP-B-621	- Boxes, Wood, Nailed and Lock-Corner.
PPP-B-636	- Boxes, Shipping, Fiberboard.

MILITARY

MIL-C-104	- Crates, Wood; Lumber and Plywood Sheathed, Nailed and Bolted.

FSC 5420

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Mobility Equipment Research and Development Command, ATTN: DRDME-DS, Fort Belvoir, VA 22060 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:07Z
Check the source to verify that this is the current version before use.

MIL-P-116	- Preservation-Packaging, Methods of.
MIL-T-704	- Treatment and Painting of Materiel.
MIL-C-3774	- Crates, Wood; Open 12,000 and 16,000 Pound Capacity.
MIL-R-12221	- Rivets, Solid: Aluminum Alloy, Grade 7277, Tempered.
MIL-R-52243	- Retainer, Bridge Pin.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-1186	- Cushioning, Anchoring, Bracing, Blocking and Waterproofing; with Appropriate Test Methods.
MIL-STD-1188	- Commercial Packaging of Supplies and Equipment.

DRAWINGS

ME

D7813-1 through 13	- Bridge, Fixed, Panel, Single Lane, Aluminum.
D7856-1	- Heavy Tactical Bridges, Footwalk, Steel, 15 Feet Long 30-Inch Walkway.

(Copies of specificatons, standards, and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

A 36	- Structural Steel.
A 108	- Cold-Finished Carbon Steel Bars, Standard Quality.
A 120	- Pipe, Steel, Black and Hot-Dipped, Zinc-Coated (Galvanized) Welded and Seamless, for Ordinary Uses.
A 148	- High-Strength Steel Castings for Structural Purposes.
A 322	- Hot-Rolled Alloy Steel Bars.
A 441	- High-Strength Low-Alloy Structural Manganese Vanadium Steel.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:07Z
Check the source to verify that this is the current version before use.

A 512	- Cold-Drawn Buttweld Carbon Steel Mechanical Tubing.
A 513	- Electric-Resistance-Welded Carbon and Alloy Steel Mechanical Tubing.
A 519	- Seamless Carbon and Alloy Steel Mechanical Tubing.
A 570	- Hot-Rolled Carbon Steel Sheet and Strip, Structural Quality.
A 611	- Steel, Cold-Rolled Sheet, Carbon, Structural.
B 209	- Aluminum-Alloy Sheet and Plate.
B 211	- Aluminum-Alloy Bars, Rod, and Wires.
B 221	- Aluminum-Alloy Extruded Bars, Rods, Wire, Shapes, and Tubes.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

AMERICAN WELDING SOCIETY (AWS)

A 5.1	- Carbon Steel Covered Arc-Welding Electrodes.
A 5.18	- Carbon Steel Filler Metals for Gas Shielded Arc Welding.
D 1.1	- Structural Welding Code.

(Application for copies should be addressed to the American Welding Society, 2501 Northwest Seventh Street, Miami, FL 33125.)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

3. REQUIREMENTS

3.1 Description. The bridge, or separately procurred components as specified (see 6.2), shall be fabricated as shown on Drawing D7813-1 through - 13, Drawing D7856-1, and as specified herein. The bridge or components required and quantity required shall be as specified (see 6.2).

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the bridge or separately procurred components. Any data (e.g, shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:07Z
Check the source to verify that this is the current version before use.

3.2 First article (preproduction model). The contractor shall furnish the bridge or separately procurred components as specified for examination within the time frame specified (see 6.2), to prove, prior to starting production, that his production methods will produce bridges or bridge components that comply with the requirements of this specification. Examination shall be as specified in Section 4 and shall be subject to surveillance and approval by the Government (see 6.3).

3.3 Material. Material shall be as specified herein and as shown on the applicable drawing. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification. Test reports and analysis for heat treated materials shall be available for inspection. Certificates for other materials and products shall be available for inspection (see 6.7).

3.3.1 Structural steel, shapes and plates. Structural steel, shapes and plates shall conform to ASTM A 36.

3.3.2 Steel bars. Steel bars shall conform to ASTM A 108, UNS G10180 or G10200. Steel for inserts shall be UNS G10350, minimum yield strength 75,000 psi, minimum ultimate tensile strength 95,000 psi.

3.3.3 Pin steel. Pin steel shall conform to ASTM A 322, grade 4140. After fabrication, the pins shall be heat treated, quenched in oil, and drawn to produce a minimum yield strength of 125,000 psi, minimum ultimate tensile strength of 125,000 psi, minimum ultimate tensile strength of 140,000 psi, and a minimum elongation of 15 percent in 2 inches.

3.3.4 Low-alloy steel. Low-alloy steel shall conform to ASTM A 441; the chemical composition shall be such as to produce a steel with acceptable welding qualitites.

3.3.5 Sheet steel. Sheet steel for footwalks shall conform to ASTM A 570 grade 30 or A 611, grade C..

3.3.6 Steel castings. Steel castings shall conform to ASTM A 148, grade 80-40 for truss shoes and grade 120-95 for floorbeam holddown brackets.

3.3.7 Aluminum-alloy plates. Aluminum-alloy plates shall conform to ASTM B 209, alloy alclad 2014, temper T6, unless alloy 6061, temper T6 is specified.

3.3.8 Aluminum-alloy bars and shapes.

3.3.8.1 Aluminum-alloy bars. Aluminum-alloy bars shall conform to ASTM B 211, or B 221, alloy 2014, temper T6.

3.3.8.2 Aluminum-alloy shapes. Aluminum-alloy shapes shall conform to ASTM B 221, alloy 2014, temper T6.

3.4 Welding electrodes. Welding electrodes shall conform to AWS A 5.1 or A 5.18, classification and size as required for the operation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:07Z
Check the source to verify that this is the current version before use.

3.5 Steel pipe. Steel pipe shall conform to ASTM A 120, standard weight or extra strong, except that ends shall be threaded and the hydrostatic test shall not be required.

3.6 Steel tubing. Steel tubing shall conform to ASTM A 512, or A 513, or A 519, grade 1025.

3.7 Retainer pin. Retainer pin shall conform to MIL-R-52243, 7-13/16 inch nominal length for panel pins and 4-1/8 inch nominal length for all other pins.

3.8 Steel chain. Chain shall conform to RR-C-271, type I, grade C, class 3, zinc-coated.

3.9 Bolts. Bolts shall conform to FF-B-575, type II, grade 2 steel, UNC-2A, cadmium or zinc-plated.

3.10 Nuts. Nuts shall conform to FF-B-836, type II, style 4, grade A steel, UNC-2B, cadmium or zinc-plated.

3.11 Washers. Washers shall conform to FF-W-92, type A, grade I, class A, medium or heavy weight, zinc, plated.

3.12 Machine screws. Machine screws shall conform to FF-S-92, type I, styles 1s and 2s, steel, zinc plated.

3.13 Turnbuckles. Turnbuckles shall conform to FF-T-791, type I, form 2, 6-inch clear opening with one jam nut as shown for type II, black, unpainted.

3.14 Aluminum rivets. Aluminum rivets shall conform to MIL-R-12221, types 6 and 7, as required.

3.15 Identification marking. The bridge component shall be metal-die stamped as shown on the applicable drawing. Die stamping shall be legible after painting.

3.16. Treatment and painting. The bridge components except as otherwise specified herein shall be cleaned, treated, and painted in accordance with MIL-T-704, type D, and unless otherwise specified (see 6.2), topcoat shall be forest green conforming to MIL-E-52798 or MIL-E-52929. Pins, bolts, nuts, washers, and threaded portions of components when applicable shall not be painted but shall be preserved as specified in 5.2. Contact surfaces, regardless of whether such contact is between similar or dissimilar metals, shall be cleaned, treated, and painted prior to assembly. Nonpermissable galvanic couples (dissimilar metals), as defined in MIL-STD-889, type II or MIL-T-704, shall be insulated from each other as specified in appropriate standard or specification.

3.17 Stenciling. The nomenclature, Federal stock number, identification mark, weight, and cube shall be stenciled on each bridge component. The letters "NET WT" shall precede the numerals in the weight and the letters "CU" shall precede the cubic displacement. The required information shall be stenciled with 3/4-inch characters on both sides near the center of the floor beams, ramp

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:07Z
Check the source to verify that this is the current version before use.

sills, ramp panels, tapered ramp panels, deck panels and male end post, and on both sides of the top chords of the truss panels and female end posts. The remaining bridge components, except bolts, nuts, and pins, shall be stenciled on one side using the largest size characters that space will permit. Stenciling shall conform to MIL-T-704. Bolts, nuts, and pins shall not be stenciled.

3.18 Workmanship.

3.18.1 Steel farbrication. Steel may be cut by shearing, sawing, or flame-cutting. Burned surfaces of flame-cut material shall be ground or machined to remove cooling checks. All bends shall be made by use of metal dies or fixtures to insure uniformity in size and shape. All burrs shall be removed.

3.18.2 Aluminum fabrication. Aluminum used in the fabrication of the component shall be free from kinks and sharp bends. Straightening of material shall be done by methods that will not cause injury to metal. Surfaces and edges of all finished members shall be smooth and free from kinks, bends, and winds. All bends of a major character shall be made with metal dies or fixtures or insure uniformity of size and shape. Sharp insturments shall not be used for marking bend lines. Aluminum shall not be cut by methods using heat. Aluminum less than 3/8 inch thick may be cut by shearing; aluminum 3/8 inch thick and over shall be cut by routing or by high-speed saws. Shearing and sawing shall be done neatly and accurately.

3.18.3 Riveted connections.

3.18.3.1 Rivet holes. Holes for countersunk manufactured heads of rivets shall be of such depth and angle as will contain the heads snugly and completely without projection and with a maximum of 1/32-inch recess. Rivet holes may be drilled full size in the solid metal at assembly or may be punched under size and reamed to full size at assembly. Holes shall be subpunched and reamed or drilled as follows:

Nominal rivet diameter, inches	Nominal diameter of punched holes, inches	Diameter of drilled or reamed hole, inches
1/2	3/8	17/32
5/8	1/2	21/32
3/4	1/2	25/32
7/8	5/8	29/32

3.18.3.2 Riveting. Parts that are shop riveted together shall be tightly bolted in position before riveting. Rivets shall be driven hot with pressure tools when practical and shall completely fill the rivet holes. Manufactured rivet heads shall be of the button or countersunk type and the driven heads shall be cone point or countersunk type. Rivets heads shall be full, concentric with the rivet shank, and in full contact with the surfaces of the member. Countersunk rivets shall be driven flush with the surrounding surface. Aluminum rivets shall not be heated in excess of 950° F. and shall be driven at a temperature of not less than 850° F. Caulking of rivets shall not be permitted.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:07Z
Check the source to verify that this is the current version before use.

3.18.4 Welders and welding.

3.18.4.1 Welders. Before assigning any welder to manual welding work covered by this specification, the contractor shall provide the contracting officer with certification that the welder has passed qualificatin tests as prescribed by either of the following listed codes for the materials joined and the type of welding operation to be performed and that such qualification is effective as defined by the particular code:

AWS D1.1, Structural Welding Code Section 5, Qualifications
Welding Qualifications of the ASME Boiler and Pressure Vessel Code (Section IX)

3.18.4.2 Welding. The surfaces of parts to be welded shall be free from scale, paint, grease, and other foreign matter. Welding shall be done by the shielded metal-arc or gas metal-arc (MIG) process. Steel welding process shall conform to the provisions of the American Welding Society publication, "D1.1 Structural Welding Code". All welded parts shall be free from cracks and other imperfections that may reduce the effectiveness of the part. Work shall be positioned for flat welding when practicable. Before welding over previously deposited weld metal, all traces of slag shall be removed and the deposit and adjoining base metal shall be wire brushed clean. Where embrittlement of the joined metal may result, preheating or annealing or both shall be employed.

3.18.4.2.1 Jigs and fixtures. Bridge components shall be assembled in steel jigs or fixtures and joined while held in position. Jigs or fixtures shall prevent distortion or limit the distortion to an amount that can be removed by straightening and stress relieving without changing the physical characteristics of the metal.

3.18.5 Steel inserts. The holes for the panel pin inserts in the truss panels and female end post shall be drilled or bored to the undersize diameter specified on the drawings. The steel insert shall be packed in dry ice for a period of not less than 12 hours for a sufficient time to lower the temperature of the insert minus 100° F. The inserts shall then be pressed into the undersize holes in the aluminum components. The insert rings need not be heat treated or refrigerated.

3.18.6 Interchangeability. Bridge components of like description shall be fabricated to be duplicates within the tolerances specified and shall be interchangeable.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsiblity for inspection. Unless otherwise specified in the contract, the contractor is responsbile for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:07Z
Check the source to verify that this is the current version before use.

4.1.1 Acceptability criteria. Bridge components which conform to all requirements in Section 3 and 5 of this specification and pass all applicable examinations in Section 4 of this specification will be considered acceptable by the Government.

4.1.2 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications, standards, and drawings as applicable.

4.1.3 Disassembly inspection. Failure of any examination or test by the preproduction model or separately procurred components, if applicable, shall be cause for disassembly, in the presence of a Government representative, of the preproduction model or components to the extent necessary to determine the cause of the failure. Each disassembled part shall be examined in detail for compliance with this specification and referenced drawings in regard to materials, dimensions, tolerances, and workmanship. Parts not complying with such requirements shall be rejected and shall be cause for rejection of the preproduction model or components. Reassembly with replacement parts and retesting shall be the responsibility of the contractor.

4.1.4 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the Quality Assurance Provisions (QAP) shown on the drawings. The drawings specify the characteristics requiring QAP inspection, the sampling plan. and the basis for acceptance and rejection (see 6.5 and 6.6).

4.2 Classification of inspection. Inspection shall be classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Quality conformance inspection (see 4.4).
(c) Inspection of packaging (see 4.6).

4.3 Preproduction inspection.

4.3.1 Examination. The preproduction bridge or separately procured components as specified shall be examined in accordance with 4.4.2.1 and for the defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.4.2 Examination.

4.4.2.1 Individual. Each bridge component shall be inspected for conformance to the dimensions covered by the Quality Assurance Provisions (QAP) shown on the drawings under "Major - 100 percent inspection." Nonconformance to any of these dimensions shall constitute failure of this examination and shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:07Z
Check the source to verify that this is the current version before use.

4.4.2.2 Sampling. Samples selected in accordance with 4.4.1 shall be examined for the major and minor defects specified in 4.5.1. QAL shall be 2.5 percent defective for major defects and 4.0 percent defective for minor defects.

4.5 Inspection procedure.

4.5.1 Examination. The bridge components shall be examined as specified herein, for the following defects:

Major

101. All dimensions designated major on the QAP other than those under 100 percent inspection not as specified.
102. Material not as specified.
103. Components missing or not as specified.
104. Workmanship not as specified.
105. Weld defects such as flux inclusions, spatter, undercutting, porosity, incorrect size, or lack of fusion with parent metal.
106. Riveting not as specified.

Minor

201. All dimensions not designated major on the QAP, not as specified.
202. Identification marking incorrect, missing or illegible.
203. Treatment and painting not as specified.
204. Stenciling not as specified.

4.6 Inspection of packaging.

4.6.1 Preproduction pack inspection.

4.6.1.1 Examination. Examine the preproduction pack for the defects specified in 4.6.2.3. Presence of one or more defects shall be cause for rejection.

4.6.1.2 Test. Subject the preproduction pack of crated bridge components for level A to the railroad-car test as specified for guide-impact tests in accordance with MIL-STD-1186, appendix A. The car shall strike a string of five empty cars with draft gear extended and brakes set, at a speed of not less than 10 miles or more than 11 miles per hour. At the conclusion of the preproduction pack test, the pack shall be examined. Any shifting of contents, loosening or breaking of holddowns, ties, stays, blocking or bracing, or any visual damage to the components shall constitute failure of the preproduction pack and shall be cause for rejection.

4.6.2 Quality conformance inspection of pack.

4.6.2.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:07Z
Check the source to verify that this is the current version before use.

4.6.2.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.6.2.3 Examination. Samples selected in accordance with 4.6.2.2 shall be examined for the following defects. AQL shall be 2.5 percent defective.

107.	Materials and containers not as specified.	Each incorrect material and each incorrect container shall constitute one defect.
108.	Unpainted and unprotected metal surfaces not coated with preservative as specified for level A.	
109.	Boxed quantities not as specified for level A.	
110.	Bundled quantities not as specified for level A packing.	
111.	Packing not as specified for level A.	
112.	Blocking, bracing, and anchoring not in accordance with the referenced documents for level A.	
113.	Shroud not provided as specified for level A.	
114.	Marking missing, illegible, incorrect, or incomplete for level A or commercial.	

5. PACKAGING

5.1 Preproduction pack. The contractor shall furnish a preproduction pack for examination and test of the crated bridge components within the time frame specified (see 6.2), to prove prior to starting production packaging that the applied preservation, packing and marking, comply with the preparation for delivery requirements of this specification. Examination and test shall be as specified in Section 4 and shall be subject to surveillance and approval by the Government (see 6.4). The preproduction pack may be accomplished utilizing either the preproduction bridge components or the production bridge components. If the preproduction model bridge components are utilized, any preservation and packing shall be removed by the contractor at no expense to the Government when requested by the Government to facilitate comparsion between the preproduction model bridge components and the production bridge components.

5.2 Preservation. Preservation shall be level A or Commercial as specified.

5.2.1 Level A.

5.2.1 Unprotected surfaces. Unpainted exterior metal surfaces of components such as pins, bolts, nuts, washers, threaded sections, or any other unpainted surfaces requiring the application of the contract preservatives in accordance with MIL-P-116, shall be coated with type P-1 preservative. The preservative shall conform to the applicable specification listed in and shall be applied in accordance with MIL-P-116.

5.2.1.2 Bolt and nuts. Bolts of like description, with nuts, preserved in accordance with 5.2.1.1, shall be placed, in quantities of 50 in snug-fitting boxes conforming to PPP-B-636, V3c. Bolts and nuts, placed in boxes of 50 each as above, shall be additionally boxed together in quantities not exceeding 250 pounds in snug-fitting wood boxes conforming to PPP-B-621, class 1, style optional or to PPP-B-601, domestic type, style optional. Strapping shall not be required.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:07Z
Check the source to verify that this is the current version before use.

5.2.1.3 Connecting pins and retainer pins. Connecting pins of like description with the required retainer pins preserved in accordance with 5.2.1.1., shall be boxed together in quantities not exceeding 250 pounds in snug-fitting wood boxes conforming to PPP-B-621, class 1, style optional, or to PPP-B-601, domestic type, style optional. Blocking in accordance with MIL-STD-1186 shall be provided. Strapping shall not be required.

5.2.1.4 Bundling. Cover plates, truss shoes, curbs, base plates, footwalk, and brackets shall be bundled together in pairs. Lateral braces, truss braces, and handrail post shall be bundled in quantities of nine each except that one bundle may contain less than nine to make up the total quantity. Bracing frames and floorbeam holddown brackets shall each be bundled together in quantities of four. Ramp bearings shall be bundled together in quantities of four with the bearings protected against mechanical damage by wood blocks placed and secured between the bearings on each assembly. Strapping conforming to QQ-S-781, type I or IV, finish B, in appropriate sizes and number of straps per bundle shall be used to secure items together into bundles.

5.2.2 Commercial. The bridge components shall be preserved in accordance with MIL-STD-1188.

5.3 Packing. Packing shall be level A or Commercial as specified (see 6.2).

5.3.1 Level A.

5.3.1.1 Loose items. Heavy structural members such as truss, panels, floorbeams, deck panels, ramp panels, tapered ramp panels, ramp sills, male end posts and female end posts shall be shipped loose.

5.3.1.2 Crated items. Boxed and bundled items shall be packed together in a crate or a minimum number of crates, as applicable. Crates shall conform to MIL-C-3774, type I, style A or MIL-C-104, type, class, and style optional. The contents shall be secured to the crate base in a manner to provide minimum cube and shall be blocked, braced, anchored and contents of open crates protected with a shroud in accordance with the appendix to the applicable crate specification and in accordance with MIL-STD-1186.

5.3.2 Commercial. The bridge components, preserved as specified in 5.2, shall be packed in accordance with MIL-STD-1188.

5.4 Marking.

5.4.1 Military. Packages, bundles, shipping containers and loose items shall be marked in accordance with MIL-STD-129.

5.4.2 Commercial. Marking for commercial packaging shall be in accordance with MIL-STD-1188.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:07Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Intended use. The bridge components are intended to be used in the assembly of prefabricated tactical bridges.

6.2 Ordering data. Procurement documents should specify the following.

(a) Title, number, and date of this specification.
(b) Bridge or bridge components required and quantity (see 3.1).
(c) Time frame required for submission of preproduction model bridge or components (see 3.2).
(d) When topcoat shall be other than forest green (see 3.16).
(e) Time frame required for submission of the preproduction pack (see 5.1).
(f) Degree of preservation and degree of packing required (see 5.2 and 5.3).

6.3 Preproduction model. Any changes or deviations of production bridge components from the approved preproduction model during production will be subject to the approval of the contracting officer. Approval of the preproduction model will not relieve the contractor of his obligation to furnish bridge components conforming to this specification.

6.4 Preproduction pack. Any changes or deviations of production packs from the approved preproduction pack will be subject to the approval of the contracting officer. Approval of the preproduction pack will not relieve the contractor of his obligation to preserve, pack, and mark the bridge components in accordance with this specification.

6.5 Quality assurance provisions (QAP). The contracting officer should require the contractor to maintain records of all QAP inspection. A suggested paragraph is as follows:

"The contractor shall maintain complete records of all examination and tests performed to verify the requirements of classified QAP characteristics. The records shall include as a minimum, lot size, sample size, drawing requirement, actual measurement, number and type of deficiencies found, quantity approved, quantity rejected, corrected action taken when applicable."

6.6 Definitions.

6.6.1 Quality assurance provisions (QAP). A QAP is a contractual requirement that supplements section 4 of the specification. QAP indicates the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

6.7 Recycled material. It is encouraged that recycled material be used when practical as long as it meets the requirements of the specification (see 3.3).

Custodians:
Army - ME
Navy - MC

Preparing activity:
Army - ME

Project 5420-0135

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:07Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE: MIL-B-13157C Bridge, Fixed: Panel, Single Lane, Aluminum

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426

REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:07Z
Check the source to verify that this is the current version before use.