15 November 1972
SUPERSEDING
MIL-M-13130B
24 February 1959

MILITARY SPECIFICATION

METER, AUDIO LEVEL TS-585( )/U

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE.

1.1 This specification covers one type of audio level meter for measuring audio frequency power over a range of 0.1 to 5,000 milliwatts and from minus 10 below to plus 37 decibels above 1 milliwatt over a frequency range of 30 to 10,000 Hz.

2. APPLICABLE DOCUMENTS.

2.1 Documents. The following documents of the issue in effect at date of invitation for bids or request for proposal, form a part of the specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

NN-P-71	Pallet, Material Handling, Wood (General Construction Requirements)
PPP-B-585	Box, Wood, Wirewound
PPP-B-601	Boxes, Wood, Cleated-Plywood
PPP-B-621	Box, Wood, Nailed and Lock Corner
PPP-B-636	Box, Fiberboard
PPP-F-320	Fiberboard; Corrugated and Solid, Steel Stock (Container Grade), and Cut Shapes
PPP-T-76	Tape, Pressure Sensitive Adhesive Paper (for Carton Sealing)
PPP-T-97	Tape, Pressure Sensitive Adhesive, Filament Reinforced
QQ-S-781	Steel Strapping, Flat

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-P-116	Preservation, Methods of
MIL-P-11268	Parts, Materials, and Processes Used in Electronic Equipment
MIL-M-13231	Marking of Electronic Items
MIL-F-14072	Finish for Ground Signal Equipment

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129	Marking for Shipment and Storage
MIL-STD-147	Palletized and Containerized Unit Loads 40" x 48" 4-Way (Partial) Pallet Skids, Runners, or Pallet-Type Base
MIL-STD-252	Wired Equipment; Classification of Visual and Mechanical Defects
MIL-STD-454	Standard General Requirements for Electronic Equipment
MIL-STD-810	Environmental Test Methods

DRAWINGS

ELECTRONICS COMMAND

SC-DL-47548	Output Meter, TS-585( )/U Drawing and Data List
SC-A-46439	List of Accessories for Package Tester

SHIPS SYSTEMS COMMAND

10-T-2145L	Shock Testing Machine, Light Weight

(Copies of specifications, standards and drawings required by contractor in connection with specific procurement functions should be obtained from the procuring activity, or as directed by the contracting officer. Both the title and number or symbol should be stipulated when requesting copies).

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 First article. When specified in the contract or purchase order, the contractor shall furnish first article units in accordance with 4.3.

3.2 Construction. The equipment shall be constructed in accordance with SC-DL-47548 and the requirements specified herein.

3.3 Parts, materials and processes-general. In addition to the requirements of this specification, the requirements of MIL-P-11268, including the selection requirements therein, shall apply.

3.4 Finish, protective. The equipment shall be finished in accordance with MIL-F-14072. This includes finish of hardware, such as screws, etc., and necessary touch-up after mounting. The final paint film of type 1 surfaces shall be final Film E, semi-gloss, light gray enamel, conforming to MIL-F-14072.

3.5 Marking. The marking shall conform to MIL-M-13231.

3.5.1 Visibility. Wherever practicable, parts and assemblies shall be so mounted that their identification markings shall be readily visible with a minimum disassembly of the equipment.

3.5.2 Serial numbers. Serial numbers are required.

3.6 Bounce preconditioning. Each equipment produced and first article shall be subjected to the bounce preconditioning of 4.6. After bounce preconditioning, the equipment shall be inspected for loose or broken parts or controls. If a failure occurs, the loose or broken part or control shall be repaired or replaced and the test repeated. Bounce preconditioning shall be performed prior to Group A inspection.

3.7 Electrical.

3.7.1 Power range and accuracy. The audio level meter shall be capable of measuring power, over the range of .1 to 5,000 milliwatts and from minus 10 decibels below to plus 37 decibels above 1 milliwatt. An auxiliary multiplier circuit shall be provided to indicate the measurement of four milliwatt ranges and four corresponding decibel ranges as follows:

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

Milliwatts	Decibels
0.1 to 5	-10 to 7
1 to 50	0 to 17
10 to 500	10 to 27
100 to 5,000	20 to 37

The accuracy of the indications of all numbered points on the milliwatt scale of each range shall be within ±10 percent, except that the midscale value (11 db point) and full scale values shall be within ±.4 db, for a frequency range of 30 to 10,000 Hz when tested in accordance with 4.7.1.

3.7.2 Impedance range and accuracy. The audio level meter shall be provided with an adjustable load impedance, variable over the range of 2.5 to 20,000 ohms in 40 discrete steps. The forty (40) discrete impedance steps shall be as follows: 2.5, 3, 4, 5, 6, 8, 10, 12.5, 15, 20, 25, 30, 40, 50, 60, 80, 100, 125, 150, 200, 250, 300, 400, 500, 600, 800, 1000, 1250, 1500, 2000, 2500, 3000, 4000, 5000,6000, 8,000, 10,000, 12,500, 15,000 and 20,000 ohms. The accuracy of each impedance value shall be within ±5 percent for a frequency range of 30 to 10,000 Hz when tested in accordance with 4.7.2.

3.7.3 Dielectric strength. There shall be no breakdown or flashover of any circuits in the audio level meter when tested in accordance with 4.7.3.

3.7.4 Impedance switch. The resistance between the blades, studs and center bushing shall not exceed 0.015 ohm. The switches shall be provided with a cam-type detent, and the contact between a switch blade and any stud shall be indicated by an audible click, or by other effective means. The switch shall show no degradation in physical and electrical performance when tested in accordance with 4.7.4.

3.8 Environmental. The audio level meter shall be constructed so that no fixed part shall become loose, cracked, flaked, pitted or blistered, no movable part of control shall be shifted in setting, position or adjustment, and no permanent degradation shall be caused below that specified in the following environmental conditions:

3.8.1 Fungus. The audio level meter shall show no evidence of viable fungus and shall meet the electrical requirements of 3.7.1 and 3.7.2 for readings specified in 4.5.3.3 a and b before and after fungus test, when tested in accordance with 4.8.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

3.8.2 Low temperature. The audio level meter shall be subjected to the low temperature extremes of -4°F operating and -65°F storage and shall meet the electrical requirements of 3.7.1 and 3.7.2 for readings specified in 4.5.3.3c and b at times specified when tested in accordance with 4.8.2.

3.8.3 High temperature. The audio level meter shall be subjected to the high temperature extremes of 125°F operating and 160°F storage and shall meet the electrical requirements of 3.7.1 and 3.7.2 for readings specified in 4.5.3.3a and b at times specified when tested in accordance with 4.8.3.

3.8 4 Altitude. The audio level meter shall be subjected to the altitudes specified and shall meet the electrical requirements of 3.7.1 and 3 7.2 for readings specified in 4 5 3.3a and b at times specified when tested in accordance with 4.8.4.

3.8 5 Humidity. The audio level meter shall exhibit no physical damage of parts and material, such as corrosion, rust, blistering, swelling, deterioration, etc., or electrical degradation, and shall meet the electrical requirements of 3 7.1 and 3 7 2 for readings specified in 4.5.3.3a and b at times specified when tested in accordance with 4.8.5.

3 8.6 Salt fog. The audio level meter shall show no evidence of corrosion as evidenced by any visible degradation that can be attributed to flaky, pitted, blistered, or otherwise loosened finish or metal surface and shall meet the electrical requirements of 3.7.1 and 3.7.2 for readings specified in 4.5 3 3a and b at times specified, when tested in accordance with 4.8.6.

3.8.7 Shock, ballistic. The audio level meter shall show no evidence of physical damage except minor surface abrasion and shall meet the electrical requirements of 3.7.1 and 3.7.2 for readings specified in 4.5.3 3a and b at times specified when tested in accordance with 4.8.7.

3.8.8 Bounce, loose cargo. The audio level meter shall show no evidence of physical damage except minor surface abrasion and shall meet the electrical requirements of 3.7.1 and 3.7.2 for readings specified in 4.5.3.3a and b before and after bounce test when tested in accordance with 4.8.8.

3.8.9 Vibration. The audio level meter shall show no evidence of breakage or loosening of parts and shall meet the electrical requirements of 3.7.1 and 3.7.2 for readings specified in 4.5.3.3a and b before and after vibration test, when tested in accordance with 4.8.9.

3.9 Interchangeability. Like units, assemblies, subassemblies and replaceable parts shall meet Requirement 7 of MIL-STD-454. Inspection shall be in accordance with 4.9.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

3.10 Workmanship.

a. Adhesives

b. Cables, cords, and wires, electrical

c. Wire (harnessing)

d. Lubricants

e. Plastic material and parts

f. Rubber

g. Tropicalization of material and parts

h. Wiring and cabling

i. Connectors (electrical)

j. Printed wiring assemblies

k. Screws, other threaded devices, and related parts

l. Tightening of threaded parts

m. Riveting

n. Brazing, soldering and welding

o. Welding

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (Does not include preparation for delivery. See 4.3).

b. Inspections covered by subsidiary documents. (See 4.4).

c. Quality conformance inspections.

(1) Quality conformance inspection of equipment before preparation for delivery. (See 4.5).

(2) Quality conformance inspection of preparation for delivery (See 4.11).

4.3 First article. Unless otherwise specified in the contract or purchase order, the first article inspection shall be performed by the contractor.

4.3.1 First article units. The contractor shall furnish three (3) first article units of the complete audio level meter and one (1) unit of the impedance switch assembly.

4.3.2 First article inspection. The first article inspection shall consist of the inspections specified in subsidiary documents covering the items listed in 4.4, preconditioning specified in 4.6, and the inspections specified for Groups A, B and C (see Tables I, II and III respectively) and a specific Group C test on one (1) unit of the impedance switch assembly. The inspection shall be performed in the following order 4.4, 4.6, Group A and B for all units, and designated units for specific subgroups within Group C. After completion of Group C environmental tests, conforming units shall be reinspected and shall pass all Group A inspections.

4.3.3 First article data. The first article test plan and test report(s) shall be as required in the contract or purchase order.

4.4 Inspection covered by subsidiary documents. The following shall be inspected under the applicable subsidiary documents as part of the inspection required by this specification, and the inspection requirement specified in the contract or purchase order.

Item	Where required
Parts, materials and processes-general	3.3
Finish	3.4
Marking	3.5
Workmanship	3.10

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

4.5 Quality conformance inspection of equipment before preparation for delivery. The contractor shall perform the inspection specified in 4.4, 4.6 and 4.5.1 through 4.5.4. This does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to insure compliance with all specification requirements.

4.5.1 Group A inspection. Each unit on contract or purchase order shall be inspected for conformance to the inspections specified in Table I. Discrete lots shall be formed only from units that pass this inspection. Factors of lot composition not defined herein, or in the contract or purchase order, shall be in accordance with MIL-STD-105. Each lot shall be subject to sampling inspection, utilizing the procedures of MIL-STD-105, using the general inspection levels, and AQL's indicated in Table 1.

4.5.1.1 Order of inspection within Group A. Group A inspection shall be performed in an order satisfactory to the Government.

TABLE 1 Group A inspection

Inspection	Req Para.	Test Para.	AQL Major	AQL Minor
Visual and mechanical				
Workmanship	3.10	4.10	1.5 dphu*	6.5 dphu
Electrical				
Power range and accuracy Impedance range and accuracy	3.7.1 3.7.2	4.7.1 4.7.2	2.5 dphu for the group	**

* Defects per hundred units
** All electrical tests are major

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

4.5.2 Group B inspection. Group B inspection shall normally be performed on inspection lots that have passed Group A inspection and on samples selected from units that have been subjected to and met the Group A inspection. This inspection shall conform to Table II and to the special inspection levels of Table I of MIL-STD-105.

TABLE II Group B inspection

Inspection	Req Para.	Test Para	AQL
Interchangeability	3.9	4.9	6.5 dphu*
Dielectric strength	3.7.3	4.7.3	4 dphu

* Defects per hundred units

4 5.2.1 Group B sampling plans. The Group B sampling plans, for the AQL's ed in Table II shall be as follows.

AQL	Inspection Level
4.0 percent	S-4
6.5 percent	S-4

4.5 2.2 Order of inspection within Group B Group B inspection shall be performed in an order satisfactory to the Government.

4.5.3 Group C inspection. Group C inspection shall be performed on units that have passed Group A and B inspection and on a unit of the impedance switch assembly. The inspection shall consist of the inspections specified in Table III. Samples shall be selected in accordance with 4.5.3.1.

4.5.3 1 Sampling for inspection.

4.5.3.1.1 Three (3) samples of complete equipment shall be selected at random, one (1) sample for each Subgroup 1 through Subgroup 3 in Table III. One (1) sample of the impedance switch assembly shall be selected at random from the production line for Subgroup 4 in Table III. The samples selected shall be at the start of the contract rom the first quality conformance inspection lot. These samples shall constitute oup C requirements for first 200 units produced.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

4.5.3.1.2 Thereafter, two (2) samples of the complete equipment shall be selected at random, one (1) sample for each Subgroup 2 and Subgroup 3 in Table III from every 200 units and fraction thereof produced.

4.5.3.1.3 The impedance switch assembly shall be selected after assembly but prior to connecting wiring.

4.5.3.2 Order of inspection within Group C. Group C inspection shall be performed in an order which is satisfactory to the Government.

Inspection	Req Para.	Test Para.
Subgroup 1		
Fungus *	3.8.1	4.8.1
Subgroup 2		
Low Temperature	3.8.2	4.8.2
High Temperature	3.8.3	4.8.3
Altitude	3.8.4	4.8.4
Humidity	3.8.5	4.8.5
Subgroup 3		
Salt Fog *	3.8.6	4.8.6
Shock, ballistic	3.8.7	4.8.7
Bounce, loose cargo	3.8.8	4.8.8
Vibration	3.8.9	4.8.9
Subgroup 4		
Impedance switch	3.7.4	4.7.4

* The equipment shall be thoroughly washed cleaned, dried and refurbished after this inspection before proceeding with subsequent inspection.

4.5.3.3 Evaluation of samples submitted to individual Group C inspection. After referenced complete equipment samples in 4.5.3.1 have been subjected to an individual Group C inspection test and prior to subjection to the next Group C test, unless otherwise specified in the individual test, the sample must be subjected to and meet the following:

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

a. Power at 30 and 10,000 Hz with multiplier at 0.1 and 10, readings shall be token at low, 11 db and high power points (ref 3.7.1 and 3.7.2).

b. Impedance at 30, 150, 1000, 3000 and 10,000 Hz with multip''er c 0.1 and 10, readings shall be taken at impedance points 2.5, 5.0 and 20,000 ohms. (ref 3.7 1 and 3.7.2).

4.5.3 4 Noncompliance. The contractor shall immediately report in writing each Group C failure occurrence, including details of the failure and characteristics affected The contractor shall immediately investigate the cause of failure and further report the results of investigation and details of the proposed corrective action on (i) the process and materials, as applicable, and (ii) all units of product which were manufactured under the same conditions and which the Government considers subject to the same failure. Reports shall be forwarded to the responsible technical activity designated in the contract through the Government quality assurance representative. After corrective action has been taken additional samples shall be subjected to Group C inspection (all inspections, or the inspections which the sample failed, at the option of the technical activity). However, final acceptance and shipment will be withheld until Group C reinspection results have shown that the corrective action was effective and approved by the technical activity.

4 5.4 Reinspection of conforming Group B and C samples Unless otherwise specified, samples which have been subjected to and passed both Group B and C inspection, except impedance switch assemblies subjected to the Subgroup 4 test in Table III, may be accepted on contract or purchase order provided all damage is repaired and the samples are subjected to and pass Group A inspection.

4.5.5 Disposition of Group C samples. Unless otherwise specified, samples which have been subjected to and passed Group C inspection, may be delivered on contract or purchase order provided samples meet requirements of 4.5.4, except impedance switch assemblies subjected to Subgroup 4 test in Table III shall not be accepted on the contract.

4.6 Bounce preconditioning. Each equipment produced and first article shall be placed in its normal operating position on the table of a package tester of suitable capacity as made by the L.A.B. Corporation, Skaneateles, New York, with accessories as per Model 1000 SC and SC-A-46439, or equal. The package tester, shafts in phase, shall have a speed such that it is just possible to insert a 1/32 inch thick strip of material under one corner or edge of the equipment under test to a distance of 3 inches as the equipment bounces. The equipment shall be subjected to this preconditioning for 1 minute and shall meet the requirements of 3.6.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

4.7 Electrical.

4.7.1 Power range and accuracy. All the numbered milliwatt scale points as well as the 11 db center scale point of each of the four ranges, shall be checked at four frequencies, namely, 30, 150, 2500, and 10,000 Hz, at the impedance values of 6, 100, 3,000 and 10,000 ohms. All measurements shall be made using sinusoidal voltages having not more than 1 percent distortion. The audio level meter shall meet the requirements of 3.7.1.

4.7.2 Impedance range and accuracy. Each of the 40 impedance values from 2.5 to 20,000 ohms shall be checked at frequencies of 30, 150, 400, 1000, 3000 and 10,000 Hz. Each impedance value shall be tested with range multiplier switch settings of "X.1" and "X10". Sufficient power shall be applied to produce a midscale (11 db point) reading on the respective range. All measurements shall be made using sinusoidal voltages having not greater than 1 percent distortion. The audio level meter shall meet the requirements of 3.7.2.

4.7.3 Dielectric strength. The insulation strength of all circuits shall be tested ro withstand a minimum of 1,500 volts. The test voltage shall be dc or peak ac of the same value, and shall be applied for 10 seconds between each circuit and ground. The audio level meter shall meet the requirements of 3.7.3.

4.7.4 Impedance switch. The impedance switch shall be connected in a circuit equivalent to that used in the equipment and operated 10,000 times. One operation shall consist of rotating the movable elements from one extreme position and then back to the initial position. After completion of 10,000 operations the switch shall be disassembled and inspected and shall meet the requirements of 3.7.4.

4.8 Environmental. The audio level meter shall be tested in accordance with the following environmental conditions:

4.8.1 Fungus. The audio level meter in its normal operating configuration, shall be subjected to 28 days of the fungus test specified in Procedure 1, Method 508 of MIL-STD-810 and shall meet the requirements of 3.8.1.

4.8.2 Low temperature. The audio level meter in its normal operating configuration shall be subjected to the low temperature test specified in Procedure 1, Method 502, of MIL-STD-810 with temperatures in Step 2 held for 24 hours and in Step 4 held for 4 hours, and shall meet the requirements of 3.8.2.

4.8.3 High temperature. The audio level meter in its normal operating configuration shall be subjected to the high temperature test specified in Procedure 1, Method 501, of MIL-STD-810, with temperature in Step 4 held for 4 hours, and shall meet the requirements of 3.8.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

4.8.4 Altitude. The audio level meter in its normal operating configuration shall be subjected to the altitude test specified in Procedure 1, Method 500 of MIL-STD-810, with altitude in Step 3 held for 1 hour, and shall meet the requirements of 3.8.4.

4.8.5 Humidity. The audio level meter in its normal operating configuration shall be subjected to the humidity test specified in Procedure II, Method 507 of MIL-STD-810, and shall meet the requirements of 3.8.5.

4.8.6 Salt fog. The audio level meter in its normal operating configuration shall be exposed to the salt fog test in accordance with Procedure 1, Method 509, of MIL-STD-810 for 48 hours and shall meet the requirements of 3.8.6.

4.8.7 Shock, ballistic. The audio level meter shall be tested as follows and shall meet the requirements of 3.8.7.

4.8.7.1 Apparatus. The shock test machine shall be in accordance with 10-T-2145-L.

4.8.7.2 Installation of equipment. The equipment, as prepared for field transportation, shall be mounted in such a way as to approximate the actual rigidity encountered in service in the utilization of the equipment.

4 8.7.3 Procedure. A total of nine blows shall be applied Three blows shall be applied parallel to each of the three principal axes of the equipment being tested. The height of hammer drop for the back blow and side blow shall be 1 foot, 2 feet and 3 feet. For the top blow, the height of hammer drop shall be 2 feet, 3 feet and 4 feet.

4.8.7.4 Performance. After each three blows of the hammer the equipment shall meet the requirements of 3.8.7. Adjustment will be permitted to external controls only.

4.8.7.5 Visual inspection. The equipment shall be visually inspected after each blow and a record made of any damage. Minor damage or distortion will be permitted, provided such damage or distortion cannot in any way impair the ability of the equipment to perform its principal functions.

4.8.8 Bounce, loose cargo. The audio level meter as prepared for field transportation, shall be subjected to the loose cargo, bounce test specified in Part 2, Procedure XI, Method 514 of MIL-STD-810 except as follows:

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

The package tester shall be operated at a speed of 284 rpm ±2 rpm for a period of 1 hour. At the end of each 10 minute period, turn the test item to rest on a different face so that at the end of the 1 hr period the test item will have rested on each of the six faces. (top, bottom, sides and ends). At the end of the 1 hr period the test item shall be operated and meet the requirements of 3.8.8.

4.8.9 Vibration. The audio level meter shall be subjected to the vibration test specified in Part 1, Procedure IX, Method 514 of MIL-STD-810, and shall meet the requirements of 3.8.9.

4.9 Interchangeability. The dimensions listed below shall be gaged or measured to determine conformance to the physical interchangeability requirements of 3.9. When a listed dimension is not within specified or design limits, it shall be considered a major defect.

a. External and internal dimensions of case, cover and insertable assemblies, when such dimensions affect mating of parts.

b. Dimensions of cavities, when such dimensions affect insertion of items.

c. Location of hinges and fasteners on separable parts or assemblies which must mate, such as case, covers and mountings.

d. Location of switches, sockets and fasteners.

e. Location of covers and fasteners on carrying case which must mate.

f. Location of panel mounting screw holes on basic unit for mating with case.

g. Location of connectors, locking pins, fasteners, slides and mountings which receive mating parts or plug-in assemblies and major units; and location of the mating parts on the plug-in assembly or major unit.

h. Size and form of special threads.

4.10 Visual and mechanical. The equipment shall be subjected to a thorough visual and mechanical inspection. The defects shall be classified in accordance with MIL-STD-252.

4.11 Quality conformance inspection of preparation for delivery. Preparation for delivery shall be inspected in accordance with MIL-P-116 to determine conformance to the requirements of Section 5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY.

5.1 Preservation and packaging. Preservation and packaging shall be level A or C, as specified (see 6.2b).

5.1.1 Level A.

5.1 1.1 Cleaning. Meter, Audio Level TS-585( )/U shall be cleaned in accordance with process C-1 of MIL-P-116.

5.1.1.2 Drying. Meter, Audio Level TS-585( )/U shall be dried in accordance with the applicable procedures of MIL-P-116.

5.1.1.3 Preservation application. None required.

5.1 1.4 Unit packaging. Unit packaging shall be in accordance with the methods prescribed in MIL-P-116, as specified herein.

5.1.1.4.1 Technical manuals. Each technical manual shall be packaged method -1.

5.1.1.4.2 Each meter, Audio Level TS-585( )/U shall be packaged method III. Cushion the meter on all surfaces with cells or pads or both fabricated of fiberboard conforming to PPP-F-320, type CF, class weather-resistant designed to protect all projections and absorb the shock of impact in handling and transit. Place the cushioned meter within a close-fitting, fiberboard box conforming to PPP-B-636, W5c. Place the technical manuals, packaged as specified in 5.1.1 4.1, on top of the contents, directly under the lid of the box. Close the box in accordance with the appendix of the box specification.

5.1.2 Level C. Each Meter, Audio Level TS-585( )/U shall be preserved and packaged in a manner that will afford adequate protection against corrosion, deterioration and damage during shipment from the supply source to the first receiving activity.

5.2 Packing. Packing shall be level A, B or C, as specified (see 6.2b)

5.2.1 Level A.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

5.2.1.1 Palletized load. A quantity of Meter, Audio Level TS-585( )/U, packaged as specified in 5.1, shall be placed on pallets in conformance with MIL-STD-147, load type 1, with a weather-resistant fiberboard cap (storage aid 4) positioned over the load.

5.2.1.2 Less than palletized load When quantities per destination are less than a pallet load a quantity of Meter, Audio Level TS-585( )/U, packaged as specified in 5.1, shall be packed within a close-fitting fiberboard box conforming to PPP-B-636, type CF, class weather-resistant. Closure shall be in accordance with the appendix of the box specification.

5.2.2 Level B.

5.2.2.1 Palletized load. A quantity of Meter, Audio Level TS-585( )/U, packaged as specified in 5.1, shall be palletized as specified in 5.2.1 1, except that the fiberboard cap shall be class domestic.

5.2.2.2 Less than palletized load. When quantities per destination are less than a pallet load, a quantity of Meter, Audio Level TS-585( )/U, packaged as specified in 5.1, shall be packed within a close-fitting fiberboard box conforming to PPP-B-636, class domestic. Closure shall be in accordance with the appendix of the box specification.

5.2.3 Level C.

5.2.3.1 Palletized load. A quantity of Meter, Audio Level TS-585( )/U, packaged as specified in 5.1, shall be palletized with pallets and caps of the type, size and kind commonly used for the purpose and shall conform to the applicable carrier rules and regulations.

5.2.3.2 Less than palletized load. Meter, Audio Level TS-585( )/U, packaged as specified in 5.1, shall be packed in shipping containers in a manner that will afford adequate protection against damage during direct shipment from the supply source to the first receiving activity. These packs shall conform to the applicable carrier rules and regulations.

5.3 Marking. In addition to any special marking required by the contract or order, each unit package, exterior container and palletized load shall be marked in accordance with MIL-STD-129.

5.4 General.

5.4 1 Army procurements (see 5.2.1, 5.2.2 and 5 2.3).

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

5.4.1.1 Level A packing shall be as follows:

5.4.1.1.1 Consolidation. A quantity of Meter, Audio Level TS-585( )/U, packaged as specified in 5.1, shall be packed within a close-fitting fiberboard box conforming to PPP-B-636, type CF, class weather-resistant. Box closure shall be as specified in the appendix of the box specification. To facilitate palletization, fiberboard boxes shall be uniform in size and contain equal quantities of the packaged items to the greatest extent practicable.

5.4.1.1.2 Palletized load. A quantity of containers, packed as specified in 5.4 1.1, shall be placed on a pallet, load type 1, conforming to MIL-STD-147, except that the pallet shall be softwood conforming to NN-P-71, type IV, size 2. A fiberboard cap shall be employed over the load having two sides extending down the stacked load at least 12 inches to accommodate marking requirements. The cap shall be fabricated of fiberboard conforming to PPP-F-320, class weather-resistant, W5s or V3c. The load shall be "bonded" to the pallet by strapping.

5.4.1.1.3 Less than palletized load. When quantities per destination are less than a pallet load, the containers packed as specified in 5.4.1.1 shall be waterproofed, tape conforming to PPP-T-76, in accordance with the taping requirements of the appendix of the box specification. A quantity of the waterproofed containers shall be placed within a close-fitting box conforming to PPP-B-601, overseas type; PPP-B-621, style 4, class 2; or PPP-B-585, style 2 or 3, class 3. When the gross weight exceeds 200 pounds, or the container length and width is 48 x 24 inches or more and the weight exceeds 100 pounds, 3 x 4 inch skids, laid flat, shall be applied in accordance with the requirements of the container specification, or if not specified in the specification, in a manner which will adequately support the item and facilitate the use of material handling equipment. Closure and strapping shall be in accordance with the applicable container specification or appendix thereto except that metal strapping shall conform to QQ-S-781, type 1, class B.

5.4.1.2 Level B, packing shall be as follows:

5.4.1.2.1 Consolidation. A quantity of Meter, Audio Level TS-585( )/U, packaged as specified in 5.1, shall be packed as specified in 5.4.1.1.1.

5.4.1.2.2 Palletized load. A quantity of containers packed as specified in 5.4.1.2.1, shall be palletized as specified in 5.4.1.1.2.

5.4.1.2.3 Less than palletized load. When quantities per destination are less than a pallet load, the containers packed as specified in 5.4.1.2.1 shall be reinforced by sure-sensitive filament tape conforming to PPP-T-97, type IV, as specified in the appendix of the box specification. No further packing shall be required.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

5.4.1.3 Level C packing shall be as follows:

5.4.1.3.1 Consolidation. A quantity of Meter, Audio Level TS-585( )/U, packaged as specified in 5.1, shall be packed as specified in 5.4.1.1 1, except that the fiberboard boxes shall be class domestic.

5.4.1.3.2 Palletized load. A quantity of containers, packed as specified in 5.4.1.3.1, shall be palletized as specified in 5.4.1.1.2, except that the fiberboard cap shall be class domestic.

5.4.1.3.3 Less than palletized load. When quantities per destination are less than a pallet load the containers packed as specified in 5.4.1 3.1 shall be used as the shipping container. No further packing shall be required.

5.4.2 Navy procurements. For Navy procurements the use of polystyrene loose fill material (such as strips, strands and beads) is prohibited for packaging and packing applications.

6. NOTES.

6 1 Intended use. The audio level meter is used at direct, general and depot support.

6.2 Ordering data. Procurement documents should specify the following:

a. Title, number and date of this specification and any amendment thereto

b. Level of preservation, packaging, packing and marking (see Section 5).

c. If rough handling and functional tests are required

d. Quantity of first articles required.

e. Place of final inspection.

f. Technical literature required.

g. Quantity of tools and running spare parts required.

6.3 Nomenclature. The contractor should apply the nomenclature (item name and type designation) in accordance with the applicable clause in the contract. The parentheses in the type designation will be deleted or replaced by a letter identifying the particular design for example: SG-12( )/U to SG-12F/U, or AN/URM-73( ) to AN/URM-73C.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

6.4 Group C inspection. Approval to ship may be withheld, at the discretion of the Government, pending the decision from the contracting officer on the adequacy of corrective action (see 4.5.3.4).

6.5 Sampling inspection. Sampling inspection by the Government will be limited to the amount deemed necessary to determine compliance with the contract or purchase order and will be limited in severity to the definitive quality assurance provisions established on this specification and the contract. The amount of sampling inspection by the Government will be adjusted to make maximum utilization of the contractor's quality control system and the quality history of the product.

Custodian:
Army - EL

Preparing Activity:
Army - EL

Review activities:
Navy - MC

User activity:
Army - AV, Mu

Project Number: 6625-0507

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

FOLD

Department of the Army
Headquarters
U S.Army Electronics Command
Fort Monmouth, New Jersey 07703

POSTAGE AND FEES PAID

OFFICIAL BUSINESS

Commanding General
U.S.Army Electronics Command
ATTN AMSEL-RD-ED
Fort Monmouth, New Jersey 07703

To detach this form, cut along this line

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No 22-R255

INSTRUCTIONS This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost Comments and the return of this form will be appreciated Fold on lines on reverse side staple in corner, and send to preparing activity Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements

SPECIFICATION MIL-M-13130C(EL) METER, AUDIO LEBEL TS-585( )/U

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1 HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A GIVE PARAGRAPH NUMBER AND WORDING

B RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2 COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3 IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4 REMARKS *(Attach any pertinent data which may be of use in improving this specification If there are additional papers attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED

ESC-FM 1068-68

To detach this form, cut along this line

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:05Z
Check the source to verify that this is the current version before use.