MIL-R-44015(GL)
AMENDMENT- 1
6 May 1982

MILITARY SPECIFICATION

REFRIGERATOR-CONTAINER, FIELD, 8 FEET BY 8 FEET BY 10 FEET

This amendment forms a part of Military Specification MIL-R-44015(GL), dated 23 November 1979, and is approved for use by Natick Research and Development Laboratories, Department of the Army and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 2

2.1, under "SPECIFICATIONS, MILITARY": Add "MIL-R-44035 Refrigerator unit, Electric for Refrigerator-Container, Field, 8 x 8 x 10 Foot".

PAGE 3

3.1, line 3: Delete "6.2" and substitute "6.3".

3.3, line 4: Delete "(see 6.5)".

Add new sentence: "Cadmium shall not be used on any hardware or components in the interior of the container (see 6.5)."

PAGE 4

3.4, line 6, after "refrigeration unit": Delete the period. Add "conforming to MIL-R-44035."

PAGE 6

3.5.4, line 4: Delete "4.5.2.9" and substitute "4.5.2.8".

3.5.6, line 8, after "higher": Add "than".

3.5.8, first sentence: Delete and substitute "Unless otherwise specified (see 6.2), the contractor shall provide one spacer block and one coupler with each container ."

Line 4, after "spacer": Delete "blocks*' and substitute "block and coupler".

Line 6, after "spacer": Delete "blocks" and substitute "block and coupler".

FSC 4110

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T23:22Z
Check the source to verify that this is the current version before use.

PAGE 11

4.4.2.1: Delete and substitute:

"4.4.2.1 End item examination. The end item shall be examined in accordance with 4.4.2. 1.1 and 4.4.2.1.2. The lot size shall be expressed in units of one container. The sample unit shall be one container. "

4.4.2.1.1: Delete and substitute:

"4.4.2.1.1 Visual examination. The end item shall be examined for the defects listed in table II. The inspection level shall be S-2 and the acceptable quality level (AQL) shall be 2.5 major and 6.5 total (major and minor combined) defects per hundred units."

PAGE 12

Table 11, third feature under "Examine": Delete "'blocks" and substitute "block and coupler".

4,4.2.1.2: Delete and substitute:

"4.4.2.1.2 Dimensional and weight examination. The end item shall be examined for conformance to the specified dimensions and weight. Any dimension or weight deviating from the specified requirement shall be classified as a defect. The inspection level shall be S-2 and the AQL shall be 4.0 defects per hundred units."

4.4.2.2: Delete and substitute:

"4.4.2.2 End item testing. Each container shall be tested as specified in 4.5.2.9. One out of 25 containers shall be tested as specified in 4.5.2.12. Two containers shall be tested as specified in 4.5.2.13. Failure to pass any test shall constitute rejection of the container and the lot it represents"

PAGE 13

4.5.1, line 2, after "painting": Delete "of" and substitute "or".

PAGE 14

4.5.2.1.2, line 9: Delete "lot" and substitute "load"*

PAGE 17

4.5.2.13, line 5: Delete "and" and substitute "end".

Line 7: Delete "periof" and substitute "period".

4.5.2.14, line 2: Delete "of" and substitute "as".

Source: https://assist.dla.mil -- Downloaded: 20260-21T23:22Z
Check the source to verify that this is the currentversion before use.

PAGE 18

5.1.1.3, in paragraph title and in line 1: Delete “blocks” and substitute “block, coupler,”.

5.2.1, first sentence: Delete and substitute “Four sets of shelving, a spacer block, a coupler, and a plug, preserved as specified in 5.1, shall be secured within the refrigerator in such a manner as to prevent movement or damage while in transit.”

6.2 (C): Delete and substitute: “(c) When a spacer block and a coupler are not required (see 3.5.8).”

6.3: Delete and substitute:

“6.3 First article. When a first article sample is required, it shall be inspected and approved under the appropriate provisions of DAR 7-104.55. The first article should consist of the first two containers produced. The contracting officer should include specific instructions in all acquisition documents regarding arrangements for inspection and approval of the first article. ”

PAGE 19

Add new paragraph:

*’6.7 Engineering design conference. Within 10 days after award of contract and prior to any work on the preproduction sample, the contracting officer should arrange an engineering design conference to discuss any questions concerning the details of Government drawings, instructions, and any technical requirements of this specification. This conference is to assist the contractor in interpretation of the specification and agreements made shall neither obligate the Government to accept equipment that is not in accordance with this specification nor relieve the contractor of his obligation to supply the equipment specified.”

Custodian:

Army - GL

Review activity:

Navy - MC

Preparing activity:

Army - GL

Project No. 4110-A012

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T23:22Z
Check the source to verify that this is the current version before use.