MIL-T-9219 (USAF)
Amendment 2
4 June 1965
Superseding
Amendment 1
4 September 1957

MILITARY SPECIFICATION

TRANSFORMER, POWER, AUTOTRANSFORMERS, AND STEP DOWN, 400 CYCLE

This amendment forms a part of Military Specification MIL-T-9219 (USAF) dated 16 September 1953.

Page 1, Paragraph 2.1: Add:

"MIL-T-9107 Test Reports, Preparation Of"

Page 6, Paragraph 4.1.1: Delete and substitute:

"4.1.1 PREPRODUCTION TESTS.- Preproduction tests are those tests accomplished on samples representative of the production transformer to determine that the production transformer meets the requirements of this specification."

Page 7, Paragraphs 4.3, 4.3.1, and 4.3.2: Delete and substitute:

"4.3 PREPRODUCTION TESTING"

"4.3.1 PREPRODUCTION TEST SAMPLES.- The contractor shall subject two transformers to the preproduction tests specified in 4.3.3 and shall submit two transformers as preproduction samples to the procuring activity."

"4.3.2 PREPRODUCTION TEST REPORT.- After the contractor completes the preproduction tests, he shall prepare a preproduction test report according to MIL-T-9107 and furnish three complete copies of the report to the procuring activity."

Page 7, Paragraph 4.3.3: Delete "qualification" and substitute "preproduction."

Page 11, Paragraph 6.2: Delete, substitute:

The address for information concerning preproduction testing and forwarding of preproduction test reports is: Hq AFLC (SGMES), Engineering & Technical Division, Wright-Patterson Air Force Base, Ohio.

PREPARING ACTIVITY:

Air Force - 85

CUSTODIAN:

Air Force - 85

FSC 5950

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T12:04Z
Check the source to verify that this is the current version before use.