MILITARY SPECIFICATION

MOVEMENT ASSEMBLY, FOR TIMER, INTERVAL, M15

1. SCOPE

1.1 This specification covers requirements, quality assurance provisions, and the preparation for delivery criteria for one type of Movement Assembly, For Timer, Interval, M15 which is used on the Sergeant warhead section.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein:

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-810	- Environmental Test Methods.
MIL-STD-1168	- Lot Numbering of Ammunition.

DRAWINGS

ORDNANCE CORPS

8829803	- Main Spring Assembly
8829949	- Lever Assembly
8829957	- Main Shaft Assembly
8829981	- Movement Assembly
8830232	- Gear Train Assembly
EL8854185	- Equipment List

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Materials. The contractor shall furnish objective evidence (see 6.2) that the material complies with the specifications listed on the applicable drawing.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

3.2 Assembly. The movement shall comply with all requirements specified on the drawing (dwg) 8829981 and 8830232, with all requirements speciifed herein, and with the requirements of all applicable specifiecations to the extent specified on the drawing and herein.

3.3 First article testing. Requirements for the submission of first article samples by the contractor shall be as specified in the contract (see 4.2).

3.4 Serialization. The contractor shall assign serial numbers as required by drawings. The contractor may select any number which complies with the drawing requirement. These numbers shall not be duplicated.

3.5 Operational log. A log of test time shall be maintained of each movement. Each time a movement is operated, an entry shall be made into the log, showing the number of runs made and the duration of each run to the nearest 10 seconds. No movement shall be accepted which has accumulated more than 5000 seconds, operational time.

3.6 Starting and operating torques. Drawing number 8830232, part number 8830232. Using a dummy drive shaft and drive gear, the torque applied to the shaft sufficient to self start the escapement and gear train assembly shall not exceed 8 inch-ounces. The maximum torque, measured at the output shaft, required to sustain functioning thru 360 degrees of drive shaft rotation, shall not exceed 9 inch-ounces when tested as specified in 4.4.2.

3.7 Winding torque. Drawing number 8829981, part number 8829981. The torque required to wind the movement assembly to time zero (T.O.) shall not exceed 25 inch-ounces when tested as specified in 4.4.4 (T.O. is defined as the location where the Main Shaft Assembly 8829957 comes to rest against the Lever Assembly 8829949 after the Main Spring 8829803 has been fully wound.

3.7.1 Mainspring torque. The main spring of each movement shall have a torque of 9.5 to 16.5 inch-ounces through the operating range of the movement when tested as specified in 4.4.4.1.

3.8 Escapement frequency regulation. Before the movement assembly is subjected to any other tests, each assembly shall be regulated to an escapement frequency of 98.772 + 1 percent Hertz (Hz) as specifed in 4.4.1.

3.9 Escapement frequency operation accuracy. The escapement frequency of the movement shall be 98.772 + 2 percent (Hz) during any functional or environmental testing when tested as specified in 4.4.5.

3.10 Gear train proof load. The gear train shall be capable of withstanding a torque of 36 inch-ounces with no evidence of slippage, when tested as specified in 4.4.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

3.11 Environmental testing. The movement shall comply with MIL-STD-810, visual inspection and failure criteria, section 3. The movement shall also comply with 3.9 before and after each environmental test. Testing shall be as specified in 4.4.6. Tests shall be conducted in the order specified.

3.11.1 High temperature. The movement shall withstand exposure to a temperature of 160 ± 5 degrees Fahrenheit (°F) at ambient humidity without evidence of damage or impairment of operation during or after exposure, when tested as specified in 4.4.6.1.

3.11.2 Low temperature. The movement shall withstand exposure to a temperature of -65°F. ± 5°F. at ambient humidity, without evidence of damage or impairment of operation during or after exposure, when tested as specified in 4.4.6.2.

3.11.3 Shock. The movement shall show no evidence of damage or impairment of operation when subjected to shocks of 30 ± 5 gravity units (g's), three times in each direction along three mutually perpendicular axes for a total of 18 shocks, when tested as specified in 4.4.6.3.

3.11.4 Transportation vibration. The movement shall show no evidence of damage or impairment of operation during or after subjection to vibration for 15 minutes in each of three mutually perpendicular axes at the frequencies and amplitudes specified below when tested as specified in 4.4.6.4.

Frequency range (Hz)	Time Cycle	Constant Acceleration or Double Amplitude
8-55-8	7-1/2 minutes	0.060 ± 0.006 inch
55-500-55	7-1/2 minutes	10 ± 1 g

3.11.5 Operational vibration. The movement shall withstand without evidence of damage or impairment of operation programed sequence of band-limited white Gaussian noise and combined noise and sine wave vibration when tested as specified in 4.4.6.5. The total time of test shall be 210 seconds: 70 seconds in each of three mutually perpendicular axes. The complex vibration test will consist of the following five sections programed continuously:

(a) White Gaussian noise at a level of 22 g root mean square (rms) band-limited between 15 and 1500 Hertz (Hz) for one (1) second.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

(b) A 4 g rms swept sine wave superimposed on 7.5 g rms of white Gaussian noise band-limited between 15 and 1500 Hz for 15 seconds. The sine wave shall be swept from 800 to 1300 Hz at rate increasing directly with frequency, one such sweep taking the full 15 seconds.

(c) An 8 g rms swept sine wave superimposed on 15 g rms of white Gaussian noise band-limited between 15 and 1500 Hz for 15 seconds. The sine wave shall be swept from 1300 to 800 Hz at a rate decreasing directly with frequency, one such sweep taking the full 15 seconds.

(d) A 4 g rms sine wave superimposed on 7.5 g rms of white Gaussian noise-band-limited between 15 and 1500 Hz for 28 seconds. The sine wave shall be swept from 15 to 1500 Hz and back to 15 Hz at a rate increasing directly with frequency. One such cycle shall take the full 38 seconds.

(e) White Gaussian noise at a level of 22 g rms band-limited between 15 and 1500 Hz for one (1) second.

3.12 Lever release. The movement shall be released when the button (refer to lever assembly 8829949) travel is 0.075 inch but shall not release when the button travel is 0.015 inch, when tested as specified in 4.4.7.

3.13 Workmanship.

3.13.1 Plastic and metal characteristics. All components shall be free from cracks, splits, cold flow, shrinkage, cold shuts, inclusions, porosity, or any similar characteristic.

3.13.2 Threads. Threads shall be full and undamaged for the entire minimum length or depth as required on the applicable drawing.

3.13.3 Burrs. Parts shall be free from burrs.

3.13.4 Foreign matter. Parts shall be free from chips, dirt, grease, rust, corrosion, or any embedded foreign material.

3.13.5 Cleaning. The cleaning method shall not be injurious to any of the parts, nor shall the parts be contaminated by the cleaning agent.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 First article inspection.

4.2.1 Quantity to be submitted. When the contract requires first article inspection, the contractor shall submit 6 complete assemblies (see dwg 8829981 and 8830232) for first article testing to the testing facility designated in the invitation for bids or request for proposal.

4.2.2 Inspection and testing to be performed. The first article inspection sample shall be subjected to the inspections and tests specified in Table I. Tests shall be conducted in order specified in Table I.

Table I

Inspection or Test	Dest	Non Dest
1. Classification of characteristics (see 4.3.2.1)		X
2. Starting and operating torques (see 3.6)		X
3. Mainspring torque (see 3.7.1)		X
4. Escapement frequency regulation (see 3.8)		X
5. Escapement frequency operation accuracy (see 3.9)		X
6. Lever release (see 3.12)		X
7. High temperature (see 3.11.1)	X	
8. Low temperature (see 3.11.2)	X	
9. Shock (see 3.11.3)	X	
10. Transportation vibration (see 3.11.4)	X	
11. Operational vibration (see 3.11.5)	X	
12. Gear train proof load (see 3.10)	X	

4.2.3 Inspection equipment. The inspection and testing specified in 4.2.2 shall be accomplished by using the gages and test equipment specified in 4.3.4.1.

4.2.4 Rejection. If any item fails to comply with any of the applicable requirements, the first article sample shall be rejected.

4.3 Quality conformance inspection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.3.1 Lot formation.

4.3.1.1 Production lot. A lot shall consist of parts and assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision. Drawing, specification and process changes not affecting safety, performance, storage, or interchangeability, as determined by the Government, shall not necessitate changing the lot interfix number. The criteria and procedures for the assignment of lot numbers shall be in accordance with MIL-STD-1168.

4.3.1.2 Inspection lot. A lot or batch and its formation, size, and presentation is described in MIL-STD-105, Section 5. Accordingly, a lot shall mean an inspection lot and a batch shall mean an inspection batch for the purpose of this specification. The manner in which each inspection lot or batch is to be presented and identified by the contractor, shall be designated or approved by the Government representative.

4.3.2 Product inspection examination. A sample shall be selected at random from each inspection lot in accordance with the applicable major or minor characteristic table (see Table II and Table III), and inspected for all characteristics in the applicable classification. Any characteristics in the sample found to be defective shall reject the inspection lot. Sequence for the inspection of characteristics in each classification need not be followed as long as all characteristic inspections are performed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

Table II
Major Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-72	all	140-141	124	256-259	177	541-549	230
73	72	142	125	260-262	178	550-559	231
74	73	143-144	126	263-265	179	560-569	232
75	74	145	127	266-268	180	570-579	233
76	75	146-147	128	269-271	181	580-590	234
77	76	148-149	129	272-275	182	591-601	235
78	77	150	130	276-278	183	602-613	236
79	78	151-152	131	279-282	184	614-625	237
80	79	153-154	132	283-285	185	626-637	238
81-82	80	155-156	133	286-289	186	638-649	239
83	81	157	134	290-293	187	650-662	240
84	82	158-159	135	294-296	188	663-676	241
85	83	160-161	136	297-300	189	677-690	242
86	84	162-163	137	301-304	190	691-704	243
87	85	164-165	138	305-308	191	705-719	244
88-89	86	166-167	139	309-312	192	720-735	245
90	87	168	140	313-316	193	736-751	246
91	88	169-170	141	317-320	194	752-768	247
92	89	171-172	142	321-324	195	769-785	248
93	90	173-174	143	325-329	196	786-804	249
94-95	91	175-176	144	330-333	197	805-823	250
96	92	177-178	145	334-338	198	824-842	251
97	93	179-180	146	339-342	199	843-863	252
98	94	181-182	147	343-347	200	864-884	253
99-100	95	183-184	148	348-352	201	885-907	254
101	96	185-187	149	353-356	202	908-930	255
102	97	188-189	150	357-361	203	931-955	256
103	98	190-191	151	362-366	204	956-981	257
104-105	99	192-193	152	367-372	205	982-1008	258
106	100	194-195	153	373-377	206	1009-1036	259
107	101	196-197	154	378-382	207	1037-1066	260
108-109	102	198-200	155	383-388	208	1067-1098	261
110	103	201-202	156	389-393	209	1099-1131	262
111	104	203-204	157	394-399	210	1132-1166	263
112-113	105	205-207	158	400-405	211	1167-1204	264
114	106	208-209	159	406-411	212	1205-1243	265
115	107	210-212	160	412-417	213	1244-1285	266
116-117	108	213-214	161	418-424	214	1286-1330	267
118	109	215-217	162	425-430	215	1331-1378	268
119	110	218-219	163	431-437	216	1379-1429	269
120-121	111	220-222	164	438-443	217	1430-1483	270
122	112	223-224	165	444-450	218	1484-1542	271
123-124	113	225-227	166	451-457	219	1543-1605	272
125	114	228-230	167	458-465	220	1606-1673	273
126-127	115	231-232	168	466-472	221	1674-1747	274
128	116	233-235	169	473-480	222	1748-1827	275
129-130	117	236-238	170	481-488	223	1828-1914	276
131	118	239-241	171	489-496	224	1915-2010	277
132-133	119	242-243	172	497-504	225	2011-2115	278
134	120	244-246	173	505-513	226	2116-2232	279
135-136	121	247-249	174	514-521	227	2233-2361	280
137	122	250-252	175	522-530	228	over 2361	298
138-139	123	253-255	176	531-540	229		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

Table III
Minor Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-16	all	28-29	23	52-56	31	132-156	39
17	16	30-31	24	57-62	32	157-191	40
18	17	32-34	25	63-69	33	192-244	41
19-20	18	35-36	26	70-76	34	245-334	42
21	19	37-40	27	77-86	35	335-519	43
22-23	20	41-43	28	87-97	36	520-1120	44
24-25	21	44-47	29	98-112	37	over 1120	45
26-27	22	48-51	30	113-131	38		

4.3.2.1 Classification of characteristics (see 3.2). Critical, major and minor characteristics are defined in MIL-STD-105. Inspection shall be conducted as follows:

4.3.2.1.1 Movement assembly (dwg. 8829981).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
101.	Mounting hole diameters	Gage
102.	Mounting hole locations	Gage
103.	Locator pin location	Gage
104.	Contour of movement	Gage
105.	Incorrect assembly	Visual
106.	Any component missing	Visual
107.	Any component damaged	Visual
108.	Any component loose	Visual/Manual
109.	Objective evidence relating to material missing or improper (see 3.1)	Visual
110.	Evidence of poor workmanship (see 3.16)	Visual
Minor:		
201.	Serialization improper or missing (see 3.4)	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.3.2.1.2 Preparation for delivery (see dwg 8829981).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Packing material and packing not in accordance with applicable drawing	Visual
	102. Marking not in accordance with applicable drawing	Visual
Minor:		
	201. Evidence of poor workmanship (see 3.13)	Visual

4.3.3 Testing. All tests shall be performed. Tests shall be performed in the order specified below:

	Test	Test Classification
a.	Starting and operating torque	Major
b.	Winding torque	Major
c.	Mainspring torque	Major
d.	Escapement frequency regulation	Major
e.	Escapement frequency operation accuracy	Major
f.	Lever release	Major
g.	High temperature	Major
h.	Low temperature	Major
i.	Shock	Major
j.	Transportation vibration	Major
k.	Operational vibration	Major
l.	Gear train proof load	Major

Of these tests, g through l are considered destructive and samples so tested shall not be returned to the lot. The destructive samples are over and above the deliverable quantity of movements required by the contract.

4.3.3.1 Starting and operating torque, winding torque, mainspring torque, escapement frequency regulation, escapement frequency operation accuracy and lever release. Each movement shall be tested in accordance with 4.4.2, 4.4.4, 4.4.4.1, 4.4.5 and 4.4.7. If any item fails to comply with 3.6, 3.7, 3.7.1, 3.8, 3.9 and 3.12, the item shall be rejected and removed from the lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.3.3.2 High temperature, low temperature, shock, transportation vibration, operational vibration and gear train proof load. A sample shall be selected at random in accordance with Table IV. The sample shall be tested in accordance with 4.4.6.1, 4.4.6.2, 4.4.6.3, 4.4.6.4, 4.4.6.5, and 4.4.3. If any item fails to comply with 3.11.1, 3.11.2, 3.11.3, 3.11.4, 3.11.5 and 3.10, the lot shall be rejected.

Table IV

Lot Size	Sample Size for No Failures
2-39	1
40-59	2
60-79	3
80-180	4
181-500	6

Lot Size Required = Number Required to be Delivered + Sample Size.

4.3.4 Acceptance inspection equipment.

4.3.4.1 Major characteristics and tests. Inspection and testing shall be performed with the acceptance inspection equipment, operating instructions, and calibration instructions specified on the Equipment Lists (EL) (see EL-8854185). When either of the conditions listed below exist, the contractor shall design required equipment or specify suitable commercial equipment and obtain approval prior to use on the contract.

a. Any deviation from equipment or procedures specified on the EL is desired (see 6.3).
b. The code "CD" is listed in the "Part or Identifying Number" column on the EL (see 6.1.2).

4.3.4.2 Minor characteristics and tests. Acceptance inspection equipment for minor characteristics is not specified on ELs. The acceptance inspection equipment, operating instructions and calibration instructions used by the contractor for minor classification inspection shall be approved by the Government representative authorized by the procuring agency.

4.4 Test methods. The tolerances specified herein are absolute with no allowance for test equipment inaccuracy. The tolerances used by the manufacturer shall be equal to the absolute tolerances less the accuracy tolerances of the test equipment used.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.4.1 Escapement frequency regulation. Mount the movement assembly in a fixture. Using a beat rate recorder, with a frequency calibrated to 98.772 + 1 percent Hz, adjust the escapement to a frequency of 98.772 + 1 percent Hz. A beat rate recorder record shall be kept for the full duration of the run, and submitted as part of the data.

4.4.2 Starting and operating torque. Mount the movement such that the mainspring will be inoperative in a holding fixture of such design, so that a weight can be applied to a driving pulley. Apply a gradually increasing load to the output shaft in the timing direction. The maximum torque, measured at the output shaft, required to self-start the escapement, shall not exceed 8 inch-ounces. This procedure shall be repeated five times. The maximum torque required to maintain escapement frequency shall not exceed 9 inch-ounces through 360° of shaft rotation.

4.4.3 Gear train proof load. Mount the movement assembly with the main spring inoperative in a fixture which simulates the timer mounting. Restrain the pallet from oscillating and carefully apply a torque at the output shaft in the timing direction until evidence of slippage or fracture in the gear train shall occur. Record torque values and a torque of less than 36 inch-ounces shall constitute a failure.

4.4.4 Winding torque. Mount the movement onto a fixture which simulates the timer mounting. Measure the static winding torque. The torque required to reset to T.O. shall not exceed 25 inch-ounces maximum.

4.4.4.1 Mainspring torque. Mount assembly in fixture and with suitable equipment determine torque of mainspring throughout the operating range of the movement.

4.4.5 Escapement frequency operation accuracy. Perform this test with the same equipment as in 4.4.1, except that frequency shall be within the limits specified in 3.9.

4.4.6 Environmental testing (see 3.11).

4.4.6.1 High temperature. The movement shall be wound and placed in a test chamber, the humidity within the chamber shall be ambient and the temperature within the chamber shall be raised to 160 + 5°F. and held for a minimum of four hours after stabilization (see 6.4). At the end of the four-hour period, the movement shall be operated in this environment and meet the requirements of escapement frequency operation accuracy (3.9). At the conclusion of these tests, the movement shall be returned to room temperature and rewound. Forced cooling such as directing air on the unit shall not be used. After return to room ambient temperature, there shall be no indication of damage to the movement and shall be tested for compliance with the requirements of escapement frequency operation accuracy (3.9).

Source: https://assist.dla.mil Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.4.6.2 Low temperature. The movement shall be wound and placed in a test chamber at ambient humidity. The chamber temperature shall be lowered to -65 + 5°F and maintained for a minimum of 4 hours after stabilization (see 6.4). After the 4-hour period and while still at -65°F temperature the movement shall be tested for compliance with escapement frequency operation accuracy (3.9). To prevent condensation freezing in the pivots, the movement shall be placed in a clear plastic bag or other suitable device. At the conclusion of this test, the movement shall be returned to room temperature and rewound. Forced warming such as directing air on the unit shall not be used. After returning to ambient room temperature the movement shall be examined for evidence of damage to the movement and shall be tested for compliance with escapement frequency operation accuracy (3.9).

4.4.6.3 Mechanical shock. The movement shall be rigidly mounted to a test fixture as applicable which shall be mounted to a suitable shock producing apparatus. The movement shall then be subjected to 3 shocks in each direction of the 3 major mutually perpendicular axes. Each shock shall be of 30 + 5 g peak amplitude and 11 + 2 milliseconds duration as measured between points which are 10 percent of the peaks. Time to peak shall be 5.5 + 1 ms. After the completion of the 18 shocks, the movement shall be examined for damage and shall be tested for compliance with the requirement of escapement frequency accuracy (3.9).

4.4.6.4 Transportation vibration. The movement shall be mounted on a vibration machine and vibrated for 15 minutes in each of three mutually perpendicular axes at the frequencies and amplitude specified in 3.11.4. Upon completion of the vibrations the movement shall be examined for damage and tested for the requirement of operational vibration (3.11.5).

4.4.6.5 Operational vibration. The movement shall be mounted on a vibration machine and virated in three mutually perpendicular planes using a standard noise or complex wave tape having the characteristics listed in the following table.

Time (sec)	Type of Signal	Ratio of Test Level To Calibration Level	RMS g Level
0-20	Noise (calibration)(1)	1.	Set gain to give 2 g rms
20-30	None	0	0
30-31	Noise (1)	11.	22.
31-46	Noise (1) plus sinusoid (2)	4.25	8.5
	Noise alone	3.75	7.5
	Sinusoid alone	2.	4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

46-61	Noise (1) plus sinusoid (3)	8.5	17.
	Noise alone	7.5	15.
	Sinusoid alone	4.	8.
61-99	Noise (1) plus sinusoid (4)	4.25	8.5
	Noise alone	3.75	7.5
	Sinusoid alone	2.	4.
99-100	Noise (1)	11.	22.

(1) Band limited (15 - 1500 Hz) white Gaussian Noise.
(2) Sine wave swept from 800 to 1300 Hz at a rate increasing directly with frequency. One full sweep in 15 seconds.
(3) Sine wave swept from 1300 to 800 Hz at a rate increasing directly with frequency. One full sweep in 15 seconds.
(4) Sine wave swept from 15 to 1500 Hz and back to 15 H at a rate increasing directly with frequency. One full cycle in 38 seconds.

For creating the random noise, the output of a General Radio random noise generator, or its equivalent, may be used if proper care is taken to insure the correct amplitude distribution of the signal. For testing the noise analyzer or any other associated equipment, the use of an amplitude distribution is suggested. For insuring correct noise bandwidth, a filter with an asymptotic slope of at least 24 decibel (Db) per octave and 3 Db points at 15 and 1500 Hz shall be considered acceptable.

4.4.6.5.1 Method and procedure with the standard noise tape. Before applying the tape, the transfer function or frequency response of the entire vibration system shall be as flat as is consistent with the present state of the art. Plus or minus 3 Db or better over the band from 15 to 1500 Hz shall be considered as an objective in this respect. After proper equalization of the system, the standard noise tape is applied. The over-all gain of the shake system is then adjusted so that with the noise calibration signal, the g level listed in 4.4.6.1 is obtained. With the same gain setting, the tape is run for the remainder of the test and the g levels obtained will conform to the levels listed in the table of 4.4.6.1.

4.4.6.5.2 The movement shall be operated using a suitable release mechanism, with the time interval (T.O.) starting at 25 ± 10 seconds after the start of the vibration. Only one (1) run shall be made in each orientation during the vibration cycle. Upon completion of the test the movement shall be inspected for compliance with escapement frequency operation accuracy (3.9).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.4.7 Lever release. With the movement wound, mount it in a fixture which has an adjustable surface contacting the actuator buttons. Pass a 0.015 inch and a 0.075 inch feeler between the adjustable surface and the buttons. Check for release of the movement as evidenced by running.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging. Preservation and packaging shall be level A or C as specified (see 6.1).

5.1.1 Level A. The movement shall be packaged in accordance with dwg 8829981 using the specified moisture barrier.

5.1.2 Level C. The movement shall be packaged in accordance with dwg 8829981 except that the moisture barrier may be omitted.

5.2 Packing.

5.2.1 Level A and C. The movement shall be packed in accordance with dwg 8829981.

5.3 Marking. Marking shall be as specified in accordance with dwg 8829981.

6. NOTES

6.1 Ordering data. Procurement documents should specify the following:

6.1.1 Procurement requirements.

a. Title, number, and date of this specification.
b. Selection of applicable level of packaging and packing required (see 5.1 and 5.2).

6.1.2 Contract data requirements (see 4.3.4.1). Data specified in 4.3.4.1 will be delivered as identified on a numbered DD Form 1664 when required on a DD Form 1423 incorporated in the contract.

6.2 Objective evidence. Records of contractor quality control and inspections which can be verified.

6.3 Acceptance inspection equipment (see 4.3.4.1). The contractor shall obtain approval from the Commanding Officer, Picatinny Arsenal, Dover, New Jersey 07801, ATTN: SARPA-QA-T.

6.4 Temperature stabilization. The temperature is considered stabilized when the greatest peaks (both highest and lowest) continually observed over 5 minutes min. do not exceed the nominal temperature plus tolerance specified.

6.5 Supersession data. This specification supersedes the requirements of Purchase description PA-PD-2147 Rev. 1 dated 22 March 1965.

Custodian:
Army - PA

Preparing activity:
Army - PA

Project No. 1135-A172

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.