MILITARY SPECIFICATION

INDICATOR, PRESSURE, 1 1/2-INCH,
INTEGRALLY LIGHTED

This amendment forms a part of Military Specification MIL-I-23479B dated 16 October 1967, and is approved for use by all Departments and Agencies of the Department of Defense.

Page 9

Para 4.4.3 Reliability tests - Delete, and substitute the following paragraphs:

"4.4.3 Reliability assurance tests - Reliability Assurance Tests shall be conducted in accordance with MIL-STD-781. Qualification Phase and Production Acceptance (Sampling) Phase Tests shall be conducted. Equipments selected for Reliability Assurance Tests shall first have passed the Individual Tests.

4.4.3.1 Reliability qualification phase - Prior to Qualification Product Listing (QPL), a minimum of three equipments shall be tested as outlined in MIL-STD-781, under the section entitled "Qualification Phase of Production Reliability Tests". The maximum number of test samples to be used shall be those listed in Table 5 of MIL-STD-781. For the Qualification Phase, Test Level F shall be used. The Accept-Reject Criteria for Test Plan I shall be used.

4.4.3.2 Reliability production acceptance (sampling) phase tests - Samples of the equipment shall be tested as outlined in MIL-STD-781, under the Section entitled "Production Acceptance (Sampling) Phase of Production Reliability Tests". For the Sampling Phase Test Level F shall be used. The Accept-Reject Criteria for Test Plan II shall be used to determine the length of the tests (until an accept or reject decision is reached).

4.4.3.2.1 Procedure for production acceptance (sampling) phase - The Reliability Production Acceptance (Sampling) Phase tests shall be conducted at least once for each lot. The number of equipments shall be in accordance with Table 5 of MIL-STD-781. The test program shall start with first

FSC 6620

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:03Z
Check the source to verify that this is the current version before use.

month's production. Equipments shall be selected and placed on test in the same manner as though one month's production was a lot. The equipments shall be tested until an accept or reject decision is reached. The test results shall be summarized monthly for the procuring activity. The procuring activity reserves the right to stop the acceptance of equipment at any time after one or more reject decisions have been reached pending a review of the contractor's efforts to improve the equipment, the equipment quality control, etc.

4.4.3.3 Procedures report and test details - The test details such as the length of the test cycle, the length of the heat portion of the cycle, the performance characteristics to be measured, special failure criteria, etc. shall be part of the test procedures to be submitted to and approved by the procuring activity prior to the beginning of the Qualification Test Phase of the Reliability Assurance Tests. The following paragraphs shall be considered as minimum requirements and apply to both phases.

4.4.3.3.1 Duty cycle - The duty cycle shall be continuous during the heating portion of the temperature cycle. The duty cycle shall consist of cycling the indicator between approximately 10 and 80 percent of full scale and return at a rate of 12 $\pm$ 1 cycles per hour. The power shall be "off" three to five minutes after each hour of "on" time. The indicator lighting shall be energized when the indicator is operating.

4.4.3.3.2 Performance characteristics to be measured - The Scale error and friction test, described under inspection methods, shall be conducted at least once each week. The indicator shall be observed daily, on regular working days, for any obvious failure such as rough pointer movement or lighting failures.

4.4.3.3.3 Failure criteria - Whenever performance characteristics fall below the acceptance requirements (4.4.3.3.2), at least one failure has occurred. If subsequent analysis reveals that several parts have deteriorated, each shall be counted a failure, unless one part caused the other parts to fail.

4.4.3.3.4 Preventive maintenance - No preventive maintenance may be accomplished on the equipments while they are on test.

4.4.3.3.5 Operational stability - No adjustment of any controls inaccessible to the operator shall be made during the Reliability Test.

4.4.3.3.6 Disposition of samples upon completion of tests - Any equipment tested may be delivered on contract provided it meets all the following requirements:

Source: https://assist.dla.mil -- Downloaded: 20260-19T17:03Z
Check the source to verify that this is the current version before use.

a. It is representative of production units currently being accepted.

b. It is in "good as new" condition or has been refurbished (see 6.5.1 and 6.5.2).

c. It is otherwise satisfactory."

Page 11

Para 6.2 Ordering data - Delete subparagraph (e) and substitute the following subparagraphs:

"(e) Reliability test results (see 4.4.3.2.1)
(f) Reliability Procedures report and test details (see 4.4.3.3)"

Page 12

Add the following paragraph:

"6.5 Definitions -

6.5.1 Good as new - "Good as new" means the Indicator has operated less than 10 percent of the specified MTBF operation.

6.5.2 Refurbished - "Refurbished" means that the Indicator has been completely overhauled with all component parts meeting current parts standards; and the Indicator has been subjected to and has met all the requirements for a new unit."

Custodians:
Air Force - 71
Navy - AS

Review Interest:
Air Force - 82

Preparing Activity:
Navy - AS

Project No. 6620-0263

Source: https://assist.dla.mil -- Downloaded: 202610-19T17:03Z
Check the source to verify that this is the current version before use.