MILITARY SPECIFICATION

TEST SET, POWER SUPPLY AN/APM-149(*)

This specification has been approved by the
Bureau of Naval Weapons, Department of the Navy.

1. SCOPE

1.1 Scope - The equipment covered by this specification shall be for shop use and shall provide a simulated klystron load for Power Supply PP-2712/APN-130 of Radar Navigation Set AN/APN-130(V).

1.2 Classification - The Test Set, Power Supply AN/APM-149 shall consist of the following items:

Item	Type Designation	Appl. Para.
Dummy Load, Electrical	DA-266(*)/APM-149	3.4.1
Cable Assembly	W-1 of AN/APM-149	3.4.2
Case, Test Set	CY-3142(*)/APM-149	3.4.3

2. APPLICABLE DOCUMENTS

2.1 General - The following documents of the issue in effect on the date of invitation for bids form a part of this specification to the extent specified herein:

SPECIFICATIONS

Military

MIL-T-5422	Testing, Environmental, Aircraft Electronic Equipment
MIL-I-6181	Interference Control Requirements, Aircraft Equipment
MIL-W-16878	Wire, Electrical Insulated, High Temperature
MIL-E-17555	Electronic and Electrical Equipment and Associated Repair Parts, Preparation for Delivery of
MIL-T-18303	Test Procedures; Preproduction and Inspection, for Aircraft Electronic Equipment, Format for
MIL-N-18307	Nomenclature and Nameplates for Aeronautical Electronic and Associated Equipment
MIL-T-21200	Test Equipment for Use with Electronic and Fire Control Systems, General Specification for

FSC 5985

Source: https://assist.dla.mil -- Downloaded: 202640-19T17:11Z
Check the source to verify that this is the currenversion before use.

STANDARDS

Military

MIL-STD-242 Electronic Equipment Parts

2.2 Availability of Documents

(1) When requesting specifications, standards, drawings and publications refer to both title and number. Copies of this specification and applicable specifications required by contractors in connection with specific procurement functions may be obtained upon application to the Commanding Officer, Naval Supply Depot, Code DCS, 5801 Tabor Avenue, Philadelphia 20, Pennsylvania.

3. REQUIREMENTS

3.1 Parts and Materials - In the selection of parts and materials, fulfillment of major design objectives shall be the prime consideration. In so doing, the following shall govern:

(1) Parts and materials requirements shall conform to Specification MIL-T-21200. Parts selected from specifications called out in Specification MIL-T-21200 shall be limited to those values, styles, tolerances, etc., set forth in MIL-STD-242.

(2) Nonrepairable subassemblies, as outlined in Specification MIL-T-21200, shall be used when practicable. The general size of the subassembly, and the amount of circuitry to be included therein shall be approved by the procuring activity. Nonrepairable subassemblies must be reliable. A mean-time-to failure of more than 5000 hours should be the goal of each.

(3) When previously produced models of this equipment did not use nonrepairable subassemblies, the design shall not be changed to employ nonrepairable assemblies without the approval of the procuring activity.

3.1.1 Nonstandard Parts and Material Approval - Approval for the use of nonstandard parts and materials shall be obtained as outlined in Specification MIL-T-21200.

3.2 Design and Construction

3.2.1 General - The equipment shall conform with all the applicable requirements of Specification MIL-T-21200 for design, construction and workmanship, unless otherwise specified herein.

3.2.2 Total Weight - The total weight of the equipment, excluding cables, shall be a minimum consistent with good design and shall not exceed 44 pounds.

3.2.3 Operating Life

3.2.3.1 Total Operating Life - The equipment shall have a minimum total operating life of 3000 hours with reasonable servicing and replacement of parts. Parts requiring replacement within this interval and the life of such parts shall be specified by the manufacturer.

3.2.3.2 Mean Operating Time Between Failures - The equipment shall have a minimum of 500 hours of mean operating time between failures. A failure shall be defined as any malfunctioning which causes the equipment to fail to meet the minimum performance requirements specified for the equipment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:11Z
Check the source to verify that this is the current version before use.

3.2.4 Cabling and Connections - The equipment shall provide for the use of cables and connectors in accordance with Specification MIL-T-21200 unless otherwise specified herein.

3.2.5 Interchangeability - The equipment shall meet the interchangeability requirements as defined in Specification MIL-T-21200.

3.2.6 Interference Control - The generation of radio interference by the equipment and the vulnerability of the equipment to radio interference shall be controlled with the limits of Specification MIL-I-6181.

3.2.7 Maintenance Provisions and Field Testing - Provisions for maintenance shall be as specified in Specification MIL-T-21200. Specific test points and test facilities shall be provided to the greatest extent practicable for ease of field testing and maintenance.

3.2.8 Nomenclature and Nameplates - Nomenclature assignment and nameplate approval for equipment identification shall be in accordance with Specification MIL-N-18307.

3.2.9 Standard Conditions - The following conditions shall be used to establish normal performance characteristics under standard conditions and for making laboratory bench tests.

Temperature	Room ambient (30° ± 10°C)
Altitude	Normal ground
Vibration	None
Humidity	Room ambient up to 90% relative humidity

3.2.10 Service Conditions - The equipment shall operate satisfactorily under any of the environmental service conditions or reasonable combination of these conditions as specified in Specification MIL-T-21200 for Class 3 equipment.

3.2.11 Warm-Up Time - The time required for the equipment to warm-up prior to operations shall be kept to a minimum and shall not exceed 5 minutes under standard conditions and 10 minutes at extreme service conditions.

3.3 Performance

3.3.1 General - Unless otherwise specified, values set forth to establish the requirements for satisfactory performance apply to performance under both standard and extreme service conditions. When reduced performance under the extreme conditions is acceptable, tolerances or values setting forth acceptable variations from the performance under the standard conditions will be specified.

3.3.2 Functional Characteristics - The test set shall provide an electrical load capable of simulating the klystron load normally placed on the klystron output of Power Supply PP-2712/APN-130.

3.3.3 Interlock Circuit - The interlock circuit shall be completed in the test set by inclusion of a jumper wire between the interlock pins of the receptacle.

3.3.4 High Voltage Load - The high voltage load shall provide a resistance of 44,000 ohms ± 5 percent and shall be capable of dissipating not less than 120 watts.

3.3.5 Filament Load - The filament load shall provide 6.3 ohms ± 5 percent and shall be capable of dissipating not less than nine watts.

3.3.6 Filament Load Potential - The filament load shall be operated at the high voltage potential.

Source: https://assist.dla.mil -- Downloaded: 202640-19T17:11Z
Check the source to verify that this is the currentversion before use.

3.4 Detail Requirements

3.4.1 Dummy Load, Electrical DA-266/APM-149- The Electrical Dummy Load shall meet the following requirements.

3.4.1.1 Function - The electrical dummy load shall contain anode and filament loads that shall simulate the demand placed on the energized power supply PP-2712/APN-130 by the klystron transmitter tube of Navigation Set, Radar AN/APN-130(V). The electrical dummy load permits testing of the Power Supply without the necessity for having the receiver-transmitter unit connected.

3.4.1.2 Form Factor and Mounting. - The maximum dimensions of the electrical dummy load shall be 10 inches long by 10-3/4 inches wide by 10-1/8 inches high. The electrical dummy load shall not require mounting isolation.

3.4.1.3 Weight. - The maximum weight of the electrical dummy load shall be seven pounds.

3.4.1.4 Contents. - The electrical dummy load shall contain resistors, connectors, necessary wire, and mechanical structures.

3.4.1.5 Electrical Connections. - Connections to external circuits shall be provided as follows.

Designation	Type (or Equivalent)	Function
J1	Whitney Blake 3-3102-22-92P	Supplies the high voltage inlet to the electrical dummy load
E2 (Ground)	Herman H. Smith, Inc. Inc. #136	Provides case ground connection on front panel

3.4.2 Cable Assembly W-1 of AN/APM-149. - The cable assembly shall meet the following requirements:

3.4.2.1 Function. - The cable assembly shall provide electrical connections between J1 on the electrical dummy load and 4J3 on the Power Supply PP-2712/APN-130.

3.4.2.2 Form Factor- The length of the cable assembly shall be 6 feet 2 inches ± 3 inches.

3.4.2.3 Weight- The weight of the cable assembly shall not exceed two pounds.

3.4.2.4 Contents- The cable assembly shall consist of two connectos, necessary wires, covering, and identification bands. One connector shall be an MS3106A-22 shell with a 92S Whitney Blake insert (or an approved equivalent) and one connector shall be an MS3106A-22 shell with a 92P Whitney Blake insert (or an approved equivalent). The cable shall contain six wires; four 20 gauge and two 16 gauge, Type D in accordance with Specification MIL-W-16878.

3.4.3 Case, Test Set CY-3142/APM-149- The test case shall meet the following requirements.

3.4.3.1 Function - The test set case shall be a protective case used to provide storage and cushioning for the electrical dummy load and all accessories.

3.4.3.2 Form Factor- The dimensions of the test case shall not exceed 21 inches long by 18 inches wide by 13-1/2 inches high.

3.4.3.3 Weight. - The weight of the test set case shall not exceed 35 pounds

Source: https://assist.dla.mil -- Downloaded: 20261O-19T17:11Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection - Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the government. The government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Classification of Tests - Items covered by this specification shall be subjected to the following tests to determine compliance with all applicable requirements:

(1) Preproduction Tests

(2) Production Sample Tests

(3) Acceptance Tests

4.2 Preproduction Tests - Preproduction tests shall be made on an equipment representative of the production equipments to be supplied under the contract. Preproduction tests shall consist of the following:

(1) Contractor's Demonstration Tests

(2) Service Approval Tests

4.2.1 Contractor's Demonstration Tests - Contractor's demonstration tests shall be accomplished under the responsibility of the contractor and shall be conducted in accordance with the approved test procedure of 4.5. The government inspector and the procuring activity shall be advised when tests are to be conducted so that a representative may be designated to witness or supervise the tests when so desired. Contractors not having adequate facilities to conduct all required tests shall obtain the service of a commercial testing laboratory satisfactory to the procuring activity.

4.2.1.1 Demonstration Test Data - The contractor shall submit all data collected in conducting these tests to the procuring agency for review and approval.

4.2.2 Service Approval Tests - At the completion of the contractor's demonstration tests and when requested by the procuring activity, the equipment shall be delivered to a specified government laboratory for additional testing. This additional testing may consist of duplicating tests previously conducted and such other tests as are deemed necessary to determine compliance with all applicable design and performance requirements.

4.2.2.1 Accessory Material - In addition to the complete equipment submitted for service approval tests, the contractor shall also submit the accessory material and design and test data specified in Specification MIL-T-21200. This information shall indicate the physical and electrical characteristics of the equipment and establish the equipment's compliance with applicable requirements.

4.2.3 Scope of Tests - Preproduction tests shall include all tests deemed necessary to determine that the equipment meets all the requirements of this specification and the contract. Preproduction tests shall include environmental tests in accordance with Specification MIL-T-5422 and interference tests in accordance with Specification MIL-I-6181. Drop tests for the case shall be in accordance with Specification MIL-T-21200.

4.2.4 Preproduction Approval - Approval of the preproduction model shall be by the procuring activity upon satisfactory completion of all tests. No production equipments shall be delivered prior to the approval of the preproduction model. Prefabrication of production equipment

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:11Z
Check the source to verify that this is the current version before use.

prior to the approval of the preproduction model is at the contractor's own risk. The approved preproduction model will be returned to the contractor for his use in the fabrication and testing of equipment to be submitted for acceptance. The preproduction model shall not be considered as one of the equipments under the contract; however, it may be reworked by the contractor and submitted for acceptance as a production equipment.

4.2.5 Production Equipments - Equipments supplied under the contract shall in all respects, including design, construction, workmanship, performance and quality be equivalent to the approved preproduction sample. Each equipment shall be capable of successfully passing the s same tests imposed on the preproduction sample. Evidence of non-compliance with the above shall constitute cause for rejection or if already accepted by the government it shall be the obligation of the contractor to make necessary corrections as approved by the procuring activity.

4.3 Production Sample Tests - When requested by the procuring activity, one equipment shall be selected from the first 10 production equipments submitted for acceptance and sent to a designated government laboratory for tests. The equipment shall be selected by the government inspector after the equipment has successfully passed all individual tests. The preproduction sample shall not be selected for this test.

4.3.1 Scope of Tests - This equipment may be subjected to any and all tests the procuring activity deems necessary to assure that the production equipment is equivalent to the previously approved preproduction sample in design, construction and performance and that it meets all applicable requirements.

4.3.2 Production Sample Approval - Approval of the production sample shall be by the procuring activity upon satisfactory completion of all tests. Any design, material or performance defect made evident during this test shall be corrected by the contractor to the satisfaction of the procuring activity. Upon failure of the production sample to pass any of the tests, delivery of equipment under the contract shall cease until proper corrective action is approved and accomplished. Corrective action shall also be accomplished on equipment previously accepted when requested by the procuring activity.

4.3.3 Reconditioning of Production Test Sample - On completion of the production sample test the equipment shall be reworked by the contractor by replacing all wear or damaged items. After reworking the contractor shall resubmit the equipment for acceptance.

4.4 Acceptance Tests - The contractor shall furnish all samples and shall be responsible for accomplishing the acceptance tests. All inspection and testing shall be under the supervision of the government inspector. Contractors not having testing facilities satisfactory to the procuring activity shall engage the service of a commercial testing laboratory acceptable to the procuring activity. The contractor shall furnish test reports showing quantitative results for all acceptance tests. Such reports shall be signed by an authorized representative of the contractor or laboratory, as applicable. Acceptance or approval of material during the course of manufacture shall not be construed as a guarantee of the acceptance of the finished product. Acceptance tests shall consist of the following:

(1) Individual Tests

(2) Sampling Tests

(3) Special Tests

4.4.1 Individual Tests - Each equipment submitted for acceptance shall be subjected to the individual tests. These tests shall be adequate to determine compliance with the requirements of material, workmanship, operational adequacy and reliability. As a minimum, each equipment accepted shall have passed the following tests.

(1) Examination of Product

Source: https://assist.dla.mil -- Downloaded: 202640-19T17:11Z
Check the source to verify that this is the currentversion before use.

(2) Operational Test

(3) Manufacturing Reliability Test

4.4.1.1 Examination of Product - Each equipment shall be examined carefully to determine that the material and workmanship requirements have been met.

4.4.1.2 Operational Test - Each equipment shall be operated long enough to permit the equipment temperature to stabilize and to check sufficient characteristics and record adequate data to assure satisfactory equipment operation.

4.4.1.3 Manufacturing Reliability Test - Each equipment shall be operated under the conditions specified herein for a period of 6 hours without failure. A failure shall be defined as anything which causes malfunctioning of the equipment.

Temperature	Ambient room
Humidity	Ambient room
Vibration (10 minutes)	Any selected frequency within the range of 20 to 30 cps (excluding resonant points) and a minimum amplitude of ±3g's

The equipment shall be vibrated (without vibration isolators) for a period of 10 minutes prior to the beginning of the 6-hour period of operation. Where feasible, the equipment shall be operated during this vibration period for the purpose of detecting flaws and imperfect workmanship. Operation within the specified limits of satisfactory performance is not necessarily required during the vibration period. The direction of vibration should be vertical to the normal mounting plane for 5 minutes and lateral to that plane for 5 minutes. Where it is not feasible to vibrate the equipment in 2 directions the vertical direction shall be used. Should a failure occur, it should be repaired and the test started over, except that the 10-minute vibration period need not be repeated when it is certain the failure was not a result of the vibration. Should repetitive failures occur, corrective action shall be taken to eliminate this defect from future equipment. A record shall be kept of all failures. The 6-hour period specified above may be composed of two 3-hour periods to conform with standard working hours.

4.4.2 Sampling Tests - Sampling tests shall be conducted on equipments which have successfully passed the individual tests. The following equipments shall be selected by the Government Inspector for sampling tests:

Quantity of Equipments Offered for Acceptance	Quantity to be Tested
First 10	1
Next 50	1
Next 75	1
Next 100	1
	1 for each additional 200 or fraction thereof

4.4.2.1 Scope of Tests - As a minimum, each equipment selected for sampling tests shall be subjected to the following tests:

(1) Complete operational test at ambient room conditions, making all necessary measurements to assure that all applicable specification requirements have been met.

(2) Operational test at certain environmental conditions. The conditions may vary for each equipment tested and should be based on results of the preproduction and special tests.

Source: https://assist.dla.mil -- Downloaded: 202640-19T17:11Z
Check the source to verify that this is the currentversion before use.

(3) Manufacturing reliability test specified in para. 4.4.1.3 except that the test duration shall be 30 hours.

4.4.3 Special Tests - Special tests shall be conducted on a quantity of equipments for the purpose of checking the effect of any design or material change on the performance of the equipment and to assure adequate quality control. The equipment selected for special tests may be selected from equipments previously subjected to the sampling tests.

4.4.3.1 Special Tests Schedule - Selection of equipments for special tests shall be made as follows:

(1) On an early production equipment.

(2) On an equipment midway of the production run.

(3) On an early equipment after an engineering change.

(4) Whenever failure reports or other information indicate additional equipments should be tested. (This will be determined by the procuring activity.)

Exceptions from the above may be necessary when the number of equipments procured under contract or other factors affecting performance may require a variation to assure satisfactory control.

4.4.3.2 Scope of Tests - Special tests shall consist of such tests as are approved by the procuring activity. Test procedures previously approved for the preproduction and sampling tests shall be used where applicable. When not applicable, the contractor shall prepare a test procedure and submit it to the procuring activity for approval prior to conducting the tests. As a minimum, the following tests shall be made, except that for those equipments selected as a result of design changes and failure reports, only those tests required to check the characteristics in question need be conducted.

(1) Temperature - Altitude Tests

(2) Vibration Test (60 minutes cycling in each of 3 planes)

(3) Humidity Tests

4.4.4 Equipment Failure - Should a failure occur during either the sampling or special tests, the following action shall be taken:

(1) Determine the cause of failure.

(2) Determine if the failure is an isolated case or design defect.

(3) Submit to the procuring activity for approval, proposed corrective action intended to reduce the possibility of the same failure(s) occurring in future tests.

(4) Where practical, include a test in the individual test to check all equipment for this requirement until reasonable assurance is obtained that the defect has been satisfactorily corrected.

4.5 Test Procedures - The procedures used for conducting preproduction tests and acceptance tests shall be prepared by the contractor and submitted to the procuring activity for review and approval. The right is reserved by the procuring activity or the government inspector to modify the tests or require any additional tests deemed necessary to determine compliance with the requirements of this specification or the contract. Specification MIL-T-18303 shall be used as a guide for preparation of test procedures. When test procedures are available from previous contracts such procedures may be used when approved by the procuring activity.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:11Z
Check the source to verify that this is the current version before use.

4.6 Presubmission Testing - No item, part or complete equipment shall be submitted by the contractor until it has been previously tested and inspected by the contractor and found to comply, to the best of his knowledge and belief, with all applicable requirements.

4.7 Rejection and Retest - Equipment which has been rejected may be reworked or have parts replaced to correct the defects and resubmitted for acceptance. Before resubmitting, full particulars concerning previous rejection and the action taken to correct the defects found in the original shall be furnished the government inspector. Units rejected after retest shall not be resubmitted without the specific approval of the procuring activity.

5. PREPARATION FOR DELIVERY

5.1 General - All major units and parts of the equipment shall be preserved, packaged, packed and marked for the level of shipment specified in the contract or order in accordance with Specification MIL-E-17555.

6. NOTES

6.1 Use - This equipment shall provide an electrical load capable of simulating the klystron load normally placed on the klystron output of Power Supply PP-2712/APN-130.

6.2 Ordering Data - Purchasers should exercise any desired options offered herein and procurement documents should specify the following:

(1) Title, number and date of this specification.

(2) Selection of applicable levels of packaging and packing.

6.3 Test Values - Normal and limiting values of performance data shall be determined at input voltages of 115 ±1.0 V AC. These data are to be used in testing the equipment at installation points for compliance with minimum acceptable standard of performance.

6.4 Precedence of Documents - When the requirements of the contract, this specification, or applicable subsidiary specifications are in conflict, the following precedence shall apply:

(1) Contract - The contract shall have precedence over any specification.

(2) This Specification - This specification shall have precedence over all applicable subsidiary specifications. Any deviations from this specification, or from subsidiary specifications where applicable, shall be specifically approved in writing by the procuring activity.

(3) Referenced Specifications - Any referenced specification shall have precedence over all applicable subsidiary specifications referenced therein. All referenced specifications shall apply to the extent specified.

6.5 The parentheses (*), when used in the type designation, shall be replaced by either a number or letter furnished by the procuring activity upon application by the contractor for assignment of nomenclature in accordance with 3.2.8. The complete type number shall be used on nameplates, shipping records and instruction books, as applicable.

6.6 Performance Objectives - Minimum size and weight, simplicity of operation, ease of maintenance, and an improvement in the performance and reliability of the specific functions beyond the requirements of this specification are objectives which shall be considered in the production of this equipment. Where it appears a substantial reduction in size and weight or improvement in simplicity of design, performance, ease of maintenance or reliability will result from the use of materials, parts and processes other than those specified in Specification MIL-T-21200, it is desired their use be investigated. When investigation shows advantages can be realized, a request

Source: https://assist.dla.mil -- Downloaded: 202640-19T17:11Z
Check the source to verify that this is the currenversion before use.

for approval shall be submitted to the procuring activity for consideration. Each request shall be accompanied by complete supporting information.

NOTICE - When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished or in any way supplied the said drawings, specifications or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use or sell any patented invention that may in any way be related thereto.

Source: https://assist.dla.mil -- Downloaded: 202640-19T17:11Z
Check the source to verify that this is the currentversion before use.

SPECIFICATION ANALYSIS SHEET
NAVWEPS FORM 4121/3 (8-62)

FORM APPROVED
BUDGET BUREAU NO. 45-R300

INSTRUCTIONS

This sheet is to be filled out by Government or contractor personnel involved in the use of this specification in procurement of products for ultimate use by the activity shown on the reverse of this sheet.

This sheet is provided for obtaining information which will aid the activity shown in insuring that through use of this specification suitable products can be procured with a minimum amount of delay and at the least cost.

Comments and the return of this sheet will be appreciated.

Fold on dotted lines on reverse side, staple in corner, and send to the activity shown.

SPECIFICATION *(No. and abbrev. title)*

ORGANIZATION	CITY	STATE

CONTRACT NUMBER	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT
		$

MATERIAL PROCURED UNDER A DIRECT GOVERNMENT CONTRACT ☐ OR A SUBCONTRACT ☐

1. HAS ANY PART OF THIS SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
(If so, give paragraph number and wording, and recommendations for correcting the deficiencies.)

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?
☐ YES ☐ NO IF YES, IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If additional papers are attached, send this form and papers in an envelope. This form is addressed for use in window envelope when appropriate.)*

SUBMITTED BY *(Print name and title)*	DATE

Source: https://assist.dla.mil -- Downloaded: 202640-19T17:11Z
Check the source to verify that this is the currentversion before use.

Fold

DEPARTMENT OF THE NAVY
BUREAU OF NAVAL WEAPONS
WASHINGTON 25, D.C.

OFFICIAL BUSINESS

POSTAGE AND FEES PAID
NAVY DEPARTMENT

Chief, Bureau of Naval Weapons (RREN-5)

Navy Department

Washington 25, D. C.

Fold

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:11Z
Check the source to verify that this is the current version before use.