MILITARY SPECIFICATION

TESTER, PRESSURIZED CABIN LEAKAGE, AIRCRAFT AF/M32T-1

This specification is approved for use by the Department of the Air Force, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers one type of portable, diesel engine driven 10 to 400 cubic feet per minute (cfm), 2 to 12.5 pounds per square inch (psi) pressurized cabin leakage tester, designated AF/M32T-1.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

* 2.1.1 Specifications and standards. Unless otherwise specified (see 6.2), the following specifications and standards of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

A-A-884	Tape, Pressure-sensative Adhesive, Box Closure.
GG-G-76	Gages, Pressure and Vacuum, Dial Indicating, (for Air, Steam, Oil, Water, Ammonia and Chloro-Fluoro Hydrocarbon Gases and Compressed Gases).
PPP-B-636	Box, Shipping, and Fiberboard.

MILITARY

MIL-C-104	Crates, Wood; Lumber and Plywood Sheathed, Nailed and Bolted.
MIL-P-116	Preservation, Methods of.
DOD-D-1000	Drawing, Engineering and Associated Lists.
MIL-H-6000	Hose, Rubber (Fuel, Oil, Coolant, Water and Alcohol).

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: the Engineering Division, San Antonio ALC/MMEDO, Kelly AFB, TX 78241 by using the self addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 4920

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.
Source: https://assist.dla.mil -- Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.

	MIL-I-7721	Indicator, Vertical Speed, 3 Inch.
	MIL-M-8090	Mobility, Towed Aerospace Ground Equipment, General Requirements for.
	MIL-A-8421	Air Transportability Requirements, General Specification for.
*	MIL-S-8512	Support Equipment, Aeronautical Special, General Specification for the Design of.
	MIL-E-10062	Engines: Preparation for Shipment and Storage of
	MIL-H-26521	Hose and Hose Assembly, Nonmetallic, Fuel, Collapsible, Low Temperature with Reattachable Couplings.

STANDARDS

FEDERAL

FED-STD-595	Color

MILITARY

MIL-STD-129	Marking for Shipment and Storage.
MIL-STD-130	Identification Marking of U.S. Military Property.
MIL-STD-143	Standards and Specifications, Order of Precedence for the Selection of.
MIL-STD-461	Electromagnetic Emission and Susceptability Requirements for the Control of Electromagnetic Interference.
MIL-STD-470	Maintainability Program Requirements (for Systems and Equipments).
MIL-STD-471	Maintainability Demonstration.
MIL-STD-781	Reliability Tests Exponential Distribution.
MIL-STD-808	Finish, Materials and Processes for Corrosion Prevention and Control in Support Equipment.
MIL-STD-810	Environmental Test Methods.
MIL-STD-831	Test Reports, Preparation of.
MIL-STD-882	System Safety Program Requirements.
MIL-STD-1186	Cushioning, Anchoring, Bracing, Blocking, and Waterproofing; with Appropriate Test Methods.
* MIL-STD-1474	Noise Limits for Army Materiel.
MS28049	Indicator, Vertical Speed, 3 Inch.
MS33660	Tubing End, Hose Connection, Standard Dimensions for.

AIR FORCE-NAVY AERONAUTICAL

AN832	Union - Flared Tube, 3/8 Bulkhead and Universal.
AN893	Bushing - Screw Thread Reducer.
AN924	Nut, Tube; Bulkhead and Universal Fitting.
AN929	Cap Assembly, Tubes Pressure Seal.
AN6270	Hose Assembly - Detachable Swivel Fitting, Low Pressure.

* 2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this specification to the extent specified herein.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.

DRAWINGS

AIR FORCE

48B7796	Ring Assembly - Tie Down, 10,000 Lb
49B6564	Ring-Eyebolt 25,000 Lb Cargo Tiedown.
50B6228	Adapter Assembly-Inlet Pressurization Test, 3 Inch Hose, 2 3/8 12 Fitting.
50B6230	Adapter Assembly-Inlet Pressurization Test, 3 Inch Hose, 1 1/4 12 Fitting
50B6335	Gasket-Inlet Adapter, Pressurization Test.
7545352	Requirement for Finishes, Protective, and Codes for San Antonio ALC Ground and Ground Support Equipment.

* (Copies of specifications and standards required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

* 2.1.3 Other publications. The following document(s) form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DoD adopted shall be the issue listed in the current DoDISS and the supplement thereto, if applicable.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS

PTC 9	Power Test Code for Displacement Compressors, Vacuum Pumps and Blowers.

(Copies of the ASME Power Test Codes may be obtained upon application to the American Society of Mechanical Engineers, 345 East 47th Street, New York N.Y. 10017).

* AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 3951	Standard Practice for Commercial Packaging.

(Application for copies of ASTM publications should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

* 2.2 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

3.1 First article. This specification makes provisions for first article inspection. (See para 4.6 & 6.3)

3.2 Components. The tester shall consist of the following major components:

Source: https://assist.dla.mil -- Downloaded: 202610-20T07:55Z
Check the source to verify that this is the current version before use.

a. Diesel engine system (see 3.9)

b. Canopy seal system (see 3.10)

c. Pressurization system (see 3.11)

d. Measuring system (see 3.12)

e. Accessories (see 3.13)

f. Trailer (see 3.14)

g. Control panel (see 3.15)

h. Housing (see 3.16)

i. Accessory box (see 3.17)

j. Pressurization hose storage device (see 3.18).

3.3 Selection of specifications and standards. Specifications and standards for necessary commodities and services not specified herein shall be selected in accordance with MIL-STD-143.

3.4 Materials.

3.4.1 Protective treatment. When materials are used in the construction of the tester that are subject to deterioration when exposed to climatic and environmental conditions likely to occur during service usage, they shall be protected against such deterioration in a manner that will in no way prevent compliance with the performance requirements of this specification. The use of any protective coating that will crack, chip, or scale with age or extremes of climatic and environmental conditions shall be avoided.

3.5 Design. The tester shall be designed to be a self-contained, mobile testing unit to furnish a supply of air under any combination of pressures and volumes specified herein and accurately measure the flow to the equipment undergoing test. The tester shall be designed to provide a range of 10 through 400 cubic feet per minute (CFM) standard airflow (0.765 through 30.6 pounds per minute (pm) and to provide a pressure range of 2 through 12.5 pounds per square inch gage (psig). The canopy seal pressure system shall provide 1 cfm standard air at 65 pounds per square inch (psi). The tester shall be designed for safety to both operator and maintenance personnel. Shields and caution notes shall be furnished where necessary and maximum use made of applicable safety devices. Design of the tester shall be in accordance with MIL-S-8512 unless otherwise specified herein.

3.5.1 Safety. The tester shall be designed to assure maximum safety consistent with requirements specified herein and the requirements of MIL-STD-882.

3.5.1.1 Safety devices. On air temperature gauge a red danger zone shall be marked on gauge face beginning at 120° Fahrenheit (F). An automatic dumping or relief device shall be incorporated to prevent overpressurization of

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.

aircraft under test. Consideration to preclude damage to equipment and items under test shall be included; however, first consideration shall be given to safety of personnel.

3.6 Construction. The tester shall be built to withstand the stresses, jars, vibrations, and other conditions incident to shipping, storage, installation, and service. Construction of the tester shall be in accordance with MIL-S-8512 unless otherwise specified herein.

3.6.1 Maintenance and servicing. The tester shall be so constructed that adjustments, repairs, and overhaul are easily accomplished by the personnel of operating units and overhaul bases. The tester shall be constructed so that simple tools may be used for maintenance and servicing and no special tools will be required.

3.6.2 Forces and acceleration. The tester structure, components, trailer, and mountings shall be constructed to withstand the gravitational forces and accelerations specified in MIL-A-8421.

3.6.3 Accessibility of controls. All operating and service controls shall be readily accessible to an operator wearing heavy gloves.

3.7 Performance. The tester shall be capable of operating under and shall show satisfactory resistance to the following conditions:

a. Operating temperatures ranging from -20° to $+120^{\circ}$F.

b. Storage in temperature ranging from -80° to $+160^{\circ}$F.

c. A relative humidity of 95 to 100 percent at a temperature of 130°F.

d. Rainfall as encountered in any locale.

e. Sand and dust particles as may be encountered in desert areas.

f. Exposure to salt-sea atmosphere.

g. Fungus growth as may be encountered in tropical climates.

3.7.1 Operating positions. The tester shall be capable of functioning satisfactorily when its normal operating plane is at an angle of 8 1/2 degrees in any direction from horizontal.

3.7.2 Operating range (altitude). The tester shall operate satisfactorily with a pressure altitude range from sea level to 6,000 feet.

3.8 Reliability and maintainability.

3.8.1 Reliability. The tester shall have a demonstrable minimum mean time between failure (MTBF) of 250 hours.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.

3.8.2 Maintainability. The tester will be designed so as to enhance accessibility for troubleshooting and repair. No special tools not ordinarily available at field level repair shops will be required unless specifically authorized by the procuring activity. The mean time to repair (MTTR) a tester shall not exceed four hours, including troubleshooting, removal and replacement of defective components and operational checkout of tester. The maximum downtime for a single failure shall not exceed eight hours. MIL-STD-470 will be the guide.

NOTE: Failure is defined as a malfunction within the tester resulting in downtime, whether immediate or deferred, for repair or replacement of any component.

3.9 Diesel engine system. Unless otherwise specified, diesel engine and all necessary accessories shall be selected and provided by the contractor in accordance with applicable document identified and furnished by the procuring activity (see 6.2.b).

3.10 Canopy seal system. A diaphragm-type air compressor, capable of providing 1 cfm standard air and 65 psi pressure shall be provided for pressurizing the aircraft canopy seals. The output of the compressor shall be controlled by an automatic pressure regulator with manual adjustment to maintain any pressure setting throughout a range of 5 to 60 psi. A safety device shall be provided to limit maximum pressure to 65 psi. A pressure gage, 0 to 100 psi scale, accurate within 2 percent of full scale shall be provided to indicate canopy seal pressure. The canopy seal pressure outlet on the tester shall be an AN832-6D fitting and an AN924-6D nut with an AN929-6D dust cap.

3.11 Pressurization system. The pressurization system shall consist of the following, arrange substantially in accordance with figure 1.

3.11.1 Blower. A single-stage or multi-stage with intercooling, lobed-impeller, positive-displacement blower shall be provided to supply 400 cfm standard air (30.6 pm) at 12.5 psi measured at the discharge end of the hose specified herein.

3.11.1.1 Impellers. The blower impellers shall be mounted on hardened shafts, encased in a cast housing, and driven through hardened gears. Gears shall be equipped with a means to permit accurate positioning of the impellers to adjust clearance and compensate for wear. The bearings used in the blower shall be easily replaceable.

3.11.1.2 Leakage. Means shall be provided for sealing the external and internal drive shaft clearance holes in the end plates to prevent leakage.

3.11.1.3 Installation or removal. Alignment of blower to engine shall not require special tools for installation or removal; nor shall it require skills which are not normally available at field level.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.

3.11.2 Intake silencer. The blower intake shall be equipped with an air intake cleaner-silencer device extending beyond the tester enclosure to the outside atmosphere, but shall not protrude more than 3 inches.

3.11.3 Blower outlet silencer. A silencer lined with sound dampening acoustical materials shall be provided in the blower discharge line between the blower and aftercooler to reduce noise and dampen the pulsation of the blower discharge air. Blower intake opening shall not be adjacent to the front of the operator's panel.

3.11.4 Aftercooler. An air-to-air aftercooler of efficient design and capable of delivering the required cooling and volume of air shall be provided. The aftercooler shall have sufficient capacity to cool blower discharge air to within 15°F of existing ambient temperatures while delivering maximum flow and pressure.

3.11.5 Aftercooler fan. An efficient, squirrel-cage-type fan shall be provided to supply the necessary cooling air for the aftercooler. The fan shall be dynamically balanced to prevent excess vibration and, if bearings are used, they shall be readily replaceable. The aftercooler fan intake shall extend to the outside of the tester housing and the intake opening shall be protected by a heavy, 1/4 inch mesh screen. The aftercooler fan exhaust shall extend to the outside of the tester housing and shall be equipped with adjustable louvers to control the flow of cooling air through the aftercooler from zero to maximum flow. The louvers shall be easily adjustable as a unit from a single control and shall provide for positive locking in any degree of opening. A drain hole shall be made in the bottom of the aftercooler fan housing and provided with a drain plug.

3.11.6 Pressure regulating device. A pressure regulating device consisting of a pressure regulating valve and valve control system shall be provided to automatically regulate the pressure in the aircraft cabin being pressurized and shall be installed between the aftercooler and flowmeter. For all pressure conditions where flow is varied between 50 and 400 cfm, the valve shall limit the rate of pressure change to 500 foot pounds per minute (fpm) as registered on the pressure equalization indicator. For all pressure conditions and where flow is varied between 10 and 50 cfm, the pressure regulating valve shall limit the rate of pressure change between ±750 fpm. The valve shall be capable of limiting pressure changes to between ±1.500 fpm during adjustment of the pressure regulator to a new pressure setting.

3.11.6.1 Valve. The pressure regulating valve shall be free from chatter and shall be of adequate capacity to bypass the total output of the main blower at any pressure above 2 psi without creating more than a 1/2 psi pressure rise above the valve setting.

3.11.6.2 Valve control system. The valve control system shall be so designed that it may be manually adjusted and fixed at any pressure within the range of 2 through 12.5 psi for all flow and temperature conditions specified herein.

Source: https://assist.dla.mil -- Downloaded: 202610-20T07:55Z
Check the source to verify that this is the current version before use.




FIGURE 1. Pressurization system arrangement.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.

The manual adjustment for the valve control system shall be located on the instrument panel and calibrated in 1/4 psi increments from 0 through 12.5 psi (cabin pressure). The valve control system shall incorporate a sensitive means to adjust flow and to correct for changes, and shall incorporate a pilot control valve, air resistor, and maximum pressure relief similar to the arrangement shown on figure 1.

3.11.6.3 System dumping. A means shall be provided to dump the system at a minimum rate of 80 cfm with the unit running.

3.11.7 Air outlet connection. A 3 inch hose connection in accordance with MS33660 shall be provided at the flowmeter discharge and shall extend 6 inches beyond the tester housing for hose connection. The outlet shall be rigidly supported by means which will prevent damage to the flowmeter in the event the protruding section of the outlet is severely damaged, twisted, or sheared off. A protective cap attached by chain or cable, shall be provided to protect the air outlet.

3.11.7.1 Other outlets. All other outlets shall be provided with dust caps attached by metal chain to the test stand.

3.11.8 Air duct. The air ducts and passages between the components specified herein shall be fabricated of aluminum tubing, steel tubing, metal flexible ducts, or box sections of aluminum or steel sheet and shall be designed to provide a minimum of elbows, restrictions, et cetera, which would create excessive pressure drop through the system. Hose of proper temperature and pressure rating is allowed between blower discharge and aftercooler inlet and between aftercooler outlet and the pressure regulator and flowmeter.

3.12 Measuring system. The following items shall be provided and arranged for maximum accuracy and facility of readings. All items shall be mounted in a manner to minimize errors due to vibration and to be easily removable for replacement or service.

3.12.1 Air flowmeter. A direct-reading, sight-type flowmeter, accurate to within 2 percent or better of scale, shall be provided to measure the flow to the aircraft being pressurized. The flowmeter or a combination of flowmeters shall provide a range from 10 through 400 cfm standard air at pressures ranging from 2.0 through 14.0 psi. The pressure lines on the air flowmeter dials shall be graduated in 2 psi increments through the pressure range.

3.12.1.1 Cover. The flowmeter shall be covered with 1/4 inch plexiglass to eliminate operator injury caused by the explosion or accidental breakage of the flowmeter glass.

3.12.2 Temperature correction curve. A legible, waterproof, pressure-temperature correction curve shall be provided and mounted on the control panel adjacent to the flowmeter for correcting observed airflow readings to ambient conditions. Pressure lines shall be provided and marked to correspond with pressure lines on the flowmeter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.

3.12.3 Conversion chart. A legible and waterproof chart shall be provided and located on the control panel for converting the airflow from cubic feet per minute to pounds per minute.

3.12.4 Pressure equalization indicator. A rate-of-climb indicator, similar to MS28049, 0 to 6,000 feet, in accordance with MIL-I-7721 shall be furnished to indicate pressure equalization of the tester output and the inclosure being pressurized. The dial face shall be modified to indicate decreasing and increasing instead of up and down and the instrument red-lined beyond the 5,000 foot mark, both increasing and decreasing. The glass dial cover shall be removed and replaced with a plastic or glass cover suitable for 12.5 psi. A caution note shall be displayed on a permanent-type, etched or engraved nameplate securely attached to the instrument panel immediately below the instrument which reads as follows: Caution - Do not increase or decrease cabin pressurization at the red-lined rates.

3.12.5 Cabin pressure indicating gage. The flush-mounted cabin-pressure gage shall have a 4 inch diameter dial and steel-alloy bourdon tube. The gage shall be accurate to within 1 percent, or less, of full scale and shall conform to GG-G-76 except, where conflicts exist, this specification shall govern. The gage shall provide a range from 0 to 15 psi and shall incorporate a means to restore the accuracy of the gage under all service conditions. The gage shall be constructed of corrosion-resistant materials throughout and shall be suitable for operation at from -20° to +160°F. The gage shall be of the recess type provided with a mounting flange at the front of the gage. The mounting flange and dial shall not extend more than 5/8 inch beyond the external surface of the panel. All gages shall incorporate a safety blowout device. The safety blowout device shall automatically relieve the gage case pressure should it reach 1/2 psi due to gage failure. The pointer shall be adjustable without removing the gage from the panel. Good quality stainless steel shall be required on all gages. The dial and pointer shall be separated from the gage movement by a wall which will prevent rupture through the front of the gage in the event of gage failure.

3.12.5.1 Mounting. Gages shall be mounted by screws and tapped panel holes to permit removal by one man from in front of the panel.

3.12.5.2 Connection. Gages shall be connected to the panel with flexible AN- or MS-type hose, or commercial equivalent, of sufficient length to permit removal and installation from the front of the panel.

3.12.5.3 Gage test fittings. The following fittings shall be mounted on the control panel, as shown on figure 1, adjacent to the appropriate gage, and the panel marked to indicate that the fittings are gage test connections:

a. An AN832-4D nipple.

b. An AN924-4D nut.

c. An AN929-4 cap.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.

3.12.6 Blower pressure indicator. A 3 inch dial size, or larger, pressure gage with a range of 0 to 30 psi and accuracy of 1 percent of full scale shall be furnished to read the blower pressure at the inlet side of the flowmeter. The gage shall meet all other requirements of 3.12.5.

3.12.7 Discharge air temperature indicator. A remote-reading, dial-type temperature indicator having a scale range from -20° to approximately +200°F and accurate within ±2°F throughout the range, shall be furnished and installed on the instrument panel. The temperature indicator shall measure the temperature of the pressurized air on the discharge side of the flowmeter. The temperature gage shall be marked by a red sector above 120°F and a caution plate attached, reading: AIR TO CABIN SHOULD NOT EXCEED 120°F. Temperature bulb shall be located in the flowmeter in such a manner as to facilitate removal through the inspection hole in the housing above the flowmeter without removal of the housing.

3.12.8 Measuring system tubing. The interconnecting air lines shall be 1/2 inch outside diameter (OD) aluminum tubing and connected to the gages, takeoff points, et cetera, by means of AN fittings. The static pressure line outlet from the tester for connection to the static hose shall be an AN832-8D fitting and an AN924-8D nut with an AN929-8D dust cap.

3.13 Accessories. The following accessories shall be furnished and stored within the tester housing:

a. One AN6270-8-300 hose, with dust caps securely attached to the hose with metal chains.

b. One AN6270-6-300 hose, with dust caps securely attached to the hose with metal chains.

* c. One AN893-12D bushing to adapt the 1/2 inch hose to the 3/8 inch tube fitting on the aircraft.

d. One AN893-2D bushing to adapt the 3/8 inch hose to the 1/4 inch canopy seal fitting on the aircraft.

e. A complete set of adapters and a gasket for each in accordance with drawing 50B6228, 50B6230, and 50B6335.

* f. One 25 foot length of 3 inch inside diameter flexible, collapsible air hose in accordance with MIL-H-26521 and the necessary clamps to secure the hose to the outlet specified in 3.11.7 and to the adapters specified in 3.13e. MIL-H-6000 hose may be used in place of MIL-H-26521 hose.

g. One stethoscope for detecting cabin leakage through the skin of the aircraft. The stethoscope shall be suitable for use at -20°F and shall be of rugged construction to withstand hard service usage.

Source: https://assist.dla.mil -- Downloaded: 202640-20T07:55Z
Check the source to verify that this is the current version before use.

3.14 Trailer. Unless otherwise specified, the components of the tester shall be mounted and assembled on a trailer having type II mobility requirements in accordance with MIL-M-8090.

* 3.14.1 Tires. The trailer shall be mounted on four size 6.90 by 9 industrial, pneumatic-type tires of 6- or 10-ply rating with free rolling tread.

3.14.2 Trailer bed. The trailer bed shall be of welded-steel construction. The ratio of width divided by length shall not exceed three-fourths.

3.14.3 Parking brakes. The trailer parking brakes shall hold the tester in a fixed position during all operating conditions and positions specified herein. The brakes shall be of the internal expanding type capable of locking the rear wheels. Brakes for both rear wheels shall be interconnected and shall operate from one handle.

3.14.3.1 Marking of control device. The parking brake control device shall be appropriately marked with operating instructions for release and application of the brakes. The marking shall be 1/4 inch black letters and shall be visible to the operator.

3.14.4 Springs. Springs shall be furnished on the trailer to provide good riding qualities, thereby precluding damage to the mounted equipment. The springs shall be of such construction that not more than 3 inches is added to the frame height for spring deflection.

3.14.5 Steering. Adequate means for lubrication shall be provided. The cramping angle shall be not less than 40 degrees.

* 3.14.6 Towbar assembly. The trailer shall be furnished with a hinged towbar assembly in accordance with MIL-M-8090.

* 3.14.6.1 Stowage. The towbar shall store in the up position.

3.14.7 Mobility. The tester shall be capable of executing full turns at a cramping angle of 40 degrees to the right and to the left while being towed at a speed of 10 miles per hour (mph) and shall not capsize or skid during turns on dry concrete or macadam.

3.14.8 Weight supporting capabilities. The trailer shall be capable of supporting 800 pounds in addition to the tester components, control panel, and housing.

3.14.9 Lifting and tiedown fittings. The trailer shall be equipped with four or more lifting and tiedown fittings in accordance with drawing 48B7796 or 49B6564 capable of withstanding the loadings specified in 3.6.2.

3.14.10 Road clearance. The fully loaded trailer shall provide at least 6 inches of road clearance. The tread width shall be 52 inches.

* 3.15 Control panel. A control panel shall be provided for mounting all the meters, valves, gages, switches, and controls furnished with the tester. The control panel shall be constructed of number (No.) 12 United States (US) gage (0.1046 inch) or thicker sheet steel and supported by a welded-steel, self-supporting framework. The control panel frame shall be bolted or welded

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.

to the trailer bed and positioned so that wheels, tow bars, et cetera, will not interfere with the operator. The control panel shall be located at sufficient height above the ground and inclined at sufficient angle, 10 degrees minimum, to facilitate observation and operation of all items by an operator approximately 5 feet 10 inches tall. If the height of the upper section of the panel is above the eye level of such operator, that section of the panel shall be vertical. Instruments subject to errors from vibration shall be shock mounted. All items mounted on the control panel shall be identified as to use and cautions by permanent etched or engraved metal or plastic nameplates permanently attached to the panel.

3.15.1 Diagram. A 4 by 6 inch, engraved, permanent-type diagram plate, arranged similar to figure 1 to show the pneumatic circuit of the tester, shall be securely fastened in the center of the instrument panel.

3.16 Housing. The tester components and control panel shall be completely inclosed and protected by a weather-resistant housing. The housing shall consist of a welded-steel framework covered with No. 16 U.S. gage (0.0598 inch) or heavier sheet metal and doors and adjustable louvers as required. The housing shall be capable of supporting a 200 pound weight distributed evenly over an area 4.5 by 5 inches and applied in any location on the top of the tester. The housing shall be adequately braced to prevent distortion or excessive vibration during handling and operation of the tester or handling of the housing while removed from the tester.

3.16.1 Ventilation. The housing shall be provided with sufficient access and ventilating doors and adjustable louvers to permit access for operating and servicing, and to ventilate the tester. Fixed openings are allowed if necessary for compatability with required accoustical treatment and related air ducting. The doors and louvers in the housing shall be free from binding and easy to operate with one hand. Provisions shall be incorporated to secure the doors rigidly in the full open or full closed position. An inspection hole in the housing at least four inches in diameter with a detachable cover shall be provided directly over the flowmeter.

3.16.2 Removability. The housing shall be easily removable by actuating not more than 12 quick-acting disconnecting fasteners and lifting or sliding the entire housing off the remainder of the tester. Handles shall be provided for this purpose. Housing may be separated into more than one piece for removal but each piece must be adequately braced to prevent distortion. If housing weight exceeds that which will allow easy removal by two men, lifting eyes or rings shall be provided for removal with hoist.

3.17 Accessory box. An accessory box shall be provided and divided into separate compartments; one compartment for the hose assemblies and fittings (installed on hose) specified in 3.13a, b, c, and d; one compartment for each adapter and its respective gasket specified in 3.13e; and one compartment for the stethoscope specified in 3.13g. The box shall be provided with a hinged cover and with a hasp to provide for holding the cover closed and possible padlocking.

Source: https://assist.dla.mil Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.

3.18 Pressurization hose storage device. A rack, tray, or compartment shall be provided within the tester housing to store the pressurization hose specified in 3.13f.

* 3.19 Interchangeability. All parts having the same manufacturer's part number shall be functionally and dimensionally interchangeable. The drawing number requirements of DOD-D-1000 shall govern changes in the manufacturer's part number.

3.20 Radio interference. The tester shall meet the requirement of MIL-STD-461, 0.15 through 150 megacycles (radiated).

* 3.21 Accoustical noise. Accoustical noise limits shall be those listed for category D of MIL-STD-1474 in each frequency band shown. These limits shall not be exceeded at ten feet from the periphery of the tester. At the operator position the limits shall be five decibels higher in each frequency band than allowed at ten feet.

NOTE: Extensive accoustical treatment will be required. Ordinary design and construction without special attention to this requirement will result in a unit which will exceed the limits given by an estimated 20 to 50 decibels.

3.22 Dimensions. The length and width of the tester and housing shall be not less than the trailer bed and shall not overhang the outline of the wheels at any point. The overall height of the tester shall be held at a minimum consistent with good design practices. Unit shall be designed for air shipment and size and weight shall be in accordance with MIL-S-8512.

3.23 Cleaning, plating and chemical films shall be in accordance with MIL-STD-808 as supplemented by Air Force drawing 7545352. The exterior of the tester shall be dark green, color 24052, film designation LG, per FED-STD-595. Inner surfaces of exterior panels or components may be the same color.

3.24 Identification of product. Equipment, assemblies, and parts shall be marked for identification in accordance with MIL-STD-130. The following special characteristic marking shall appear on the nameplate.

10 - 00 CFM STD AIR, 2 to 12.5 PSI GAGE
GROSS WEIGHT _____
TOWING SPEED 20 MPH MAX.

3.25 Air transportability markings. Marking pertaining to air transportability and associated handling operations shall be provided in accordance with MIL-A-8421.

3.26 Workmanship.

3.26.1 General. The tester, including all parts and accessories, shall be fabricated and finished in a workmanlike manner. Particular attention shall be given to freedom from blemishes, defects, burrs, and sharp edges; accuracy

Source: https://assist.dla.mil/ -- Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.

of dimensions, radii of fillets, and marking of parts and assemblies; thoroughness of soldering, welding, brazing, painting, wiring, and riveting; alignment of parts and tightness of assembly screws and bolts; et cetera.

3.26.2 Riveting. Riveting operations shall be carefully performed to insure that the rivets are tight and satisfactorily headed.

3.26.3 Cleaning. The tester shall be thoroughly cleaned, and loose, spattered, or excess solder, metal chips, and other foreign material removed during and after final assembly.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of tests. The inspection and testing of the tester shall be classified as follows:

a. Quality conformance inspection (see 4.3).

b. First article inspection (see 4.6).

4.3 Quality conformance inspection. Quality conformance inspection shall consist of the following:

a. Individual tests.

b. Sampling plan and tests.

c. Maintainability demonstration (see 4.5.17).

d. Reliability testing (see 4.5.18).

4.3.1 Individual tests. Each tester shall be subjected to the following tests as described under 4.5:

a. Examination of product (see 4.5.1).

b. Operational test (see 4.5.2).

c. Calibration test (see 4.5.3).

4.3.2 Sampling plan and tests. One tester shall be selected at random from each lot, not to exceed 50 testers, manufactured under essentially the same conditions and subjected to the following tests:

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.

4.3.2.1 Applicable tests. The tester shall be subjected to tests a through g listed in 4.5.7 for 20 percent of the endurance test time specified. The calibration tests specified in 4.5.7a and 4.5.7h shall be performed before the start and after completion of the endurance tests.

4.3.2.1.1 Rejection and retest. When one or more testers from a lot fail to meet the specification, acceptance of all testers in the lot shall be withheld until the extent and cause of failure are determined. After corrections have been made, all necessary tests shall be repeated.

4.3.2.1.2 Individual tests may continue. For production reasons, individual tests may be continued pending the investigation of a sampling test failure. Final acceptance of the entire lot shall not be made until it is determined that the lot meets all the requirements of the specification.

4.3.2.1.3 Defects in testers already accepted. The investigation of a test failure could indicate that defects may exist in items already accepted. If so, the contractor shall fully advise the procuring activity of all defects likely to be found and methods of correcting them.

4.4 Test conditions.

4.4.1 Standard atmospheric conditions. Whenever the pressure and temperature existing at the time of the test are not specified definitely, it is understood that the test is to be made at atmospheric pressure approximately 29.92 inches mercury and at room temperature approximately 73°F. All airflow readings shall be reduced to standard air readings of 0.07651 pound per cubic foot at 59.6°F.

4.4.2 Apparatus and instruments. Apparatus and instruments used in conjunction with testing specified herein shall be of laboratory precision type and shall be carefully checked to ascertain that they have been installed in a satisfactory manner for durability and accurate operation and shall be calibrated at intervals properly spaced to assure laboratory efficiency.

4.4.3 Airflow. The airflow shall be measured by means of a nozzle box and nozzles constructed in accordance with ASME power test code PTC9. In lieu of the above, the most accurate scientifically recognized techniques, instruments, and methods shall be utilized to measure the airflow and, if certified for accuracy, shall be acceptable.

4.4.4 Test periods. Unless otherwise specified, any test run shorter than 1 hour shall not be counted as test time.

4.4.5 Preliminary run-in and calibration test. Any preliminary run-in of the tester as may be recommended by the manufacturer shall be performed by the manufacturer prior to submission of the tester for testing. A certified log of all preliminary running time, calibration data, et cetera, shall be submitted to the procuring activity for entry in the log book.

4.5 Test methods.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.

4.5.1 Examination of product. The tester shall be inspected to determine compliance with requirements specified herein with respect to parts, materials, workmanship, and marking.

4.5.2 Operational test. The operation of the tester shall be checked at 400, 200,100, and 10 cfm standard air at each pressure condition of 12.5, 7.5, and 2.0 pounds per square inch gage with hoses installed. All valves, gages, meters, adjustable louvers, accessories, and the canopy seal system shall be checked for satisfactory performance during the operational test.

4.5.3 Calibration test. The 25 foot length of 3 inch supply hose and 25 foot length of 1/2 inch static hose shall be connected to their respective fittings on the tester and connected to similar fittings on a 60 cubic foot test tank. The output of the test tank shall be directed through a throttling valve into the nozzle box and nozzle specified in 4.4.3. A laboratory test gage with accuracy of one half of 1 percent of full scale shall be installed to read the pressure within the test tank. Other gages, manometers, and thermometers in accordance with 4.4.2 shall be installed as required. The calibration of the tester shall then be checked at 400, 300, 200, 100, and 10 cfm standard air at each pressure condition of 10, 7.48, 6.55, 4.8, 3.2, and 2.75 psig. The pounds per minute airflow readings of the tester (as determined by the tester's gages, flowmeter, conversion and correction charts, et cetera) shall agree within 3 percent or less to the readings of the calibration equipment at all of the pressure-flow settings listed. The accuracy of the cabin pressure indicated as specified in 3.12.5 shall be checked against the test tank gage and the pressure equalization indicator performance shall be checked against the test tank gage and a stopwatch (lowering and raising pressure in the test tank at the 5,000 foot rate). The pressure regulating valve shall be checked for compliance with 3.11.6 and 3.11.6.1.

4.5.4 Towing test. The tester shall be completely assembled with all accessories and fluid and towed a distance of 5 miles over unimproved roads and then tested in accordance with 4.5.3. The tester shall not lose calibration. All components shall remain securely fastened in position.

4.5.5 Initial disassembly inspection. The tester submitted for first article tests shall be disassembled to the maximum practical extent and completely inspected, the breakdown weights determined, and measurements made which may be used to determine wear. All gages, meters, and instruments shall be laboratory checked against certified calibrating equipment and failure to meet the accuracy requirements specified in section 3 shall be cause for rejection. All requirements of section 3 which may be determined by weight or dimensional measurements or inspection shall be checked for compliance, and failure to meet the requirements of section 3 shall be cause for rejection. Following this inspection, the tester shall be reassembled and subjected to the remainder of the first article tests.

4.5.6 Environmental. The tester shall be subject to the following tests conducted in accordance with MIL-STD-810. Upon completion of the tests, the tester shall be subjected to each of the tests specified in 4.5.2. Failure of the tester to operate as required during or after each exposure, or failure of any item or assembly due to deterioration from exposures in this test, or formation of any undesirable condition which cannot be remedied by routine maintenance procedures shall be cause for rejection.

Source: https://assist.dla.mil/ -- Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.

4.5.6.1 Low temperature. The tester shall be subjected to low temperature in accordance with Method 502.2. After the required length of exposure at -80°F, the ambient temperature in the cold room shall be increased to -20°F, starting procedures shall be accomplished. The engine shall start within 10 minutes and the tester shall reach rated output of 400 cfm standard air at 12.5 psi in not more than 15 minutes after starting. All gages, valves, meters, accessories, louvers, regulators, et cetera, shall be operated and shall perform satisfactorily in the -20°F ambient temperature condition.

4.5.6.2 High temperature. The tester shall be subjected to high temperature in accordance with Method 501.2. Upon completion of the 50-hour exposure, the ambient temperature shall be lowered to 120°F and the test specified in 4.5.2 shall be conducted. Failure of the aftercooler system to limit the temperature of the pressurized air leaving the tester to a maximum of 135°F while the tester is operating at full capacity of 400 cfm standard air and 12.5 psi in the 120°F ambient shall be cause for rejection.

4.5.6.3 Salt spray. The tester shall be subjected to salt spray in accordance with the procedure specified.

4.5.6.4 Sand and dust. The tester shall be subjected to sand and dust in accordance with Method 510.2.

4.5.6.5 Fungus resistance. The tester shall be subjected to fungus in accordance with Method 508.3. Certificate to the effect that no nutrients for fungus have been used in the manufacture of the test stand may be provided in lieu of testing.

4.5.6.6 Humidity. The tester shall be subjected to humidity in accordance with Method 507.2.

4.5.6.7 Rain test. The tester shall be subjected to rain in accordance with Method 506.2. The tester shall be positioned on the test chamber floor in its normal operating position. After exposure to rain for 1 hour and while still in the rain test, the tester shall be started and operated at 400 cfm and 12.5 psi for a period of 30 minutes. Failure of the tester to start or operate satisfactorily during the rain tests shall be cause for rejection. Any collection of moisture, within the housing, in excess of 1/8 inch deep or which could be detrimental to the operation of the tester, after the rain test, shall be cause for rejection.

4.5.7 Endurance. The tester shall be connected through the hose specified in 3.13f to a throttling device to create the required pressure and flow conditions (pressures and flows shall be measured at the hose outlet) and the following 430-hour endurance tests accomplished. Readings shall be recorded every hour, of all gages, meters, and instruments of the tester, and output flow, pressure, and temperature shall be measured as specified in 4.4 and recorded. Barometric pressure and ambient temperature shall be recorded for each reading.

Source: https://assist.dla.mil - Downloaded: 202640-20T07:55Z
Check the source to verify that this is the current version before use.

a. Conduct the tests specified in 4.5.3.

b. Two hundred and fifteen hours operation at 400 cfm and 12.5 psi.

c. Forty three hours operation at 400 cfm and 8 psi.

d. Forty three hours operation at 400 cfm and 2 psi.

e. Forty three hour operation at 200 cfm and 12.5 psi.

f. Forty three hours operation at 100 cfm and 8 psi.

g. Forty three hours operation at 10 cfm and 2 psi.

h. Conduct the tests specified in 4.5.3. Comparison of these data with data recorded under 4.5.7a shall indicate that the tester is in excellent condition and that no failure or undue wear has resulted from the endurance test.

4.5.8 Air Compressor test. The canopy seal air compressor shall be operated at least 25 percent of the time during all endurance tests specified under 4.5.7. The performance of the compressor shall be checked periodically during each first article inspection. Failure of the drive coupling or any marked decrease in performance or failure of a component part of the pressurizing system shall be cause for rejection.

4.5.9 Radio interference. The tester shall be tested as a complete unit for radio interference suppression. The test shall be conducted in accordance with MIL-STD-461 for radiated interference, except that whenever a shielded room is not readily available, a test location shall be selected in lieu of a shielded room, where the inherent background level and the area background level are within the limits specified in MIL-STD-461. The meter and test specimen shall have a common ground potential in substitution for the ground plane, and the antenna shall be limited to 6 feet from the perimeter of the test specimen.

4.5.10 Noise level. The noise level of the tester shall be measured 10 feet from the perimeter of the test specimen and shall not exceed the noise level shown in 3.21. Measurements shall be taken out-of-doors on a paved surface from at least 12 different positions, 30 degrees apart in a horizontal plane parallel to the trailer bed. During this test, the tester shall be operating at 200 standard cubic feet per minute (scfm) output and 200 scfm bypass.

4.5.11 Operation in the tilted position. The tester shall rest on a platform and be kept from rolling by the parking brakes. The platform supporting the tester shall be tilted in eight different directions, 45 degrees apart, on an 8 1/2 degree incline with the true horizontal plane. The tester shall be started and operated at 400 cfm and 12.5 psi for 15 minutes in each position. The tester shall perform satisfactorily in every respect and the parking brakes shall prevent the tester from moving on the platform.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.

4.5.12 Serviceability. The tester shall be inspected and evaluated from the standpoint of ease of maintenance, servicing, operation, and safety. Particular note shall be made with regard to provisions to prevent accumulation of dirt, snow, ice, et cetera which may hinder servicing and operation.

4.5.13 Road tests. The tester shall be loaded with 800 pounds of weight, distributed so that 400 pounds rest uniformly over the top of the housing and 400 pounds are supported by the trailer frame. The tester shall be towed by a truck 50 miles over improved roads at a speed of 20 miles per hour (mph) and 10 miles at 10 mph over unimproved roads. The 800 pounds of weight shall be removed and the tester shall execute 10 full turns (turning radius shall be the minimum attainable with the truck) to the right and 10 to the left on dry concrete or macadam at an average speed of 10 mph. The tester shall not skid or capsize during the turns. Upon completion of the road tests, the tester shall satisfactorily pass the tests specified in 4.5.3.

4.5.14 Safety demonstration. The tester shall be inspected and functionally checked to ascertain that safety requirements have been incorporated in the design and manufacture of the stand. Potential hazards shall be identified, the safety device or method shall be shown and an assessment of adequacy will be made.

4.5.15 Final disassembly inspection. The tester shall be disassembled to the maximum practical extent for a thorough examination of all parts to disclose failure, distortion, excessive wear, or other unsatisfactory conditions. If measurements are made to determine wear, they shall be compared with similar measurements made during initial disassembly inspection. Testers not conforming to requirements specified herein shall be rejected.

4.5.16 Tie down and lifting rests. The complete assembled tester shall be subjected to the tests specified in MIL-A-8421. The tester shall be secured during this test by means of the lifting and tie down fittings only, and each load shall be applied at least one time. Upon completion of this test, the tester shall be inspected to determine adequacy of bracing, tie down and lifting fittings, installation and security of mounting of all components. The tester is not required to be operational after this test. In accordance with MIL-A-8421, calculations may be provided in place of testing.

4.5.17 Maintainability demonstration. Two tests shall be conducted to assure that the design requirements for maintainability have been met. An Air Force technician shall perform the tests. Each test shall consist of restoring to operation a test set that had a fault intentionally introduced prior to the test. The technician will use the written instructions furnished by the contractor and the tools and spare parts available at the repair shop. Repair and operational checkout of the tester shall not average more than four hours each, and no single tester shall require more than eight hours. The faults introduced for these tests shall be chosen by Technical Services of the procuring activity. Also, the maintainability demonstration shall include, but not be limited to, the removal and replacement of the following items: flowmeter assembly, blower, selector valve, relief valve, canopy compressor, gearbox, temperature gauge, pilot valve, and dial assembly, gauges and switches on control panel. MIL-STD-471 will be the guide. Engine malfunctions will not be included in the maintainability demonstration; however, access for engine service and repair must be shown.

Source: https://assist.dla.mil -- Downloaded: 20260-20T07:55Z
Check the source to verify that this is the current version before use.

4.5.18 Reliability testing. Two or more test sets shall be tested. The tests shall demonstrate a minimum MTBF of 250 hours (θ_1) as defined in MIL-STD-781. Use Test Plan VIII of MIL-STD-781. During testing, the test sets shall operate at full load under adverse conditions and will operate continuously three or more hours without shutdown. Sets used in environmental or other first article testing may be used for reliability testing. In this event, time and failures experienced in previous testing shall be counted toward reliability accept/reject decisions. Four hundred and thirty (430) hours of endurance testing represents one cycle of testing to be repeated until an accept/reject decision is reached. Failure which can be validly attributed to a Government furnished engine, not as a result of contractor abuse or incompatible stand design, will not be charged against the contractor.

4.6 First article inspection.

4.6.1 First article sample. One tester, as specified in the contract, shall be tested for design approval by the procuring activity or, when so specified in the contract, at the contractor's plant under the supervision of the procuring activity.

4.6.1.1 First article inspection report. If the contractor performs the first article inspection, he shall prepare a first article inspection report in accordance with MIL-STD-831 and furnish the report to the procuring activity.

4.6.2 Inspection. The first article inspection shall consist of all the tests described under 4.5.1 through 4.5.16, conducted in the same order.

4.7 Inspection of preparation for delivery. The preservation, packaging, packing and marking shall be inspected to determine compliance with section 5.

5. PACKAGING

5.1 Preservation and packaging. Preservation and packaging shall be level A or C as specified (see 6.2).

5.1.1 Level A. Each tester (except engine, spares, accessories and tools) shall be preserved and packaged in accordance with MIL-P-116, method I. P-2 preservation shall be applied to all external bare metal surfaces.

5.1.1.1 Engine. The engine shall be preserved and packaged in accordance with MIL-E-10062.

5.1.1.2 Spares, accessories and tools. Spares, accessories and tools shall be individually preserved and packaged method III. Packaged items shall be packed in PPP-B-636, V3c containers with adequate cushioning material. Boxes shall be secured to the unit with tape or strapping.

5.1.2 Level C. Each tester shall be preserved and packaged to afford adequate protection against corrosion, deterioration and physical damage during shipment from the supply source to the first receiving activity.

Source: https://assist.dla.mil -- Downloaded: 202610-20T07:55Z
Check the source to verify that this is the current version before use.

* 5.1.3 Each tester shall be preserved and packaged in accordance with ASTM D-3951.

5.2 Packing. Packing shall be Level A, B or C as specified (see 6.2).

5.2.1 Level A. Each tester preserved and packaged as specified in 5.1.1 shall be packed in a container conforming to MIL-C-104, type I, class 2, style A. Interior cushioning, anchoring, blocking and bracing shall be in accordance with MIL-STD-1186. Containers shall be of uniform size and shape and of minimum tare and cube.

5.2.2 Level B and C. The tester shall be shipped as a mobile unit. All door openings, louvers, vents, et cetera shall be sealed with tape conforming to A-A-884 to prevent direct entry of water, snow and dust.

* 5.2.3 Commercial. Each tester shall be packed in accordance with ASTM D-3951.

5.3 Marking. In addition to any special marking required by the contract or order, interior packages and exterior containers shall be marked in accordance with MIL-STD-129.

6. NOTES.

6.1 Intended use. The AF/M32T-1 tester covered by this specification is intended for use in ground checking and maintenance of aircraft pressurized cabins.

6.2 Ordering data.

6.2.1 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.

b. Identification of applicable document for engine selection and, if applicable, particular engine to be used (see 3.9).

c. Whether or not Government will furnish engines (see 3.9).

d. Levels of preservation, packaging and packing required (see 5.1 and 5.2).

6.3 First article inspection tests. One tester will be required as a first article sample to be subjected to the first article tests to determine compliance with the requirements of the specification. The point of inspection for these tests should be specified.

6.4 International standardization agreeemnt. Certain provisions of 3.13 of this specification are the subject of international standardization agreements ABC Standard 17/33. When amendment, revision, or cancellation of this specification is proposed which will modify the international agreement concerned, the preparing activity will take appropriate reconciliation action through international standardization channels including departmental standardization offices to change the agreement or make other appropriate accommodations.

Source: https://assist.dla.mil -- Downloaded: 202610-20T07:55Z
Check the source to verify that this is the current version before use.

6.5 Changes from previous issue. The margins of this specification are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

Custodian:
Air Force - 99

Preparing activity:
Air Force - 82

(Project 4920-F392)

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-T-26141D	Tester, Pressurized Cabin Leakage, Aircraft AF/M32T-1

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR ☐ USER ☐ MANUFACTURER ☐ OTHER *(Specify)*: _____
b. ADDRESS *(Street, City, State, ZIP Code)*	

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T07:55Z
Check the source to verify that this is the current version before use.