MILITARY SPECIFICATION
STATIC LINE, ASSEMBLY: XM164

1. SCOPE

1.1 This specification covers Static Line Assembly for use in conjunction with aircraft.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals form a part of this specification to the extent specified herein.

SPECIFICATIONS

Federal
- PPP-B-636 - Box, Fiberboard

Military
- MIL-A-2550 - Ammunition and Special Weapons, General Specification for
- MIL-C-5424 - Cable, Stainless Steel

STANDARDS

Military
- MIL-STD-105 - Sampling Procedures and Table for Inspection by Attributes
- MIL-STD-109 - Quality Assurance Terms and Definitions
- MIL-STD-129 - Marking for Shipment and Storage
- MIL-STD-417 - Rubber, Compositions, Vulcanized General Purpose Solid
- MIL-STD-1167 - Ammunition Data Card

DRAWINGS

U.S. Army Munitions Command
- C10542412 - Static Line Assembly
- IEL-10542412 - Inspection Equipment List for Static Line, Assembly, for Use on Flare, Aircraft, Parachute, MK 24

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:54Z
Check the source to verify that this is the current version before use.

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 General.- Materials, parts and assembly shall comply with the requirements specified on the applicable drawings and referenced specification.

3.2 Material.- The contractor shall be responsible for selecting from the classification list contained in the raw material specification, the surface and physical condition of the raw material intended for use in manufacture.

3.3 Functional.

3.3.1 The static line assembly shall function without mechanical failure (See 6.1).

3.3.2 The static line assembly under load (See 6.2) shall perform as follows:

3.3.2.1 The static line shall be capable of withstanding a minimum of 3000 lbs. tensile strength at the rate of 3.5 inches per minute when applied to the hook fasteners.

3.3.3 The static line assembly shall comply with all the functional requirements at the temperature range of minus 65 degrees to plus 125 degrees F.

3.4 Workmanship.- Requirements for workmanship are as specified on the applicable drawings, referenced specifications and the following:

3.4.1 Metal defects.- All components and assemblies shall be free from cracks, splits, cold shuts, inclusions, porosity, broken ends, frayed ends or any other defects.

3.4.2 Rubber defects.- All components and assemblies shall be free from blisters, bubbles, cracks, porosity or any other defects.

3.4.3 Physical properties.- The physical properties specified on the applicable drawings and referenced specifications shall be uniform throughout each component.

3.4.4 Burr.- No part shall have a burr which might be injurious to personnel handling the item.

3.4.5 Foreign matter.- No part or assembly shall contain dirt, chips, grease, oil, rust, corrosion or other foreign matter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:54Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.- Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specifications where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Quality assurance terms and definitions.- Reference shall be made to MIL-STD-109 to define the quality assurance terms used.

4.1.2 Inspection.- Inspection shall be in accordance with MIL-A-2550, except as specified herein.

4.2 First article sample.

4.2.1 Initial production sample.- At the beginning of regular production, samples shall be submitted in accordance with contractual requirements and shall consist of 9 completed static line assemblies and 5 sets of unassembled components for physical and visual examination. The samples shall be manufactured using the same materials, equipment processes and procedures as used in regular production. All parts and materials including packaging and packing, shall be the same as used in regular production and shall be obtained from the same source of supply.

4.2.1.1 Examination and test.- After inspection and provisional acceptance at source, the 9 completed static line assemblies shall be inspected in accordance with 4.4 at the temperatures specified in 4.3.3.1, three assemblies at each temperature. The unassembled components shall be inspected for all the requirements on the applicable drawings. These examinations and tests shall be performed at a Government laboratory or such other facility specified in the contract.

4.2.1.2 Initial production sample failure.- Failure of the sample to comply with the requirements of the drawings and specifications shall result in sample disapproval.

4.3 Inspection provisions.

4.3.1 Lot.

4.3.1.1 Submission of product.- The product shall be submitted in accordance with MIL-STD-105.

4.3.1.2 Size of lot.- A lot shall consist of an identifiable group of assembled units containing components produced by a homogeneous process.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:54Z
Check the source to verify that this is the current version before use.

4.3.2 Examination.- One hundred percent examination shall be performed on all critical defects. Examination for major and minor defects shall be performed on a defect basis in accordance with the classification of defects contained herein using the sampling plan and associated criteria in Table I and II. For an individual defect (single characteristic) the criteria in Table I shall be used. For total defects within a major or minor class, the criteria in Table II shall be used. All nonconforming material shall be rejected. Inspection for Steel Cable shall be in accordance with MIL-C-5424 and inspection for Vulcanize Rubber composition shall be in accordance with MIL-STD-417. A four power (4X) magnification may be used in performing visual examination for such defects as burrs and foreign matter.

TABLE I

Lot Size	Sample Size	Major		Minor	
		Accept	Reject	Accept	Reject
1 - 300	100% Examination	-	-	-	-
301 - 1,300	110	1	2	2	3
1301 - 3,200	150	2	3	3	4
3201 - 8,000	225	3	4	4	5
8001 - 22,000	300	4	5	5	6

TABLE II

	Total allowable defects per sample size			
Sample size for Major Defects	110	150	225	300
Number of defects in class				
2 - 3	1	2	3	4
4 - 7	2	3	4	5
8 - 19	3	4	5	7
20 - 43	4	5	8	10
Over 43	6	8	11	14
Sample size for Minor Defects	110	150	225	300
Number of defects in class				
2 - 3	2	3	4	5
4 - 7	3	4	5	7
8 - 16	4	5	8	10
17 - 48	6	8	11	14
Over 48	8	11	17	20

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:54Z
Check the source to verify that this is the current version before use.

4.3.2.1 Static Line, Assembly, Drawing C10542412

Defect		Method of Inspection
CRITICAL		
None defined		
MAJOR		
101.	Metal defect	Visual
102.	Improper assembly	Visual
103.	Burr	Visual
104.	Foreign matter	Visual
105.	Location of swaging indentation (B10542408)	Gage
MINOR		
201.	Length to snap hooks	Gage
202.	Length to adapters	Gage

4.3.2.2 Wire Assembly, Drawing C10542409 covering a detail of Drawing C10542412.

CRITICAL		
None defined		
MAJOR		
101.	Rubber defect	Visual
102.	Quantity of cables	Visual
103.	Distance of end cable to edge of rubber	Gage
104.	Length of exposed cable	Gage
MINOR		
201.	Overall length of rubber	Gage
202.	Thickness of rubber	Gage

4.3.2.3 Adapter, Drawing B10542408 covering a detail of Drawing C10542412.

CRITICAL		
None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:54Z
Check the source to verify that this is the current version before use.

4.3.2.3 (Cont'd)

Defect	Method of Inspection
MAJOR	
101. Drilled and reamed hole	Gage
102. Location of drilled and reamed hole	Gage
103. Location of 8 equally spaced holes	Gage
MINOR	
201. Width of slot	Gage
202. Depth of 8 equally spaced holes	Gage
203. Diameter of 8 equally spaced holes	Gage
204. Length of slot	Gage
205. Length from wire hole end to base of angle	Gage
206. Overall length	Gage
207. Overall width	Gage
208. Overall thickness	Gage
209. Length of flat	Gage
210. Angles	Gage

4.3.2.4 Hook, snap, swivel, eye (modified), drawing B10542315 covering a detail of drawing C10542412.

CRITICAL

None defined

MAJOR	
101. Radius	Gage
102. Operability	Manual
MINOR	

None defined

4.3.2.5 Cable, stainless steel, drawing A10542410 covering a detail of drawing C10542412.

CRITICAL

None defined

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:54Z
Check the source to verify that this is the current version before use.

4.3.2.5 (Cont'd)

Defect	Method of Inspection
MAJOR	
101. Length	Gage
102. Diameter	Gage
103. Construction	Visual
104. Metal defects	Visual
MINOR	
201. Burr	Visual

4.3.3 Functional testing.- The following test shall be performed in accordance with the provisions of 4.4.

4.3.3.1 Functional.- Forty-five completed static line assemblies shall be tested in accordance with 3.3 under the following conditions:

Sample Size	Temperature
15	-60° to -65°F
15	+65° to +75°F
15	+120° to +125°F

Failure of any assembly to comply shall be cause for rejection of the lot of assemblies.

4.3.4 Inspection equipment.- The examination and tests shall be made using equipment listed on IEL-10542412.

4.4 Test methods and procedures.

4.4.1 Functional.- The completed static line assembly shall be tested on tensile strength test equipment by applying the specified load at the hook fasteners at the required time rate.

4.4.2 Temperature conditioning.- The completed static line assemblies shall be stored in a temperature conditioning chamber at the temperatures specified in 4.3.3.1 to reach the required test temperatures before testing.

5. PREPARATION FOR DELIVERY

5.1 Packing.- 25 completed static line assemblies shall be packed and shipped in fiber board boxes in accordance with PPP-B-636.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:54Z
Check the source to verify that this is the current version before use.

5.2 Marking.- Shipments shall be marked in conformance with MIL-STD-129.

5.3 Data card.- Data card information shall be as specified in MIL-STD-1167.

6. NOTES

6.1 A mechanical failure is defined as any deformation or breakage of a part, the occurrence of which is other than a design function.

6.2 Load.- The expected performance of the static line assembly, under conditions simulating those existing in actual use shall be referred to as load conditions in this specification.

6.3 Ordering data.- Procurement documents should specify the title, number and date of this specification.

Custodian:

Army - MU

Preparing activity:

Army - MU

Project No. 1370-A301

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:54Z
Check the source to verify that this is the current version before use.