MIL-T-22495D(AS)
17 September 1971
SUPERSEDING
MIL-T-22495C
24 March 1970

MILITARY SPECIFICATION

TEST HARNESS, RADAR, AN/APM-145D

This specification has been approved by the
Naval Air Systems Command, Department of the Navy

1. SCOPE

1.1 Scope - Test Harness, Radar, AN/APM-145D, hereinaftee referred to as the equipment, covered by this specification is for Intermediate level use and shall facilitate testing and maintenance of Radar Set AN/APQ-149.

1.2 Classification - The Test Harness, Radar, AN/APM-145D shall be one type and shall consist of the following items:

Items	Type Designation	Appl Para.
Stand, Test	MT-2579/APM-145A	3.3.1
Mounting, Indicator	MT-2346/APM-145B	3.3.2
Mounting	MT-2306A/APM-145	3.3.3
Table, Gyro Positioning	MT-2310/APM-145	3.3.4
Mounting	MT-2307/APM-145	3.3.5
Mounting	MT-2308/APM-145	3.3.6
Wiring Harness, Branched	CX-6116D/APM-145	3.3.7
Interconnecting Box	J-1158A/APM-145	3.3.8
Cable Assembly, Special Purpose, Electrical	CX-6115/APM-145	3.3.9
Wiring Harness, Branched	CX-6117/APM-145	3.3.10
Hose Assembly, Hydraulic	MX-5053/APM-145C	3.3.11
Hose Assembly, Hydraulic	MX-3012/APM-145	3.3.12
Hose Assembly, Hydraulic	MX-3571/APM-145A	3.3.13
Hose Assembly, Hydraulic	MX-3572/APM-145A	3.3.14
Wiring Harness, Branched	CX-7324/APM-145A	3.3.15
Mounting	MT-3249/APM-145B	3.3.16
Base, Electrical Equipment	MT-4003/APM-145C	3.3.17

1.3 Associated Equipment - This equipment shall operate with associated equipment listed in 6 5.

FSC 4940

Source: https://assist.dla.mil -- Downloaded: 202640-19T12:41Z
Check the source to verify that this is the currentversion before use.

2. APPLICABLE DOCUMENTS

2.1 General - The following documents of the issue in effect on the date of invitation for bids, form a part of this specification to the extent specified herein.

SPECIFICATIONS

Military

MIL-T-5422	Testing, Environmental, Aircraft Electronic Equipment
MIL-I-6181	Interference Control Requirements, Aircraft Equipment
MIL-R-24000B, Amend. 1	Radar Set AN/APQ-149, Military Specification for
MIL-H-15362	Harness; Test Bench, Avionic Equipment, General Specification for
MIL-E-17555	Electronic and Electrical Equipment and Associated Repair Parts, Preparation for Delivery of
MIL-N-18307	Nomenclature and Nameplates for Airborne Electronic and Associated Equipment
MIL-T-21200	Test Equipment for Use with Electronic and Fire Control Systems, General Specifications for
AR-41	Technical Directives (Letter Types), Preparation of

DRAWINGS

Bureau of Ships

S90101-212410	Shipboard Workbench for Aviation Electronic Shops

2.2 Availability of Documents - When requesting specifications, standards, drawings, and publications, refer to both title and number. Copies of this specification and applicable specifications required by contractors in connection with specific procurement functions may be obtained upon application to the Commanding Officer, Naval Supply Depot, 5801 Tabor Avenue, Philadelphia, Pennsylvania 19120, Attention: Code 105.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:41Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Parts and Materials - In the selection of parts and materials, the following shall govern:

(a) Parts and materials requirements shall conform to MIL-T-21200.

(b) Nonrepairable subassemblies, as outlined in MIL-T-21200, shall be used when practicable. The general size of the subassembly and the amount of circuitry to be included therein shall be approved by the procuring activity. Nonrepairable subassemblies must be reliable. A mean-time-to failure of more than 5000 hours should be the goal of each.

(c) When previously produced models of this equipment did not use nonrepairable subassemblies, the design shall not be changed to employ nonrepairable assemblies without the approval of the procuring activity.

3.1.1 Nonstandard Parts and Material Approval - Approval for the use of nonstandard parts and materials shall be obtained as specified in MIL-T-21200.

3.2 Design and Construction

3.2.1 General - The equipment shall fulfill the applicable design, construction and workmanship requirements in accordance with MIL-H-15362, unless otherwise specified herein.

3.2.2 Standard Conditions - The following conditions shall be used to establish normal performance requirements and for making laboratory bench tests:

Temperature	Room Ambient (30° ±10°C)
Altitude	Normal Ground
Vibration	None
Humidity	Room Ambient up to 90% relative humidity
Input Power Voltage	115/208 ±6 VAC, 400 ±20 HZ, 3 phase and 28 + 1, -3 VDC

3.2.3 Service Conditions - The equipment shall operate satisfactorily under any of the environmental service conditions, or reasonable combination of these conditions, as specified in MIL-H-15362. Sand, dust, fungus, explosion and crash safety tests shall not be applicable to this equipment.

3.2.4 Installation - The Test Harness, Radar Set, AN/APM-145D shall be used primarily for installation and operation on benches as specified in Drawing S9101-212410, but shall be designed also to pass through an opening 26 inches by 54 inches with rounded corners of 8 inches in accordance with MIL-H-15362.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:41Z
Check the source to verify that this is the current version before use.

3.2.5 Workshop Primary Power - The equipment shall utilize the following power:

Voltage	Frequency	Phase
28 +1, -3	DC	
115/208 ±6	400 ±20 HZ	3

3.2.6 Nomenclature and Nameplates - Nomenclature assignment and nameplate approval for equipment identification shall be in accordance with MIL-N-18307.

3.2.7 Interchangeability - The equipment shall meet the interchangeability requirements as specified in MIL-T-21200. Unless otherwise specified, interchangeability shall be measured against a model supplied by the procuring activity.

3.2.8 Maintenance Provisions and Field Testing - Provisions for maintenance shall be as specified in MIL-T-21200.

3.2.9 Undervoltage Protection - The equipment shall not be damaged by operations at 98 volts and shall automatically resume normal operation when the voltage returns within limits.

3.3 Detail Requirements

3.3.1 Stand, Test MT-2579/APM-145A - The Test Stand shall meet the following requirements:

3.3.1.1 Function - The Test Stand shall position the Radar Set Group (See 6.1) to facilitate the adjustment, alignment, testing, repair and replacement of components. The stand shall be capable of cantilevering suspension of the radar, allowing free access to the chassis for ease of maintenance. The rack shall allow rotation of the radar about its major axis approximately 180 degrees, with provision to lock the rotation in intermediate positions. The rack can also be rotated 90 degrees toward the front of the bench to facilitate maintenance of the antenna and both sides of the radar simultaneously. Provision shall also be made for locking the rotation in the 0 degree and the 90 degree positions.

3.3.1.2 Form Factor - The over-all dimensions of this unit shall not exceed 31 inches by 32 inches by 28 inches.

3.3.2 Mounting, MT-2346/APM-145B - The indicator mounting shall meet the following requirements:

3.3.2.1 Function - This unit shall provide facilities for mounting and holding the Azimuth-Range Indicator (See 6.1) during radar tests.

3.3.2.2 Form Factor - The over-all dimensions of this unit in locked position shall not exceed 10-1/2 inches by 10 inches by 12 inches. In an unlock position, the maximum width dimension shall be 13-1/2 inches.

3.3.3 Mounting MT-2306A/APM-145 - The mounting shall meet the following requirements.

Source: https://assist.dla.mil -- Downloaded: 202640-19T12:41Z
Check the source to verify that this is the currentversion before use.

3.3.3.1 Function - This unit shall provide facilities for mounting the Radar Set Control, Electrical Synchronizer, Hand Control Simulator, Attitude Simulator during radar tests. (See 6.1). A switch shall be provided to function as the Lead-No-Lead control and Missile Station Selector for the Computer, Deviated Pursuit, CP-742A/AP and a control shall provide a Range Strobe Start Position for the Foresight, Acquisition, and Track function. A switch shall be provided to simulate the BAT Acquisition Switch on the flight stick.

3.3.3.2 Form Factor - The over-all dimensions of this unit shall not exceed 3-1/2 inches by 7-1/8 inches by 4-1/8 inches.

3.3.4 Table, Gyro Position MT-2310/APM-145 - The gyroscope mounting shall meet the following requirements:

3.3.4.1 Function - This unit shall provide facilities for mounting and holding the Gyroscope Assembly Mount MT-2093/APQ-83 and shall provide a method of tilting the assembly +45 degrees and -30 degrees and a method of rotating the assembly plus or minus 45 degrees in azimuth. A method shall be incorporated to lock the assembly in any intermediate position.

3.3.4.2 Form Factor - The over-all dimensions of the unit in normal position shall not exceed 11-1/4 inches by 7-5/8 inches by 10-1/4 inches, except that if the table is put in maximum tilt, the height dimensions shall not exceed 9 inches.

3.3.5 Mounting, MT-2307/APM-145 - The computer mounting shall meet the following requirements:

3.3.5.1 Function - This unit shall provide facilities for mounting and holding the Missile Release Computer (See 6.1) during radar tests.

3.3.5.2 Form Factor - The over-all dimensions of the unit in locked position shall not exceed 13-5/8 inches by 4 inches. In an unlocked position, the length shall not exceed 17 inches.

3.3.6 Mounting MT-2308/APM-145 - The Amplifier-Control Mounting shall meet the following requirements.

3.3.6.1 Function - This unit shall provide facilities for mounting and holding the Amplifier-Control (See 6.1) during radar tests.

3.3.6.2 Form Factor - The over-all dimensions of the unit shall not exceed 11-3/4 inches by 1-1/2 inches by 17-1/2 inches.

3.3.7 Wiring Harness Branched CX-6116D/APM-145 - The branched Wiring Harness CX-6116D/APM-145 shall provide the necessary interconnections required for testing and maintaining the Radar Set AN/APQ-149. Additional wiring shall be provided for the necessary radar signals for interconnecting the Infrared Search and Track Set, AN/AAS-15, and AFCS EX-16. This unit shall not exceed 160 inches in length.

3.3.8 Interconnecting Box-J-1158A/APM-145 - The Interconnecting Box J-1158A/APM-145 shall meet the following requirements:

Source: https://assist.dla.mil -- Downloaded: 202640-19T12:41Z
Check the source to verify that this is the current version before use.

3.3.8.1 Function - The Interconnecting Box J-1158A/APM-145 shall provide the necessary circuitry, switches, indicator lamps, circuit breakers and binding posts for testing of Radar Set AN/APQ-83A, AN/APQ-83B, AN/APQ-94, or AN/APQ-149.

3.3.8.2 Form Factor and Mounting - The Interconnecting Box J-1158A/APM-145 shall be surface-mounted and shall not exceed 9-7/8 inches by 9-1/8 inches by 5-3/4 inches.

3.3.9 Cable Assembly, Special Purpose CX-6115/APM-145 - The cable assembly shall provide all necessary circuits for interconnection to the hydraulic supply from the Interconnecting Box J-1158A/APM-145. This unit shall not exceed 148 inches in length.

3.3.10 Wiring Harness, Branched CX-6117/APM-145 - The cable assembly shall provide all necessary circuits to provide 115/208 volts, 400-cycle, 3-phase power and 28 VDC power to the Interconnecting Box J-1158A/APM-145. This unit shall not exceed 34 inches in length.

3.3.11 Hose Assembly, Hydraulic MX-5053/APM-145C - The hose assembly shall provide a means of transmitting hydraulic power from the bench top to the Radar Set Group when testing the radar set. Two of these hoses shall be required for each installation. This hose shall not exceed 74 inches in length.

3.3.12 Hose Assembly, Hydraulic MX-3012/APM-145 - The hose assembly shall provide a means of transmitting hydraulic power from the hydraulic supply to the bench top. Two of these hoses shall be required for each installation. This hose shall not exceed 50 inches in length.

3.3.13 Hose Assembly, Hydraulic MX-3571/APM-145A - The hose assembly shall provide the hydraulic power return line from the Radar Set Group (OA-3271/APQ-94 only) to the Stand, Test, MT-2579/APM-145A. This hose shall not exceed 36 inches in length.

3.3.14 Hose Assembly, Hydraulic MX-3572/APM-145A - The hose assembly shall provide the hydraulic power pressure line from the Stand, Test, MT-2579/APM-145A to the Radar Set Group (OA-3271/APQ-94 only). This hose shall not exceed 30 inches in length.

3.3.15 Wiring Harness, Branched CX-7324/APM-145A - The cable assembly shall provide interconnecting facilities between Radar Set Group OA-3271/APQ-94 and Wiring Harness, Branched, CX-6116C/APM-145. This unit shall not exceed 80 inches in length.

3.3.16 Mounting MT-3249/APM-145B - The computer mounting shall meet the following requirements:

3.3.16.1 Function - This unit shall provide the facilitities for mounting and holding the Deviated Pursuit Computer (see 6.1) during radar tests.

3.3.16.2 Form Factor - The over-all dimensions of this unit shall not exceed 5-3/4 inches by 11-1/2 inches by 3-3/4 inches.

3.3.17 Base, Electrical Equipment, MT-4003/APM-145C - The indicator mounting shall meet the following requirements:

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:41Z
Check the source to verify that this is the current version before use.

3.3.17.1 Function - This unit shall provide facilities for mounting and holding Missile Release Indicator ID-1485/APQ.

3.3.17.. Form Factor - The over-all dimensions of this unit shall not exceed 13/16 inches by 1-3/8 inches by 13/16 inches.

3.4 Performance - Unless otherwise specified, values set forth to establish the requirements for satisfactory performance apply to performance under both standard and extreme service conditions. When reduced performance under extreme conditions is acceptable, tolerances or values setting forth acceptable variations from the performance under the standard conditions will be specified.

3.5 Preproduction Sample - Unless otherwise specified in the contract or order, a preproduction sample of the Test Harness, Radar AN/APM-145D shall be manufactured such that it is representative of the production lot in all respects. The sample will be tested as specified in 4, herein, and is for the purpose of determining that the contractor, prior to his starting production is capable of yielding items that comply with the technical requirements of the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 General - The supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own or any other inspection facilities and services acceptable to the Government. Inspection records of the examination and tests shall be kept complete and available to the Government as specified in the contract or order. The Government reserves the right to perform any of the inspections set forth in the specification when such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Tests Required - Items covered by this specification shall be subjected to the following tests to determine compliance with all applicable requirements.

(a) Preproduction

(b) Sample Tests

(c) Acceptance Test

(d) Life Tests

4.1.1.1 Preproduction Tests - Preproduction tests shall be made on one or more equipments representative of the production equipments to be supplied under the contract.

4.1.1.1.1 Scope of Tests - Preproduction tests shall include all tests deemed necessary to determine that the equipment meets all the requirements of this specification and the contract. Preproduction tests shall include environmental tests in accordance with MIL-T-5422 to the extent specified herein, interference tests in accordance with MIL-I-6181 and drop tests for transit and combination cases in accordance with MIL-T-21200. Preproduction tests shall consist of the following:

(a) Contractor's Demonstration Tests

(b) Service Approval Tests

Source: https://assist.dla.mil -- Downloaded: 20261O-19T12:41Z
Check the source to verify that this is the current version before use.

4.1.1.1.1.1 Contractor's Demonstration Tests - Contractor's demonstration tests shall be accomplished under the responsibility of the contractor and shall be conducted in accordance with the approval test procedure of 4.1.1.1.1.2. Data obtained by the contractor in conducting these tests shall be submitted to the procuring activity for review and approval prior to shipping the equipment to the specified destination for service approval tests. The government inspector and the procuring activity shall be advised when tests are to be conducted so that a representative may be designated to witness or supervise the tests when so desired.

4.1.1.1.1.2 Service Approval Tests - At the completion of the contractor's demonstration tests and when requested by the procuring activity, the equipment shall be delivered to a specified government laboratory for additional testing. This additional testing may consist of duplicating tests previously conducted and such other tests as are deemed necessary to determine compliance with all applicable design and performance requirements.

4.1.1.1.2 Preproduction Approval - Approval of the preproduction model shall be by the procuring activity upon satisfactory completion of all tests. No production equipments shall be delivered prior to the approval of the preproduction model. Prefabrication of production equipment prior to the model will be returned to the contractor for his use in fabrication and testing of equipment to be submitted for acceptance. The preproduction model shall not be considered as one of the equipments under the contract.

4.1.1.2 Sample Tests - When requested by the procuring activity, one equipment shall be selected from the first 10 production equipments submitted for acceptance and shall have successfully passed the individual tests.

4.1.1.2.1 Scope of Test - As a minimum, each equipment selected for sampling tests shall be subjected to the following test.

(a) Complete operation test at ambient room conditions, making all necessary measurements to assure that all applicable specifications requirements have been met.

(b) Operational test at certain environmental conditions. The conditions may vary for each equipment tested and should be based on results of the preproduction and special tests.

4.1.1.2.2 Sample Approval - Approval of the production sample shall be by the procuring activity upon satisfactory completion of all tests. Any design, material or performance defect made evident during this test shall be corrected by the contractor to the satisfaction of the procuring activity. Upon failure of the production sample to pass any of the tests, delivery of equipment under the contract shall cease until proper corrective action is approved and accomplished. Corrective action shall also be accomplished on equipment previously accepted when requested by the procuring activity.

4.1.1.3 Acceptance Tests - The contractor shall furnish all samples and shall be responsible for accomplishing the acceptance tests. All inspection and testing shall be under the supervision of the government inspector. The contractor shall furnish test reports showing quantitative results for all acceptance tests. Such reports shall be signed by an authorized representative of the contractor or laboratory, as applicable. Acceptance or approval of material during the course of manufacture shall not be construed as a guarantee of the acceptance of the finished product. Acceptance tests shall consist of the following:

Source: https://assist.dla.mil -- Downloaded: 20260-19T12:41Z
Check the source to verify that this is the current version before use.

(a) Individual Tests

(b) Special Tests

4.1.1.3.1 Individual Tests - Each equipment submitted for acceptance shall be subjected to the individual tests. These tests shall be adequate to determine compliance with the requirements of material, workmanship, operational adequacy and reliability. As a minimum, each equipment accepted shall have passed the following tests.

(a) Examination of Product

(b) Operational Test

(c) Manufacturing Reliability Test

4.1.1.3.1.1 Examination of Product - Each equipment shall be examined carefully to determine that the material and workmanship requirements have been met.

4.1.1.3.1.2 Operational Test - Each equipment shall be operated long enough to permit the equipment temperature to stabilize and to check sufficient characteristics and record data to assure satisfactory equipment operation.

4.1.1.3.1.3 Manufacturing Reliability Test - Each equipment shall be operated at the conditions specified herein a total accrued running time of 6 hours. Only those adjustments will be permitted which can be made by using such controls and adjustments that are accessible to the operator during the normal use of this equipment.

Temperature	Ambient Room
Humidity	Ambient Room
Vibration (10 minutes)	Any selected frequency within the range of 20 to 30 HZ (excluding resonant points) and a maximum double amplitude to 0.02 inch.

The equipment shall be vibrated (without vibration isolators) for a period of 10 minutes as specified herein. The direction of vibration should be vertical to the normal mounting plane. The equipment shall be non-operating during the 10-minute vibration period. The 6-hour period of operation shall include that time necessary for performing all equipment tests and calibrations. Only that time necessary to make a total accrued running time of 6 hours is required for operation after the 10 minute vibration period. During the 6-hour period of operation, the equipment shall be mechanically cycled periodically through its various phases of operation. Should a failure occur, it should be repaired and the test continued. Should repetitive failures occur, corrective action shall be taken to eliminate this defect from future equipment. A record shall be kept of all failures.

4.1.1.3.2 Special Tests - Special tests shall be conducted on a quantity of equipments for the purpose of checking the effect of any design or material change on the performance of the equipment, to assure adequate quality control. The equipment selected for special tests may be selected from equipments previously subjected to the sampling tests.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:41Z
Check the source to verify that this is the current version before use.

4.1.1.3.2.1 Special Test Schedule - Selection of equipments for special tests shall be made as follows:

(a) On an early production equipment.

(b) On an equipment midway of the production run.

(c) On an early equipment after an engineering change.

(d) Whenever failure reports or other information indicates additional equipments should be tested. (This will be determined by the procuring activity.)

Exceptions from the above may be necessary when the number of equipments procured under contract or other factors affecting performance may require variations to assure satisfactory control.

4.1.1.3.2.1.1 Scope of Tests - Special tests shall consist of such tests as are approved by the procuring activity. These procedures previously approved for the preproduction and sampling tests shall be used where applicable. When not applicable, the contractor shall prepare a test procedure and submit it to the procuring activity for approval prior to conducting the tests. As a minimum, the following tests shall be made, except for those equipments selected as a result of design changes and failure reports, only those tests required to check the characteristics in question need be conducted.

(a) Temperature - Altitude Tests

(b) Vibration Test (60 minute cycling in each of 3 planes)

(c) Humidity Tests

4.1.1.4 Life Tests - When requested by the procuring activity, one unit shall be selected from the current production equipment and shall have successfully passed the individual tests.

4.1.1.4.1 Scope of Test - A 200 hour life test shall be conducted at the contractor's plant on an early equipment representative of the current production. The life test shall be performed under the conditions specified in 4.1.1.4.1.1. A performance check shall be made to determine the equipment is operating satisfactorily.

4.1.1.4.1.1 Test Conditions - The life test shall be conducted under the following simulated service conditions

Temperature	Normal Room
Altitude	Normal Ground (0 - 5000 ft.)
Humidity	Room Ambient
A. C. Voltage	115 ±5 volts (at lowest applicable frequency)
D. C. Voltage	27.0 ±2.0 volts

Source: https://assist.dla.mil -- Downloaded: 202640-19T12:41Z
Check the source to verify that this is the currenversion before use.

4.1.1.4.1.2 Test Periods - The test may be run continuously or intermittenly. Any period of operation shall be of sufficient duration to permit the equipment temperature to stabilize. Periodically, the equipment shall be turned on and off several times and put through its various phases of operation.

4.1.1.4.1.3 Performance Check - At approximate 8-hour intervals during the test, a limited performance check shall be made. The performance check proposed by the contractor shall be subject to approval by the procuring activity.

4.1.1.4.2 Test Data - The contractor shall keep a daily record of the performance of the equipment, making particular note of any deficiencies or failures. In the event of part failure, the defective part shall be replaced and the operation resumed for the balance of the test period. A record shall be kept of all failures throughout the test, including all tube failures. This record shall indicate the following:

(a) Part type number

(b) The circuit reference symbol number

(c) The part function

(d) Name of the manufacturer

(e) Nature of the failure

The number of hours which the part operated prior to failure.

4.1.1.4.3 Failure Report - In the event of a failure, the government inspector shall be notified immediately. A report shall be submitted to the procuring activity upon completion of the test. In this report, the contractor shall propose suitable and adequate design or material corrections for all failures which occurred. The procuring activity will review such proposals and determine whether they are acceptable.

4.5 Presubmission Testing - No item, part or complete equipment shall be submitted by the contractor until it has been previously tested and inspected by the contractor and found to comply, to the best of his knowledge and belief, with all applicable requirements.

4.6 Equipment Changes - After approval of the preproduction model, no changes which affect weight, installation interchangeability and interchangeability of maintenance parts or assemblies shall be incorporated in the equipment unless approved by the procuring activing. To obtain procuring activity approval, the contractor shall submit an Engineering Change Proposal (ECP) giving the necessary information concerning the change. This shall apply for either a procuring activity's recommended change or a contractor's proposed change. When required, the contractor shall also prepare a Material Change (MC) and a Material Bulletin (MB) to cover the approved change. Engineering Change Proposals, Material Changes and Material Bulletins shall be prepared in accordance with MIL-T-23336.

5. PREPARATION FOR DELIVERY

5.1 General - All major units and parts of the equipment shall be preserved, packaged, packed and marked for the level of shipment specified in the contract or order in accordance with MIL-E-17555.

Source: https://assist.dla.mil -- Downloaded: 202610-19T12:41Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Support equipment shall include items to position, support, and interconnect [illegible] Group [illegible] 13/APQ-13 Indicator, Azimuth-Range IP-1074/APQ-[illegible], Amplifier-Control AM-6416/APQ-[illegible], Mount, Gyroscope [illegible], Synchronizer, Electrical SA-253/APQ-83, Computer, [illegible] and CP-1738/APQ-83, Computer, Deviated Pursuit CP-742/APQ-[illegible], Simulator, Hand Control SM-214/APQ-83, Simulator, Attitude SM-213/APQ-83, and test equipment, during test operation on the test bench.

6.2 The parentheses (*), when used in the type designation, shall be replaced by either a number or letter furnished by the procuring activity, upon application by the contractor for assignment of nomenclature in accordance with 3.2.6. The complete type number shall be used on nameplates, shipping records and instruction books, as applicable.

6.3 Precedence of Documents - When the requirements of the contract, this specification or applicable subsidiary specifications are in conflict, the following precedence shall apply:

(a) Contract - The contract shall have precedence over the specification.

(b) This Specification - This specification shall have precedence over all applicable subsidiary specifications. Any deviation from this specification, or from subsidiary specifications where applicable, shall be specifically approved in writing by the procuring activity.

(c) Referenced Specifications - Any referenced specifications shall have precedence over all applicable subsidiary specifications referenced therein. All referenced specifications shall apply to the extent specified.

6.4 Notation of Revisions - A bar in the margin denotes a change, made in the adjacent paragraph, from the previous version of the document. This has been done as a convenience only, and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document, based on the entire content as written, irrespective of the marginal notations and relationship to the last previous issue.

6.5 **Associated Equipment - The equipment shall operate with the following associated equipment:**

(a) Simulator Hand Control SM-214/APQ-83

(b) Simulator Aircraft Attitude SM-213/APQ-83

(c) Pumping Unit Hydraulic - Bench MX-3196/APQ-83

(d) Test Set Radar AN/UPM-116B

Project No. 4940-N307

Source: https://assist.dla.mil -- Downloaded: 202640-19T12:41Z
Check the source to verify that this is the currentversion before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity *(as indicated on reverse hereof)*.

SPECIFICATION

MIL-T-22495D(AS) TEST HARNESS , RADAR AN/APM-145D

ORGANIZATION *(Of submitter)*

CITY AND STATE

CONTRACT NO.

QUANTITY OF ITEMS PROCURED

DOLLAR AMOUNT

$

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES.

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)*

DATE

DD, FORM, 1 APR 63 1426

8-8878

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:41Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE NAVY
Naval Air Systems Command
Washington, D.C. 20360

POSTAGE AND FEES PAID
NAVY DEPARTMENT

OFFICIAL BUSINESS

NAVAL AIR SYSTEMS COMMAND (AIR-52021)
DEPARTMENT OF THE NAVY
WASHINGTON, D. C. 20360

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:41Z
Check the source to verify that this is the current version before use.