MIL-T-48295 (PA)
5 FEBRUARY 1974
SUPERSESSION DATA
(See 6.4)

MILITARY SPECIFICATION

TEST SET, ELECTRICAL CIRCUIT, BOMB DISPENSER A/E 24T-79

This Specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This Specification covers the metal parts for one type of test set designated as Test Set, Electrical Circuit, Bomb Dispenser A/E 24T-79.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550	- Ammunition, General Specification For
MIL-A-8625	- Anodic Coatings for Aluminum and Aluminum Alloys
MIL-C-14550	- Copper Plating (Electrodeposited)
MIL-E-5272	- Environmental Testing, Aeronautical and Associated Equipment, General Specification For

STANDARDS

FEDERAL

FED-STD-151	- Metals; Test Methods

FSC: 4925

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-202 - Test Methods for Electronic and Electrical Component Parts
MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U.S. ARMY PICATINNY ARSENAL

PRODUCT AND PACKAGING DRAWINGS

9209981 - Test Set, Electrical Circuit, Bomb Dispenser A/E 24T-79
9218793 - Drum, Metal Shipping for Test Set, Electrical Circuit, Bombs Dispenser: A/E 24T-79

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer.)

3. REQUIREMENTS

3.1 Material. - Materials shall be in accordance with the applicable drawings and specifications.

3.2 Parts. - The parts shall comply with all requirements specified on Drawing (dwg.) 9209981, and with all requirements specified in applicable specifications.

3.3 Copper Plating of the Cable Seal. - The copper plating of the cable seal shall be in accordance with the requirements specified in the finish specification MIL-C-14550.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

3.4 Continuity and Short Circuits. - The test set, electrical circuit, bomb dispenser A/E 24T-79 shall be continuous from the ohmmeter to each switch position (1 to 40) and from the switch positions to cable assembly connector pins as indicated below:

Switch Position	Connector Pin	Switch Position	Connector Pin
1	D	21	P
2	F	22	J
3	B	23	S
4	K	24	H
5	M	25	D
6	H	26	M
7	S	27	B
8	U	28	X
9	P	29	F
10	Y	30	V
11	A	31	R
12	W	32	Z
13	E	33	N
14	G	34	J
15	C	35	T
16	K	36	G
17	N	37	C
18	I	38	L
19	R	39	A
20	Q	40	E

There shall also be continuity from Pin BB of the connector to the terminal of the ohmmeter. The test set shall show no evidence of shorts between any two (2) pins of the connector.

3.5 Current Leakage of the Cable Assembly and Accessory Cable Assembly. - The leakage current shall not be more than one (1) milliampere at 500 VRMS, or the insulation resistance shall be greater than 2.0 Meg-Ohms when measured at 500 VDC.

3.6 Continuity and Resistance of the Accessory Cable Assembly. - The accessory cable assembly shall show evidence of continuity from the "red" test prod to Pin "D" of the connector and from the "Black" test prod to Pin "BB" of the connector. There shall be no more than .1 Ohms resistance between either the "Red" test prod and Pin "D" or the "Black" test prod and Pin "BB" of the connector.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

3.7 Workmanship. - All parts and assemblies shall be fabricated and finished in a thorough, workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, unblended radii, surface defects, dirt, grease, rust, corrosion products, and other foreign matter. The cleaning method used shall not be injurious to any part, nor shall the parts be contaminated by the cleaning agents. All required markings shall be neat, legible and sharply defined.

3.8 First Article Inspection. - This specification contains technical provisions for first article inspection. Requirements for the submission of first article samples by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of Product.-At the time each completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted.

a. A statement that the lot complies with all of the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agents authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First Article Inspection

4.2.1 Submission.-Prior to the start of regular production the contractor shall submit a first article sample (see 6.1c) to a Government approved facility as designated by the contracting officer for evaluation in accordance with the provisions of 4.2.2 and 4.2.3. The first article sample shall consist of the following:

ITEM		QUANTITY
a.	Test Set, Electrical Circuit, Bomb Dispenser A/E 24T-79 (9209981)	1
b.	Accessory Cable Assembly (9209982)	2
c.	Panel (9209970)	2
d.	Cable Assembly (9209966)	2
e.	Cable Seal (See dwg. 9209964 and 9209966)	4

In addition, panels or coupons of the coating process of the panel (9209970) of the size and number as specified in Specification MIL-A-8625 shall be submitted for salt spray test.

All parts and completed assemblies shall have been produced by the Contractor or furnished by a supplier and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials including packaging and packing shall be obtained from the same source of supply as will be used in regular production. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample, including a certificate of conformance for materials. A sample containing known defects will not be submitted unless specifi-

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

cally authorized by the Contracting Officer. A first article sample, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days or whenever a change occurs in manufacturing process, material used, drawing or specification such as to significantly affect product uniformity as determined by the Government.

4.2.2 Inspections to be performed.-Assemblies and components will be subjected by the Government to any or all of the examinations and tests specified in this specification and any or all requirements of the applicable drawings.

4.2.2.1 Salt Spray. - The panels or coupons of the panel (9209970) shall be subjected to this test. The test shall be performed as specified in Specification MIL-A-8625 except exposure time shall be 96 hours.

4.2.2.2 Plating Finish. - The four (4) cable seals shall be subjected to the inspections and test specified in Specification MIL-C-14550, Destructive Test. Parts so tested shall not be returned to the lot.

4.2.3 Rejection. - If any component or subassembly fails to comply with any or all of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an inert component or subassembly to comply with any of the stated requirements.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer in one unchanged process using the same materials and methods in accordance with the same drawings, same drawing revisions, same specifications and same specification revisions and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to the process, specifications, or drawings not

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168.

4.3.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable sub-paragraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Accessory Cable Assembly (see dwg. 9209982 covering a detail of dwg. 9209981)

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Incorrect color coding of wires	Visual	01001
102.	Soldering improper	Visual	01002
Minor:	AQL 1.00 percent		
201.	Length	Gage	01003
202.	Evidence of poor workmanship (see 3.7)	Visual	01004

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

4.3.2.2 Cable Assembly (see dwg. 9209966, covering a detail of dwg. 9209981).

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	Braided wire loose or improperly fastened to either connector and/or not completely under either hyring	Visual/ Manual	02001
Major:	AQL 0.65 percent		
101.	Wiring of connector incorrect.	Visual	02002
102.	Soldering improper	Visual	02003
103.	Any component missing or damaged	Visual	02004
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.7)	Visual	02005

4.3.2.3 Panel (see dwg. 9209970 covering a detail of dwg. 9209981).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major: None defined			
Minor:	AQL 1.00 percent		
201.	Marking misleading or unidentifiable	Visual	03001
202.	Evidence of poor workmanship (see 3.7)	Visual	03002

4.3.2.4 Panel and Cable Assembly (see dwg. 9209965 covering a detail of dwg. 9209981).

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	Braid assembled improperly	Visual	04001

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.65 percent		
101.	Wiring incorrect	Visual	04002
102.	Soldering improper	Visual	04003
103.	Pads improperly assembled	Visual	04004
Minor:	AQL 2.50 percent		
201.	Extended length of cable incorrect	Gage	04005
202.	Dial improperly assembled	Visual	04006
203.	Identification plate missing or improperly marked	Visual	04007
204.	Lacing tape missing	Visual	04008
205.	Any component missing or damaged	Visual	04009
206.	Evidence of poor workmanship (see 3.7)	Visual	04010

4.3.2.5 Test Set, Electrical Circuit, Bomb Dispenser A/E 24T-79 (See dwg. 9209981).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Accessory cable missing	Visual	05001
Minor:	AQL 1.50 percent		
201.	Panel and cable assembly improperly assembled into case .	Visual	05002
202.	Any component missing or damaged	Visual	05003
203.	Evidence of poor workmanship (see 3.7)	Visual	05004

4.3.3 TESTING

4.3.3.1 Current Leakage of the Cable Assembly and Accessory Cable Assembly (see 3.5) - Major Defect - Code No. 06001. - Each cable assembly and accessory cable assembly shall be subjected to this test. This test shall be performed in accordance with MIL-STD-202, Method 302, Test Condition B, between each wire and each wire and ground. Any cable assembly or accessory cable assembly that fails to comply with the applicable requirement shall be classified defective and removed from the lot. (Non-destructive test)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

4.3.3.2 Continuity and Resistance of the Accessory Cable Assembly (see 3.6) Major Defect - Code No. 07001. - Each accessory cable assembly shall be subjected to this test. The test shall be performed as specified in 4.4.1. Any accessory cable assembly classified defective shall be removed from the lot. (Non-destructive Test)

4.3.3.3 Continuity, and Short Circuits of the Test Set (see 3.4) - Major Defect - Code No. 08001. - Each Test Set, Electrical Circuit, Bomb Dispenser A/E 24T-79 shall be subjected to this test. The test shall be performed as specified in 4.4.2. Any test set classified defective shall be removed from the lot. (Non-destructive test)

4.3.3.4 Salt Spray of Panel (see dwg. 9209970) Major Defect Code No. 09001. - Panels or coupons of the size and number of each coating process of the panel as specified in finish specification MIL-A-8625 shall be subjected to this test. The test shall be performed as specified in specification MIL-A-8625, exposure time shall be for 96 hours. Rejection criteria shall be as specified in specification MIL-A-8625.

4.3.4 Inspection Equipment. - Inspection equipment required to perform the inspections prescribed in this specification is identified in the Examination (4.3.2) and Test Method (4.4) paragraphs herein. See 6.3 for details concerning responsibilities for inspection design and approval.

4.4 TEST METHODS AND PROCEDURES

4.4.1 Continuity and resistance of the accessory cable assembly. - The accessory cable assembly shall be assembled to an approved fixture and the electrical circuits checked for continuity and resistance. Any cable assembly failing to comply with the applicable requirements shall be classed defective.

4.4.2 Continuity and Short Circuit of Test Set Assembly. - The test set assembly shall be tested for continuity and short circuits utilizing an approved test fixture. Any test set failing to conform to the applicable requirements shall be classed defective.

5. PREPARATION FOR DELIVERY

5.1 Preservation and Packaging

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

5.1.1 Level A. - The Test Set, Electrical Circuit, Bomb Dispenser A/E 24T-79 shall be preserved and packaged in accordance with drawing 9218793.

5.2 Packing

5.2.1 Level A. - The Test Set, Electrical Circuit, Bomb Dispenser A/E 24T-79, preserved and packaged as specified in 5.1.1, shall be packed in accordance with dwg. 9218793.

5.3 Marking. - Marking shall be in accordance with dwg. 9218793.

5.4 Shipping. - When shipments from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards. - Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of first article samples.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. They should be cited as references on drawings of equipment designs submitted by the contractor to the Government for approval (see 6.3.3).

6.3 Inspection Equipment Designs.-Inspection equipment designs are of two types - Government Special Inspection Equipment (SIE) designs and contractor designs. SIE designs are designated by drawing numbers under the "Method of Inspection" headings in Section 4. Design responsibility for all other inspection equipment is assigned to the contractor. The contractor need not furnish any design when a complete Government SIE design is provided. Unless otherwise specified, however, the contractor may submit alternate or modified contractor designs of SIE in accordance with 6.3.2 and 6.3.3

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

should he elect to do so.

6.3.1 SIE designs.-SIE designs may consist of any of the following:

a. Detailed drawings which completely depict all information necessary for the fabrication and use of the item of inspection equipment.

b. A source control drawing or a specification control drawing as defined in MIL-STD-100.

c. An envelope drawing, as defined in MIL-STD-100, which establishes the criteria which a detailed design shall meet. When envelope drawings are specified, the contractor shall prepare designs which comply with the criteria therein.

6.3.2 Contractor designs.-Contractor designs are required for all inspection equipment for which SIE designs are not specified and may include commercial equipment which the contractor proposes to use. (Commercial equipment is defined as unmodified equipment which is cataloged and available for purchase by the general public). Contractor designs shall include appropriate operating instructions, calibration procedures and maintenance procedures. Commercial equipment shall be fully described by catalog listings or other means which provide sufficient information to permit identification and evaluation by the Government and may include illustrations and engineering data. Designs shall be prepared for any special fixture(s) required to be used with commercial equipment, or with SIE designs if not otherwise covered thereby (see 6.3.1c). Designs shall be of the category and form (per MIL-D-1000) specified in the Contract Data Requirements Lists (DD Form 1423). The contractor is referred to MIL-HDBK-204, "Inspection Equipment Design" for guidance. The specification number and the applicable five digit defect code number (or other specific identifying information) from Section 4 of this specification shall be referenced on each contractor design together with the component or assembly drawing number and revision letter to which the specific design applies.

6.3.3 Submission of Designs for Approval.-Contractor designs shall be approved by the Government prior to fabricating or procuring the equipment. Designs shall be submitted for approval to Picatinny Arsenal, ATTN: SARPA-QA-A-M, Dover, New Jersey 07801 in accordance with the stipulations, time frame and distribution specified in the Contract Data Requirements List (DD Form 1423) or in the contract. The contractor must include in his sub-

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

mission of designs a listing of any and all Government SIE designs which will be utilized. Partial submission of inspection designs is permissible and encouraged. However, the completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will normally be accomplished within one month after receipt.

6.4 Supersession Data. - This specification includes the requirements of AEI-364, dated 20 October 1966.

Custodian:
Army-PA

Preparing Activity:
Army-PA

Project Number: 4925-A-024

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.