MILITARY STANDARD

SWITCHES AND ASSOCIATED HARDWARE,
SELECTION AND USE OF

TO ALL HOLDERS OF MIL-STD-1132A:

1. THE FOLLOWING SECTIONS OF MIL-STD-1132A HAVE BEEN REVISED AND SUPERSEDE THE SECTIONS LISTED:

NEW SECTION	DATE	SUPERSEDED SECTION	DATE
102A	20 June 1977	102 (pages 102.1 thru 102.71)	23 March 1976
104A	20 June 1977	104 (page 104.1)	23 March 1976
111A	20 June 1977	111 (pages 111.1 thru 111.23)	23 March 1976

2. THE FOLLOWING PAGES OF MIL-STD-1132A HAVE BEEN REVISED AND SUPERSEDE THE PAGES LISTED:

NEW PAGE	DATE	SUPERSEDED PAGE	PAGE
103.1		(REPRINTED WITHOUT CHANGE)	23 March 1976
103.2	20 June 1977	103.2	23 March 1976
106.1	20 June 1977	106.1	23 March 1976
106.2	20 June 1977	106.2	23 March 1976
106.3	20 June 1977	106.3	23 March 1976
106.4		(REPRINTED WITHOUT CHANGE)	23 March 1976
106.9	20 June 1977	106.9	23 March 1976
106.10		(REPRINTED WITHOUT CHANGE)	23 March 1976
106.11	20 June 1977	106.11	23 March 1976
106.12	20 June 1977	106.12	23 March 1976
107.1	20 June 1977	107.1	23 March 1976
107.2		(REPRINTED WITHOUT CHANGE)	23 March 1976
107.29		(REPRINTED WITHOUT CHANGE)	23 March 1976
107.30	20 June 1977		
107.31	20 June 1977		
107.32	20 June 1977		
107.33	20 June 1977		
110.1		(REPRINTED WITHOUT CHANGE)	23 March 1976
110.2	20 June 1977	110.2	23 March 1976
110.101		(REPRINTED WITHOUT CHANGE)	23 March 1976
110.102	20 June 1977		
110.103	20 June 1977		
110.104	20 June 1977		
110.105	20 June 1977		
112.1		(REPRINTED WITHOUT CHANGE)	23 March 1976
112.2	20 June 1977	112.2	23 March 1976
112.17		(REPRINTED WITHOUT CHANGE)	23 March 1976
112.18	20 June 1977	112.18	23 March 1976
112.19	20 June 1977	112.19	23 March 1976
112.20	20 June 1977	112.20	23 March 1976
112.21	20 June 1977	112.21	23 March 1976
112.22	20 June 1977	112.22	23 March 1976
112.23	20 June 1977	112.23	23 March 1976
112.24		(REPRINTED WITHOUT CHANGE)	23 March 1976
112.25	20 June 1977	112.25	23 March 1976
112.26		(REPRINTED WITHOUT CHANGE)	23 March 1976
112.27	20 June 1977	112.27	23 March 1976
112.28		(REPRINTED WITHOUT CHANGE)	23 March 1976
112.31		(REPRINTED WITHOUT CHANGE)	23 March 1976
112.32	20 June 1977		
112.33	20 June 1977		
202.17	20 June 1977	202.17	23 March 1976

FSC 5930

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

4. RETAIN THIS NOTICE AND INSERT BEFORE TABLE OF CONTENTS.

5. Holders of MIL-STD-1132A will verify that changes indicated above have been entered. This notice page will be retained as a check sheet. This issuance, together with appended pages, is a separate publication. Each notice is to be retained by stocking points until the Military Standard is completely revised or canceled.

Custodians:
Army - EL
Navy - EC
Air Force - 11

Review activities:
Army -
Navy -
Air Force - 85, 17
DLA - ES

User activities:
Army -
Navy - CG
Air Force -

Preparing activity:
Navy - EC

Agent:
DLA - ES

(Project 5930-1039)

Source: https://assist.dla.mil -- Downloaded: 202640-26T07:41Z
Check the source to verify that this is the current version before use.

FOREWORD

This standard provides selected standard switches and associated hardware which are mandatory for use in the design of military equipment.

The application information contained in this standard is offered for guidance only and is not to be considered as mandatory. Additional application information will be added when coordinated with the three military departments.

Additional sections of this standard will be developed as the standard switches and associated hardware of a given specification family are selected and coordinated with the three military departments.

Source: https://assist.dla.mil -- Downloaded: 202640-26T07:41Z
Check the source to verify that this is the current version before use.

CONTENTS

		Page
Paragraph 1.	SCOPE	1
1.1	Scope	1
1.2	Purpose of standard	1
2.	REFERENCED DOCUMENTS	2
3.	DEFINITIONS	3
4.	GENERAL REQUIREMENTS	6
4.1	Choice of switch types and associated hardware	6
4.2	Conflict of requirements	6
4.3	Criteria for inclusion in this standard	6
5.	DETAILED REQUIREMENTS	7
6.	APPLICATION INFORMATION	8
6.1	General	8
6.2	Principal applications	8
6.3	Switch selection	9
6.4	Switch parameters	10
6.5	Environmental considerations	11
7.	SUPPLEMENTARY INFORMATION	13
7.1	Drawing notes	13
Section 100	SWITCHES	100.1
200	ASSOCIATED SWITCH HARDWARE	200.1

CROSS REFERENCE
(Section number to specification number)

Switches

Section		Applicable specification(s)
101	(Reed)	MIL-S-55433
102	(Push button, Illuminated)	MIL-S-22885
103	(Interlock)	MIL-S-8805
104	(Multistation)	MIL-S-24317
105	(Pressure)	MIL-S-9395
106	(Push Button)	MIL-S-8805
107	(Rotary)	MIL-S-3786, MIL-S-6807, and MIL-S-15291
108	(Rotary, Electro-Mechanical Actuated, Solenoid Type)	MIL-S-3786
109	(Rotary, Printed Circuit, Thumbwheel and Pushbutton)	MIL-S-22710
110	(Sensitive)	MIL-S-8805
111	(Thermostatic)	MIL-S-24236 and MIL-S-28827
112	(Toggle)	MIL-S-3950, MIL-S-8834, and MIL-S-8805
113	(Modular Switch Assemblies)	MIL-S-22885

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

1. SCOPE

1.1 Scope. This standard establishes requirements for selection of switches and their associated hardware, shown in detail in sections 100 and 200, for use in military equipment. Included are the following:

(a) Selected standard switch types and associated hardware chosen jointly by the Departments of the Army, the Navy, and the Air Force for use in the design and manufacture of military equipment under the jurisdiction of the Department of Defense.

(b) Guides for the choice and application of switches and associated hardware for use in military equipment.

Complete detailed requirements for switches and associated hardware listed in this standard are covered in the applicable specification sheets or MS sheets (see 4.2). (The complete part number or type designation, and the number of the applicable specification sheet or MS sheet should be referenced in procurement documents for the switches or associated hardware.) When it has been determined that circuit requirements cannot be met by using the switch styles or characteristics listed in this standard, the design engineer with the approval of the cognizant military activity should select from the applicable switch specification, styles or characteristics not listed herein.

1.2 Purpose of standard. The purpose of this standard is to:

(a) Provide the equipment designer with a list of switches and their associated hardware that are considered to be the most flexible for military applications.

(b) Control and minimize the variety of switches used in military equipment in order to facilitate logistic support of the equipment in the field.

(c) Establish criteria pertinent to the choice, application, and use of switches and their associated hardware in military equipment.

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the currentversion before use.

2. REFERENCED DOCUMENTS

2.1 The issues of the following documents in effect on the date of invitation for bids form a part of this standard to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-S-3786 - Switches, Rotary (Circuit Selector, Low-Current Capacity), General Specification For.
MIL-S-3950 - Switches, Toggle, Environmentally Sealed, General Specification For.
MIL-B-5423 - Boots, Dust and Water Seal (For Toggle and Pushbutton Switches, Circuit Breakers, and Rotary-Actuated Parts), General Specification For.
MIL-S-6807 - Switches, Rotary, Selector Power, General Specification For.
MIL-G-7703 - Guard, Switch, General Specification For.
MIL-S-8805 - Switches and Switch Assemblies, Sensitive and Push (Snap Action), General Specification For.
MIL-S-8834 - Switches, Toggle, Positive Break, General Specification For.
MIL-S-9395 - Switches, Pressure, (Absolute, Gauge and Differential) General Specification For.
MIL-S-15291 - Switches, Rotary, Snap Action.
MIL-S-22710 - Switches, Rotary, (Printed Circuit), (Thumbwheel, Inline, and Pushbutton), General Specification For.
MIL-S-22885 - Switch, Push Button, Illuminated, General Specification For.
MIL-S-24236 - Switches, Thermostatic, (Metallic and Bimetallic) General Specification For.
MIL-S-24317 - Switches, *Multistation, Pushbutton,* (Illuminated and Non-Illuminated), General Specification For.
MIL-S-28827 - Switches, Thermostatic, (Volatile Liquid), Hermetically Sealed, General Specification For.
MIL-S-55433 - Switches, Reed, General Specification For.

(Copies of specifications, standards, drawings, and publications required by contractors in connection with specific procurement functions should be obtained from the procuring agency or as directed by the contracting officer.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

(k) MIL-S-24236 - Switches, Thermostatic (Metallic and Bimetallic). Used primarily in ac and dc applications where temperature protection or accurate temperature control of an enclosure is required.
(l) MIL-S-24317 - Switches, Multistation, Pushbutton (Illuminated and Non-Illuminated). Used as panel displays and switching devices in ac and dc applications.
(m) MIL-S-55433 - Switches, Reed. Used in circuits as a separate element where magnetically-actuated, hermetically sealed switch contacts are required. These reed switches are capable of millions of operations and operations with low-level (dry circuit) loads.
(n) MIL-S-28827 - Switches, Thermostatic (Volatile Liquid), Hermetically Sealed. Used primarily in ac and dc applications that require rapid temperature response.

6.3 Switch selection. The designer, in selecting a switch type for a particular function to be performed, must weigh numerous factors before coming to a final decision. Selection normally starts with the most important characteristic for the application, then selecting and compromising other characteristics.

6.3.1 Selection factors. Some of the most important of these factors are noted below:

(a) Design and construction:

(1) Open or enclosed construction.
(2) Sealed (hermetically, environmentally (resilient), dust-tight, water-tight, explosion).
(3) Mounting (bushing, multihole, mounting bracket, mounting plate).
(4) Illuminated or non-illuminated.

(b) Operating characteristics:

(1) Actuation - pushbutton, toggle, rotary, sensing.
(2) Switching action - momentary action, maintained action, alternate action, snap action.

(c) Contacts:

(1) Type of contacts and contact arrangement.
(2) Contact ratings - resistive, inductive, lamp, motor, low-level (dry circuit), and frequency.
(3) Contact bounce time.
(4) Contact resistance.
(5) Make-before-break, break-before-make; shorting or non-shorting contacts.

(d) Environmental considerations:

(1) Temperature range.
(2) Moisture.
(3) Altitude.
(4) Shock and vibration.
(5) Acceleration.
(6) Sand and dust.
(7) Explosion.

(e) Insulation requirements:

(1) Insulation resistance.
(2) Breakdown voltage.

(f) Switching speed:

(1) Actuation speed.

Source: https://assist.dla.mil -- Downloaded: 202640-26T07:41Z
Check the source to verify that this is the current version before use.

(g) Life:

(1) Mechanical.
(2) Electrical at elevated temperature.

(h) Terminals:

(1) Solder.
(2) Screw.
(3) Wire.
(4) Plug-in termination.
(5) Integrated wire termination.
(6) Printed-circuit board terminations.

6.4 Switch parameters.

6.4.1 Design and construction.

(a) Design. Design of the switch, related to available space, mounting dimensions, handling of the actuating element, type of connections to the switch, and aspects relating to ruggedness and safety, is an important selection factor.

(b) Construction. Many types of enclosures are available to protect the switch from external conditions, particularly high humidity and dirt. Switches may be classified according to the degree of protection offered by the enclosure. Such classifications include the following: Open, sealed, enclosed, environmentally (resilient), and hermetically sealed. With the open construction switch, no effort is made to protect the switch or its parts from atmospheric conditions. The enclosed switch is one in which the contacts are enclosed in a closed case made of plastic or metal and plastic. The environmentally (resilient) sealed switch is one in a completely sealed case where any portion of the seal is a resilient material such as a gasket or a seal in the bushing of a panel-mounted switch. The hermetically sealed switch is made airtight by a sealing process which involves fusing or soldering and does not use a gasket. The hermetically sealed enclosure offers the greatest protection because it insulates against such elements as moisture, harmful gases, and dirt. It also eliminates the increased arcing by low atmospheric pressures at high altitudes.

6.4.2 Contacts. The contacts which carry the electrical load can be classified by function, current-carrying capacity, and application. The contact arrangements vary in complexity from a simple make or break, through make-before-break, break-before-make, make-make, break-break, etc, and from single throw to multiple throw, and single pole to multipole and various combinations of these features.

6.4.2.1 Contact ratings. Contacts are usually given multiple ratings dependent on the type of load being switched. These ratings consist of resistive, low-level (dry circuit), lamp, motor, or inductive loads. Most switches are given the resistive load rating and in most instances at least one additional of the above ratings.

6.4.2.2 Contact operate and bounce times. In many applications, critical operate and bounce times of the contacts are important. Operate time in a double-throw switch is defined as the time it takes the moving contact to separate from the normally closed contact, travel to the normally open contact and make the circuit (this does not include bounce time). Bounce time is the interval between first make of the contact until the uncontrolled making and breaking of the contact ceases. In many electronic circuits, a millisecond is a long time and operate and bounce times become critical parameters.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

SECTION 102A

SWITCHES, PUSH BUTTON, ILLUMINATED
(Applicable specification: MIL-S-22885)


FIGURE NUMBER	APPLICABLE SPECIFICATION SHEET	SWITCH CHARACTERISTICS				PAGE
		Operation	Circuit	Electrical rating (28 Vdc resistive)	Remarks	
102-1	MIL-S-22885/8	Momentary & push-pull	2-circuit	5 amperes	Single lamp, drip-proof seal	102.2
102-1A*	MIL-S-22885/1					
102-2	MIL-S-22885/9 & MIL-S-22885/10	Momentary & alternate	2PDT & 4PDT	5 amperes	4-lamp, rectangular, modular construction	102.4
102-3	MIL-S-22885/15 & MIL-S-22885/16	Momentary & alternate	2PDT & 4PDT	5 amperes	4-lamp, rectangular, clip mounted, modular construction	102.6
102-4	MIL-S-22885/18	Momentary & alternate	2PDT & 2-circuit	2 amperes	Single lamp, drip-proof seal	102.8
102-4A*	MIL-S-22885/22					
102-4B*	MIL-S-22885/19					
102-5	MIL-S-22885/27	Momentary & alternate	4- & 8-circuit	10 amperes	Single lamp	102.10
102-5A*	MIL-S-22885/28					
102-6	MIL-S-22885/56	Momentary & alternate	2PDT & 4PDT	2 amperes	4-lamp, square, RFI shielding option	102.12
102-7	MIL-S-22885/67	Momentary & alternate	2PDT & 3PDT	7 amperes	4-lamp, square, RFI shielding option	102.14
102-8	MIL-S-22885/74	Momentary & alternate	2PDT & 4PDT	5 amperes	4-lamp, square, integrated wire termination system	102.16
102-9	MIL-S-22885/75	Momentary & alternate	2PDT, 3PDT, & 4PDT	7 amperes	4-lamp, square, RFI shielding option	102.18
102-10	MIL-S-22885/77	Momentary, alternate, & magnetic hold	2PDT, 3PDT, & 4PDT	7.5 amperes	4-lamp, square, RFI shielding option, integrated wire termination system	102.20
102-11	MIL-S-22885/79	Momentary	SPDT	7 (silver) or 1 (gold) amperes	Single lamp, drip-proof seal option	102.22
102-12	MIL-S-22885/58	Momentary & alternate	2PDT & 4PDT	3 amperes	2-lamp, rectangular	102.24
102-13	MIL-S-22885/81	Momentary & alternate	2PDT & 4PDT	5 amperes	Single lamp, drip-proof seal	102.25
102-14	MIL-S-22885/71	Momentary & alternate	2PDT	7 amperes	4-lamp, square, RFI shielded	102.26
102-15	MIL-S-22885/72 & MIL-S-22885/73	Momentary & alternate	4- & 8-circuit	10 amperes	4-lamp, square, modular construction	102.28
102-16	MIL-S-22885/80	Momentary	2PDT & 4PDT	5 amperes	4-lamp, square, RFI shielded, moisture seal, high shock	102.30
102-17	MIL-S-22885/86	Momentary & alternate	2PDT & 4PDT	2 amperes	4-lamp, square, RFI shielded, modular construction	102.32

* Applicable lens.

Supersedes Section 102 (pages 102.1 thru 102.71) of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)	
	28 Vdc	115 Vac
Resistive - - - - -	5	5
Inductive - - - - -	3	3




INCHES	MM
.25	6.35
.312	7.92
.38	9.65
.39	9.91
.44	11.18
.625	15.88
.75	19.05
.94	23.88
2.27	57.66

Switch Part No. M22885/8-		Lens (screw-in type) (see figure 102-1A)				
Momentary	Push-pull	Configuration	Color	Brightness (3/4 face) ft L	Part No. M22885/1-	Dimension "A" inch (mm)
		Switch housings without lens				
01	02	A	Yellow	225	01	.81 (20.57)
03	28		White	250	02	
04	29		Red	20	03	
05	30		Green	11	04	
06	31		Blue	7	05	
07	32					
08	33	B	Yellow	150	06	.75 (19.05)
09	34		White	200	07	
10	35		Red	15	08	
11	36		Green	18	09	
12	37		Blue	4	10	
13	38	C	Yellow	300	11	.67 (17.02)
14	39		White	300	12	
15	40		Red	25	13	
16	41		Green	40	14	
17	42		Blue	10	15	
18	43	D	Yellow	150	16	.62 (15.75)
19	44		White	200	17	
20	45		Red	15	18	
21	46		Green	18	19	
22	47		Blue	4	20	
23	48	E	Yellow	120	21	.88 (22.35)
24	49		White	135	22	
25	50		Red	14	23	
26	51		Green	14	24	
27	52		Blue	2	25	


Operating force:
Momentary - 4 ± 1 pounds initial, 2.5 pounds minimum after life.
Push-pull - 1.5 pounds.
Circuit characteristics: Two circuit 1 NO.

FIGURE 102-1. Switch housings, push button, illuminated, momentary and push-pull (MIL-S-22885/8).


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



Configurations A and D



Configurations B and E



Configuration C


INCHES	MM
.312	7.92
.437	11.10
.50	12.70

FIGURE 102-1A. Screw-in lenses (MIL-S-22885/1).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		50,000 feet
	28 Vdc	115 Vac	28 Vdc
Resistive - - -	5.0	5.0	5.0
Inductive - - -	3.0	5.0	2.5
Lamp - - - - -	2.4	1.5	2.4

INCHES	MM
.050	1.27
.078	1.98
.250	6.35
.327	8.31
.625	15.88
.850	21.59
.960	24.38
1.040	26.42
1.200	30.48
1.75	44.45



Complete switch consists of:
- 1 - Indicator light module, MIL-S-22885/10 (with narrow or extended front lens plate per MIL-S-22885/85)
- 1 - Switch module, MIL-S-22885/11

Additional parts that may be ordered, if required:
- 4 - Color filters, MIL-S-22885/12
- 1 - Panel seal, MIL-S-22885/13
- 4 - Lamps (T-1-3/4 midget-flange-base incandescent type)


Operating force:
- Momentary - 4 pounds, maximum.
- Alternate - 6 pounds, maximum (2PDT) or 7 pounds, maximum (4PDT).


FIGURE 102-2. Switches, push button, illuminated, 4-lamp, solid mount (MIL-S-22885/9 and /10).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

1/ Part No. M22885/9-				Lens style code	Lamp wiring code	Indicator light module M22885/10-
Momentary		Alternate				
Switch module M22885/11		Switch module M22885/11				
-01 2PDT	-02 4PDT	-03 2PDT	-04 4PDT			
NARROW FRONT LENS PLATE, M22885/85-01						
01	02	03	04	A	1	01
09	10	11	12	B	1	03
13	14	15	16	B	2	04
17	18	19	20	C	1	05
21	22	23	24	C	3	06
25	26	27	28	A	3	07
167	168	169	170	A	2	08
EXTENDED FRONT LENS PLATE, M22885/85-02						
29	30	31	32	A	1	09
33	34	35	36	B	1	10
37	38	39	40	B	2	11
41	42	43	44	C	1	12
45	46	47	48	C	3	13
49	50	51	52	A	3	14
171	172	173	174	A	2	15
WITHOUT LENS PLATE						
53	54	55	56	A	1	16
57	58	59	60	B	1	17
61	62	63	64	B	2	18
65	66	67	68	C	1	19
69	70	71	72	C	3	20
73	74	75	76	A	3	21
175	176	177	178	A	2	22

1/ Part numbers are for units without color filters. When color filters are required (see section 203 - MIL-S-22885/12), the color symbols of MIL-S-22885 will be added following the dash number with the location sequence as shown in the following:









FIGURE 102-2. Switches, push button, illuminated, 4-lamp, solid mount (MIL-S-22885/9 and /10) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		50,000 feet
	28 Vdc	115 Vac	28 Vdc
Resistive - - -	5.0	5.0	5.0
Inductive - - -	3.0	5.0	2.5
Lamp - - - - -	2.4	1.5	2.4



INCHES	MM
.225	5.72
.845	21.46
.875	22.23
1.085	27.56
1.100	27.94
1.115	28.32
1.355	34.42
1.750	44.45

Complete switch shall consist of the following:
1 - Indicator light module, MIL-S-22885/16
1 - Switch module, MIL-S-22885/11 (see section 113)

Additional parts that may be ordered, if required:
4 - Color filters, MIL-S-22885/12 (see section 203)
4 - Lamps (T-1-3/4 midget-flange-base incandescent type)


Operating force:
Momentary - 4 pounds, maximum
Alternate - 6 pounds, maximum (2PDT) or 7 pounds, maximum (4PDT)


FIGURE 102-3. Switches, push button, illuminated, 4-lamp, clip mounted (MIL-S-22885/15 and /16)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

1/ Part No. M22885/15-						
Momentary		Alternate				
Switch module M22885/11-		Switch module M22885/11-		Lens style code	Lamp wiring code	Indicator light module M22885/16-
-01	-02	-03	-04			
2PDT	4PDT	2PDT	4PDT			
CONFIGURATION A						
01	02	03	04	A	1	01
05	06	07	08	B	1	05
09	10	11	12	B	2	07
13	14	15	16	C	1	09
17	18	19	20	C	3	11
21	22	23	24	A	3	13
49	50	51	52	A	4	15
53	54	55	56	B	4	17
57	58	59	60	C	4	19
CONFIGURATION B						
25	26	27	28	A	1	02
29	30	31	32	B	1	06
33	34	35	36	B	2	08
37	38	39	40	C	1	10
41	42	43	44	C	3	12
45	46	47	48	A	3	14
61	62	63	64	A	4	16
65	66	67	68	B	4	18
69	70	71	72	C	4	20

1/ Part numbers are for units without color filters. When color filters are required (see section 203 - MIL-S-22885/12), the color symbols of MIL-S-22885 will be added following the dash number with the location sequence as shown in the following:










FIGURE 102-3. Switches, push button, illuminated, 4-lamp, clip mounted (MIL-S-22885/15 and /16) - Continued.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes) 28 Vdc	115 Vac (60/400 Hz)
Resistive - - - -	2.0	2.0
Inductive - - - -	1.5	1.5
Lamp - - - - - -	0.5	0.5






INCHES	MM	INCHES	MM
.13	3.30	.615	15.62
.27	6.86	.650	16.51
.36	9.14	2.12	53.85
.42	10.67		



Part No. M22885/18- Momentary DPDT	Momentary 2-Circuit	Alternate DPDT	Alternate 2-Circuit	Configuration	Color	Brightness (3/4 face) ft. L	Part No. M22885/
				Lens (threaded type) (see figure 102-4A)			
				Switch housings without lens			
01	03	02	04	A	Yellow	350	22-01
09	49	29	69		White	300	-02
10	50	30	70		Red	100	-03
11	51	31	71		Green	75	-04
12	52	32	72		Blue	20	-05
13	53	33	73	B	Yellow	350	-06
14	54	34	74		White	300	-07
15	55	35	75		Red	100	-08
16	56	36	76		Green	75	-09
17	57	37	77		Blue	20	-10
18	58	38	78	C	Yellow	350	-11
19	59	39	79		White	300	-12
20	60	40	80		Red	100	-13
21	61	41	81		Green	75	-14
22	62	42	82		Blue	20	-15
23	63	43	83	D	Yellow	350	-16
24	64	44	84		White	300	-17
25	65	45	85		Red	100	-18
26	66	46	86		Green	75	-19
27	67	47	87		Blue	20	-20
28	68	48	88				
Part No. M22885/18-				Lens (snap-in type) (see figure 102-4B)			
05	07	06	08	Switch housings without lens			
89	119	104	134	A	Yellow	150	19-01
90	120	105	135		White	200	-02
91	121	106	136		Red	15	-03
92	122	107	137		Green	20	-04
93	123	108	138		Blue	5	-05
94	124	109	139	B	Yellow	150	-06
95	125	110	140		White	200	-07
96	126	111	141		Red	15	-08
97	127	112	142		Green	20	-09
98	128	113	143		Blue	5	-10
99	129	114	144	C	Yellow	150	-11
100	130	115	145		White	200	-12
101	131	116	146		Red	15	-13
102	132	117	147		Green	20	-14
103	133	118	148		Blue	5	-15

FIGURE 102-4. Switch housings, push button, illuminated, drip proof seal (MIL-S-22885/18).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.








FIGURE 102-4A and 4B. Threaded and snap-in lenses (MIL-S-22885/22 and /19).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		70,000 feet
	28 Vdc	115 Vac, 60 Hz	28 Vdc
Resistive - - - -	10.0	5.0	10.0
Inductive - - - -	5.0	5.0	2.0
Lamp - - - - - -	3.0	1.5	---



M22885/27-01 and -02




M22885/27-03 and -04

INCHES	MM
.040	1.02
.09	2.29
.19	4.83
.25	6.35
.36	9.14
.67	17.02
.75	19.05
.78	19.81
1.16	29.46

Part No. M22885/27-	Circuit characteristic	Dimension "A" inches (mm)	Basic switch Part No.	Basic switch Specification No.	Operating force (max)
01	4 circuit	.66 (16.76)	MS27217-1	MIL-S-8805/7	1.5 pounds
02	4 circuit	1.09 (27.69)	MS27217-1	MIL-S-8805/7	6.0 pounds
03	8 circuit	1.00 (25.40)	M8805/77-001	MIL-S-8805/77	2.5 pounds
04	8 circuit	1.44 (36.58)	M8805/77-001	MIL-S-8805/77	6.0 pounds


FIGURE 102-5. Switch housings, push button, illuminated, double break (MIL-S-22885/27).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




SCHEMATIC DIAGRAM
MOMENTARY ACTION

M22885/27-01




SCHEMATIC DIAGRAM
ALTERNATE ACTION

M22885/27-02




SCHEMATIC DIAGRAM
MOMENTARY ACTION

M22885/27-03



SCHEMATIC DIAGRAM
ALTERNATE ACTION

M22885/27-04




Color	Part No. M22885/28- Dimension "A" - Round lens .62 inch (15.75)	.75 inch (19.05)	.81 inch (20.57)	1.12 inch (28.45)	Dimension "A" - Square lens .62 inch (15.75)	.75 inch (19.05)
Blue	01	07	13	19	25	31
Green	02	08	14	20	26	32
Red	03	09	15	21	27	33
Yellow	05	11	17	23	29	35
White	06	12	18	24	30	36


FIGURE 102-5A. Lenses (MIL-S-22885/28).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS (amperes)	
	28 Vdc	115 Vac
Resistive - - - -	2.0	2.0
Inductive - - - -	1.0	1.0
Lamp - - - - - -	0.75	0.75



INCHES	MM	INCHES	MM
.060	1.52	.684	17.37
.07	1.78	.690	17.53
.188	4.78	.781	19.84
.21	5.33	.800	20.32
.24	6.10	2.36	59.94
.36	9.14	2.65	67.31



FLUSH LENS



EXTENDED LENS WITH REMOVAL LATCH HEIGHT SHOWN TO ACCOMMODATE EDGE LIGHTED PANEL

Complete switch consists of:
1 - Lamp module, MIL-S-22885/52 or /53
1 - Switch module (housing with mounting bracket)

Additional parts that may be ordered, if required:
4 - Lamps (T-1-3/4 midget-flange-base incandescent type)

Operating force: 3.5 ± 1.0 pounds

FIGURE 102-6. Switches, push button, illuminated, 4-lamp, solid mounting (MIL-S-22885/56).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

1/ Part No. M22885/56-								Lens code
Momentary Lens height				Alternate Lens height				
Extended		Flush		Extended		Flush		
4PDT	2PDT	4PDT	2PDT	4PDT	2PDT	4PDT	2PDT	
WITHOUT RFI SHIELDING								
001	141	003	143	002	142	004	144	---
005	021	037	053	013	029	045	061	A
006	022	038	054	014	030	046	062	B
007	023	039	055	015	031	047	063	C
008	024	040	056	016	032	048	064	D
009	025	041	057	017	033	049	065	E
010	026	042	058	018	034	050	066	F
011	027	043	059	019	035	051	067	G
012	028	044	060	020	036	052	068	H
WITH RFI SHIELDING								
133	137	135	139	134	138	136	140	---
069	085	101	117	077	093	109	125	A
070	086	102	118	078	094	110	126	B
071	087	103	119	079	095	111	127	C
072	088	104	120	080	096	112	128	D
073	089	105	121	081	097	113	129	E
074	090	106	122	082	098	114	130	F
075	091	107	123	083	099	115	131	G
076	092	108	124	084	100	116	132	H

1/ Part numbers are for units without filters or caps. When required, the color symbols in the table below will be added following the dash number in the Color Symbol Position shown. EXAMPLE: M22885/56-010G1R1 denotes a 4PDT momentary switch without RFI shielding; extended lens, code "F"; with color filters (green in Position 1 and red in Position 2).


COLOR SYMBOL		COLOR
Filter (see MIL-S-22885/54)	Cap (see MIL-S-22885/55)	
B1	B2	Blue
G1	G2	Green
R1	R2	Red
W1	W2	White
Y1	Y2	Yellow

LENS CODE	LENS STYLE	COLOR SYMBOL POSITION
A	4 - WAY SPLIT	
B	3 - WAY SPLIT	
C	SPLIT HORIZONTALLY	
D	SOLID	
E	3 - WAY SPLIT	
F	SPLIT VERTICALLY	
G	3 - WAY SPLIT	
H	3 - WAY SPLIT	

FIGURE 102-6. Switches, push button, illuminated, 4-lamp, solid mounting (MIL-S-22885/56) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes) Sea level 28 Vdc	Sea level 115 Vac, 60 Hz	50,000 feet 28 Vdc
Resistive - - - -	7	7	4
Inductive - - - -	4	7	2.5
Lamp - - - - - -	2.5	2	2.5



INCHES	MM
.010	.25
.041	1.04
.09	2.29
.15	3.81
.22	5.59
.531	13.49
.688	17.48
.750	19.05
2.620	66.55

Complete switch consists of:
1 - Lens assembly (color filters in accordance with MIL-S-22885/70)
1 - Switch housing (with mounting sleeve and panel spacer)

Additional parts that may be ordered, if required:
4 - Lamps (T-1-3/4 midget-flange-base incandescent type)


Operating force: 2 to 5 pounds.

FIGURE 102-7. Switches, push button, illuminated, 4-lamp, solid mount (MIL-S-22885/67).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

1/ Part No. M22885/67- Lens configuration								Operation	Characteristics	Lens design 2/
0	1	2	3	4	5	6	7			
WITHOUT EMI SCREENING										
009	010	011	012	013	014	015	016	Momentary	2PDT	Nonremovable
017	018	019	020	021	022	023	024	Momentary	3PDT	Nonremovable
033	034	035	036	037	038	039	040	Alternate	2PDT	Nonremovable
041	042	043	044	045	046	047	048	Alternate	3PDT	Nonremovable
049	050	051	052	053	054	055	056	Momentary	2PDT	Removable
057	058	059	060	061	062	063	064	Momentary	3PDT	Removable
065	066	067	068	069	070	071	072	Alternate	2PDT	Removable
073	074	075	076	077	078	079	080	Alternate	3PDT	Removable
WITH EMI SCREENING										
081	082	083	084	085	086	087	088	Momentary	2PDT	Removable
089	090	091	092	093	094	095	096	Momentary	3PDT	Removable
097	098	099	100	101	102	103	104	Alternate	2PDT	Removable
105	106	107	108	109	110	111	112	Alternate	3PDT	Removable

1/ Part numbers are for units without color filters. When required, the segment placement number (see lens configuration) and color symbol will be added following the dash number.
EXAMPLE: M22885/67-012 6B 7G 8R 9Y



2/ Nonremovable lens assembly is capable of having lamps removed but is restricted in complete removal from switch housing; removable lens assembly is capable of being removed from switch housing.






FIGURE 102-7. Switches, push button, illuminated, 4-lamp, solid mount (MIL-S-22885/67) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS (amperes) 28 Vdc	115 Vac
Resistive - - - -	5.0	5.0
Inductive - - - -	2.5	2.5
Lamp - - - - - -	1.5	1.5





4PDT SWITCH CIRCUITRY
TERMINALS 6,9,11,14,16,19
OMITTED ON 2PDT CIRCUIT

INCHES	MM
.040	1.02
.050	1.27
.200	5.08
.350	8.89
.740	18.80
.900	22.86
2.960	75.18
3.500	88.90



PLUG-IN MODULES

Complete switch consists of:
1 - Lens assembly
1 - Switch housing (terminal junction module in accordance with MIL-T-81714) with mounting sleeve.

Additional parts that may be ordered, if required:
4 - Lamps (T-1-3/4 midget-flange-base incandescent type).
- Crimp contacts, M39029/1-16-20.

Operating force: 4 pounds, maximum

FIGURE 102-8. Switches (conforming to integrated wire termination system), push button, illuminated, 4-lamp, solid mount (MIL-S-22885/74).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

Part No. M22885/74-				Circuit	Operation	Lens style
Complete assembly 1/	Indicator module	Lamp module 1/	Housing			
01	41	36	39	2PDT	Momentary	A
02	42			4PDT	Momentary	
03	43			2PDT	Alternate	
04	44			4PDT	Alternate	
05	45	37	39	2PDT	Momentary	B
06	46			4PDT	Momentary	
07	47			2PDT	Alternate	
08	48			4PDT	Alternate	
09	49	38	39	2PDT	Momentary	C
10	50			4PDT	Momentary	
11	51			2PDT	Alternate	
12	52			4PDT	Alternate	
13	53	36	39	---	Indicator	A
14	54	37	39	---	Indicator	B
15	55	38	39	---	Indicator	C

1/ Part numbers are for units without color filters. When color filters are required, the color symbols of MIL-S-22885 will be added following the dash number; the location sequence is shown in the Lens Assembly diagram.

Lens assembly.




Code	Lens style		Lamp schematic
A	Solid - common ground		
B	Split horizontally - horizontal split ground		
C	Split vertically - vertical split ground		

FIGURE 102-8. Switches (conforming to integrated wire termination system), push button, illuminated, 4-lamp, solid mount (MIL-S-22885/74) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		50,000 feet
	28 Vdc	115 Vac, 60 Hz	28 Vdc
Resistive - - - -	7.0	7.0	4.0
Inductive - - - -	4.0	7.0	2.5
Lamp - - - - - -	2.5	2.0	2.5



INCHES	MM
.010	.25
.015	.38
.09	2.29
.296	7.52
.62	15.75
.730	18.54
.750	19.05
.870	22.10
2.750	69.85

Complete switch consists of:
1 - Lens assembly (color filters in accordance with MIL-S-22885/70)
1 - Switch housing (with mounting sleeve)

Additional parts that may be ordered, if required:
4 - Lamps (T-1-3/4 midget-flange-base incandescent type)

Operating force: 2 to 5 pounds.

FIGURE 102-9. Switches, push button, illuminated, 4-lamp, momentary and alternate action (MIL-S-22885/75).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

1/ Part No. M22885/75- Lens configuration								Operation	Characteristics	2/ Lens design
0	1	2	3	4	5	6	7			
WITHOUT EMI SHIELDING										
009	010	011	012	013	014	015	016	Momentary	2PDT	Nonremovable
017	018	019	020	021	022	023	024	Momentary	3PDT	Nonremovable
025	026	027	028	029	030	031	032	Momentary	4PDT	Nonremovable
041	042	043	044	045	046	047	048	Alternate	2PDT	Nonremovable
049	050	051	052	053	054	055	056	Alternate	3PDT	Nonremovable
057	058	059	060	061	062	063	064	Alternate	4PDT	Nonremovable
065	066	067	068	069	070	071	072	Momentary	2PDT	Removable
073	074	075	076	077	078	079	080	Momentary	3PDT	Removable
081	082	083	084	085	086	087	088	Momentary	4PDT	Removable
089	090	091	092	093	094	095	096	Alternate	2PDT	Removable
097	098	099	100	101	102	103	104	Alternate	3PDT	Removable
105	106	107	108	109	110	111	112	Alternate	4PDT	Removable
WITH EMI SHIELDING										
113	114	115	116	117	118	119	120	Momentary	2PDT	Removable
121	122	123	124	125	126	127	128	Momentary	3PDT	Removable
129	130	131	132	133	134	135	136	Momentary	4PDT	Removable
137	138	139	140	141	142	143	144	Alternate	2PDT	Removable
145	146	147	148	149	150	151	152	Alternate	3PDT	Removable
153	154	155	156	157	158	159	160	Alternate	4PDT	Removable

1/ Part numbers are for units without color filters. When required, the segment placement number (see lens configuration) and color symbol will be added following the dash number.
EXAMPLE: M22885/75-012 6B 7G 8R 9Y
- 9Y — Yellow (9th position)
- 8R — Red (8th position)
- 7G — Green (7th position)
- 6B — Blue (6th position)

2/ Nonremovable lens assembly is capable of having lamps removed but is restricted in complete removal from switch housing; removable lens assembly is capable of being removed from switch housing.

LENS CONFIGURATION
(with segment placement numbers)





FIGURE 102-9. Switches, push button, illuminated, 4-lamp, momentary and alternate action (MIL-S-22885/75) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		50,000 feet
	28 Vdc	115 Vac, 60 Hz	28 Vdc
Resistive - - - -	7.5	7.5	4.0
Inductive - - - -	5.0	5.0	2.5
Lamp 1/ - - - -	1.0	1.0	1.0

1/ Inrush, 10:1 for 20 milliseconds maximum.



INCHES	MM	INCHES	MM
.010	.25	.53	13.47
.020	.51	.62	15.74
.04	1.02	.679	17.26
.060	1.52	.688	17.48
.100	2.54	.75	19.05
.180	4.57	2.93	74.42
.220	5.59	3.56	90.42
.240	6.10		

Complete switch consists of:
1 - Lens assembly (color filters in accordance with MIL-S-22885/78)
1 - Switch housing (with mounting sleeve and panel spacer)

Additional parts that may be ordered, if required:
4 - Lamps (T-1-3/4 midget-flange-base incandescent type)
- Crimp contacts, M39029/1-16-20

Operating force: 3.5 ±1.5 pounds

FIGURE 102-10. Switches, 4-lamp, solid mount, insertable crimp terminations (MIL-S-22885/77).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

1/ Part No. M22885/77- Lens configuration								Operation	Characteristics	2/ Lens design
0	1	2	3	4	5	6	7			
WITHOUT EMI SHIELDING										
001	002	003	004	005	006	007	008	Momentary	2PDT	Nonremovable
009	010	011	012	013	014	015	016	Momentary	3PDT	Nonremovable
017	018	019	020	021	022	023	024	Momentary	4PDT	Nonremovable
025	026	027	028	029	030	031	032	3/	2PDT	Nonremovable
033	034	035	036	037	038	039	040	3/	3PDT	Nonremovable
041	042	043	044	045	046	047	048	3/	4PDT	Nonremovable
049	050	051	052	053	054	055	056	Mag. hold	2PDT	Nonremovable
057	058	059	060	061	062	063	064	Mag. hold	3PDT	Nonremovable
065	066	067	068	069	070	071	072	Mag. hold	4PDT	Nonremovable
073	074	075	076	077	078	079	080	Momentary	2PDT	Removable
081	082	083	084	085	086	087	088	Momentary	3PDT	Removable
089	090	091	092	093	094	095	096	Momentary	4PDT	Removable
097	098	099	100	101	102	103	104	3/	2PDT	Removable
105	106	107	108	109	110	111	112	3/	3PDT	Removable
113	114	115	116	117	118	119	120	3/	4PDT	Removable
121	122	123	124	125	126	127	128	Mag. hold	2PDT	Removable
129	130	131	132	133	134	135	136	Mag. hold	3PDT	Removable
137	138	139	140	141	142	143	144	Mag. hold	4PDT	Removable
WITH EMI SHIELDING										
145	146	147	148	149	150	151	152	Momentary	2PDT	Removable
153	154	155	156	157	158	159	160	Momentary	3PDT	Removable
161	162	163	164	165	166	167	168	Momentary	4PDT	Removable
169	170	171	172	173	174	175	176	3/	2PDT	Removable
177	178	179	180	181	182	183	184	3/	3PDT	Removable
185	186	187	188	189	190	191	192	3/	4PDT	Removable
193	194	195	196	197	198	199	200	Mag. hold	2PDT	Removable
201	202	203	204	205	206	207	208	Mag. hold	3PDT	Removable
209	210	211	212	213	214	215	216	Mag. hold	4PDT	Removable

1/ Part numbers are for units without color filters. When required, the segment placement number (see lens configuration) and color symbol will be added following the dash number.
EXAMPLE: M22885/77-004 6B 7G 8R 9Y
- 9Y — Yellow (9th position)
- 8R — Red (8th position)
- 7G — Green (7th position)
- 6B — Blue (6th position)

2/ Nonremovable lens assembly is capable of having lamps removed but is restricted in complete removal from switch housing; removable lens assembly is capable of being removed from switch housing.

3/ Maintained depressed alternate action.





FIGURE 102-10. Switches, 4-lamp, solid mount, insertable crimp terminations (MIL-S-22885/77) - Continued.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS (amperes)				
	Silver contacts, MS24547-1			Gold contacts, MS24547-2	
	Sea level		50,000 feet	Sea level	50,000 feet
	28 Vdc	115 Vac, 60 Hz	28 Vdc	28 Vdc	28 Vdc
Resistive - - - -	7.0	7.0	4.0	1.0	1.0
Inductive - - - -	4.0	7.0	2.5	.5	.5
Lamp - - - - - -	2.5	2.0	2.5	---	---






SCHEMATIC DIAGRAM





DRIP PROOF SEAL (REF)



"D" STYLE LENS SHOWN FOR REF. ONLY. SEAL IS AVAILABLE FOR ANY LENS STYLE.

INCHES	MM
.005	.13
.010	.25
.020	.51
.03	.76
.075	1.91
.11	2.79
.25	6.35
.358	9.09
.375	9.53
.408	10.36
.425	10.80
.44	11.18
.447	11.35
.469	11.91
.50	12.70
.505	12.83
.540	13.72
.56	14.22
.562	14.27
.608	15.44
.625	15.88
.656	16.66
.75	19.05
.858	21.79
1.00	25.40
1.13	28.70

FIGURE 102-11. Switch bodies and lenses (with or without dripproof seal) (MIL-S-22885/79).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

Part No. M22885/79- Lens color					Lens style (snap-in)	Switch contacts
Green	Red	White	Yellow	Blue		
WITHOUT DRIPPROOF SEAL						
001	002	003	004	005	B	MS24547-1
006	007	008	009	010	C	↕
011	012	013	014	015	D	
016	017	018	019	020	E	
021	022	023	024	025	F	MS24547-1
026	027	028	029	030	B	MS24547-2
031	032	033	034	035	C	↕
036	037	038	039	040	D	
041	042	043	044	045	E	
046	047	048	049	050	F	MS24547-2
WITH DRIPPROOF SEAL						
051	052	053	054	055	B	MS24547-1
056	057	058	059	060	C	↕
061	062	063	064	065	D	
066	067	068	069	070	E	
071	072	073	074	075	F	MS24547-1
076	077	078	079	080	B	MS24547-2
081	082	083	084	085	C	↕
086	087	088	089	090	D	
091	092	093	094	095	E	
096	097	098	099	100	F	MS24547-2
BASIC SWITCH BODY WITHOUT LENS						
101					None	MS24547-1
102					None	MS24547-2


Complete switch consists of:
1 - Push button lens assembly.
1 - Lamp (T-1-3/4 midget-flange-base incandescent type #387, 28 volts - long life)
1 - Switch body

Operating force: 22 ± 4 ounces

FIGURE 102-11. Switch bodies and lenses (with or without dripproof seal) (MIL-S-22885/79) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes) Sea level	
	28 Vdc	115 Vac
Resistive - - - -	3.0	3.0
Inductive - - - -	1.5	1.5
Lamp - - - - - -	1.5	1.0



Complete switch consists of:
1 - Lamp module
1 - Switch housing
2 - Lamps (T-1-3/4 midget-flange-base incandescent type) - Not included, order separately

Operating force: 4.0 pounds maximum

1/ Part No. M22885/58-				Lens plate code
Momentary		Alternate		
2PDT	4PDT	2PDT	4PDT	
01	04	07	10	A
02	05	08	11	B
03	06	09	12	C

1/ Part numbers are for units without color filters. When color filters are required, the color symbols of MIL-S-22885 will be added following the dash number with the location sequence shown in the Lens Plate diagram.






FIGURE 102-12. Switches, push button, illuminated, 2-lamp, solid mount (MIL-S-22885/58).


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		50,000 feet
	28 Vdc	115 Vac, 60 Hz	28 Vdc
Resistive - - - -	5.0	5.0	5.0
Inductive - - - -	3.0	5.0	2.5
Lamp - - - - - -	2.4	1.5	2.4






2 POLE
ALTERNATE ACTION



4 POLE
MOMENTARY



4 POLE
ALTERNATE ACTION

INCHES	MM
.022	.56
.050	1.27
.366	9.30
.660	16.76
.730	18.54
.750	19.05
.800	20.32
.940	23.88
1.042	26.47
1.200	30.48


Part No. M22885/81- Lens color					Switch circuitry	Dimension "A"
Red	Green	Yellow	Blue	White		inch (mm)
01R	01G	01Y	01B	01W	2 pole momentary	2.61 (66.29)
02R	02G	02Y	02B	02W	2 pole alternate action	2.90 (73.66)
03R	03G	03Y	03B	03W	4 pole momentary	2.61 (66.29)
04R	04G	04Y	04B	04W	4 pole alternate action	2.90 (73.66)


Complete switch consists of:
1 - Lens/lampholder
1 - Switch housing (utilizes MS25085-2 basic switches)
1 - Lamp (T-1-3/4 midget-flange-base incandescent type) - Not included, order separately

FIGURE 102-13. Switches, push button, illuminated, 1-lamp, panel sealed (MIL-S-22885/81).


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS (amperes) 28 Vdc
Resistive - - - -	7.0
Inductive - - - -	4.0





SWITCH CIRCUITRY
(MOMENTARY ACTION)





LAMP CIRCUIT SCHEMATIC


INCHES	MM
.165	4.19
.540	13.72
.73	18.54
.920	23.37
.935	23.75
2.135	54.23

Complete switch consists of:
1 - Lamp module
1 - Switch housing
1 - Legend plate
4 - Lamps (T-1 sub-midget-flange-base incandescent type) - Not included, order separately


FIGURE 102-14. Switches, push button, illuminated, 4-lamp, RFI shielded, solid mount (MIL-S-22885/71).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


Part No. M22885/71- Lens style								Switching action	Max weight	Operating force
A	B	C	D	E	F	G	H			
01	02	03	04	05	06	07	08	Momentary	(ounces) 1.9	(ounces) 12 to 48
09	10	11	12	13	14	15	16	Alternate (two-level)	1.9	12 to 48
17	18	19	20	21	22	23	24	Indicator	1.7	---




STYLE A (SOLID)




STYLE B (HORIZONTAL SPLIT)




STYLE C (VERTICAL SPLIT)




STYLE D (4 WAY SPLIT)




STYLE E (3 WAY SPLIT)



STYLE F (3 WAY SPLIT)



STYLE G (3 WAY SPLIT)





STYLE H (3 WAY SPLIT)

FIGURE 102-14. Switches, push button, illuminated, 4-lamp, RFI shielded, solid mount (MIL-S-22885/71) - Continued.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		10,000 feet
	28 Vdc	115 Vac	28 Vdc
Resistive - - - -	10.0	5.0	10.0
Inductive - - - -	5.0	5.0	2.0
Lamp - - - - - -	3.0	1.5	---





LAMP CIRCUIT SCHEMATIC



INCHES	MM
.250	6.35
.875	22.22
1.500	38.10
1.875	47.62
2.125	53.98


Complete switch consists of:
1 - Indicator light module, MIL-S-22885/73
1 - Switch module, MIL-S-22885/26 (see Section 113)
4 - Lamps (T-1-3/4 midget-flange-base incandescent type) - Not included, order separately

FIGURE 102-15. Switches, push button, illuminated, 4-lamp, modular constructed (MIL-S-22885/72 and MIL-S-22885/73).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

1/ Switch Part No. M22885/72-			Dimension "A"	Circuit	Operation	Switch module	
1/ Indicator M22885/73-01	1/ Indicator M22885/73-02	1/ Indicator M22885/73-03				Part No. M22885/26-	Operating force (maximum)
Lens code A	Lens code B	Lens code C	inches (mm)				pounds
01	07	13	3.125(79.38)	2 two-circuit	Momentary	01	4
02	08	14	3.281(83.34)	2 two-circuit	Alternate	02	6
03	09	15	3.125(79.38)	4 two-circuit	Momentary	03	4
04	10	16	3.281(83.34)	4 two-circuit	Alternate	04	7
05	11	17	3.031(76.99)	2 four-circuit	Momentary	05	4
06	12	18	3.438(87.43)	2 four-circuit	Alternate	06	7

1/ Part numbers are for units without color filters. When color filters are required, the color symbols of MIL-S-22885 will be added following the dash number; the location sequence is shown in the following:



VIEW FROM FRONT OF PANEL


COLOR FILTER LOCATION


CODE	LENS STYLE
A	SOLID
B	VERTICALLY SPLIT
C	HORIZONTALLY SPLIT

FIGURE 102-15. Switches, push button, illuminated, 4-lamp, modular constructed (MIL-S-22885/72 and MIL-S-22885/73) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes) Sea level	
	28 Vdc	115 Vac
Resistive - - - -	5.0	5.0
Inductive - - - -	2.5	2.5





PLUG-IN SWITCH / INDICATOR MODULE

Complete switch consists of:
1 - Plug-in switch indicator module
1 - Switch housing with MIL-S-22885/80-50 insertable solder type terminals
4 - Lamps (T-1-3/4 midget-flange-base incandescent type) - Not included, order separately

Operating force: 4 pounds maximum




FIGURE 102-16. Switches, push button, illuminated, 4-lamp, RFI shielded, Moisture sealed, high impact shock, modular construction (MIL-S-22885/80).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

1/ Part No. M22885/80-			Circuit characteristics, operation, and part	Type
Lamp code 1 Lens code A	Lamp code 2 Lens code B	Lamp code 3 Lens code C		
COMPLETE SWITCH OR INDICATOR ASSEMBLY				
01	02	03	2PDT momentary switch	I
04	05	06	4PDT momentary switch	I
07	08	09	Indicator	I
10	11	12	2PDT momentary switch	II
13	14	15	4PDT momentary switch	II
16	17	18	Indicator	II
PLUG-IN SWITCH OR INDICATOR MODULES WITHOUT HOUSINGS				
19	20	21	2PDT momentary switch	I
22	23	24	4PDT momentary switch	I
25	26	27	Indicator	I
28	29	30	2PDT momentary switch	II
31	32	33	4PDT momentary switch	II
34	35	36	Indicator	II

1/ Part numbers are for units without color filters. When color filters are required, the color symbols of MIL-S-22885 will be added following the dash number; the location sequence is shown in Lens Code diagram.

LENS CODE

CODE	A	B	C
	FULL	HORIZONTAL SPLIT	VERTICAL SPLIT
LENS STYLE			





CODE	LAMP CIRCUITRY
1	
2	
3	


FIGURE 102-16. Switches, push button, illuminated, 4-lamp, RFI shielded, Moisture sealed, high impact shock, modular construction (MIL-S-22885/80) - Continued.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS (amperes) 28 Vdc	115 Vac
Resistive - - - -	2.0	2.0
Inductive - - - -	1.0	1.0
Lamp - - - - - -	0.75	0.75

INCHES	MM
.032	.81
.12	3.05
.125	3.18
.18	4.57
.21	5.33
.50	12.70
.685	17.40
.735	18.67
.870	22.10
1.22	30.99
1.24	31.50
2.82	71.63










Complete switch consists of:
- 1 - Lens assembly (MIL-S-22885/52)
- 1 - Plug-in switch module
- 1 - Housing
- 4 - Lamps (T-1-3/4 midget-flange base incandescent type). Not included, order separately.

Operating force: 3.5 ± 1.0 pounds.

FIGURE 102-17. Switches, push button, illuminated, 4-lamp, square, RFI shielded, modular construction (MIL-S-22885/86).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



INCHES	MM	INCHES	MM
.022	.56	.090	2.29
.034	.86	.18	4.57
.036	.91	.50	12.70

PLUG-IN SWITCHES, INDICATORS, AND HOUSINGS			
Part No. M22885/86- Circuit		Part	Switch action
4PDT	2PDT		
001	003	Plug-in switch	Momentary
002	004	Plug-in switch	Alternate
005		Plug-in indicator	---
Terminal		Part	RFI shielded
Type S	Type W		
006	098	Housing	No
007	099	Housing	Yes

SWITCH ASSEMBLIES WITHOUT LENS					
Part No. M22885/86-				Terminal type	RFI shielded
4PDT		2PDT			
Momentary	Alternate	Momentary	Alternate		
008	009	010	011	S	No
013	014	015	016	S	Yes
100	101	102	103	W	No
105	106	107	108	W	Yes

INDICATOR ASSEMBLIES WITHOUT LENS		
Part No. M22885/86-	Terminal type	RFI shielded
012	S	No
017	S	Yes
104	W	No
109	W	Yes

FIGURE 102-17. Switches, push button, illuminated, 4-lamp, square, RFI shielded, modular construction (MIL-S-22885/86) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

COMPLETE SWITCH ASSEMBLY										
1/ Part No. M22885/86- Lens code								Terminal type	RFI shielded	
A	B	C	D	E	F	G	H			
018	019	020	021	022	023	024	025	S	No	4PDT momentary
026	027	028	029	030	031	032	033	S	Yes	4PDT momentary
034	035	036	037	038	039	040	041	S	No	4PDT alternate
042	043	044	045	046	047	048	049	S	Yes	4PDT alternate
050	051	052	053	054	055	056	057	S	No	2PDT momentary
058	059	060	061	062	063	064	065	S	Yes	2PDT momentary
066	067	068	069	070	071	072	073	S	No	2PDT alternate
074	075	076	077	078	079	080	081	S	Yes	2PDT alternate
110	111	112	113	114	115	116	117	W	No	4PDT momentary
118	119	120	121	122	123	124	125	W	Yes	4PDT momentary
126	127	128	129	130	131	132	133	W	No	4PDT alternate
134	135	136	137	138	139	140	141	W	Yes	4PDT alternate
142	143	144	145	146	147	148	149	W	No	2PDT momentary
150	151	152	153	154	155	156	157	W	Yes	2PDT momentary
158	159	160	161	162	163	164	165	W	No	2PDT alternate
166	167	168	169	170	171	172	173	W	Yes	2PDT alternate
COMPLETE INDICATOR ASSEMBLY										
082	083	084	085	086	087	088	089	S	No	
090	091	092	093	094	095	096	097	S	Yes	
174	175	176	177	178	179	180	181	W	No	
182	183	184	185	186	187	188	189	W	Yes	

1/ Part numbers are for units without color filters. The color symbols of MIL-S-22885 will be added following the dash number in the sequence shown in Lens Style diagram.

LENS CODE	LENS STYLE	COLOR SYMBOL POSITION
A	4 - WAY SPLIT	
B	3 - WAY SPLIT	
C	SPLIT HORIZONTALLY	
D	SOLID	
E	3 - WAY SPLIT	
F	SPLIT VERTICALLY	
G	3 - WAY SPLIT	
H	3 - WAY SPLIT	

FIGURE 102-17. Switches, push button, illuminated, 4-lamp, square, RFI shielded, modular construction (MIL-S-22885/86) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

SECTION 103


SWITCHES, INTERLOCK

(Applicable specification: MIL-S-8805)


TABLE 103.I Switches, interlock, parameters and characteristics.

Figure number	Applicable specification sheet	Part number	Operating characteristics				Shock	Vibration	Temperature
			Switch action	Approximate plunger travel		Switch circuit			
				Push	Pull				
				(inch)	(inch)		(G)	(Hz)	(° C)
103-1	MIL-S-8805/56	MS16106-1	Push-pull	.250	.187	SPDT	50	10 to 500	-55 to +85
		MS16106-2	Push-pull	.250	.187	DPDT			
		MS16106-3	Push-pull	.250	.188	4PDT			
		MS16106-4	Push-pull	.156	.156	SPDT			
		MS16106-5	Push-pull	.250	.187	DPDT			


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



MS16106-1



MS16106-2



MS16106-3

FIGURE 103-1. Switch assemblies, sensitive, interlock.


Supersedes page 103.2
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

SECTION 104A

SWITCHES, MULTISTATION
(Applicable specification: MIL-S-24317)


FIGURE NUMBER	APPLICABLE SPECIFICATION SHEET	SWITCH CHARACTERISTICS				PAGE
		Switch module	Type	Operation	Circuit	
104-1	MIL-S-24317/9	MIL-S-22885/86	Illuminated	Momentary and alternate	2PDT 4PDT	104.2



Supersedes Section 104
(page 104.1 of 23 March 1976)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)	
	28 Vdc	115 Vac
Resistive	2.0	2.0
Inductive	1.0	1.0
Lamp	0.75	0.75




Terminals 8 thru 13 are omitted for 2PDT configurations.

FLANGE ARRANGEMENT FOR RFI SHIELDING

FIGURE 104-1. Switches, multistation, illuminated, matrix arrangement for (MIL-S-24317/9).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



INCHES	MM
.022	.56
.034	.86
.036	.91
.090	2.29
.18	4.57
.50	12.70

OPERATING FORCE: 3.5 ±1.0 pounds.

PART NUMBER: Part numbers in the tabulation are for matrix frame with flanges and receptacles and do not include the switch/indicator or lens assemblies (see MIL-S-22885/86 and /52).

Without RFI shielding			With RFI shielding			No. of stations	Dimension	
Part No. M24317/9-		No. of flanges	Part No. M24317/9-		No. of flanges		A ±.015 (.38)	B ±.015 (.38)
Type S	Type W		Type S	Type W				
001	011	2V	021	031	2V2H	1	.755 (19.18)	.755 (19.18)
002	012		022	032		2	1.510 (38.35)	
003	013		023	033		3	2.265 (57.53)	
004	014		024	034		4	3.020 (76.71)	
005	015		025	035		5	3.775 (95.89)	
006	016		026	036		6	4.530 (115.06)	
007	017	2H	027	037		7	5.285 (134.24)	
008	018		028	038		8	6.040 (153.42)	
009	019		029	039		9	6.795 (172.59)	
010	020		030	040		10	7.550 (191.77)	
041	051	2V	061	071		2	.755 (19.18)	1.510 (38.35)
042	052		062	072		4	1.510 (38.35)	
043	053		063	073		6	2.265 (57.53)	
044	054		064	074		8	3.020 (76.71)	
045	055		065	075		10	3.775 (95.89)	
046	056		066	076		12	4.530 (115.06)	
047	057	2H	067	077		14	5.285 (134.24)	
048	058		068	078		16	6.040 (153.42)	
049	059		069	079		18	6.795 (172.59)	
050	060		070	080		20	7.550 (191.77)	

FIGURE 104-1. Switches, multistation, illuminated, matrix arrangement for (MIL-S-24317/9) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

SECTION 106


SWITCHES, PUSH BUTTON
(Applicable specification: MIL-S-8805)

FIGURE NUMBER	SWITCH CHARACTERISTICS				PAGE
	Specification sheet	Operation	Circuit	Electrical ratings at 28 Vdc	
				(amperes)	
106-1	MIL-S-8805/3	Momentary and push-pull	Single circuit and 2 circuit	10 resistive	106.2
106-2	MIL-S-8805/20	Momentary	2 circuit	1 inductive at 120 Vdc, .07 Henry load	106.4
106-3	MIL-S-8805/23	Momentary	2PDT 4PDT	5 resistive	106.5
106-4	MIL-S-8805/25	Alternate	2PDT 4PDT	5 resistive	106.6
106-5	MIL-S-8805/38	Momentary	4 circuit	4 resistive	106.7
106-6	MIL-S-8805/55	Momentary-foot operated	2PST	.75 inductive	106.8
106-7	MIL-S-8805/95	Momentary	2PDT	1 resistive	106.9
106-8	MIL-S-8805/96	Momentary	SPST	5 resistive	106.10
106-9	MIL-S-8805/99	Momentary and alternate	2 circuit and DPDT	2 resistive	106.11


Supersedes page 106.1
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		50,000 feet
	28 Vdc	115 Vac, 60/400 Hz	28 Vdc
Resistive - - -	10	10	---
Inductive - - -	5	5	5
Lamp- - - - - -	3	3	---



TYPE A TYPE B TYPE C *



TYPE E TYPE F * TYPE G * TYPE H *



INCHES	MM
.062	1.57
.086	2.18
.156	3.96
.312	7.92
.375	9.53
.438	11.13
.562	14.27
.623	15.82
.625	15.88
.688	17.48
.739	18.77
.875	22.23
1.375	34.93

*Button style illustrated is for momentary action switches; push-pull configuration is shown below.

FIGURE 106-1. Switches, push button, dusttight (MIL-S-8805/3).

Supersedes page 106.2
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

MOMENTARY ACTION SWITCHES

1/ Part No. MS25089-


Type A Button color			Type B Button color			Type C Button color			Type E Button color			Type F Button color			Type G Button color			Type H Button color			Switch circuit
Black	Red	White	Black	Red	White	Black	Red	White	Black	Red	White	Black	Red	White	Black	Red	White	Black	Red	White	
1A	1AR	1AW	1B	1BR	1BW	1C	1CR	1CW	1E	1ER	1EW	1F	1FR	1FW	1G	1GR	1GW	1H	1HR	1HW	NO
2A	2AR	2AW	2B	2BR	2BW	2C	2CR	2CW	2E	2ER	2EW	2F	2FR	2FW	2G	2GR	2GW	2H	2HR	2HW	NC
3A	3AR	3AW	3B	3BR	3BW	3C	3CR	3CW	3E	3ER	3EW	3F	3FR	3FW	3G	3GR	3GW	3H	3HR	3HW	2 Circuit
4A	4AR	4AW	4B	4BR	4BW	4C	4CR	4CW	4E	4ER	4EW	4F	4FR	4FW	4G	4GR	4GW	4H	4HR	4HW	3 Term NO
5A	5AR	5AW	5B	5BR	5BW	5C	5CR	5CW	5E	5ER	5EW	5F	5FR	5FW	5G	5GR	5GW	5H	5HR	5HW	3 Term NC
PUSH-PULL SWITCHES																					
None			None			1C-1 2C-1 3C-1 4C-1 5C-1	1CR-1 2CR-1 3CR-1 4CR-1 5CR-1	1CW-1 2CW-1 3CW-1 4CW-1 5CW-1	None			1F-1 2F-1 3F-1 4F-1 5F-1	1FR-1 2FR-1 3FR-1 4FR-1 5FR-1	1FW-1 2FW-1 3FW-1 4FW-1 5FW-1	1G-1 2G-1 3G-1 4G-1 5G-1	1GR-1 2GR-1 3GR-1 4GR-1 5GR-1	1GW-1 2GW-1 3GW-1 4GW-1 5GW-1	1H-1 2H-1 3H-1 4H-1 5H-1	1HR-1 2HR-1 3HR-1 4HR-1 5HR-1	1HW-1 2HW-1 3HW-1 4HW-1 5HW-1	NO NC 2 Circuit 3 Term NO 3 Term NC


1/ Examples of part numbers:
MS25089-4C = Switch, Push, Dusttight, 3 Terminal (NO), Type C, Momentary, Black Button.
MS25089-4CR-1 = Switch, Push, Dusttight, 3 Terminal (NO), Type C, Push-Pull, Red Button.

OPERATING CHARACTERISTICS:
Total plunger travel - - - - - - - - - - - - - - - - .085 inch ±.015.
Operating force:
Momentary - 4 pounds ±1 pound.
Push pull - 1/2 to 2 pounds.
Releasing force - - - - - - - - - - - - - - - - - - 1 pound minimum, momentary.

FIGURE 106-1. Switches, push button, dusttight (MIL-S-8805/3) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.





INCHES	MM
.031	.79
.187	4.75
.250	6.35
.390	9.91
.500	12.70
.562	14.27
.652	16.56
1.250	31.75


ELECTRICAL RATINGS	ENDURANCE
Inductive	
(amperes)	(cycles)
15 at 0.5 power factor (120 Vac, 60 Hz)	40,000
1 at 0.07 Henry (120 Vdc)	40,000
0.05 at 2 Henries (230 Vdc)	5,000

OPERATING CHARACTERISTICS:
Actuating force: 3-1/2 ±1 pounds.
Total travel: .085 inch approximately.

PART NUMBER: MS16712-1.

FIGURE 106-2. Switch, push, momentary, 2 circuit, unsealed (MIL-S-8805/20).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



SCHEMATIC DIAGRAM

INCHES	MM
.13	3.30
.136	3.45
.156	3.96
.282	7.16
.469	11.91
1.297	32.91

LOAD	ELECTRICAL RATINGS	
	28 Vdc	115 Vac, 60 Hz
	ampere	ampere
Resistive - - -	1	1
Inductive - - -	1	1

OPERATING CHARACTERISTICS:
Total plunger travel: .093 inch minimum.
Operating force: 1.50 ±.75 pounds.


PART NUMBER: See following tabulation.

Part number M8805/95-	Button color	Case color	Hex nut
001	Black	Clear	MS25082-14
002	Red	Clear	MS25082-14
003	Black	Black	MS25082-B14
004	Red	Black	MS25082-B14

FIGURE 106-7. Switches, push, 2PDT, momentary, 1 ampere, unsealed (MIL-S-8805/95).

Supersedes page 106.9
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



INCHES	MM
.136	3.45
.282	7.16
.343	8.71
1.046	26.50

CIRCUIT DIAGRAM



LOAD	ELECTRICAL RATINGS	
	28 Vdc	115 Vac, 60 Hz
	amperes	amperes
Resistive - - -	5.0	5.0
Inductive - - -	2.0	2.0

OPERATING CHARACTERISTICS:
Total plunger travel: .095 ±.015 inch.
Operating force:
Unsealed: 1.50 ±.5 pounds.
Dusttight: 1.75 ±.5 pounds.


PART NUMBER: See following tabulation.

Part number M8805/96-	Plunger cap color	Circuit characteristics	Case color	Hex nut	Enclosure design
001	Red	SPST-NO	Clear	MS25082-14	1 (unsealed)
002	Black	SPST-NO	Clear	MS25082-14	1 (unsealed)
003	Red	SPST-NC	Clear	MS25082-14	1 (unsealed)
004	Black	SPST-NC	Clear	MS25082-14	1 (unsealed)
005	Red	SPST-NO	Black	MS25082-B14	1 (unsealed)
006	Black	SPST-NO	Black	MS25082-B14	1 (unsealed)
007	Red	SPST-NC	Black	MS25082-B14	1 (unsealed)
008	Black	SPST-NC	Black	MS25082-B14	1 (unsealed)
009	Red	SPST-NO	Clear	MS25082-14	2 (dusttight)
010	Black	SPST-NO	Clear	MS25082-14	2 (dusttight)
011	Red	SPST-NC	Clear	MS25082-14	2 (dusttight)
012	Black	SPST-NC	Clear	MS25082-14	2 (dusttight)
013	Red	SPST-NO	Black	MS25082-B14	2 (dusttight)
014	Black	SPST-NO	Black	MS25082-B14	2 (dusttight)
015	Red	SPST-NC	Black	MS25082-B14	2 (dusttight)
016	Black	SPST-NC	Black	MS25082-B14	2 (dusttight)

FIGURE 106-8. Switches, push, momentary, SPST, 5 amperes (MIL-S-8805/96).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

INCHES	MM	INCHES	MM
.002	.05	.442	11.23
.003	.08	.449	11.40
.005	.13	.468	11.89
.048	1.22	.469	11.91
.050	1.27	.50	12.70
.16	4.06	.62	15.75
.19	4.83	.75	19.05
.28	7.19	.88	22.35
.344	8.74	1.16	29.46
.44	11.18		



Circuit schematic.

FIGURE 106-9. Switches, push, 2 circuit and DPDT, alternate and momentary action, 2 amperes, dripproof (MIL-S-8805/99).

Supersedes page 106.11
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS	
	Sea level	70,000 feet
	28 Vdc 115 Vac, 400 Hz	28 Vdc
	(amperes)	(amperes)
Resistive - - -	2.0	2.0
Inductive - - -	1.5	1.5
Lamp- - - - - -	0.5	0.5

OPERATING CHARACTERISTICS:
Actuating force: 4 ±1 pounds.
Plunger travel: .160 inch maximum.

PART NUMBER: See following tabulation.

Part number	Dress ring	Switch action	Switch circuit	Button color
M8805/99-001	A	Alternate action	2 circuit	Black
-002	B	Alternate action	2 circuit	Black
-003	C	Alternate action	2 circuit	Black
-004	None	Alternate action	2 circuit	Black
-005	A	Alternate action	2 circuit	Red
-006	B	Alternate action	2 circuit	Red
-007	C	Alternate action	2 circuit	Red
-008	None	Alternate action	2 circuit	Red
-009	A	Momentary	2 circuit	Black
-010	B	Momentary	2 circuit	Black
-011	C	Momentary	2 circuit	Black
-012	None	Momentary	2 circuit	Black
-013	A	Momentary	2 circuit	Red
-014	B	Momentary	2 circuit	Red
-015	C	Momentary	2 circuit	Red
-016	None	Momentary	2 circuit	Red
-017	A	Alternate action	DPDT	Black
-018	B	Alternate action	DPDT	Black
-019	C	Alternate action	DPDT	Black
-020	None	Alternate action	DPDT	Black
-021	A	Alternate action	DPDT	Red
-022	B	Alternate action	DPDT	Red
-023	C	Alternate action	DPDT	Red
-024	None	Alternate action	DPDT	Red
-025	A	Momentary	DPDT	Black
-026	B	Momentary	DPDT	Black
-027	C	Momentary	DPDT	Black
-028	None	Momentary	DPDT	Black
-029	A	Momentary	DPDT	Red
-030	B	Momentary	DPDT	Red
-031	C	Momentary	DPDT	Red
-032	None	Momentary	DPDT	Red

FIGURE 106-9. Switches, push, 2 circuit and DPDT, alternate and momentary action, 2 amperes, dripproof (MIL-S-8805/99) - Continued.

Supersedes page 106.12
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

SECTION 107

SWITCHES, ROTARY
(Applicable specifications: MIL-S-3786, MIL-S-6807, and MIL-S-15291)


FIGURE NO.	SWITCH CHARACTERISTICS						PAGE
	Style	Specification sheet No. or specification No.	Section size, excluding terminals (inches)	Type of construction	Current rating (amperes)	Shaft	
107-1	SR01 SR02 SR03 SR09 SR10	MIL-S-3786/1 MIL-S-3786/2 MIL-S-3786/3 MIL-S-3786/9 MIL-S-3786/10	2.094 max dia 1.594 max dia 1.375 max dia 2.344 max dia 2.328 max dia	Open	1/2	Single	107.2
107-2	SR14 SR15	MIL-S-3786/14 MIL-S-3786/15	1.750 square 2.531 square max	Open	1/2	Single	107.3
107-3	SR05	MIL-S-3786/5	1.047 max dia	Open	1/5	Single	107.4
107-4	SR31	MIL-S-3786/31	1.05 max dia	Open	1/4	Single (lever actuated)	107.6
107-5	SR28	MIL-S-3786/28	1.328 max dia	Open	1	Single	107.8
107-6	SR19	MIL-S-3786/19	.500 dia	Closed	1/10	Single	107.9
107-7	SR20	MIL-S-3786/20	.500 dia	Closed	1/5	Single	107.10
107-8	SR25	MIL-S-3786/25	1.50 dia	Closed	1/5	Single (key operated)	107.11
107-9	SR35	MIL-S-3786/35	.562 dia	Closed	1/5	Single	107.12
107-10	SR37	MIL-S-3786/37	.500 dia	Closed	1/5	Single	107.14
107-11	SR36	MIL-S-3786/36	1.350 dia (15°) 1.190 dia (18° & 22-1/2°)	Closed	1/4	Single	107.16
107-12	SR13	MIL-S-3786/13	.800 max dia (including terminals)	Closed	1/2	Single	107.20
107-13	SR04-1 SR04-2 SR04-3	MIL-S-3786/4	1.306 max dia (including terminals)	Closed	2	Single Concentric ADD-A-POT	107.23
107-14	---	MIL-S-6807	1.950 max dia (including terminals)	Closed	5	Single	107.29
107-15	SR41	MIL-S-3786/41	.765 max dia	Closed	1/2	Single	107.30
107-16	SR40	MIL-S-3786/40	1.781 square max	Open	Low level & 1/2	Single	107.32

NOTES:
1. For the styles listed under MIL-S-3786, the following variations are considered standard:
   (a) Operating-shaft length, diameter, shape, and special construction.
   (b) Deck-to-deck spacing dimensions.
   (c) Optional assemblies, such as spring return and push-to-turn actions.
   (d) Terminal angles.
   (e) Bushing thread size and diameter, and thread length.
   (f) Addition of a shield.
2. Standard switches are to be established for MIL-S-15291.

Supersedes page 107.1
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (milliamperes)			
	28 Vdc	115 Vrms		300 Vrms
		SR01 & 03	SR02, 09, & 10	
Resistive:				
At atmospheric pressure - - - - - -	500	225	250	50
At reduced barometric pressure- - -	350	100	100	---
Inductive (2.8 Henries):				
At atmospheric pressure - - - - - -	50	---	---	---




STYLE	PROCUREMENT DOCUMENT	DIMENSIONS			
		A max	B max	C max	D nom
SR01	MIL-S-3786/1	2.094 (53.19)	2.328 (59.13)	1.188 (30.20)	.750 (19.05)
SR02	MIL-S-3786/2	1.594 (40.49)	1.750 (44.45)	1.188 (30.20)	.500 (12.70)
SR03	MIL-S-3786/3	1.375 (34.93)	1.625 (41.28)	1.062 (26.97)	.500 (12.70)
SR09	MIL-S-3786/9	2.344 (59.54)	2.062 (52.37)	1.312 (33.32)	.500 (12.70)
SR10	MIL-S-3786/10	2.328 (59.13)	2.625 (66.68)	1.312 (33.32)	.500 (12.70)

NOTES:
1. For shipboard applications, switches must withstand the high impact shock test of MIL-S-3786.
2. Mounting brackets are recommended for switches that protrude over 3.50 inches (88.90 mm) behind panel or have more than five sections.
3. These switches are identified by a type designation (see MIL-S-3786).

FIGURE 107-1. SR01, SR02, SR03, SR09, and SR10 switches, rotary, open construction, 1/2 ampere, single shaft (MIL-S-3786/1, /2, /3, /9, and /10).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)	
	28 Vdc	115 Vac, 400 Hz
Resistive	5	5
Inductive	5	---
Lamp	2	---
Power factor, 50%	---	3




Number of wafers	Part number	
	Shock method I	Shock methods I and II
1	MS25002-1	MS25002-12
2	MS25002-2	MS25002-22
3	MS25002-3	MS25002-32
4	MS25002-4	MS25002-42
5	MS25002-5	MS25002-52
6	MS25002-6	MS25002-62

FIGURE 107-14. Switches, rotary, closed construction, 5 amperes, single shaft (MIL-S-6807).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS (milliamperes)	
	28 Vdc	115 Vrms, 60 Hz
Resistive:		
At atmospheric pressure	125 to 500	75 to 500
At reduced barometric pressure	50	20
Inductive (2.8 Henries):		
At atmospheric pressure	50 to 250	---
At reduced barometric pressure	10	---



INCHES	MM	INCHES	MM
.125	3.18	.700	17.78
.300	7.62	.750	19.05
.312	7.92	.765	19.43
.375	9.52	.800	20.32
.670	17.02		

"E" CONSTRUCTION STYLE

(EXPLOSION-PROOF, CLOSED CONSTRUCTION WITHOUT SEALED SHAFT AND BUSHING)



"F" CONSTRUCTION STYLE

(EXPLOSION-PROOF, CLOSED CONSTRUCTION WITH SEALED SHAFT AND BUSHING)

FIGURE 107-15. SR41 switches, rotary, closed construction, 1/2 ampere, single shaft (MIL-S-3786/41).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER: Consists of "M3786/41" followed by a dash and a four-character code. The four-character code used in the following example identifies a switch of construction style E, 30° angle of throw, 1 pole per deck, temperature-life characteristic B, three positions; the switch has two decks with nonshorting switching characteristics and three decks with shorting switching characteristics. (NOTE: Switches with both nonshorting and shorting decks have the nonshorting decks in front (nearer the panel).)

EXAMPLE: M3786/41- A B C D

- A — CONSTRUCTION STYLE, ANGLE OF THROW, AND NUMBER OF POLES PER DECK (see table I)
- B — TEMPERATURE-LIFE CHARACTERISTIC AND NUMBER OF POSITIONS (see table II)
- C — NUMBER OF DECKS WITH NONSHORTING SWITCHING CHARACTERISTICS (see table III)
- D — NUMBER OF DECKS WITH SHORTING SWITCHING CHARACTERISTICS (see table IV)

TABLE I. Code characters for construction style, angle of throw, and number of poles per deck.

	Poles per deck					Angle of throw
	1	2	3	4	6	
CONSTRUCTION STYLE E						
Code - - -	A	B	C	D	E	30°
Code - - -	F	G	--	--	--	36°
Code - - -	H	J	--	K	--	45°
Code - - -	L	M	N	--	--	60°
CONSTRUCTION STYLE F						
Code - - -	P	Q	R	S	T	30°
Code - - -	U	V	--	--	--	36°
Code - - -	W	X	--	Y	--	45°
Code - - -	Z	8	9	--	--	60°

TABLE II. Code letters for temperature-life characteristic and number of positions.

	Number of positions												Temperature-life characteristic
	2	3	4	5	6	7	8	9	10	11	12	C 1/	
Code - - -	A	B	C	D	E	F	G	H	J	K	L	M	B
Code - - -	N	P	Q	R	S	T	U	V	W	X	Y	Z	C

1/ Switch is continuous rotation type (no stops), and number of positions is dependent on angle of throw: 12 positions for 30° angle of throw; 10 positions for 36° angle of throw; 8 positions for 45° angle of throw; and 6 positions for 60° angle of throw.

TABLE III. Code letters for number of decks with nonshorting switching characteristics.

Code	Number of decks with nonshorting switching	Code	Number of decks with nonshorting switching	Code	Number of decks with nonshorting switching
A - - -	0	E - - -	4	J - - -	8
B - - -	1	F - - -	5	K - - -	9
C - - -	2	G - - -	6	L - - -	10
D - - -	3	H - - -	7		


TABLE IV. Code letters for number of decks with shorting switching characteristics.


Code	Number of decks with shorting switching	Code	Number of decks with shorting switching	Code	Number of decks with shorting switching
A - - -	0	E - - -	4	J - - -	8
B - - -	1	F - - -	5	K - - -	9
C - - -	2	G - - -	6	L - - -	10
D - - -	3	H - - -	7		

FIGURE 107-15. SR41 switches, rotary, closed construction, 1/2 ampere, single shaft (MIL-S-3786/41) - Continued.

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD (At atmospheric pressure)	ELECTRICAL RATINGS (milliamperes)		
	28 Vdc	115 Vrms	300 Vrms
Resistive - - - - - - - - - - -	500	125	50
Inductive (2.8 Henries) - - -	50	---	---





1. Common terminal #1.
2. Common terminal #2.
3. Common terminal #3.
4. Common terminal #4. Common #1 (only) required for one pole switch. Commons #1 and #2 (only) required for two pole switch. Commons #1, #2, #3 and #4, required for four pole switch.

PRINTED CIRCUIT BOARD PIN TERM.

INCHES	MM	INCHES	MM	INCHES	MM	INCHES	MM	INCHES	MM
.001	.03	.031	.79	.250	6.35	.531	13.49	.797	20.24
.003	.08	.040	1.02	.300	7.62	.563	14.30	1.000	25.40
.007	.18	.050	1.27	.310	7.87	.578	14.68	1.375	34.92
.010	.25	.060	1.52	.312	7.92	.688	17.48	1.438	36.53
.015	.38	.125	3.18	.375	9.52	.755	19.18	1.750	44.45
.020	.51	.216	5.49	.392	9.96				

FIGURE 107-16. SR40 switches, rotary, open construction, low level and 1/2 ampere (MIL-S-3786/40).

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER: Consists of "M3786/40" followed by a dash and a three-character code. The three-character code used in the following example identifies a switch of construction type S, 30° angle of throw, with nonshorting switching characteristic; 3 decks, 1 pole per deck, solder-lug terminals, and has 10 positions.

EXAMPLE: M3786/40- M C K

CONSTRUCTION TYPE, ANGLE OF THROW, AND SWITCHING CHARACTERISTIC (see table I)

NUMBER OF DECKS, NUMBER OF POLES PER DECK, AND TYPE OF TERMINALS (see table II)

NUMBER OF POSITIONS (see table III)

TABLE I. Code letters for construction type, angle of throw, and switching characteristic.

	Construction type		Angle of throw	Switching characteristic
	N	S		
Code - - -	A	G	11.25°	S
Code - - -	B	H	15°	S
Code - - -	C 1/	J 1/	22.5°	S
Code - - -	D 1/	K 1/	30°	S
Code - - -	E	L	22.5°	NS
Code - - -	F	M	30°	NS

1/ Adjacent terminals must be connected together in pairs to obtain shorting characteristic.

TABLE II. Code characters for number of decks, number of poles per deck, and type of terminals.

	Number of decks										Poles per deck	Type of terminals
	1	2	3	4	5	6	7	8	9	10		
Code - - -	A	B	C	D	E	F	G	H	J	K	1	Solder lug
Code - - -	L	M	N	P	Q	R	-	-	-	-	2	Solder lug
Code - - -	S	T	U	V	-	-	-	-	-	-	4	Solder lug
Code - - -	W	-	-	-	-	-	-	-	-	-	1	Printed circuit (PC)
Code - - -	-	X	Y	Z	2	-	-	-	-	-	1	Rear deck PC 1/
Code - - -	3	-	-	-	-	-	-	-	-	-	2	Printed circuit
Code - - -	-	4	5	6	-	-	-	-	-	-	2	Rear deck PC 1/
Code - - -	7	-	-	-	-	-	-	-	-	-	4	Printed circuit
Code - - -	-	8	-	-	-	-	-	-	-	-	4	Rear deck PC 1/

1/ Multi-deck switches with PC terminals on the rear deck have solder lug terminals on all other decks.

TABLE III. Code characters for number of positions.

Code	Number of positions	Code	Number of positions	Code	Number of positions
A - - -	1/ Continuous	M - - -	12 (with stops)	Y - - -	23 (with stops)
B - - -	2 (with stops)	N - - -	13	Z - - -	24
C - - -	3	P - - -	14	2 - - -	25
D - - -	4	Q - - -	15	3 - - -	26
E - - -	5	R - - -	16	4 - - -	27
F - - -	6	S - - -	17	5 - - -	28
G - - -	7	T - - -	18	6 - - -	29
H - - -	8	U - - -	19	7 - - -	30
J - - -	9	V - - -	20	8 - - -	31 (with stops)
K - - -	10	W - - -	21		
L - - -	11(with stops)	X - - -	22 (with stops)		

1/ Switch is continuous rotation type (no stops), and number of positions is dependent on angle of throw: 12 positions for 30° angle; 16 positions for 22.5° angle; 24 positions for 15° angle; and 32 positions for 11.25° angle.

FIGURE 107-16. SR40 switches, rotary, open construction, low level and 1/2 ampere (MIL-S-3786/40) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

SECTION 110

SWITCHES, SENSITIVE

(Applicable specification: MIL-S-8805)

TABLE 110.I. Switches, sensitive, characteristics.

Figure number	Applicable specification sheet MIL-S-8805	Operation	Circuit	Electrical ratings (28 Vdc resistive) (amperes)	General remarks
110-1	/1	Momentary	SPDT	2	
110-2	/2	Momentary	SPDT	5	
110-3	/4	Momentary	SPDT	7	
110-4	/5	Latching - reset button	4 circuit	15	
110-5	/7	Momentary	2 circuit	10	
110-6	/8	Momentary	SPDT	4	Hermetic seal
110-7	/11	Momentary	2 circuit	10	
110-8	/14	Latching - reset button	2 circuit	10	
110-9	/15	Momentary	4 circuit	15	
110-10	/16	Latching - reset button	4 circuit	15	
110-11	/17	Latching - reset button	6 circuit	15	
110-12	/18	Momentary	6 circuit	15	
110-13	/19	Momentary	2 circuit	40	
110-14	/27	Momentary	SPST, SPDT	10	
110-15	/28	Momentary	SPDT	7.5	
110-16	/29	Momentary	SPDT double break	10	
110-17	/31	Momentary	DPDT	10	
110-18	/32	Momentary	SPDT	7	Watertight seal
110-19	/34	Latching - reset button	2 circuit	40	
110-20	/39	Momentary	2PDT 4PDT	7	Plunger - resilient seal
110-21	/40	Momentary	2PDT 2 circuit 4 circuit	4,10 15 15	Plunger - resilient seal
110-22	/41	Momentary	2PDT	5	Plunger - hermetic seal
110-23	/42	Momentary	SPDT	6	Plunger - watertight seal
110-24	/43	Momentary	2PDT 4PDT	7	Pin and roller plunger - resilient seal
110-25	/44	Momentary	SPDT	5	Resilient seal
110-26	/45	Momentary	SPDT	5	Resilient seal
110-27	/47	Momentary	SPDT	25	Hermetic seal
110-28	/48	Roller lever - self return	2PDT 2 circuit 4 circuit	5,10 15 15	Resilient seal
110-29	/49	Rotary linkage lever (nonself-return)	2PDT 2 circuit 4 circuit	4,10 15 10,15	Resilient seal
110-30	/65	Momentary	2PDT	5	Plunger - resilient seal
110-31	/68	Momentary	SPDT	7	Hermetic seal

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

TABLE 110.I. Switches, sensitive, characteristics - Continued.

Figure number	Applicable specification sheet MIL-S-8805	Operation	Circuit	Electrical ratings (28 Vdc resistive) (amperes)	General remarks
110-32	/70	Momentary	2PDT	7	Pin and roller plunger-hermetic seal 1/
			4PDT		
110-33	/72	Momentary	SPDT	7	Plunger-hermetic seal 1/
110-34	/73	Momentary	SPDT	7	Plunger-hermetic seal 1/
110-35	/74	Momentary	SPDT	7	Plunger-hermetic seal 1/
110-36	/76	Momentary	2 circuit	5	
110-37	/77	Momentary	4 circuit	10	
110-38	/78	Momentary	6 circuit	10	
110-39	/80	Momentary	2PDT	5	Plunger-hermetic seal
110-40	/84	Momentary	2 circuit	10	Watertight seal
110-41	/85	Rotary - nonself-return	2PDT	4	Resilient seal
			4PDT		
110-42	/90	Momentary	SPDT	10	
110-43	/101	Momentary	2 circuit	5	
110-44	/100	Momentary	2PDT	10	Pin and roller
			4PDT	7	Plunger-resilient seal 2/
110-45	/104	Momentary	4PDT	7	Pin and roller Plunger-resilient seal 2/

1/ Minimum current applicable.
2/ Low level circuit and icing applicable.

Supersedes page 110.2
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


Electrical ratings.

Load	Sea level, 28 Vdc		70,000 feet, 28 Vdc	
	NO or NC	2 circuit	NO or NC	2 circuit
	amperes	amperes	amperes	amperes
Resistive - - - -	8	5	8	5
Inductive - - - -	5	3	3	2
Motor - - - - - -	5	---	---	---


Operating characteristics:


Actuating force:	8 ounces maximum
Pretravel:	.035 inch maximum
Overtravel:	.004 inch minimum
Movement differential:	.010 inch minimum

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




ROLLER PLUNGER






PIN PLUNGER

INCHES	MM
.015	.38
.030	.76
.120	3.05
.250	6.35
.500	12.70
.626	15.90
.794	20.17
1.030	26.16
1.375	34.92
1.781	45.24




2PDT



4PDT

FIGURE 110-44. Switches, sensitive, plunger, resilient seal.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



INCHES	MM
.350	8.89
.800	20.32
.925	23.50
1.030	26.16
1.200	30.48
1.315	33.40

WIRE LEADS: M22759/7-20, 72^{+2}_{-0} inches long.

FIGURE 110-44. Switches, sensitive, plunger, resilient seal - Continued.

Procurement document: MIL-S-8805/100.

Electrical ratings. 1/

Load	Sea level 28 Vdc		80,000 ft. 28 Vdc	
	2 PDT	4 PDT	2 PDT	4 PDT
	Amperes	Amperes	Amperes	Amperes
Resistive	10	7	10	7
Inductive	4	2	4	2
Motor	6	4	6	4
Lamp	3	2	2	1

1/ Low level circuit applicable.

Operating characteristics:


Actuating force:	9 ±3 pounds.
Full overtravel force:	30 pounds maximum.
Releasing force:	5 pounds minimum.
Pretravel:	.070 inch maximum.
Movement differential:	.035 inch maximum.
Overtravel:	.250 inch minimum.


TABLE 110.XXVI. Part numbers and configuration.

Part number M8805/100-	Actuator	Lead wires
011	Pin plunger	Six wire leads brought out in two rows of three leads each.
012	Pin plunger	Six wire leads brought out from the bottom of the switch.
013	Roller plunger	Six wire leads brought out in two rows of three leads each.
014	Roller plunger	Six wire leads brought out from the bottom of the switch.
015	Pin plunger	Twelve wire leads brought out in two rows of six each.
016	Pin plunger	Twelve wire leads brought out from bottom of switch.
017	Roller plunger	Twelve wire leads brought out in two rows of six each.
018	Roller plunger	Twelve wire leads brought out from bottom of switch.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

INCHES	MM	INCHES	MM
.015	.38	.895	22.73
.030	.76	1.000	25.40
.120	3.05	1.100	27.94
.375	9.52	1.125	28.58
.475	12.06	1.375	34.92
.525	13.34	1.719	43.66
.850	21.59	2.0	50.80
		72.0	1828.80






M8805/104-001
PIN PLUNGER




M8805/104-002
ROLLER PLUNGER

FIGURE 110-45. Switches, sensitive, plunger, resilient seal.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.





CIRCUIT SCHEMATIC

INCHES	MM
.100	2.54
.700	17.78
.850	21.59
1.200	30.48

M8805/104-003,004
AXIAL LEAD UNITS

WIRE LEADS: M22710/7-20, 72^{+2}_{-0} inches long.

FIGURE 110-45. Switches, sensitive, plunger, resilient seal - Continued.

Procurement document: MIL-S-8805/104.

Operating characteristics:

Actuating force:	9 +3 pounds.
Full overtravel force:	30 pounds maximum.
Releasing force:	5 pounds minimum.
Pretravel:	.050 inch maximum.
Movement differential:	.030 inch maximum.
Overtravel:	.125 inch minimum.

Electrical ratings. 1/

Load	28 Vdc		115 Vac, 400 Hz	
	Sea level	80,000 ft.	Sea level	80,000 ft.
	Amperes	Amperes	Amperes	Amperes
Resistive	7	7	1	1
Inductive	3	3	1	1
Motor	4	4	1	1
Lamp	2	1	1	1

1/ Low level circuit applicable.

TABLE 110.XXVII. Part numbers.

Part number M8805/104	Actuator	Wire exit
-001	Pin plunger	Side
-002	Roller plunger	
-003	Pin plunger	Bottom
-004	Roller plunger	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

SECTION 111A

SWITCHES, THERMOSTATIC


(Applicable specifications: MIL-S-24236 and MIL-S-28827)

FIGURE NO.	SWITCH CHARACTERISTICS			PAGE
	Specification sheet number	Circuitry	Electrical rating	
111-1	MIL-S-24236/11	SPST	1 ampere	111.2
111-2	MIL-S-24236/13	SPST	1 ampere	111.4
111-3	MIL-S-24236/19	SPST	1 ampere	111.6
111-4	MIL-S-24236/20	SPST	2 amperes	111.8
111-5	MIL-S-24236/2	SPST	5 amperes	111.10
111-6	MIL-S-24236/1	SPST	5 amperes	111.12
111-7	MIL-S-24236/24	SPDT	2 amperes	111.20
111-8	MIL-S-24236/25	SPST	2 amperes	111.23
111-9	MIL-S-24236/26	SPST-SPDT	2 amperes	111.26
111-10	MIL-S-28827/1	SPDT	1 ampere	111.28


Supersedes Section 111 (pages 111.1 thru 111.23) of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS			ENDURANCE
	Sea level		70,000 ft	
	28 V	115 V, 60 Hz	28 V	
	(ampere)	(ampere)	(ampere)	(cycles)
Resistive - - -	1.0	1.0	1.0	10,000
Inductive - - -	.5	.5	.5	10,000
Lamp- - - - - -	.2	.2	.2	10,000



CONFIGURATION 1



CONFIGURATION 2




CONFIGURATION 3

INCHES	MM
.11	2.79
.14	3.56
.320	8.13
.36	9.14
.362	9.19
.39	9.91
.415	10.54
.422	10.72
.445	11.30
.50	12.70
.75	19.05
1.25	31.75
11.5	292.10
12.5	317.50

FIGURE 111-1. Switches, thermostatic (MIL-S-24236/11).

Source: https://assist.dla.mil ÷ Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



CONFIGURATION 4

INCHES	MM	INCHES	MM
.17	4.32	.565	14.35
.20	5.08	.69	17.53
.320	8.13	11.5	292.10
.535	13.59	12.5	317.50

PART NUMBER: Consists of "M24236/11" followed by a dash and a four-letter code as shown in the following example:

M24236/11- A A CD

CONFIGURATION AND CONTACT ACTION (see table I)
PROBE LENGTH (see table II)
HIGH TEMPERATURE SETTING (to nearest 25°F, table III; to nearest 5°F, table IV)

TABLE I. Configuration and contact action.

	Configuration				Contact action
	1	2	3	4	
Code - - - -	A	C	E	G	Open on increasing temperature
Code - - - -	B	D	F	H	Close on increasing temperature

TABLE II. Probe length.

Code	Dimension A (inches)
A - - - - -	1.5 (38.10)
B - - - - -	2.0 (50.80)
C - - - - -	2.5 (63.50)
D - - - - -	3.0 (76.20)
E - - - - -	4.0 (101.60)

TABLE III. High temperature setting to the nearest 25°F.

Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)
A - - -	0	F - - -	125	L - - -	250
B - - -	25	G - - -	150	M - - -	275
C - - -	50	H - - -	175	N - - -	300
D - - -	75	J - - -	200	P - - -	325
E - - -	100	K - - -	225	Q - - -	350


TABLE IV. High temperature setting to the nearest 5°F.

Code	Temperature (°F)
A - - -	-10
B - - -	-5
C - - -	0
D - - -	+5
E - - -	+10

FIGURE 111-1. Switches, thermostatic (MIL-S-24236/11) - Continued.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		ENDURANCE (cycles)
	28 Vdc	115 Vac, 60 Hz	
Resistive - -	0.5	1.0	10,000



INCHES	MM
.015	.38
.021	.53
.080	2.03
.130	3.30
.263	6.68
.575	14.61
12.000	304.80

CONFIGURATION 1



CONFIGURATION 2

FIGURE 111-2. Switches, thermostatic (MIL-S-24236/13).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER: Consists of "M24236/13" followed by a dash and a three-letter code as shown in the following example:

M24236/13- A H C

CONFIGURATION AND CONTACT ACTION (see table I)

TEMPERATURE SETTING TO WITHIN 20°F (see table II)

TEMPERATURE SETTING TO WITHIN 5°F (see table III)

TABLE I. Configuration and contact action.

	Configuration		Contact action
	1	2	
Code - - - -	A	C	Open on increasing temperature
Code - - - -	B	D	Close on increasing temperature

TABLE II. High temperature setting to within 20°F.

Code	Temperature (°F)	Code	Temperature (°F)
A - - -	-30	L - - -	170
B - - -	-10	M - - -	190
C - - -	10	N - - -	210
D - - -	30	P - - -	230
E - - -	50	Q - - -	250
F - - -	70	R - - -	270
G - - -	90	S - - -	290
H - - -	110	T - - -	310
J - - -	130	U - - -	330
K - - -	150	V - - -	350


TABLE III. High temperature setting to within 5°F.

Code	Temperature (°F)
A - - -	0
B - - -	+5
C - - -	+10
D - - -	+15


FIGURE 111-2. Switches, thermostatic (MIL-S-24236/13) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		ENDURANCE (cycles)
	28 Vdc	115 Vac, 60 Hz	
Resistive - - - - - -	0.5	1.0	10,000




CONFIGURATION 1




CONFIGURATION 2

INCHES	MM
.040	1.02
.060	1.52
.070	1.78
.093	2.36
.110	2.79
.112	2.84
.136	3.45
.156	3.96
.168	4.27
.170	4.32
.189	4.80
.203	5.16
.215	5.46
.250	6.35
.281	7.14
.290	7.37



CONFIGURATION 3



CONFIGURATION 4

NOTE: All configurations are of grounded construction. Configuration 3 has an isolated mounting stud.

FIGURE 111-3. Switches, thermostatic (MIL-S-24236/19).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER: Consists of "M24236/19" followed by a dash and a three-letter code as shown in the following example:

M24236/19- A H C

- A: CONFIGURATION AND CONTACT ACTION (see table I)
- H: HIGH TEMPERATURE SETTING TO WITHIN 20°F (see table II)
- C: HIGH TEMPERATURE SETTING TO WITHIN 5°F (see table III)

TABLE I. Configuration and contact action.

	Configuration				Contact action
	1	2	3	4	
Code - - -	A	C	E	G	Close on increasing temperature
Code - - -	B	D	F	H	Close on decreasing temperature

TABLE II. Temperature setting to within 20°F.

Code	Temperature (°F)	Code	Temperature (°F)
A - - -	-30	L - - -	170
B - - -	-10	M - - -	190
C - - -	10	N - - -	210
D - - -	30	P - - -	230
E - - -	50	Q - - -	250
F - - -	70	R - - -	270
G - - -	90	S - - -	290
H - - -	110	T - - -	310
J - - -	130	U - - -	330
K - - -	150	V - - -	350


TABLE III. Temperature setting to within 5°F.

Code	Unit
A - - -	0
B - - -	+5
C - - -	+10
D - - -	+15


FIGURE 111-3. Switches, thermostatic (MIL-S-24236/19) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS		ENDURANCE
	28 Vdc	115 Vac, 60 Hz	
	(amperes)	(amperes)	(cycles)
Resistive - - -	2.0	2.0	250,000
Inductive - - -	1.0	1.5	250,000
Lamp	1.0	0.5	250,000




CONFIGURATION A



CONFIGURATION B



CONFIGURATION C



MOUNTING BRACKET
(CONFIGURATIONS A1, B1, AND C1)

INCHES	MM	INCHES	MM
.003	.08	.171	4.34
.005	.13	.218	5.54
.007	.18	.300	7.62
.010	.25	.426	10.82
.015	.38	.453	11.51
.031	.79	.550	13.97
.063	1.60	.660	16.76
.078	1.98	.937	23.80
.104	2.64	1.477	37.52
.125	3.18	1.497	38.02

FIGURE 111-4. Switches, thermostatic (MIL-S-24236/20).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER: Consists of "M24236/20" followed by a dash and a four-letter code. The four-letter code used in the following example identifies a switch of configuration A which closes on increasing temperature at 140 ±4°F and closes on decreasing temperature 2 to 5°F below the actual closing temperature. EXAMPLE:

M24236/20- A GF B

CONFIGURATION AND CONTACT ACTION (see table I)

OPERATING TEMPERATURE (see tables II and III)

TEMPERATURE DIFFERENTIAL (see table IV)

TABLE I. Configuration and contact action.

	Configuration						Contact action
	A	A1	B	B1	C	C1	
Code - - -	A	C	E	G	J	L	Close on increasing temperature
Code - - -	B	D	F	H	K	M	Close on decreasing temperature
Code 1/- -	N	Q	S	U	W	Y	Open on increasing temperature
Code 1/- -	P	R	T	V	X	Z	Open on decreasing temperature

1/ Available tolerance is ±5°F only (see table III).

TABLE II. Temperature setting to the nearest 25°F.

Code	Temperature	Code	Temperature
	°F		°F
A - - -	0	K - - -	225
B - - -	25	L - - -	250
C - - -	50	M - - -	275
D - - -	75	N - - -	300
E - - -	100	P - - -	325
F - - -	125	Q - - -	350
G - - -	150	R - - -	375
H - - -	175	S - - -	400
J - - -	200		

TABLE III. Temperature setting to the nearest 5°F.

	Unit					Tolerance
	-10	-5	0	+5	+10	
Code - - -	A 1/	B	C	D	E	±3°F
Code - - -	F	G	H	J	K	±4°F
Code - - -	L	M	N	P	Q	±5°F

1/ Available to 250°F only.

TABLE IV. Temperature differential.

Code	Available differential	Operating temp. range
A - - -	2 - 4°F	-10° to +250°F
B - - -	2 - 5°F	
C - - -	3 - 7°F	+251° to +400°F

FIGURE 111-4. Switches, thermostatic (MIL-S-24236/20) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

INCHES	MM
.060	1.52
.360	9.14
.390	9.91
.50	12.70
.670	17.02
.990	25.15

LOAD	ELECTRICAL RATINGS		ENDURANCE
	28 V	115 V, 60 Hz	
	(amperes)	(amperes)	(cycles)
Resistive - - -	5.0	2.0	100,000
Inductive - - -	2.5	1.0	100,000
Lamp- - - - - -	1.0	0.5	100,000

INCHES	MM
1.000	25.40
1.010	25.65
1.115	28.32
1.135	28.83
12.00	304.80

NOTE: Do not use in applications where basic switch will be exposed to pressures over 250 psig.




FIGURE 111-5. Switches, thermostatic (MIL-S-24236/2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER: Consists of "M24236/2" followed by a dash and a six-letter code as shown in the following example:

M24236/2- A B G F E H

- CONFIGURATION AND CONTACT ACTION (see table I)
- PROBE LENGTH (see table II)
- HIGH TEMPERATURE SETTING (to nearest 25°F, see table III)
- HIGH TEMPERATURE SETTING (to nearest 5°F and its tolerance, see table IV)
- LOW TEMPERATURE SETTING (to nearest 25°F, see table III)
- LOW TEMPERATURE SETTING (to nearest 5°F and its tolerance, see table IV)

TABLE I. Configuration and contact action.

	Configuration				Contact action
	1	2	3	4	
Code - - -	A	C	E	G	Open on increasing temperature
Code - - -	B	D	F	H	Close on increasing temperature

TABLE II. Probe length.

Code	Dimension A ±.030 (.76) (inches)
A - - -	1.50 (38.10)
B - - -	2.00 (50.80)
C - - -	2.50 (63.50)
D - - -	3.00 (76.20)
E - - -	4.00 (101.60)

TABLE III. Temperature settings to within 25°F.

Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)
A - - -	-75	J - - -	125	S - - -	325
B - - -	-50	K - - -	150	T - - -	350
C - - -	-25	L - - -	175	U - - -	375
D - - -	0	M - - -	200	V - - -	400
E - - -	25	N - - -	225	W - - -	425
F - - -	50	P - - -	250	X - - -	450
G - - -	75	Q - - -	275	Y - - -	475
H - - -	100	R - - -	300	Z - - -	500


TABLE IV. Temperature settings to within 5°F.

	Tolerance						Unit
	±3°F	±5°F	±8°F	±10°F	±15°F	±25°F	
Code - - -	A	F	L	R	W	2	-10
Code - - -	B	G	M	S	X	3	-5
Code - - -	C	H	N	T	Y	4	0
Code - - -	D	J	P	U	Z	5	+5
Code - - -	E	K	Q	V	1	6	+10


FIGURE 111-5. Switches, thermostatic (MIL-S-24236/2) - Continued.

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS			ENDURANCE
	Sea level		80,000 feet	
	28 V	115 V, 60 Hz	28 V	
	(amperes)	(amperes)	(amperes)	(cycles)
Resistive - - -	5.0	2.0	5.0	100,000
Inductive - - -	2.5	1.0	2.5	100,000
Lamp- - - - - -	1.0	0.5	1.0	100,000




CONFIGURATION A
(MOUNTING BRACKETS NOT FURNISHED)



CONFIGURATION A1



CONFIGURATION A2




CONFIGURATION A 3


INCHES	MM	INCHES	MM	INCHES	MM	INCHES	MM
.005	.13	.071	1.80	.295	7.49	.560	14.22
.007	.18	.140	3.56	.300	7.62	.640	16.26
.010	.25	.187	4.75	.325	8.26	.937	23.80
.021	.53	.243	6.17	.395	10.03	1.190	30.23
.045	1.14	.250	6.35	.437	11.10	1.260	32.00
.070	1.78	.280	7.11	.468	11.89		

FIGURE 111-6. Switches, thermostatic (MIL-S-24236/1).


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




CONFIGURATION B
(MOUNTING BRACKETS NOT FURNISHED)




CONFIGURATION B1



CONFIGURATION B2



CONFIGURATION B3



CONFIGURATION B4

INCHES	MM	INCHES	MM	INCHES	MM
.005	.13	.187	4.75	.500	12.70
.007	.18	.250	6.35	.531	13.49
.010	.25	.280	7.11	.560	14.22
.015	.38	.295	7.49	.640	16.26
.021	.53	.300	7.62	.680	17.27
.071	1.80	.325	8.26	.937	23.80
.125	3.18	.395	10.03	1.190	30.23
.140	3.56	.468	11.89	1.260	32.00

FIGURE 111-6. Switches, thermostatic (MIL-S-24236/1) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

CONFIGURATION A

Operating points				Part No. M24236/1-	Operating points				Part No. M24236/1-
Open on incr temp	Close on decr temp	Open on decr temp	Close on incr temp		Open on incr temp	Close on decr temp	Open on decr temp	Close on incr temp	
(°F)	(°F)	(°F)	(°F)		(°F)	(°F)	(°F)	(°F)	
60 ±5	35 ±5	---	---	0105	115 ±5	80 ±7	---	---	0130
60 ±8	40 ±5	---	---	0100	165 ±5	145 ±5	---	---	0131
70 ±8	50 ±5	---	---	0110	180 ±5	160 ±5	---	---	0132
75 ±8	45 ±8	---	---	0115	215 ±5	195 ±5	---	---	0133
80 ±5	60 ±7	---	---	0120	---	---	150 ±5	170 ±7	0135
90 ±8	70 ±5	---	---	0125	---	---	275 ±10	325 ±12	0140

CONFIGURATION A1

Operating points		Part No. M24236/1-	Operating points		Part No. M24236/1-
Open on increasing temperature	Close on decreasing temperature		Open on increasing temperature	Close on decreasing temperature	
(°F)	(°F)		(°F)	(°F)	
35 ±5	15 ±5	0200	158 ±5	131 ±5	0320
37	20	0205	160 ±3	150	026
45	32	0210	160 ±5	140	0321
50	30	0214	160	145	0325
50	35	0215	167	158	0330
50	40	0220	170	158	0329
55	40	0230	170	160	0331
60	40	0250	173 ±3	149	0335
60	45	0255	173 ±5	158	0336
60	50	0245	176	160	0340
65	50	0260	180	135	0345
70	40	0262	180	170	0350
75	60	0265	185	165	0355
77	72	0590	185	170	0356
85	65	0270	190	170	0360
95	85	0275	194	176	0365
120	100	0280	200	160	0370
125	110	004	200	180	0371
125	120	0281	200	185	0372
128	112	0285	210 ±8	175	0375
131 ±3	120	024	212 ±8	192	0380
135 ±5	110 ±10	0290	230 ±5	205	0379
140	130 ±5	0295	230	220	0381
145	135	025	235	215	032
147	132	0300	250 ±8	210 ±8	0383
150	120	0304	265	180 ±5	0385
150	135	0305	270	230 ±6	0390
150	140	0306	272	220 ±6	0395
155	135	0310	275	200 ±6	0400
158	123	0315	350 ±12	310 ±10	0405
Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-	Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-
(°F)	(°F)		(°F)	(°F)	
17 ±5	31 ±5	027	50 ±5	65 ±5	0435
19	36	0410	62	77	0440
28	38	0415	80	95	0450
28	45	0420	85	95	0451
32 ±9	54 ±9	0425	86	112	0455
40 ±5	60 ±5	0430	86	120	0460

FIGURE 111-6. Switches, thermostatic (MIL-S-24236/1) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

CONFIGURATION A1					
Operating points		Part No. M24236/1-	Operating points		Part No. M24236/1-
Open on decreasing temperature	Close on increasing temperature		Open on decreasing temperature	Close on increasing temperature	
(°F)	(°F)		(°F)	(°F)	
95 ±5	115 ±7	0465	144 ±5	158 ±5	0507
110 ±8	130 ±6	0470	149 ±8	165 ±6	0510
120 ±5	130 ±5	028	150 ±5	160 ±5	0515
120	140	0475	151	167	0520
120	160	0480	165	185	0523
125 ±7	150	0485	170	200	0525
130 ±5	140	0476	174	194	0530
130 ±8	145 ±6	0490	175	190	0535
131 ±5	151 ±3	0495	176	185	0540
133	158 ±5	003	180	200	0549
140	150	0486	180	210 ±6	0545
145	155	0496	185	200 ±5	0550
135	175	0500	192	219	0555
155	175	0501	200	250	0560
138	153	0506	230 ±8	260	0565
138 ±8	153 ±6	0505			

CONFIGURATION A2					
Operating points		Part No. M24236/1-	Operating points		Part No. M24236/1-
Open on increasing temperature	Close on decreasing temperature		Open on increasing temperature	Close on decreasing temperature	
(°F)	(°F)		(°F)	(°F)	
80 ±5	60 ±5	0600	150 ±5	141 ±5	0640
80	65	0605	158	140	0645
90	75	0610	175	160	0650
100	85	0611	181	165	0655
120	111	0615	185	120	0660
130	110	0620	212 ±9	185 ±9	0665
131	116 ±7	0625	225 ±8	150 ±5	0670
140	105 ±7	0630	239 ±5	221 ±5	0675
145	130 ±5	0635	250 ±8	220 ±6	0680
145	135 ±5	0636	480 ±25	420 ±25	0684
Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-	Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-
(°F)	(°F)		(°F)	(°F)	
45 ±5	73 ±5	0685	140 ±5	155 ±5	0710
80	100 ±5	0686	140	160	0715
85	105 ±7	0690	145	160	0720
95	100 ±5	0687	160	180	0725
111	120	0695	170	185	0730
116	125	0700	175	225	0735
120	130	0701	240	255	0736
140	150 ±7	0705	200	280	0740

FIGURE 111-6. Switches, thermostatic (MIL-S-24236/1) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

CONFIGURATION A3					
Operating points		Part No. M24236/1-	Operating points		Part No. M24236/1-
Open on increasing temperature	Close on decreasing temperature		Open on increasing temperature	Close on decreasing temperature	
(°F)	(°F)		(°F)	(°F)	
50 ±5	30 ±5	0800	225 ±10	195 ±8	0830
80	55	0805	230 ±5	210 ±5	0835
158	140	001	239	221	002
170	140	0815	240	227	0836
170	150	0810	248 ±14	194 ±10	0840
190	170	0818	299 ±8	280 ±6	0845
197	177	0820	302 ±12	202 ±6	0850
212 ±8	176	0825			
Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-	Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-
(°F)	(°F)		(°F)	(°F)	
40 ±10	60 ±5	0855	165 ±5	195 ±5	0883
100 ±5	120	0860	175 ±5	205	0884
105	120	0865	180 ±6	210	0885
130	160	0871	185 ±5	210	0886
140	165	0872	195 ±5	220	0887
149	158 ±4	0870	200 ±8	230 ±8	0888
150	175 ±5	0876	205	230	0889
155	170	0875	210	240	0891
155	185	0881	220	250	0892
160	185	0882	248	266 ±6	0890
165	180	0880			

CONFIGURATION B					
Operating points		Part No. M24236/1-	Operating points		Part No. M24236/1-
Open on increasing temperature	Close on decreasing temperature		Open on increasing temperature	Close on decreasing temperature	
(°F)	(°F)		(°F)	(°F)	
75 ±5	55 ±5	0895	212 ±8	194 ±5	0935
100 ±8	85	0900	224 ±4	See 1/	0940
125 ±5	100	0905	229 ±3	199 ±5	0945
160 ±3	See 1/	0915	275 ±8	235 ±6	0948
160 ±5	40 ±5	0910	290 ±8	250 ±6	0949
176 ±3	See 1/	0920	350 ±12	310 ±10	0950
194 ±15	175 ±15	0925	420 ±15	350 ±10	0955
205 ±3	See 1/	0930			
Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-	Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-
(°F)	(°F)		(°F)	(°F)	
115 ±5	130 ±5	0960	See 2/	88 ±3	0985
173	203	0965	See 2/	124 ±3	0990
180	200	0970	See 2/	153 ±5	0995
215 ±8	250 ±8	0975	See 2/	176 ±5	1000
215 ±8	245 ±8	0980	See 2/	205 ±4	1005

1/ 9-14 below open.
2/ 9-14 below close.

FIGURE 111-6. Switches, thermostatic (MIL-S-24236/1) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

CONFIGURATION B1

Operating points: Open on increasing temperature	Operating points: Close on decreasing temperature	Part No. M24236/1-	Operating points: Open on increasing temperature	Operating points: Close on decreasing temperature	Part No. M24236/1-
(°F)	(°F)		(°F)	(°F)	
25 ±5	10 ±5	1100	160 ±5	150 ±5	1275
30	20	1105	164	149	006
43	28	1110	165	155	1280
45	30	1115	170	130 ±10	1290
50	30	1116	172	159 ±5	1295
50	35	1120	175	150	1296
50	40	1121	178	158	1305
55	40	1125	180	160	1310
See 1/	60 ±3	1130	180	165	1315
60 ±5	40 ±7	1135	185	175	1320
65	50 ±5	1140	190	175	1325
70	40	1145	190	180	1330
70	55	1150	194	180	1335
75	35 ±10	1155	196	176	1340
77	37 ±5	1159	198	170 ±7	1345
78	58	1160	200	180 ±5	1350
80	70	1165	200	185 ±5	1355
90	80	1170	205	182 ±7	1360
95	60	1175	205 ±6	230 ±8	1365
95	81	1180	207 ±8	192 ±5	1370
95	85	1185	212	150	1375
99	90	1195	215	195	1380
115	100	1200	220	176	1385
115 ±4	105 ±4	1205	220	200	1395
130 ±5	115 ±5	1210	230	210 ±6	1400
135	120	1215	239 ±6	180 ±12	1405
135	125	1220	239 ±8	209 ±6	1410
140	120	1225	240	220	1415
140	125	1230	240	230	1420
145	135 ±4	1235	250	230	1425
150	130 ±5	1240	260	230	1430
150	135 ±5	1245	260 ±5	248 ±5	1431
155	100 ±10	1250	274 ±7	194 ±15	1435
155	140 ±5	1255	275 ±7	245 ±10	1440
158	138 ±5	1260	280 ±8	250 ±6	1445
160	120 ±7	1265	320 ±7	305 ±7	1451
160	140 ±5	1270	400 ±10	350 ±10	005
Open on decreasing temperature	**Close on increasing temperature**	**Part No. M24236/1-**	**Open on decreasing temperature**	**Close on increasing temperature**	**Part No. M24236/1-**
(°F)	(°F)		(°F)	(°F)	
32 ±5	77 ±5	1455	70 ±5	100 ±5	1505
35	50	1460	70	105	1510
45	55	1465	80	100	1515
50	68	1475	85	95	1520
50 ±6	65	1470	95	105	1525
55 ±5	65	1480	105	120	1530
See 2/	66 ±3	1485	See 2/	115 ±3	1535
See 2/	87 ±3	1490	115 ±5	130 ±5	1540
68 ±5	95 ±5	1495	See 2/	124 ±3	1545
See 2/	97 ±3	1500	140 ±5	160 ±5	1550

See footnotes at end of configuration B1.

FIGURE 111-6. Switches, thermostatic (MIL-S-24236/1) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

CONFIGURATION B1					
Operating points		Part No. M24236/1-	Operating points		Part No. M24236/1-
Open on decreasing temperature	Close on increasing temperature		Open on decreasing temperature	Close on increasing temperature	
(°F)	(°F)		(°F)	(°F)	
140 ±5	165 ±5	1555	185 ±5	215 ±6	1585
140	180 ±5	1560	190	210	1590
165	175 ±4	1285	200	250	1595
145	160 ±5	1565	210 ±8	240	1600
See 3/	156 ±3	1570	230 ±8	265	1605
156 ±6	176 ±5	1575	255 ±8	300	1610
174 ±5	194	1580	305 ±10	330 ±10	1611
185 ±5	195	1581			

1/ 3-7 above close.
2/ 2-6 below close.
3/ 1-4 below close.

CONFIGURATION B2					
Operating points		Part No. M24236/1-	Operating points		Part No. M24236/1-
Open on increasing temperature	Close on decreasing temperature		Open on decreasing temperature	Close on increasing temperature	
(°F)	(°F)		(°F)	(°F)	
70 ±5	61 ±5	1700	75 ±5	125 ±5	1725
160	140	1705	96 ±5	110 ±5	1730
162	153	1706	125 ±5	140 ±5	1735
200	180	031	145 ±5	160 ±5	030
248 ±8	218 ±6	1710	240 ±8	260 ±6	1755
255 ±8	220	1715			
325 ±12	285	1720			
482 ±25	420 ±25	1723			

CONFIGURATION B3		
Operating points		Part No. M24236/1-
Open on increasing temperature	Close on decreasing temperature	
(°F)	(°F)	
75 ±8	55 ±5	1800
252 ±9	203 ±9	1805
325 ±12	275 ±12	1810

FIGURE 111-6. Switches, thermostatic (MIL-S-24236/1) - Continued.

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER (if not in tabulation): Shall consist of "M24236/1" followed by a dash and a five-letter code. The five-letter code used in the following example identifies a temperature switch of configuration A which opens on increasing temperature at 65° ±5°F and closes on decreasing temperature at 25° ±5°F EXAMPLE:




TABLE I. Configuration and contact action.

	Configuration									Contact action
	A	A1	A2	A3	B	B1	B2	B3	B4	
Code -	A	C	E	G	J	L	N	Q	S	Open on increasing temperature
Code -	B	D	F	H	K	M	P	R	T	Open on decreasing temperature

TABLE II. Temperature setting to the nearest 25°F.

Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)
A - - -	-75	J - - -	125	S - - -	325
B - - -	-50	K - - -	150	T - - -	350
C - - -	-25	L - - -	175	U - - -	375
D - - -	0	M - - -	200	V - - -	400
E - - -	25	N - - -	225	W - - -	425
F - - -	50	P - - -	250	X - - -	450
G - - -	75	Q - - -	275	Y - - -	475
H - - -	100	R - - -	300	Z - - -	500


TABLE III. Temperature setting to the nearest 5°F.

	Tolerance						Units
	±3°F	±5°F	±8°F	±10°F	±15°F	±25°F	
Code - - -	A	F	L	R	W	2	-10
Code - - -	B	G	M	S	X	3	-5
Code - - -	C	H	N	T	Y	4	0
Code - - -	D	J	P	U	Z	5	+5
Code - - -	E	K	Q	V	1	6	+10

FIGURE 111-6. Switches, thermostatic (MIL-S-24236/1) - Continued.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS			ENDURANCE
	Sea level		80,000 feet	
	28 V	115 V, 60 Hz	28 V	
	(amperes)	(amperes)	(amperes)	(cycles)
Resistive - - -	2.0	2.0	2.0	100,000
Inductive - - -	1.0	1.0	1.0	100,000
Lamp- - - - - -	0.5	0.5	0.5	100,000




CONFIGURATION A

(MOUNTING BRACKETS NOT FURNISHED)



CONFIGURATION A1




CONFIGURATION A2


INCHES	MM
.005	.13
.007	.18
.021	.53
.039	.99
.055	1.40
.070	1.78
.140	3.56
.160	4.06
.164	4.17
.265	6.73
.285	7.24
.328	8.33
.350	8.89
.405	10.29
.468	11.89
.500	12.70
.560	14.22
.640	16.26
.800	20.32
.937	23.80
1.140	28.96
1.200	30.48
1.260	32.00

FIGURE 111-7. Switches, thermostatic (MIL-S-24236/24).


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




Configuration A3 (stud mounted)




Configuration B
(MOUNTING BRACKETS NOT FURNISHED)



Configuration B1



Configuration B2



WIRING DIAGRAM

Below low temperature setting, circuit 1-2 is open.
Above high temperature setting, circuit 2-3 is open.

FIGURE 111-7. Switches, thermostatic (MIL-S-24236/24) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER: Consists of "M24236/24" followed by a dash and a five-letter code. The five-letter code used in the following example identifies a switch of configuration A which actuates at 65 ±6°F and deactuates at 25 ±6°F. EXAMPLE:




TABLE I. Configuration.

	Configuration						
	A	A1	A2	A3	B	B1	B2
Code - - -	A	B	C	D	E	F	G

TABLE II. Temperature setting to the nearest 25°F.

Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)
A- - -	-75	F- - -	50	L- - -	175	R- - -	300
B- - -	-50	G- - -	75	M- - -	200	S- - -	325
C- - -	-25	H- - -	100	N- - -	225	T- - -	350
D- - -	0	J- - -	125	P- - -	250	U- - -	375
E- - -	25	K- - -	150	Q- - -	275	V- - -	400


TABLE III. Temperature setting to the nearest 5°F.

	Unit					Tolerance
	-10	-5	0	+5	+10	
Code - - -	A	B	C	D	E	±4°F
Code - - -	F	G	H	J	K	±6°F
Code - - -	L	M	N	P	Q	±8°F
Code - - -	R	S	T	U	V	±10°F
Code - - -	W	X	Y	Z	1	±12°F

FIGURE 111-7. Switches, thermostatic (MIL-S-24236/24) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		ENDURANCE
	28 Vdc	115 Vac, 60 Hz	(cycles)
Res stive - - - -	2.0	2.0	250,000
Ind ctive - - - -	1.0	1.5	250,000
Lam - - - - - - -	1.0	0.5	250,000



INCHES	MM
.360	9.14
.390	9.91
.394	10.01
.665	16.89
.990	25.15
1.010	25.65
12.00	304.80

PART NUMBER: Consists of "M24236/25" followed by a dash and a five-letter code as shown in the following example:

M24236/25- A GF B C

- A — CONFIGURATION AND CONTACT ACTION (see table I)
- GF — CLOSING TEMPERATURE (see tables II and III)
- B — TEMPERATURE DIFFERENTIAL (see table IV)
- C — PROBE LENGTH (see table V)

FIGURE 111-8. Switches, thermostatic (MIL-S-24236/25).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




TABLE I. Configuration and contact action.

	Configuration				Contact action
	A	B	C	D	
Code - - -	A	C	E	G	Close on increasing temperature
Code - - -	B	D	F	H	Close on decreasing temperature

TABLE II. Temperature setting to the nearest 25°F.

Code	Temperature (°F)	Code	Temperature (°F)
A - - -	0	K - - -	225
B - - -	25	L - - -	250
C - - -	50	M - - -	275
D - - -	75	N - - -	300
E - - -	100	P - - -	325
F - - -	125	Q - - -	350
G - - -	150	R - - -	375
H - - -	175	S - - -	400
J - - -	200		

FIGURE 111-8. Switches, thermostatic (MIL-S-24236/25) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

TABLE III. Temperature setting to the nearest 5°F.

	Tolerance			Unit
	* ±3°F	±4°F	±5°F	
Code - - -	A	F	L	-10
Code - - -	B	G	M	-5
Code - - -	C	H	N	0
Code - - -	D	J	P	+5
Code - - -	E	K	Q	+10

*Available to 250°F only.

TABLE IV. Temperature differential.

Code	Available differential	Closing temperature range
A - - -	2-4°F	-10°F to +250°F
B - - -	2-5°F	
C - - -	3-7°F	+251°F to +400°F

TABLE V. Probe length.

Code	Length ±.030 (.76)	Code	Length ±.030 (.76)
	inches (mm)		inches (mm)
A - - -	1.5 (38.10)	F - - -	4.0 (101.60)
B - - -	2.0 (50.80)	G - - -	4.5 (114.30)
C - - -	2.5 (63.50)	H - - -	5.0 (127.00)
D - - -	3.0 (76.20)	J - - -	5.5 (139.70)
E - - -	3.5 (88.90)	K - - -	6.0 (152.40)

FIGURE 111-8. Switches, thermostatic (MIL-S-24236/25) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		ENDURANCE (cycles)
	28 Vdc	115 Vac, 60 Hz	
Resistive - - - - -	2.0	2.0	50,000
Inductive - - - - -	1.0	1.0	50,000
Lamp- - - - - - - -	0.5	0.5	50,000






FIGURE 111-9. Switches, thermostatic (MIL-S-24236/26).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



CONFIGURATION C



CONFIGURATION D

INCHES	MM
.045	1.14
.051	1.30
.170	4.32
.250	6.35
.438	11.13
.440	11.18
.562	14.27
.625	15.88
.890	22.61
2.113	53.67
2.520	64.01

OPERATING TEMPERATURE DIFFERENTIAL: 10°F to 55°F.

PART NUMBER: Consists of "M24236/26" followed by a dash and a three-letter code as shown in the following example:

M24236/26- A H C

CONFIGURATION AND CONTACT ACTION (see table I)
TEMPERATURE SETTING TO WITHIN 25°F (see table II)
TEMPERATURE SETTING TO WITHIN 5°F (see table III)

TABLE I. Configuration and contact action.

	Configuration				Contact action
	A	B	C	D	
Code - - -	A	D	G	K	SPST, close on temperature rise
Code - - -	B	E	H	L	SPST, open on temperature rise
Code - - -	C	F	J	M	SPDT

TABLE II. Operating temperature setting to the nearest 25°F.

Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)
A - - -	100	H - - -	275	Q - - -	450
B - - -	125	J - - -	300	R - - -	475
C - - -	150	K - - -	325	S - - -	500
D - - -	175	L - - -	350	T - - -	525
E - - -	200	M - - -	375	U - - -	550
F - - -	225	N - - -	400	V - - -	575
G - - -	250	P - - -	425	W - - -	600


TABLE III. Temperature setting to the nearest 5°F.

	Tolerance				Temperature (°F)
	±8°F	±10°F	±12°F	±15°F	
Code - - -	A	F	L	R	-10
Code - - -	B	G	M	S	- 5
Code - - -	C	H	N	T	0
Code - - -	D	J	P	U	+ 5
Code - - -	E	K	Q	V	+10

FIGURE 111-9. Switches, thermostatic (MIL-S-24236/26) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATING (amperes) 28 Vdc	ENDURANCE (cycles)
Resistive	.080 to 1.0	25,000



CONFIGURATION I

CONFIGURATION II

INCHES	MM
.35	8.89
.38	9.65
.68	17.27
.75	19.05
.813	20.65
1.65	41.91
1.85	46.99
3.00	76.20



ELECTRICAL RECEPTACLE

FIGURE 111-10. Switches, thermostatic (MIL-S-28827/1).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER: Consists of "M28827/1" followed by a dash and a five-letter code as shown in the following example:

M28827/1- A CD AB

- A — CONFIGURATION AND SETTING MODE (see table I)
- CD — HIGH TEMPERATURE SETTING (first code, within 20°F; second code, within 2°F (see table II)) or DIFFERENTIAL SETTING (first code, low end; second code, high end) (see table III)
- AB — LOW TEMPERATURE SETTING (first code, within 20°F; second code, within 2°F (see table II)) or DIFFERENTIAL SETTING (first code, low end; second code, high end) (see table III)

TABLE I. Configuration and setting modes.

	Configuration I	Configuration II	High setting	Low setting
Code - - -	A	J	At temperature with applicable tolerance of table II	At temperature with applicable tolerance of table II
Code - - -	B	K	At temperature with applicable tolerance of table II	By maximum or minimum temperature of table II
Code - - -	C	L	At temperature with applicable tolerance of table II	Differential (see table III)
Code - - -	D	M	By maximum or minimum temperature of table II	At temperature with applicable tolerance of table II
Code - - -	E	N	By maximum or minimum temperature of table II	By maximum or minimum temperature of table II
Code - - -	F	P	By maximum or minimum temperature of table II	Differential (see table III)
Code - - -	G	Q	Differential (see table III)	At temperature with applicable tolerance of table II
Code - - -	H	R	Differential (see table III)	By maximum or minimum temperature of table II

TABLE II. Temperature settings.

TEMPERATURE SETTINGS TO WITHIN 20 °F

Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)
A - - -	100	F - - -	200	L - - -	300	R - - -	400
B - - -	120	G - - -	220	M - - -	320	S - - -	420
C - - -	140	H - - -	240	N - - -	340	T - - -	440
D - - -	160	J - - -	260	P - - -	360	U - - -	460
E - - -	180	K - - -	280	Q - - -	380	V - - -	480
						W - - -	500

TEMPERATURE SETTINGS TO WITHIN 2°F

	Maximum, minimum, or +5°F tolerance	+10°F tolerance	+25°F tolerance	Temperature		Maximum, minimum, or +5°F tolerance	+10°F tolerance	+25°F tolerance	Temperature
Code - -	A	L	W	0	Code - -	F	R	2	10
Code - -	B	M	X	2	Code - -	G	S	3	12
Code - -	C	N	Y	4	Code - -	H	T	4	14
Code - -	D	P	Z	6	Code - -	J	U	5	16
Code - -	E	Q	1	8	Code - -	K	V	6	18

TABLE III. Differential temperature settings.

Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)
A - -	0	E - -	20	J - -	40
B - -	5	F - -	25	K - -	45
C - -	10	G - -	30	L - -	50
D - -	15	H - -	35	M - -	60
				N - -	75

FIGURE 111-10. Switches, thermostatic (MIL-S-28827/1) - Continued.

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.

SECTION 112

SWITCHES, TOGGLE
(Applicable specifications: MIL-S-3950, MIL-S-8834, and MIL-S-8805)

FIGURE AND SPEC NUMBER	MS NUMBER (see NOTE)	SWITCH CHARACTERISTICS			PAGE
		Dash No. for:		Circuit characteristics	
		3 Position	2 Position		
112-1 - MIL-S-3950	MS24523	21,27,31	22,23,26,29,30	One pole	112.3
112-2 - MIL-S-3950	MS24524	21,27,31	22,23,26,29,30	Two pole	112.4
	MS24525	21,27,31	22,23,26,29,30	Four pole	
	MS27406	1,2,3	---	Four pole	
	MS27407	1,2,3	---	Two pole	
112-3 - MIL-S-3950	* MS24658	21,27,31	22,23,26,28,29, 30,32	One pole	112.5
112-4 - MIL-S-3950	* MS24659	21,27,31	22,23,26,28,29, 30,32	Two pole	112.6
	* MS24660	21,27,31	22,23,26,28,29, 30,32	Four pole	
	* MS27408	1,2,3	---	Two pole	
	* MS27409	1,2,3	---	Four pole	
112-5 - MIL-S-3950	MS27722	21,27,31	22,23,26,28,29, 30,32	One pole	112.7
	MS27784	21,27,31	22,23,26,28,29, 30,32	One pole	
112-6 - MIL-S-3950	MS27723	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Two pole	112.8
	MS27724	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Four pole	
112-7 - MIL-S-3950	MS27785	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Two pole	112.9
	MS27786	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Four pole	
112-8 - MIL-S-3950	* MS27782	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Two pole	112.10
	* MS27783	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Four pole	
112-9 - MIL-S-3950	* MS27788	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Two pole	112.11
	* MS27789	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Four pole	
112-10 - MIL-S-3950	* MS27781	21,27,31	22,23,26,28,29, 30,32	One pole	112.12
	* MS27787	21,27,31	22,23,26,28,29, 30,32	One pole	
112-11 - MIL-S-3950	MS27734	21,27,31	22,23,26,28,29, 30,32	One pole	112.13
112-12 - MIL-S-3950	MS27735	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Two pole	112.14
	MS27736	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Four pole	
112-13 - MIL-S-3950	* MS27737	21,27,31	22,23,26,28,29, 30,32	One pole	112.15
112-14 - MIL-S-3950	* MS27738	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Two pole	112.16
	* MS27739	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Four pole	
112-15 - MIL-S-8834	MS14001	212,272,312	222,232,242, 262,282,292,302	One pole	112.17
	MS14002	212,272,312	222,232,242, 262,282,292,302	Two pole	
	MS14003	212,272,312	222,232,242, 262,282,292,302	Four pole	


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

FIGURE AND SPEC NUMBER	MS NUMBER (see NOTE)	SWITCH CHARACTERISTICS			PAGE
		Dash No. for:		Circuit characteristics	
		3 Position	2 Position		
112-16 - MIL-S-8834	* MS21026	211,271,311	221,231,241,281	One pole	112.18
	* MS21027	211,271,311,371	221,231,241,281,381	Two pole	
112-17 - MIL-S-8834	MS21346	211,271,311	221,231,241,281	One pole	112.19
	MS21347	211,271,311	221,231,241,281	Two pole	
112-18 - MIL-S-8834	MS21350	---	321	One pole	112.20
	MS21351	---	321	One pole	
112-19 - MIL-S-8834	MS21352	331,341,351	321	Two pole	112.21
	MS21353	331,341,351	321	Two pole	
112-20 - MIL-S-8834	MS21354	211,271,311	221,231,241,281	One pole	112.22
	MS21355	211,271,311	221,231,241,281	Two pole	
112-21 - MIL-S-8834	MS21356	211,271,311	221,231,241,281	One pole	112.23
	MS21357	211,271,311	221,231,241,281	Two pole	
112-22 - MIL-S-8834	* MS24612	212,272,312	222,232,242, 262,282,292,302	One pole	112.24
	* MS24613	212,272,312	222,232,242, 262,282,292,302	Two pole	
	* MS24614	212,272,312	222,232,242, 262,282,292,302	Four pole	
112-23 - MIL-S-8834	MS24655	211,271,311	221,231,241,281	One pole	112.25
	MS24656	211,271,311	221,231,241,281	Two pole	
112-24 - MIL-S-8834	MS25306	212,272,312	222,232,242, 262,282,292,302	One pole	112.26
	MS25307	212,272,312	222,232,242, 262,282,292,302	Two pole	
	MS25308	212,272,312	222,232,242, 262,282,292,302	Four pole	
112-25 - MIL-S-8834	MS90310	211,271,311	221,231,241,281	One pole	112.27
	MS90311	211,271,311	221,231,241,281	Two pole	
112-26 - MIL-S-8805/26	*	005,006,007, 008,009,010	001,003	Two pole	112.28
		011,012,013, 014	---	Three pole	
		---	002,004	Four pole	
112-27 - MIL-S-8805/92	*	005,006,007, 008,009,010, 011,012,013, 014,015,016, 017,018	001	Two pole	112.30
		019	---	Three pole	
		---	002,003,004	Four pole	
112-28 - MIL-S-8805/93	*	001 thru 007 008 thru 014 015 thru 021 022 thru 028	--- --- --- ---	Two pole Four pole Six pole Eight pole	112.32

NOTE: The part number consists of the MS number followed by the dash number; however, an asterisk (*) indicates that the "MS" part number will require an additional letter, or an "M" part number is applicable, as shown in the figure.

Supersedes page 112.2
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)					
	Opposite keyway side	Center	Keyway side	28 Vdc and 115 Vac, 400 Hz Load			115 Vac, 60 Hz Load		
				Lamp	Resistive	Inductive	Lamp	Resistive	Inductive
-212	ON	OFF	ON	7	25	15	7	20	15
-222	ON	NONE	OFF						
-232	ON	NONE	ON						
-242	ON	OFF	NONE						
-262	ON	NONE	MOM-ON						
-272	MOM-ON	OFF	MOM-ON						
-282	NONE	OFF	MOM-ON						
-292	ON	NONE	MOM-OFF						
-302	OFF	NONE	MOM-ON						
-312	ON	OFF	MOM-ON						

1/ Applicable terminal numbers are marked on the switch.

PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-15. MS14001, MS14402, and MS14003 toggle switches, positive break, environmentally sealed, solder lug, .469 mounting bushing (MIL-S-8834).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



KEYWAY SIDE →

A LOCKED IN THREE POSITIONS	B LOCKED IN CENTER POSITION	C LOCKED IN KEYWAY SIDE	E LOCKED OUT OF CENTER POSITION
F LOCKED IN CTR POS MOM. EITHER SIDE	G LOCKED OUT OF KEYWAY SIDE, MOM. KEYWAY SIDE	H LOCKED OUT OF SIDE OPP KEYWAY, MOM. EITHER SIDE	J LOCKED OUT OF & INTO SIDE OPP KEYWAY
K LOCKED IN CTR POS, MOM. KEYWAY SIDE	L LOCKED OUT OF SIDE OPP KEYWAY, MOM. KEYWAY SIDE		


Number	Locking comb.	1/ Circuit with toggle lever in			Current capacity (amperes)						Minimum current capacity per pole 5 mV ac-dc
					Resistive load			Inductive load			
		Opposite keyway side	Center	Keyway side	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	(μA)
211	A	ON	OFF	ON	5	2	3	1	1	2	25
221	C,E	ON	NONE	OFF							
231	C,E	ON	NONE	ON							
241	J,B	ON	OFF	NONE							
271	F,H	MOM-ON	OFF	MOM-ON							
281	K	NONE	OFF	MOM-ON							
311	G,K,L	ON	OFF	MOM-ON							
2/ 371	F,H	MOM-ON	OFF	MOM-ON							
2/ 381	K	NONE	OFF	MOM-ON							

1/ Applicable terminal numbers are marked on the switch.
2/ MS21027 only.

PART NUMBER: Consists of the applicable MS number followed by the locking combination letter and the three-digit number as shown in the tabulation.

FIGURE 112-16. MS21026 and MS21027 toggle switches, positive break, lever lock, miniature, toggle sealed, solder lug, .469 mounting bushing (MIL-S-8834).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)						Life low current level switching 5 mV
				Resistive load			Inductive load			
	Opposite keyway side	Center	Keyway side	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	
										(μA)
-211	ON	OFF	ON	5	2	3	1	1	2	25
-221	ON	NONE	OFF							
-231	ON	NONE	ON							
-241	ON	OFF	NONE							
-271	MOM-ON	OFF	MOM-ON							
-281	NONE	OFF	MOM-ON							
-311	ON	OFF	MOM-ON							

1/ Applicable terminal numbers are marked on the switch.


PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-17. MS21346 and MS21347 toggle switches, positive break, miniature, toggle sealed, integrated wire terminals, .469 mounting bushing (MIL-S-8834).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



(635)
MS 21350 (.250 MOUNTING BUSHING)



(11.91)
MS 21351 (.469 MOUNTING BUSHING)


Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)						Life low current level switching 5 mV
				Resistive load			Inductive load			
	Opposite keyway side	Center	Keyway side	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	
										(μA)
-321	NONE	ON	MOM-ON	5	2	3	1	1	2	25

1/ Applicable terminal numbers are marked on the switch.


PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-18. MS21350 and MS21351 toggle switches, positive break, special circuit, miniature, toggle sealed, solder lug, single pole (MIL-S-8834).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



(635)
MS 21352 (.250 MOUNTING BUSHING)



(11.91)
MS 21353 (.469 MOUNTING BUSHING)

Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)						Life low current level switching 5 mV
				Resistive load			Inductive load			
				28 Vdc	115 Vac		28 Vdc	115 Vac		
	Opposite keyway side	Center	Keyway side		60 Hz	400 Hz		60 Hz	400 Hz	
										(μA)
-321	NONE	ON	MOM-ON	5	2	3	1	1	2	25
-331	ON	ON	ON							
-341	MOM-ON	ON	MOM-ON							
-351	ON	ON	MOM-ON							


1/ Applicable terminal numbers are marked on the switch.

PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-19. MS21352 and MS21353 toggle switches, positive break, special circuit, miniature, toggle sealed, solder lug, double pole (MIL-S-8834).

Supersedes page 112.21
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)						Life low current level switching 5 mV
				Resistive load			Inductive load			
	Opposite locking tab side	Center	Locking tab side	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	(μA)
-211	ON	OFF	ON	5	2	3	1	1	2	25
-221	ON	NONE	OFF							
-231	ON	NONE	ON							
-241	ON	OFF	NONE							
-271	MOM-ON	OFF	MOM-ON							
-281	NONE	OFF	MOM-ON							
-311	ON	OFF	MOM-ON							


1/ Applicable terminal numbers are marked on the switch.

PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-20. MS21354 and MS21355 toggle switches, positive break, miniature, toggle sealed, printed circuit board terminals, .250 mounting bushing (MIL-S-8834).

Supersedes page 112.22
~~of 23 March 1976~~

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)						Life low current level switching 5 mV
				Resistive load			Inductive load			
	Opposite keyway side	Center	Keyway side	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	(μA)
-211	ON	OFF	ON	5	2	3	1	1	2	25
-221	ON	NONE	OFF							
-231	ON	NONE	ON							
-241	ON	OFF	NONE							
-271	MOM-ON	OFF	MOM-ON							
-281	NONE	OFF	MOM-ON							
-311	ON	OFF	MOM-ON							

1/ Applicable terminal numbers are marked on the switch.











PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-21. MS21356 and MS21357 toggle switches, positive break, miniature, toggle sealed, printed circuit board terminals, .469 mounting bushing (MIL-S-8834).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



KEYWAY SIDE →

A  LOCKED IN THREE POSITIONS	B  LOCKED IN CENTER POSITION	C  LOCKED IN KEYWAY SIDE	E  LOCKED OUT OF CENTER POSITION
F  LOCKED IN CTR POS MOM. EITHER SIDE	G  LOCKED OUT OF KEYWAY SIDE, MOM. KEYWAY SIDE	H  LOCKED OUT OF SIDE OPP KEYWAY, MOM. EITHER SIDE	J  LOCKED OUT OF & INTO SIDE OPP KEYWAY
K  LOCKED IN CTR POS, MOM. KEYWAY SIDE	L  LOCKED OUT OF SIDE OPP KEYWAY, MOM. KEYWAY SIDE	M  LOCKED OUT OF SIDE OPP KEYWAY, MOM. KEYWAY SIDE	N  LOCKED OUT OF & INTO SIDE OPP KEYWAY, MOM KWY SIDE


Number	Available locking combinations	1/ Circuit with toggle lever in			Current capacity (amperes)					
					28 Vdc and 115 Vac, 400 Hz			115 Vac, 60 Hz		
		Opposite keyway side	Center	Keyway side	Load			Load		
					Lamp	Resistive	Inductive	Lamp	Resistive	Inductive
212	A	ON	OFF	ON	7	25	15	7	20	15
222	C,E	ON	NONE	OFF						
232	C,E	ON	NONE	ON						
242	J,B	ON	OFF	NONE						
262	L	ON	NONE	MOM-ON						
272	F,H	MOM-ON	OFF	MOM-ON						
282	K	NONE	OFF	MOM-ON						
292	L	ON	NONE	MOM-OFF						
302	L	OFF	NONE	MOM-ON						
312	G,K,M,N	ON	OFF	MOM-ON						

1/ Applicable terminal numbers are marked on the switch.

PART NUMBER: Consists of the applicable MS number followed by the locking combination letter and the three-digit number as shown in the tabulation.

FIGURE 112-22. MS24612, MS24613, and MS24614 toggle switches, positive break, lever lock, environmentally sealed, screw terminals, .469 mounting bushing (MIL-S-8834).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)						Life low current level switching 5 mV
				Resistive load			Inductive load			
	Opposite locking tab side	Center	Locking tab side	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	(μA)
-211	ON	OFF	ON	5	2	3	1	1	2	25
-221	ON	NONE	OFF							
-231	ON	NONE	ON							
-241	ON	OFF	NONE							
-271	MOM-ON	OFF	MOM-ON							
-281	NONE	OFF	MOM-ON							
-311	ON	OFF	MOM-ON							


1/ Applicable terminal numbers are marked on the switch.


PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-23. MS24655 and MS24656 toggle switches, positive break, miniature, toggle sealed, solder lug, .250 mounting bushing (MIL-S-8834).

Supersedes page 112.25
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.






Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)					
				28 Vdc and 115 Vac, 400 Hz			115 Vac, 60 Hz		
				Load			Load		
	Opposite keyway side	Center	Keyway side	Lamp	Resistive	Inductive	Lamp	Resistive	Inductive
-212	ON	OFF	ON	7	25	15	7	20	15
-222	ON	NONE	OFF						
-232	ON	NONE	ON						
-242	ON	OFF	NONE						
-262	ON	NONE	MOM-ON						
-272	MOM-ON	OFF	MOM-ON						
-282	NONE	OFF	MOM-ON						
-292	ON	NONE	MOM-OFF						
-302	OFF	NONE	MOM-ON						
-312	ON	OFF	MOM-ON						

1/ Applicable terminal numbers are marked on the switch.

PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-24. MS25306, MS25307, and MS25308 toggle switches, positive break, environmentally sealed, screw terminals, .469 mounting bushing (MIL-S-8834).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)						Minimum current capacity per pole 5 mV ac-dc
				Resistive load			Inductive load			
								115 Vac		
	Opposite keyway side	Center	Keyway side	28 Vdc	50 Vdc	115 Vac, 60 and 400 Hz	28 Vdc	60 Hz	400 Hz	(μA)
-211	ON	OFF	ON	5	2	3	1	1	2	25
-221	ON	NONE	OFF							
-231	ON	NONE	ON							
-241	ON	OFF	NONE							
-271	MOM-ON	OFF	MOM-ON							
-281	NONE	OFF	MOM-ON							
-311	ON	OFF	MOM-ON							

1/ Applicable terminal numbers are marked on the switch.

PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-25. MS90310 and MS90311 toggle switches, miniature, toggle sealed, solder lug, .469 mounting bushing (MIL-S-8834).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS		
	Sea level		50,000 feet
	28 Vdc	115 Vac, 60 Hz	28 Vdc
	amperes	amperes	amperes
Resistive - - -	5	5	5
Inductive - - -	3	5	2.5
Lamp- - - - - -	2.4	1.5	2.4

INCHES	MM
.060	1.52
.115	2.92
.36	9.14
.470	11.94
.500	12.70
.720	18.29
.860	21.84
.990	25.15
1.125	28.58
1.160	29.46





FIGURE A FIGURE B FIGURE C



STANDARD LEVER TAB LEVER

FIGURE 112-26. Switch assemblies, sensitive, toggle lever (with integral leaf), 5 amperes, unsealed (MIL-S-8805/26).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

TABLE I. Part numbers and characteristics.

Dash No.	Figure	Locking combination	Circuit configuration (see table II)	Switch action		
				Opposite keyway	Center	Keyway
-001	A	D	1	Main	None	Main
-002	C	D	4	Main	None	Main
-003	C	F	4	Main	None	Main
-004	C	G	4	Main	None	Main
-005	A	E	2	Mom	Main	Mom
-006	A	A	2	Main	Main	Main
-007	A	D	2	Main	Main	Main
-008	A	E	2	Main	Main	Main
-009	A	F	2	Main	Main	Main
-010	A	G	2	Main	Main	Main
-011	A	J	2	Main	Main	Main
-012	A	K	2	Main	Main	Main
-013	A	L	2	Main	Main	Main
-014	A	M	2	Main	Main	Main
-015	A	N	2	Main	Main	Main
-016	A	B	2	Mom	Main	Main
-017	A	E	2	Mom	Main	Main
-018	A	P	2	Mom	Main	Main
-019	B	A	3	Main	Main	Main

TABLE II. Circuit configuration.

Circuit configuration	Switch pole number	Circuit closed with toggle lever in		
		Opposite keyway side	Center	Keyway side
1	1	C-NC	None	C-NO
1	2	C-NC	None	C-NO
2	1	C-NO	C-NC	C-NC
2	2	C-NC	C-NC	C-NO
3	1	C-NO	C-NC	C-NC
3	2	C-NC	C-NC	C-NO
3	3	C-NO	C-NC	C-NC
4	1	C-NC	None	C-NO
4	2	C-NC	None	C-NO
4	3	C-NC	None	C-NO
4	4	C-NC	None	C-NO

OPERATING CHARACTERISTICS:
Coincidence of operating and releasing points: All poles transfer within 10 degrees of lever travel.
Locking arrangement: Positive locking is accomplished and prevents motion of the toggle lever until the locking mechanism is manually released.
Locking mechanism release: The force required to release the locking mechanism is 3 to 5 pounds.


PART NUMBER: Consists of "M8805/92" followed by the dash number shown in table I.

FIGURE 112-27. Switch assemblies, sensitive, lever lock, 5 amperes, unsealed (MIL-S-8805/92) - Continued.

Source: https://assist.dla.mil -- Downloaded: 202640-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		50,000 feet
	28 Vdc	115 Vac, 60 Hz	28 Vdc
Resistive - - - -	7.0	7.0	4.0
Inductive - - - -	4.0	7.0	2.5
Lamp- - - - - - -	2.5	2.0	2.5

INCHES	MM
.003	.08
.13	3.30
.240	6.10
.50	12.70
.670	17.02
.720	18.29
.930	23.62
1.15	29.21
1.16	29.46
1.17	29.72
1.30	33.02



Part No. M8805/93-				Operation
Type I 2PDT	Type II 4PDT	Type III 6PDT	Type IV 8PDT	
001	008	015	022	Maint-off-maint
002	009	016	023	Mom-off-maint
003	010	017	024	Maint-off-mom
004	011	018	025	Mom-off-mom
005	012	019	026	Maint-none-maint
006	013	020	027	Mom-none-maint
007	014	021	028	Maint-none-mom

FIGURE 112-28. Switch assemblies, sensitive, lever, unsealed, 7 amperes (MIL-S-8805/93)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




FIGURE 112-28. Switch assemblies, sensitive, lever, unsealed, 7 amperes (MIL-S-8805/93) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




FIGURE 202-15. Panel seal.

Intended use: Panel seal for 4 lamp, illuminated, push switch MIL-S-22885/9, and 4 lamp modular indicator light in accordance with MIL-S-22885/10.

Procurement document: MIL-S-22885/13.

Part number: M22885/13-02.

Supersedes page 202.17
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

MILITARY STANDARD

SWITCHES AND ASSOCIATED HARDWARE,
SELECTION AND USE OF

TO ALL HOLDERS OF MIL-STD-1132A:

1. THE FOLLOWING SECTIONS OF MIL-STD-1132A HAVE BEEN REVISED AND SUPERSEDE THE SECTIONS LISTED:

NEW SECTION	DATE	SUPERSEDED SECTION	DATE
102A	20 June 1977	102 (pages 102.1 thru 102.71)	23 March 1976
104A	20 June 1977	104 (page 104.1)	23 March 1976
111A	20 June 1977	111 (pages 111.1 thru 111.23)	23 March 1976

2. THE FOLLOWING PAGES OF MIL-STD-1132A HAVE BEEN REVISED AND SUPERSEDE THE PAGES LISTED:

NEW PAGE	DATE	SUPERSEDED PAGE	PAGE
103.1		(REPRINTED WITHOUT CHANGE)	23 March 1976
103.2	20 June 1977	103.2	23 March 1976
106.1	20 June 1977	106.1	23 March 1976
106.2	20 June 1977	106.2	23 March 1976
106.3	20 June 1977	106.3	23 March 1976
106.4		(REPRINTED WITHOUT CHANGE)	23 March 1976
106.9	20 June 1977	106.9	23 March 1976
106.10		(REPRINTED WITHOUT CHANGE)	23 March 1976
106.11	20 June 1977	106.11	23 March 1976
106.12	20 June 1977	106.12	23 March 1976
107.1	20 June 1977	107.1	23 March 1976
107.2		(REPRINTED WITHOUT CHANGE)	23 March 1976
107.29		(REPRINTED WITHOUT CHANGE)	23 March 1976
107.30	20 June 1977		
107.31	20 June 1977		
107.32	20 June 1977		
107.33	20 June 1977		
110.1		(REPRINTED WITHOUT CHANGE)	23 March 1976
110.2	20 June 1977	110.2	23 March 1976
110.101		(REPRINTED WITHOUT CHANGE)	23 March 1976
110.102	20 June 1977		
110.103	20 June 1977		
110.104	20 June 1977		
110.105	20 June 1977		
112.1		(REPRINTED WITHOUT CHANGE)	23 March 1976
112.2	20 June 1977	112.2	23 March 1976
112.17		(REPRINTED WITHOUT CHANGE)	23 March 1976
112.18	20 June 1977	112.18	23 March 1976
112.19	20 June 1977	112.19	23 March 1976
112.20	20 June 1977	112.20	23 March 1976
112.21	20 June 1977	112.21	23 March 1976
112.22	20 June 1977	112.22	23 March 1976
112.23	20 June 1977	112.23	23 March 1976
112.24		(REPRINTED WITHOUT CHANGE)	23 March 1976
112.25	20 June 1977	112.25	23 March 1976
112.26		(REPRINTED WITHOUT CHANGE)	23 March 1976
112.27	20 June 1977	112.27	23 March 1976
112.28		(REPRINTED WITHOUT CHANGE)	23 March 1976
112.31		(REPRINTED WITHOUT CHANGE)	23 March 1976
112.32	20 June 1977		
112.33	20 June 1977		
202.17	20 June 1977	202.17	23 March 1976

FSC 59

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

MIL-STD-1132A
NOTICE 1

20 June 1977

4. RETAIN THIS NOTICE AND INSERT BEFORE TABLE OF CONTENTS.

5. Holders of MIL-STD-1132A will verify that changes indicated above have been entered. This notice page will be retained as a check sheet. This issuance, together with appended pages, is a separate publication. Each notice is to be retained by stocking points until the Military Standard is completely revised or canceled.

Custodians:
Army - EL
Navy - EC
Air Force - 11

Review activities:
Army -
Navy -
Air Force - 85, 17
DLA - ES

User activities:
Army -
Navy - CG
Air Force -

Preparing activity:
Navy - EC

Agent:
DLA - ES

(Project 5930-1039)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

SECTION 102A

SWITCHES, PUSH BUTTON, ILLUMINATED
(Applicable specification: MIL-S-22885)


FIGURE NUMBER	APPLICABLE SPECIFICATION SHEET	SWITCH CHARACTERISTICS				PAGE
		Operation	Circuit	Electrical rating (28 Vdc resistive)	Remarks	
102-1	MIL-S-22885/8	Momentary & push-pull	2-circuit	5 amperes	Single lamp, drip-proof seal	102.2
102-1A*	MIL-S-22885/1					
102-2	MIL-S-22885/9 & MIL-S-22885/10	Momentary & alternate	2PDT & 4PDT	5 amperes	4-lamp, rectangular, modular construction	102.4
102-3	MIL-S-22885/15 & MIL-S-22885/16	Momentary & alternate	2PDT & 4PDT	5 amperes	4-lamp, rectangular, clip mounted, modular construction	102.6
102-4	MIL-S-22885/18	Momentary & alternate	2PDT & 2-circuit	2 amperes	Single lamp, drip-proof seal	102.8
102-4A*	MIL-S-22885/22					
102-4B*	MIL-S-22885/19					
102-5	MIL-S-22885/27	Momentary & alternate	4- & 8-circuit	10 amperes	Single lamp	102.10
102-5A*	MIL-S-22885/28					
102-6	MIL-S-22885/56	Momentary & alternate	2PDT & 4PDT	2 amperes	4-lamp, square, RFI shielding option	102.12
102-7	MIL-S-22885/67	Momentary & alternate	2PDT & 3PDT	7 amperes	4-lamp, square, RFI shielding option	102.14
102-8	MIL-S-22885/74	Momentary & alternate	2PDT & 4PDT	5 amperes	4-lamp, square, integrated wire termination system	102.16
102-9	MIL-S-22885/75	Momentary & alternate	2PDT, 3PDT, & 4PDT	7 amperes	4-lamp, square, RFI shielding option	102.18
102-10	MIL-S-22885/77	Momentary, alternate, & magnetic hold	2PDT, 3PDT, & 4PDT	7.5 amperes	4-lamp, square, RFI shielding option, integrated wire termination system	102.20
102-11	MIL-S-22885/79	Momentary	2PDT	7 (silver) or 1 (gold) amperes	Single lamp, drip-proof seal option	102.22
102-12	MIL-S-22885/58	Momentary & alternate	2PDT & 4PDT	3 amperes	2-lamp, rectangular	102.24
102-13	MIL-S-22885/61	Momentary & alternate	2PDT & 4PDT	5 amperes	Single lamp, drip-proof seal	102.25
102-14	MIL-S-22885/71	Momentary & alternate	2PDT	7 amperes	4-lamp, square, RFI shielded	102.26
102-15	MIL-S-22885/72 & MIL-S-22885/73	Momentary & alternate	4- & 8-circuit	10 amperes	4-lamp, square, modular construction	102.28
102-16	MIL-S-22885/80	Momentary	2PDT & 4PDT	5 amperes	4-lamp, square, RFI shielded, moisture seal, high shock	102.30
102-17	MIL-S-22885/86	Momentary & alternate	2PDT & 4PDT	2 amperes	4-lamp, square, RFI shielded, modular construction	102.32

* Applicable lens.

Supersedes Section 102 (pages 102.1 thru 102.71) of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)	
	28 Vdc	115 Vac
Resistive - - - - -	5	5
Inductive - - - - -	3	3




INCHES	MM
.25	6.35
.312	7.92
.38	9.65
.39	9.91
.44	11.18
.625	15.88
.75	19.05
.94	23.88
2.27	57.66

Switch Part No. M22885/8-		Lens (screw-in type) (see figure 102-1A)				
Momentary	Push-pull	Configuration	Color	Brightness (3/4 face) ft L	Part No. M22885/1-	Dimension "A" inch (mm)
		Switch housings without lens				
01	02	A	Yellow	225	01	.81 (20.57)
03	28		White	250	02	
04	29		Red	20	03	
05	30		Green	11	04	
06	31		Blue	7	05	
07	32	B	Yellow	150	06	.75 (19.05)
08	33		White	200	07	
09	34		Red	15	08	
10	35		Green	18	09	
11	36		Blue	4	10	
12	37	C	Yellow	300	11	.67 (17.02)
13	38		White	300	12	
14	39		Red	25	13	
15	40		Green	40	14	
16	41		Blue	10	15	
17	42	D	Yellow	150	16	.62 (15.75)
18	43		White	200	17	
19	44		Red	15	18	
20	45		Green	18	19	
21	46		Blue	4	20	
22	47	E	Yellow	120	21	.88 (22.35)
23	48		White	135	22	
24	49		Red	14	23	
25	50		Green	14	24	
26	51		Blue	2	25	
27	52					


Operating force:
Momentary - 4 + 1 pounds initial, 2.5 pounds minimum after life.
Push-pull - 1.5 pounds.
Circuit characteristics: Two circuit 1 NO.

FIGURE 102-1. Switch housings, push button, illuminated, momentary and push-pull (MIL-S-22885/8).


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



Configurations A and D



Configurations B and E



Configuration C


INCHES	MM
.312	7.92
.437	11.10
.50	12.70

FIGURE 102-1A. Screw-in lenses (MIL-S-22885/1).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		50,000 feet
	28 Vdc	115 Vac	28 Vdc
Resistive - - -	5.0	5.0	5.0
Inductive - - -	3.0	5.0	2.5
Lamp - - - - -	2.4	1.5	2.4

INCHES	MM
.050	1.27
.078	1.98
.250	6.35
.327	8.31
.625	15.88
.850	21.59
.960	24.38
1.040	26.42
1.200	30.48
1.75	44.45



Complete switch consists of:
- 1 - Indicator light module, MIL-S-22885/10 (with narrow or extended front lens plate per MIL-S-22885/85)
- 1 - Switch module, MIL-S-22885/11

Additional parts that may be ordered, if required:
- 4 - Color filters, MIL-S-22885/12
- 1 - Panel seal, MIL-S-22885/13
- 4 - Lamps (T-1-3/4 midget-flange-base incandescent type)


Operating force:
- Momentary - 4 pounds, maximum.
- Alternate - 6 pounds, maximum (2PDT) or 7 pounds, maximum (4PDT).


FIGURE 102-2. Switches, push button, illuminated, 4-lamp, solid mount (MIL-S-22885/9 and /10).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

1/ Part No. M22885/9-				Lens style code	Lamp wiring code	Indicator light module M22885/10-
Momentary		Alternate				
Switch module M22885/11		Switch module M22885/11				
-01 2PDT	-02 4PDT	-03 2PDT	-04 4PDT			
NARROW FRONT LENS PLATE, M22885/85-01						
01	02	03	04	A	1	01
09	10	11	12	B	1	03
13	14	15	16	B	2	04
17	18	19	20	C	1	05
21	22	23	24	C	3	06
25	26	27	28	A	3	07
167	168	169	170	A	2	08
EXTENDED FRONT LENS PLATE, M22885/85-02						
29	30	31	32	A	1	09
33	34	35	36	B	1	10
37	38	39	40	B	2	11
41	42	43	44	C	1	12
45	46	47	48	C	3	13
49	50	51	52	A	3	14
171	172	173	174	A	2	15
WITHOUT LENS PLATE						
53	54	55	56	A	1	16
57	58	59	60	B	1	17
61	62	63	64	B	2	18
65	66	67	68	C	1	19
69	70	71	72	C	3	20
73	74	75	76	A	3	21
175	176	177	178	A	2	22

1/ Part numbers are for units without color filters. When color filters are required (see section 203 - MIL-S-22885/12), the color symbols of MIL-S-22885 will be added following the dash number with the location sequence as shown in the following:









FIGURE 102-2. Switches, push button, illuminated, 4-lamp, solid mount (MIL-S-22885/9 and /10) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		50,000 feet
	28 Vdc	115 Vac	28 Vdc
Resistive - - -	5.0	5.0	5.0
Inductive - - -	3.0	5.0	2.5
Lamp - - - - -	2.4	1.5	2.4



INCHES	MM
.225	5.72
.845	21.46
.875	22.23
1.085	27.56
1.100	27.94
1.115	28.32
1.395	34.42
1.750	44.45

Complete switch shall consist of the following:
1 - Indicator light module, MIL-S-22885/16
1 - Switch module, MIL-S-22885/11 (see section 113)

Additional parts that may be ordered, if required:
4 - Color filters, MIL-S-22885/12 (see section 203)
4 - Lamps (T-1-3/4 midget-flange-base incandescent type)


Operating force:
Momentary - 4 pounds, maximum
Alternate - 6 pounds, maximum (2PDT) or 7 pounds, maximum (4PDT)


FIGURE 102-3. Switches, push button, illuminated, 4-lamp, clip mounted (MIL-S-22885/15 and /16)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

1/ Part No. M22885/15-				Lens style code	Lamp wiring code	Indicator light module M22885/16-
Momentary		Alternate				
Switch module M22885/11-		Switch module M22885/11-				
-01	-02	-03	-04			
2PDT	4PDT	2PDT	4PDT			
CONFIGURATION A						
01	02	03	04	A	1	01
05	06	07	08	B	1	05
09	10	11	12	B	2	07
13	14	15	16	C	1	09
17	18	19	20	C	3	11
21	22	23	24	A	3	13
49	50	51	52	A	4	15
53	54	55	56	B	4	17
57	58	59	60	C	4	19
CONFIGURATION B						
25	26	27	28	A	1	02
29	30	31	32	B	1	06
33	34	35	36	B	2	08
37	38	39	40	C	1	10
41	42	43	44	C	3	12
45	46	47	48	A	3	14
61	62	63	64	A	4	16
65	66	67	68	B	4	18
69	70	71	72	C	4	20

1/ Part numbers are for units without color filters. When color filters are required (see section 203 - MIL-S-22885/12), the color symbols of MIL-S-22885 will be added following the dash number with the location sequence as shown in the following:










FIGURE 102-3. Switches, push button, illuminated, 4-lamp, clip mounted (MIL-S-22885/15 and /16) - Continued.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes) 28 Vdc	115 Vac (60/400 Hz)
Resistive - - - -	2.0	2.0
Inductive - - - -	1.5	1.5
Lamp - - - - - -	0.5	0.5



INCHES	MM	INCHES	MM
.13	3.30	.615	15.62
.27	6.86	.650	16.51
.36	9.14	2.12	53.85
.42	10.67		






Part No. M22885/18- Momentary DPDT	Momentary 2-Circuit	Alternate DPDT	Alternate 2-Circuit	Configuration	Color	Brightness (3/4 face) ft. l	Part No. M22885/
				Lens (threaded type) (see figure 102-44)			
				Switch housings without lens			
01	03	02	04	A	Yellow	350	22-01
09	49	29	69		White	300	-02
10	50	30	70		Red	100	-03
11	51	31	71		Green	75	-04
12	52	32	72		Blue	20	-05
13	53	33	73	B	Yellow	350	-06
14	54	34	74		White	300	-07
15	55	35	75		Red	100	-08
16	56	36	76		Green	75	-09
17	57	37	77		Blue	20	-10
18	58	38	78	C	Yellow	350	-11
19	59	39	79		White	300	-12
20	60	40	80		Red	100	-13
21	61	41	81		Green	75	-14
22	62	42	82		Blue	20	-15
23	63	43	83	D	Yellow	350	-16
24	64	44	84		White	300	-17
25	65	45	85		Red	100	-18
26	66	46	86		Green	75	-19
27	67	47	87		Blue	20	-20
28	68	48	88				
Part No. M22885/18-				Lens (snap-in type) (see figure 102-45)			
				Switch housings without lens			
05	07	06	08	A	Yellow	150	19-01
89	119	104	134		White	200	-02
90	120	105	135		Red	15	-03
91	121	106	136		Green	20	-04
92	122	107	137		Blue	5	-05
93	123	108	138	B	Yellow	150	-06
94	124	109	139		White	200	-07
95	125	110	140		Red	15	-08
96	126	111	141		Green	20	-09
97	127	112	142		Blue	5	-10
98	128	113	143	C	Yellow	150	-11
99	129	114	144		White	200	-12
100	130	115	145		Red	15	-13
101	131	116	146		Green	20	-14
102	132	117	147		Blue	5	-15
103	133	118	148				

FIGURE 102-4. Switch housings, push button, illuminated, drip proof seal (MIL-S-22885/18).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.








FIGURE 102-4A and 4B. Threaded and snap-in lenses (MIL-S-22885/22 and /19).

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		70,000 feet
	28 Vdc	115 Vac, 60 Hz	28 Vdc
Resistive - - - -	10.0	5.0	10.0
Inductive - - - -	5.0	5.0	2.0
Lamp - - - - - -	3.0	1.5	---



M22885/27-01 and -02




M22885/27-03 and -04

INCHES	MM
.040	1.02
.09	2.29
.19	4.83
.25	6.35
.36	9.14
.67	17.02
.75	19.05
.78	19.81
1.16	29.46

Part No. M22885/27-	Circuit characteristic	Dimension "A" inches (mm)	Basic switch Part No.	Basic switch Specification No.	Operating force (max)
01	4 circuit	.66 (16.76)	MS27217-1	MIL-S-8805/7	1.5 pounds
02	4 circuit	1.09 (27.69)	MS27217-1	MIL-S-8805/7	6.0 pounds
03	8 circuit	1.00 (25.40)	M8805/77-001	MIL-S-8805/77	2.5 pounds
04	8 circuit	1.44 (36.58)	M8805/77-001	MIL-S-8805/77	6.0 pounds


FIGURE 102-5. Switch housings, push button, illuminated, double break (MIL-S-22885/27).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




SCHEMATIC DIAGRAM
MOMENTARY ACTION

M22885/27-01




SCHEMATIC DIAGRAM
ALTERNATE ACTION

M22885/27-02




SCHEMATIC DIAGRAM
MOMENTARY ACTION

M22885/27-03



SCHEMATIC DIAGRAM
ALTERNATE ACTION

M22885/27-04




Color	Part No. M22885/28- Dimension "A" - Round lens .62 inch (15.75)	.75 inch (19.05)	.81 inch (20.57)	1.12 inch (28.45)	Dimension "A" - Square lens .62 inch (15.75)	.75 inch (19.05)
Blue	01	07	13	19	25	31
Green	02	08	14	20	26	32
Red	03	09	15	21	27	33
Yellow	05	11	17	23	29	35
White	06	12	18	24	30	36


FIGURE 102-5A. Lenses (MIL-S-22885/28).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS (amperes) 28 Vdc	115 Vac
Resistive - - - -	2.0	2.0
Inductive - - - -	1.0	1.0
Lamp - - - - - -	0.75	0.75



INCHES	MM	INCHES	MM
.060	1.52	.684	17.37
.07	1.78	.690	17.53
.188	4.78	.781	19.84
.21	5.33	.800	20.32
.24	6.10	2.36	59.94
.36	9.14	2.65	67.31



FLUSH LENS



EXTENDED LENS WITH REMOVAL LATCH HEIGHT SHOWN TO ACCOMMODATE EDGE LIGHTED PANEL

Complete switch consists of:
1 - Lamp module, MIL-S-22885/52 or /53
1 - Switch module (housing with mounting bracket)

Additional parts that may be ordered, if required:
4 - Lamps (T-1-3/4 midget-flange-base incandescent type)

Operating force: 3.5 ± 1.0 pounds

FIGURE 102-6. Switches, push button, illuminated, 4-lamp, solid mounting (MIL-S-22885/56).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

1/ Part No. M22885/56-								Lens code
Momentary				Alternate				
Lens height				Lens height				
Extended		Flush		Extended		Flush		
4PDT	2PDT	4PDT	2PDT	4PDT	2PDT	4PDT	2PDT	
WITHOUT RFI SHIELDING								
001	141	003	143	002	142	004	144	---
005	021	037	053	013	029	045	061	A
006	022	038	054	014	030	046	062	B
007	023	039	055	015	031	047	063	C
008	024	040	056	016	032	048	064	D
009	025	041	057	017	033	049	065	E
010	026	042	058	018	034	050	066	F
011	027	043	059	019	035	051	067	G
012	028	044	060	020	036	052	068	H
WITH RFI SHIELDING								
133	137	135	139	134	138	136	140	---
069	085	101	117	077	093	109	125	A
070	086	102	118	078	094	110	126	B
071	087	103	119	079	095	111	127	C
072	088	104	120	080	096	112	128	D
073	089	105	121	081	097	113	129	E
074	090	106	122	082	098	114	130	F
075	091	107	123	083	099	115	131	G
076	092	108	124	084	100	116	132	H

1/ Part numbers are for units without filters or caps. When required, the color symbols in the table below will be added following the dash number in the Color Symbol Position shown. EXAMPLE: M22885/56-010G1R1 denotes a 4PDT momentary switch without RFI shielding; extended lens, code "F"; with color filters (green in Position 1 and red in Position 2).


COLOR SYMBOL		COLOR
Filter (see MIL-S-22885/54)	Cap (see MIL-S-22885/55)	
B1	B2	Blue
G1	G2	Green
R1	R2	Red
W1	W2	White
Y1	Y2	Yellow

LENS CODE	LENS STYLE	COLOR SYMBOL POSITION
A	4 - WAY SPLIT	
B	3 - WAY SPLIT	
C	SPLIT HORIZONTALLY	
D	SOLID	
E	3 - WAY SPLIT	
F	SPLIT VERTICALLY	
G	3 - WAY SPLIT	
H	3 - WAY SPLIT	

FIGURE 102-6. Switches, push button, illuminated, 4-lamp, solid mounting (MIL-S-22885/56) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		50,000 feet
	28 Vdc	115 Vac, 60 Hz	28 Vdc
Resistive - - - -	7	7	4
Inductive - - - -	4	7	2.5
Lamp - - - - - -	2.5	2	2.5



INCHES	MM
.010	.25
.041	1.04
.09	2.29
.15	3.81
.22	5.59
.531	13.49
.688	17.48
.750	19.05
2.620	66.55

Complete switch consists of:
1 - Lens assembly (color filters in accordance with MIL-S-22885/70)
1 - Switch housing (with mounting sleeve and panel spacer)

Additional parts that may be ordered, if required:
4 - Lamps (T-1-3/4 midget-flange-base incandescent type)

Operating force: 2 to 5 pounds.

FIGURE 102-7. Switches, push button, illuminated, 4-lamp, solid mount (MIL-S-22885/67).

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.

1/ Part No. M22885/67- Lens configuration								Operation	Characteristics	Lens design 2/
0	1	2	3	4	5	6	7			
WITHOUT EMI SCREENING										
009	010	011	012	013	014	015	016	Momentary	2PDT	Nonremovable
017	018	019	020	021	022	023	024	Momentary	3PDT	Nonremovable
033	034	035	036	037	038	039	040	Alternate	2PDT	Nonremovable
041	042	043	044	045	046	047	048	Alternate	3PDT	Nonremovable
049	050	051	052	053	054	055	056	Momentary	2PDT	Removable
057	058	059	060	061	062	063	064	Momentary	3PDT	Removable
065	066	067	068	069	070	071	072	Alternate	2PDT	Removable
073	074	075	076	077	078	079	080	Alternate	3PDT	Removable
WITH EMI SCREENING										
081	082	083	084	085	086	087	088	Momentary	2PDT	Removable
089	090	091	092	093	094	095	096	Momentary	3PDT	Removable
097	098	099	100	101	102	103	104	Alternate	2PDT	Removable
105	106	107	108	109	110	111	112	Alternate	3PDT	Removable

1/ Part numbers are for units without color filters. When required, the segment placement number (see lens configuration) and color symbol will be added following the dash number.
EXAMPLE: M22885/67-012 6B 7G 8R 9Y

- 9Y — Yellow (9th position)
- 8R — Red (8th position)
- 7G — Green (7th position)
- 6B — Blue (6th position)

2/ Nonremovable lens assembly is capable of having lamps removed but is restricted in complete removal from switch housing; removable lens assembly is capable of being removed from switch housing.






FIGURE 102-7. Switches, push button, illuminated, 4-lamp, solid mount (MIL-S-22885/67) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS (amperes) 28 Vdc	115 Vac
Resistive	5.0	5.0
Inductive	2.5	2.5
Lamp	1.5	1.5



INCHES	MM
.040	1.02
.050	1.27
.200	5.08
.350	8.89
.740	18.80
.900	22.86
2.960	75.18
3.500	88.90



4PDT SWITCH CIRCUITRY
TERMINALS 6,9,11,14,16,19 OMITTED ON 2PDT CIRCUIT



PLUG-IN MODULES

Complete switch consists of:
1 - Lens assembly
1 - Switch housing (terminal junction module in accordance with MIL-T-81714) with mounting sleeve.

Additional parts that may be ordered, if required:
4 - Lamps (T-1-3/4 midget-flange-base incandescent type).
- Crimp contacts, M39029/1-16-20.

Operating force: 4 pounds, maximum

FIGURE 102-8. Switches (conforming to integrated wire termination system), push button, illuminated, 4-lamp, solid mount (MIL-S-22885/74).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

Part No. M22885/74-				Circuit	Operation	Lens style
Complete assembly 1/	Indicator module	Lamp module 1/	Housing			
01	41	36	39	2PDT	Momentary	A
02	42			4PDT	Momentary	
03	43			2PDT	Alternate	
04	44			4PDT	Alternate	
05	45	37	39	2PDT	Momentary	B
06	46			4PDT	Momentary	
07	47			2PDT	Alternate	
08	48			4PDT	Alternate	
09	49	38	39	2PDT	Momentary	C
10	50			4PDT	Momentary	
11	51			2PDT	Alternate	
12	52			4PDT	Alternate	
13	53	36	39	---	Indicator	A
14	54	37	39	---	Indicator	B
15	55	38	39	---	Indicator	C

1/ Part numbers are for units without color filters. When color filters are required, the color symbols of MIL-S-22885 will be added following the dash number; the location sequence is shown in the Lens Assembly diagram.

Lens assembly.




Code	Lens style		Lamp schematic
A	Solid - common ground		
B	Split horizontally - horizontal split ground		
C	Split vertically - vertical split ground		

FIGURE 102-8. Switches (conforming to integrated wire termination system), push button, illuminated, 4-lamp, solid mount (MIL-S-22885/74) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		50,000 Feet
	28 Vdc	115 Vac, 60 Hz	28 Vdc
Resistive - - - -	7.0	7.0	4.0
Inductive - - - -	4.0	7.0	2.5
Lamp - - - - - -	2.5	2.0	2.5



INCHES	MM
.010	.25
.015	.38
.09	2.29
.296	7.52
.62	15.75
.730	18.54
.750	19.05
.870	22.10
2.750	69.85

Complete switch consists of:
1 - Lens assembly (color filters in accordance with MIL-S-22885/70)
1 - Switch housing (with mounting sleeve)

Additional parts that may be ordered, if required:
4 - Lamps (T-1-3/4 midget-flange-base incandescent type)

Operating force: 2 to 5 pounds.

FIGURE 102-9. Switches, push button, illuminated, 4-lamp, momentary and alternate action (MIL-S-22885/75).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

1/ Part No. M22885/75- Lens configuration								Operation	Characteristics	2/ Lens design
0	1	2	3	4	5	6	7			
WITHOUT EMI SHIELDING										
009	010	011	012	013	014	015	016	Momentary	2PDT	Nonremovable
017	018	019	020	021	022	023	024	Momentary	3PDT	Nonremovable
025	026	027	028	029	030	031	032	Momentary	4PDT	Nonremovable
041	042	043	044	045	046	047	048	Alternate	2PDT	Nonremovable
049	050	051	052	053	054	055	056	Alternate	3PDT	Nonremovable
057	058	059	060	061	062	063	064	Alternate	4PDT	Nonremovable
065	066	067	068	069	070	071	072	Momentary	2PDT	Removable
073	074	075	076	077	078	079	080	Momentary	3PDT	Removable
081	082	083	084	085	086	087	088	Momentary	4PDT	Removable
089	090	091	092	093	094	095	096	Alternate	2PDT	Removable
097	098	099	100	101	102	103	104	Alternate	3PDT	Removable
105	106	107	108	109	110	111	112	Alternate	4PDT	Removable
WITH EMI SHIELDING										
113	114	115	116	117	118	119	120	Momentary	2PDT	Removable
121	122	123	124	125	126	127	128	Momentary	3PDT	Removable
129	130	131	132	133	134	135	136	Momentary	4PDT	Removable
137	138	139	140	141	142	143	144	Alternate	2PDT	Removable
145	146	147	148	149	150	151	152	Alternate	3PDT	Removable
153	154	155	156	157	158	159	160	Alternate	4PDT	Removable

1/ Part numbers are for units without color filters. When required, the segment placement number (see lens configuration) and color symbol will be added following the dash number.
EXAMPLE: M22885/75-012 6B 7G 8R 9Y

- 9Y — Yellow (9th position)
- 8R — Red (8th position)
- 7G — Green (7th position)
- 6B — Blue (6th position)

2/ Nonremovable lens assembly is capable of having lamps removed but is restricted in complete removal from switch housing; removable lens assembly is capable of being removed from switch housing.





FIGURE 102-9. Switches, push button, illuminated, 4-lamp, momentary and alternate action (MIL-S-22885/75) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		50,000 feet
	28 Vdc	115 Vac, 60 Hz	28 Vdc
Resistive - - - -	7.5	7.5	4.0
Inductive - - - -	5.0	5.0	2.5
Lamp 1/ - - - -	1.0	1.0	1.0

1/ Inrush, 10:1 for 20 milliseconds maximum.



INCHES	MM	INCHES	MM
.010	.25	.53	13.47
.020	.51	.62	15.74
.04	1.02	.679	17.26
.060	1.52	.688	17.48
.100	2.54	.75	19.05
.180	4.57	2.93	74.42
.220	5.59	3.56	90.42
.240	6.10		

Complete switch consists of:
1 - Lens assembly (color filters in accordance with MIL-S-22885/78)
1 - Switch housing (with mounting sleeve and panel spacer)

Additional parts that may be ordered, if required:
4 - Lamps (T-1-3/4 midget-flange-base incandescent type)
- Crimp contacts, M39029/1-16-20

Operating force: 3.5 ±1.5 pounds

FIGURE 102-10. Switches, 4-lamp, solid mount, insertable crimp terminations (MIL-S-22885/77).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

1/ Part No. M22885/77- Lens configuration 0	1	2	3	4	5	6	7	Operation	Characteristics	2/ Lens design
WITHOUT EMI SHIELDING										
001	002	003	004	005	006	007	008	Momentary	2PDT	Nonremovable
009	010	011	012	013	014	015	016	Momentary	3PDT	Nonremovable
017	018	019	020	021	022	023	024	Momentary	4PDT	Nonremovable
025	026	027	028	029	030	031	032	3/	2PDT	Nonremovable
033	034	035	036	037	038	039	040	3/	3PDT	Nonremovable
041	042	043	044	045	046	047	048	3/	4PDT	Nonremovable
049	050	051	052	053	054	055	056	Mag. hold	2PDT	Nonremovable
057	058	059	060	061	062	063	064	Mag. hold	3PDT	Nonremovable
065	066	067	068	069	070	071	072	Mag. hold	4PDT	Removable
073	074	075	076	077	078	079	080	Momentary	2PDT	Removable
081	082	083	084	085	086	087	088	Momentary	3PDT	Removable
089	090	091	092	093	094	095	096	Momentary	4PDT	Removable
097	098	099	100	101	102	103	104	3/	2PDT	Removable
105	106	107	108	109	110	111	112	3/	3PDT	Removable
113	114	115	116	117	118	119	120	3/	4PDT	Removable
121	122	123	124	125	126	127	128	Mag. hold	2PDT	Removable
129	130	131	132	133	134	135	136	Mag. hold	3PDT	Removable
137	138	139	140	141	142	143	144	Mag. hold	4PDT	Removable
WITH EMI SHIELDING										
145	146	147	148	149	150	151	152	Momentary	2PDT	Removable
153	154	155	156	157	158	159	160	Momentary	3PDT	Removable
161	162	163	164	165	166	167	168	Momentary	4PDT	Removable
169	170	171	172	173	174	175	176	3/	2PDT	Removable
177	178	179	180	181	182	183	184	3/	3PDT	Removable
185	186	187	188	189	190	191	192	3/	4PDT	Removable
193	194	195	196	197	198	199	200	Mag. hold	2PDT	Removable
201	202	203	204	205	206	207	208	Mag. hold	3PDT	Removable
209	210	211	212	213	214	215	216	Mag. hold	4PDT	Removable

1/ Part numbers are for units without color filters. When required, the segment placement number (see lens configuration) and color symbol will be added following the dash number.

EXAMPLE: M22885/77-004 6B 7G 8R 9Y

- 9Y — Yellow (9th position)
- 8R — Red (8th position)
- 7G — Green (7th position)
- 6B — Blue (6th position)

2/ Nonremovable lens assembly is capable of having lamps removed but is restricted in complete removal from switch housing; removable lens assembly is capable of being removed from switch housing.

3/ Maintained depressed alternate action.






FIGURE 102-10. Switches, 4-lamp, solid mount, insertable crimp terminations (MIL-S-22885/77) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS (amperes)				
	Silver contacts, MS24547-1			Gold contacts, MS24547-2	
	Sea level		50,000 feet	Sea level	50,000 feet
	28 Vdc	115 Vac, 60 Hz	28 Vdc	28 Vdc	28 Vdc
Resistive - - - -	7.0	7.0	4.0	1.0	1.0
Inductive - - - -	4.0	7.0	2.5	.5	.5
Lamp - - - - - -	2.5	2.0	2.5	---	---







SCHEMATIC DIAGRAM

INCHES	MM
.005	.13
.010	.25
.020	.51
.03	.76
.075	1.91
.11	2.79
.25	6.35
.358	9.09
.375	9.53
.408	10.36
.425	10.80
.44	11.18
.447	11.35
.469	11.91
.50	12.70
.505	12.83
.540	13.72
.56	14.22
.563	14.27
.608	15.44
.625	15.88
.656	16.66
.75	19.05
.858	21.79
1.00	25.40
1.13	28.70





DRIP PROOF SEAL (REF)



"D" STYLE LENS SHOWN FOR REF. ONLY.
SEAL IS AVAILABLE FOR ANY LENS STYLE.

FIGURE 102-11. Switch bodies and lenses (with or without dripproof seal) (MIL-S-22885/79).

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.

Part No. M22885/79- Lens color					Lens style (snap-in)	Switch contacts
Green	Red	White	Yellow	Blue		
WITHOUT DRIPPROOF SEAL						
001	002	003	004	005	B	MS24547-1
006	007	008	009	010	C	
011	012	013	014	015	D	
016	017	018	019	020	E	
021	022	023	024	025	F	MS24547-1
026	027	028	029	030	B	MS24547-2
031	032	033	034	035	C	
036	037	038	039	040	D	
041	042	043	044	045	E	
046	047	048	049	050	F	MS24547-2
WITH DRIPPROOF SEAL						
051	052	053	054	055	B	MS24547-1
056	057	058	059	060	C	
061	062	063	064	065	D	
066	067	068	069	070	E	
071	072	073	074	075	F	MS24547-1
076	077	078	079	080	B	MS24547-2
081	082	083	084	085	C	
086	087	088	089	090	D	
091	092	093	094	095	E	
096	097	098	099	100	F	MS24547-2
BASIC SWITCH BODY WITHOUT LENS						
101					None	MS24547-1
102					None	MS24547-2


Complete switch consists of:
1 - Push button lens assembly.
1 - Lamp (T-1-3/4 midget-flange-base incandescent type #387, 28 volts - long life)
1 - Switch body

Operating force: 22 ± 4 ounces

FIGURE 102-11. Switch bodies and lenses (with or without dripproof seal) (MIL-S-22885/79) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes) 50Hz (avg)	
	28 Vdc	115 Vac
Resistive - - - -	3.0	3.0
Inductive - - - -	1.5	1.5
Lamp - - - - - -	1.5	1.0



Complete switch consists of:
1 - Lamp module
1 - Switch housing
2 - Lamps (T-1-3/4 midget-flange-base incandescent type) - Not included, order separately

Operating force: 4.0 pounds maximum

1/ Part No. M22885/58-				Lens plate code
Momentary		Alternate		
2PDT	4PDT	2PDT	4PDT	
01	04	07	10	A
02	05	08	11	B
03	06	09	12	C

1/ Part numbers are for units without color filters. When color filters are required, the color symbols of MIL-S-22885 will be added following the dash number with the location sequence shown in the Lens Plate diagram.





FIGURE 102-12. Switches, push button, illuminated, 2-lamp, solid mount (MIL-S-22885/58).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		50,000 feet
	28 Vdc	115 Vac, 60 Hz	28 Vdc
Resistive - - - -	5.0	5.0	5.0
Inductive - - - -	3.0	5.0	2.5
Lamp - - - - - -	2.4	1.5	2.4



INCHES	MM
.022	.56
.050	1.27
.366	9.30
.660	16.76
.730	18.54
.750	19.05
.800	20.32
.940	23.88
1.042	26.47
1.200	30.48


Part No. M22885/81- Lens color					Switch circuitry	Dimension "A"
Red	Green	Yellow	Blue	White		Inch (mm)
01R	01G	01Y	01B	01W	2 pole momentary	2.61 (66.29)
02R	02G	02Y	02B	02W	2 pole alternate action	2.90 (73.66)
03R	03G	03Y	03B	03W	4 pole momentary	2.61 (66.29)
04R	04G	04Y	04B	04W	4 pole alternate action	2.90 (73.66)


Complete switch consists of:
1 - Lens/lampholder
1 - Switch housing (utilizes MS25085-2 basic switches)
1 - Lamp (T-1-3/4 midget-flange-base incandescent type) - Not included, order separately

FIGURE 102-13. Switches, push button, illuminated, 1-lamp, panel sealed (MIL-S-22885/81).


Source: https://assist.dla.mil -- Downloaded: 202640-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS (amperes) 28 Vdc
Resistive	7.0
Inductive	4.0





SWITCH CIRCUITRY
(MOMENTARY ACTION)





LAMP CIRCUIT SCHEMATIC


INCHES	MM
.165	4.19
.540	13.72
.73	18.54
.920	23.37
.935	23.75
2.135	54.23

Complete switch consists of:
1 - Lamp module
1 - Switch housing
1 - Legend plate
4 - Lamps (T-1 sub-midget-flange-base incandescent type) - Not included, order separately


FIGURE 102-14. Switches, push button, illuminated, 4-lamp, RFI shielded, solid mount (MIL-S-22885/71).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


Part No. M22885/71- Lens style								Switching action	Max weight	Operating force
A	B	C	D	E	F	G	H		(ounces)	(ounces)
01	02	03	04	05	06	07	08	Momentary	1.9	12 to 48
09	10	11	12	13	14	15	16	Alternate (two-level)	1.9	12 to 48
17	18	19	20	21	22	23	24	Indicator	1.7	---




STYLE A (SOLID)




STYLE B (HORIZONTAL SPLIT)




STYLE C (VERTICAL SPLIT)




STYLE D (4 WAY SPLIT)




STYLE E (3 WAY SPLIT)



STYLE F (3 WAY SPLIT)



STYLE G (3 WAY SPLIT)





STYLE H (3 WAY SPLIT)

FIGURE 102-14. Switches, push button, illuminated, 4-lamp, RFI shielded, solid mount (MIL-S-22885/71) - Continued.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		10,000 feet
	28 Vdc	115 Vac	90 Vdc
Resistive - - - -	10.0	5.0	10.0
Inductive - - - -	5.0	5.0	2.0
Lamp - - - - - -	3.0	1.5	---





LAMP CIRCUIT SCHEMATIC



INCHES	MM
.250	6.35
.875	22.22
1.500	38.10
1.875	47.62
2.125	53.98


Complete switch consists of:
1 - Indicator light module, MIL-S-22885/73
1 - Switch module, MIL-S-22885/26 (see Section 113)
4 - Lamps (T-1-3/4 midget-flange-base incandescent type) - Not included, order separately

FIGURE 102-15. Switches, push button, illuminated, 4-lamp, modular constructed (MIL-S-22885/72 and MIL-S-22885/73).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

1/ Switch Part No. M22885/72-			Dimension "A"	Circuit	Operation	Switch module	
1/ Indicator M22885/73-01 Lens code A	1/ Indicator M22885/73-02 Lens code B	1/ Indicator M22885/73-03 Lens code C				Part No. M22885/26-	Operating force (maximum)
			Inches (mm)				pounds
01	07	13	3.125(79.38)	2 two-circuit	Momentary	01	4
02	08	14	3.281(83.34)	2 two-circuit	Alternate	02	6
03	09	15	3.125(79.38)	4 two-circuit	Momentary	03	4
04	10	16	3.281(83.34)	4 two-circuit	Alternate	04	7
05	11	17	3.031(76.99)	2 four-circuit	Momentary	05	4
06	12	18	3.438(87.43)	2 four-circuit	Alternate	06	7

1/ Part numbers are for units without color filters. When color filters are required, the color symbols of MIL-S-22885 will be added following the dash number; the location sequence is shown in the following:



VIEW FROM FRONT OF PANEL


COLOR FILTER LOCATION


CODE	LENS STYLE
A	SOLID
B	VERTICALLY SPLIT
C	HORIZONTALLY SPLIT

FIGURE 102-15. Switches, push button, illuminated, 4-lamp, modular constructed (MIL-S-22885/72 and MIL-S-22885/73) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes) Sea level	
	28 Vdc	115 Vac
Resistive - - - -	5.0	5.0
Inductive - - - -	2.5	2.5





PLUG-IN SWITCH/INDICATOR MODULE

Complete switch consists of:
1 - Plug-in switch indicator module
1 - Switch housing with MIL-S-22885/80-50 insertable solder type terminals
4 - Lamps (T-1-3/4 midget-flange-base incandescent type) - Not included, order separately

Operating force: 4 pounds maximum

FIGURE 102-16. Switches, push button, illuminated, 4-lamp, RFI shielded, Moisture sealed, high impact shock, modular construction (MIL-S-22885/80).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

1/ Part No. M22885/80-			Circuit characteristics, operation, and part	Type
Lamp code 1 Lens code A	Lamp code 2 Lens code B	Lamp code 3 Lens code C		
COMPLETE SWITCH OR INDICATOR ASSEMBLY				
01	02	03	2PDT momentary switch	I
04	05	06	4PDT momentary switch	I
07	08	09	Indicator	I
10	11	12	2PDT momentary switch	II
13	14	15	4PDT momentary switch	II
16	17	18	Indicator	II
PLUG-IN SWITCH OR INDICATOR MODULES WITHOUT HOUSINGS				
19	20	21	2PDT momentary switch	I
22	23	24	4PDT momentary switch	I
25	26	27	Indicator	I
28	29	30	2PDT momentary switch	II
31	32	33	4PDT momentary switch	II
34	35	36	Indicator	II

1/ Part numbers are for units without color filters. When color filters are required, the color symbols of MIL-S-22885 will be added following the dash number; the location sequence is shown in Lens Code diagram.

LENS CODE

CODE	A	B	C
LENS STYLE	FULL	HORIZONTAL SPLIT (1 / 2)	VERTICAL SPLIT (1 | 2)




CODE	LAMP CIRCUITRY
1	
2	
3	

FIGURE 102-16. Switches, push button, illuminated, 4-lamp, RFI shielded, Moisture sealed, high impact shock, modular construction (MIL-S-22885/80) - Continued.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS (amperes) 28 Vdc	115 Vac
Resistive - - - -	2.0	2.0
Inductive - - - -	1.0	1.0
Lamp - - - - - -	0.75	0.75

INCHES	MM
.032	.81
.12	3.05
.125	3.18
.18	4.57
.21	5.33
.50	12.70
.685	17.40
.735	18.67
.870	22.10
1.22	30.99
1.24	31.50
2.82	71.63










Complete switch consists of:
- 1 - Lens assembly (MIL-S-22885/52)
- 1 - Plug-in switch module
- 1 - Housing
- 4 - Lamps (T-1-3/4 midget-flange base incandescent type). Not included, order separately.

Operating force: 3.5 ± 1.0 pounds.

FIGURE 102-17. Switches, push button, illuminated, 4-lamp, square, RFI shielded, modular construction (MIL-S-22885/86).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



INCHES	MM	INCHES	MM
.022	.56	.090	2.29
.034	.86	.18	4.57
.036	.91	.50	12.70

PLUG-IN SWITCHES, INDICATORS, AND HOUSINGS			
Part No. M22885/86- Circuit		Part	Switch action
4PDT	2PDT		
001	003	Plug-in switch	Momentary
002	004	Plug-in switch	Alternate
005		Plug-in indicator	---
Terminal		Part	RFI shielded
Type S	Type W		
006	098	Housing	No
007	099	Housing	Yes

SWITCH ASSEMBLIES WITHOUT LENS					
Part No. M22885/86-				Terminal type	RFI shielded
4PDT		2PDT			
Momentary	Alternate	Momentary	Alternate		
008	009	010	011	S	No
013	014	015	016	S	Yes
100	101	102	103	W	No
105	106	107	108	W	Yes

INDICATOR ASSEMBLIES WITHOUT LENS		
Part No. M22885/86-	Terminal type	RFI shielded
012	S	No
017	S	Yes
104	W	No
109	W	Yes

FIGURE 102-17. Switches, push button, illuminated, 4-lamp, square, RFI shielded, modular construction (MIL-S-22885/86) - Continued.

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.

COMPLETE SWITCH ASSEMBLY										
1/ Part No. MZ2885/86-										
Lens code								Terminal type	RFI shielded	
A	B	C	D	E	F	G	H			
018	019	020	021	022	023	024	025	S	No	4PDT momentary
026	027	028	029	030	031	032	033	S	Yes	4PDT momentary
034	035	036	037	038	039	040	041	S	No	4PDT alternate
042	043	044	045	046	047	048	049	S	Yes	4PDT alternate
050	051	052	053	054	055	056	057	S	No	2PDT momentary
058	059	060	061	062	063	064	065	S	Yes	2PDT momentary
066	067	068	069	070	071	072	073	S	No	2PDT alternate
074	075	076	077	078	079	080	081	S	Yes	2PDT alternate
110	111	112	113	114	115	116	117	M	No	4PDT momentary
118	119	120	121	122	123	124	126	M	Yes	4PDT momentary
126	127	128	129	130	131	132	133	M	No	4PDT alternate
134	135	136	137	138	139	140	141	M	Yes	4PDT alternate
142	143	144	145	146	147	148	149	M	No	2PDT momentary
150	151	152	153	154	155	156	157	M	Yes	2PDT momentary
158	159	160	161	162	163	164	165	M	No	2PDT alternate
166	167	168	169	170	171	172	173	M	Yes	2PDT alternate
COMPLETE INDICATOR ASSEMBLY										
082	083	084	085	086	087	088	089	S	No	
090	091	092	093	094	095	096	097	S	Yes	
174	175	176	177	178	179	180	181	M	No	
182	183	184	185	186	187	188	189	M	Yes	

1/ Part numbers are for units without color filters. The color symbols of MIL-S-22885 will be added following the dash number in the sequence shown in Lens Style diagram.

LENS CODE	LENS STYLE	COLOR SYMBOL POSITION
A	4 - WAY SPLIT	
B	3 - WAY SPLIT	
C	SPLIT HORIZONTALLY	
D	SOLID	
E	3 - WAY SPLIT	
F	SPLIT VERTICALLY	
G	3 - WAY SPLIT	
H	3 - WAY SPLIT	

FIGURE 102-17. Switches, push button, illuminated, 4-lamp, square, RFI shielded, modular construction (MIL-S-22885/86) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

SECTION 103


SWITCHES, INTERLOCK

(Applicable specification: MIL-S-8805)


TABLE 103.I Switches, interlock, parameters and characteristics.

Figure number	Applicable specification sheet	Part number	Operating characteristics				Shock	Vibration	Temperature
			Switch action	Approximate plunger travel		Switch circuit			
				Push (inch)	Pull (inch)		(G)	(Hz)	(°C)
103-1	MIL-S-8805/56	MS16106-1	Push-pull	.250	.187	SPDT	50	10 to 500	-55 to +85
		MS16106-2	Push-pull	.250	.187	DPDT			
		MS16106-3	Push-pull	.250	.188	4PDT			
		MS16106-4	Push-pull	.156	.156	SPDT			
		MS16106-5	Push-pull	.250	.187	DPDT			


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



MS16106-1



MS16106-2



MS16106-3

FIGURE 103-1. Switch assemblies, sensitive, interlock.

Supersedes page 103.2
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

SECTION 104A


SWITCHES, MULTISTATION
(Applicable specification: MIL-S-24317)

FIGURE NUMBER	APPLICABLE SPECIFICATION SHEET	SWITCH CHARACTERISTICS				PAGE
		Switch module	Type	Operation	Circuit	
104-1	MIL-S-24317/9	MIL-S-22885/86	Illuminated	Momentary and alternate	2PDT 4POT	104.2

Supersedes Section 104
(page 104.1 of 23 March 1976)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS (amperes)	
	28 Vdc	115 Vac
Resistive	2.0	2.0
Inductive	1.0	1.0
Lamp	0.75	0.75



FLANGE ARRANGEMENT FOR RFI SHIELDING

FIGURE 104-1. Switches, multistation, illuminated, matrix arrangement for (MIL-S-24317/9).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



INCHES	MM
.022	.56
.034	.86
.036	.91
.090	2.29
.18	4.57
.50	12.70

OPERATING FORCE: 3.5 ±1.0 pounds.

PART NUMBER: Part numbers in the tabulation are for matrix frame with flanges and receptacles and do not include the switch/indicator or lens assemblies (see MIL-S-22885/86 and /52).

Without RFI shielding			With RFI shielding			No. of stations	Dimension	
Part No. M24317/9-		No. of flanges	Part No. M24317/9-		No. of flanges		A ±.015 (.38)	B ±.015 (.38)
Type S	Type W		Type S	Type W				
001	011	2V	021	031	2V2H	1	.755 (19.18)	.755 (19.18)
002	012		022	032		2	1.510 (38.35)	
003	013		023	033		3	2.265 (57.53)	
004	014		024	034		4	3.020 (76.71)	
005	015		025	035		5	3.775 (95.89)	
006	016		026	036		6	4.530 (115.06)	
007	017	2H	027	037		7	5.285 (134.24)	
008	018		028	038		8	6.040 (153.42)	
009	019		029	039		9	6.795 (172.59)	
010	020		030	040		10	7.550 (191.77)	
041	051	2V	061	071		2	.755 (19.18)	1.510 (38.35)
042	052		062	072		4	1.510 (38.35)	
043	053		063	073		6	2.265 (57.53)	
044	054		064	074		8	3.020 (76.71)	
045	055		065	075		10	3.775 (95.89)	
046	056		066	076		12	4.530 (115.06)	
047	057	2H	067	077		14	5.285 (134.24)	
048	058		068	078		16	6.040 (153.42)	
049	059		069	079		18	6.795 (172.59)	
050	060		070	080		20	7.550 (191.77)	

FIGURE 104-1. Switches, multistation, illuminated, matrix arrangement for (MIL-S-24317/9) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

SECTION 106


SWITCHES, PUSH BUTTON
(Applicable specification: MIL-S-8805)


FIGURE NUMBER	SWITCH CHARACTERISTICS				PAGE
	Specification sheet	Operation	Circuit	Electrical ratings at 28 Vdc	
				(amperes)	
106-1	MIL-S-8805/3	Momentary and push-pull	Single circuit and 2 circuit	10 resistive	106.2
106-2	MIL-S-8805/20	Momentary	2 circuit	1 inductive at 120 Vdc, .07 Henry load	106.4
106-3	MIL-S-8805/23	Momentary	2PDT 4PDT	5 resistive	106.5
106-4	MIL-S-8805/25	Alternate	2PDT 4PDT	5 resistive	106.6
106-5	MIL-S-8805/38	Momentary	4 circuit	4 resistive	106.7
106-6	MIL-S-8805/55	Momentary-foot operated	2PST	.75 inductive	106.8
106-7	MIL-S-8805/95	Momentary	2PDT	1 resistive	106.9
106-8	MIL-S-8805/96	Momentary	SPST	5 resistive	106.10
106-9	MIL-S-8805/99	Momentary and alternate	2 circuit and DPDT	2 resistive	106.11


Supersedes page 106.1
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		50,000 feet
	28 Vdc	115 Vac, 60/400 Hz	28 Vdc
Resistive - - -	10	10	---
Inductive - - -	5	5	5
Lamp- - - - - -	3	3	---







INCHES	MM
.062	1.57
.086	2.18
.156	3.96
.312	7.92
.375	9.53
.438	11.13
.562	14.27
.623	15.82
.625	15.88
.688	17.48
.739	18.77
.875	22.23
1.375	34.93

*Button style illustrated is for momentary action switches; push-pull configuration is shown below.

FIGURE 106-1. Switches, push button, dusttight (MIL-S-8805/3).

Supersedes page 106.2
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

MOMENTARY ACTION SWITCHES

1/ Part No. MS25089-


Type A Button color			Type B Button color			Type C Button color			Type E Button color			Type F Button color			Type G Button color			Type H Button color			Switch circuit
Black	Red	White	Black	Red	White	Black	Red	White	Black	Red	White	Black	Red	White	Black	Red	White	Black	Red	White	
1A	1AR	1AW	1B	1BR	1BW	1C	1CR	1CW	1E	1ER	1EW	1F	1FR	1FW	1G	1GR	1GW	1H	1HR	1HW	NO
2A	2AR	2AW	2B	2BR	2BW	2C	2CR	2CW	2E	2ER	2EW	2F	2FR	2FW	2G	2GR	2GW	2H	2HR	2HW	NC
3A	3AR	3AW	3B	3BR	3BW	3C	3CR	3CW	3E	3ER	3EW	3F	3FR	3FW	3G	3GR	3GW	3H	3HR	3HW	2 Circuit
4A	4AR	4AW	4B	4BR	4BW	4C	4CR	4CW	4E	4ER	4EW	4F	4FR	4FW	4G	4GR	4GW	4H	4HR	4HW	3 Term NO
5A	5AR	5AW	5B	5BR	5BW	5C	5CR	5CW	5E	5ER	5EW	5F	5FR	5FW	5G	5GR	5GW	5H	5HR	5HW	3 Term NC
PUSH-PULL SWITCHES																					
None			None			1C-1 2C-1 3C-1 4C-1 5C-1	1CR-1 2CR-1 3CR-1 4CR-1 5CR-1	1CW-1 2CW-1 3CW-1 4CW-1 5CW-1	None			1F-1 2F-1 3F-1 4F-1 5F-1	1FR-1 2FR-1 3FR-1 4FR-1 5FR-1	1FW-1 2FW-1 3FW-1 4FW-1 5FW-1	1G-1 2G-1 3G-1 4G-1 5G-1	1GR-1 2GR-1 3GR-1 4GR-1 5GR-1	1GW-1 2GW-1 3GW-1 4GW-1 5GW-1	1H-1 2H-1 3H-1 4H-1 5H-1	1HR-1 2HR-1 3HR-1 4HR-1 5HR-1	1HW-1 2HW-1 3HW-1 4HW-1 5HW-1	NO NC 2 Circuit 3 Term NO 3 Term NC


1/ Examples of part numbers:
MS25089-4C = Switch, Push, Dusttight, 3 Terminal (NO), Type C, Momentary, Black Button.
MS25089-4CR-1 = Switch, Push, Dusttight, 3 Terminal (NO), Type C, Push-Pull, Red Button.

OPERATING CHARACTERISTICS:
Total plunger travel - - - - - - - - - - - - - - - .085 inch ±.015.
Operating force:
Momentary - 4 pounds ±1 pound.
Push pull - 1/2 to 2 pounds.
Releasing force - - - - - - - - - - - - - - - - - - 1 pound minimum, momentary.

FIGURE 106-1. Switches, push button, dusttight (MIL-S-8805/3) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.





INCHES	MM
.031	.79
.187	4.75
.250	6.35
.390	9.91
.500	12.70
.562	14.27
.652	16.56
1.250	31.75


ELECTRICAL RATINGS	ENDURANCE
Inductive	
(amperes)	(cycles)
15 at 0.5 power factor (120 Vac, 60 Hz)	40,000
1 at 0.07 Henry (120 Vdc)	40,000
0.05 at 2 Henries (230 Vdc)	5,000

OPERATING CHARACTERISTICS:
Actuating force: 3-1/2 ±1 pounds.
Total travel: .085 inch approximately.


PART NUMBER: MS16712-1.

FIGURE 106-2. Switch, push, momentary, 2 circuit, unsealed (MIL-S-8805/20).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



INCHES	MM
.13	3.30
.136	3.45
.156	3.96
.282	7.16
.469	11.91
1.297	32.91



SCHEMATIC DIAGRAM

LOAD	ELECTRICAL RATINGS	
	28 Vdc	115 Vac, 60 Hz
	ampere	ampere
Resistive - - -	1	1
Inductive - - -	1	1

OPERATING CHARACTERISTICS:
Total plunger travel: .093 inch minimum.
Operating force: 1.50 ±.75 pounds.


PART NUMBER: See following tabulation.

Part number M8805/95-	Button color	Case color	Hex nut
001	Black	Clear	MS25082-14
002	Red	Clear	MS25082-14
003	Black	Black	MS25082-B14
004	Red	Black	MS25082-B14

FIGURE 106-7. Switches, push, 2PDT, momentary, 1 ampere, unsealed (MIL-S-8805/95).

Supersedes page 106.9
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 202640-26T07:41Z
Check the source to verify that this is the current version before use.



INCHES	MM
.136	3.45
.282	7.16
.343	8.71
1.046	26.50

CIRCUIT DIAGRAM



LOAD	ELECTRICAL RATINGS	
	28 Vdc	115 Vac, 60 Hz
	amperes	amperes
Resistive - - -	5.0	5.0
Inductive - - -	2.0	2.0

OPERATING CHARACTERISTICS:
Total plunger travel: .095 ±.015 inch.
Operating force:
Unsealed: 1.50 ±.5 pounds.
Dusttight: 1.75 ±.5 pounds.


PART NUMBER: See following tabulation.

Part number M8805/96-	Plunger cap color	Circuit characteristics	Case color	Hex nut	Enclosure design
001	Red	SPST-NO	Clear	MS25082-14	1 (unsealed)
002	Black	SPST-NO	Clear	MS25082-14	1 (unsealed)
003	Red	SPST-NC	Clear	MS25082-14	1 (unsealed)
004	Black	SPST-NC	Clear	MS25082-14	1 (unsealed)
005	Red	SPST-NO	Black	MS25082-B14	1 (unsealed)
006	Black	SPST-NO	Black	MS25082-B14	1 (unsealed)
007	Red	SPST-NC	Black	MS25082-B14	1 (unsealed)
008	Black	SPST-NC	Black	MS25082-B14	1 (unsealed)
009	Red	SPST-NO	Clear	MS25082-14	2 (dusttight)
010	Black	SPST-NO	Clear	MS25082-14	2 (dusttight)
011	Red	SPST-NC	Clear	MS25082-14	2 (dusttight)
012	Black	SPST-NC	Clear	MS25082-14	2 (dusttight)
013	Red	SPST-NO	Black	MS25082-B14	2 (dusttight)
014	Black	SPST-NO	Black	MS25082-B14	2 (dusttight)
015	Red	SPST-NC	Black	MS25082-B14	2 (dusttight)
016	Black	SPST-NC	Black	MS25082-B14	2 (dusttight)

FIGURE 106-8. Switches, push, momentary, SPST, 5 amperes (MIL-S-8805/96).

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.

INCHES	MM	INCHES	MM
.002	.06	.442	11.23
.003	.08	.449	11.40
.005	.13	.468	11.89
.048	1.22	.469	11.91
.050	1.27	.50	12.70
.16	4.06	.62	15.75
.19	4.83	.75	19.05
.28	7.19	.88	22.35
.344	8.74	1.16	29.46
.44	11.18		



Circuit schematic.

FIGURE 106-9. Switches, push, 2 circuit and DPDT, alternate and momentary action, 2 amperes, drippproof (MIL-S-8805/99).

Supersedes page 106.11
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS	
	Sea level	70,000 Feet
	28 Vdc 115 Vac, 400 Hz	28 Vdc
	(amperes)	(amperes)
Resistive - - -	2.0	2.0
Inductive - - -	1.5	1.5
Lamp- - - - - -	0.5	0.5

OPERATING CHARACTERISTICS:
Actuating force: 4 ±1 pounds.
Plunger travel: .160 inch maximum.

PART NUMBER: See following tabulation.

Part number	Dress ring	Switch action	Switch circuit	Button color
M8805/99-001	A	Alternate action	2 circuit	Black
-002	B	Alternate action	2 circuit	Black
-003	C	Alternate action	2 circuit	Black
-004	None	Alternate action	2 circuit	Black
-005	A	Alternate action	2 circuit	Red
-006	B	Alternate action	2 circuit	Red
-007	C	Alternate action	2 circuit	Red
-008	None	Alternate action	2 circuit	Red
-009	A	Momentary	2 circuit	Black
-010	B	Momentary	2 circuit	Black
-011	C	Momentary	2 circuit	Black
-012	None	Momentary	2 circuit	Black
-013	A	Momentary	2 circuit	Red
-014	B	Momentary	2 circuit	Red
-015	C	Momentary	2 circuit	Red
-016	None	Momentary	2 circuit	Red
-017	A	Alternate action	DPDT	Black
-018	B	Alternate action	DPDT	Black
-019	C	Alternate action	DPDT	Black
-020	None	Alternate action	DPDT	Black
-021	A	Alternate action	DPDT	Red
-022	B	Alternate action	DPDT	Red
-023	C	Alternate action	DPDT	Red
-024	None	Alternate action	DPDT	Red
-025	A	Momentary	DPDT	Black
-026	B	Momentary	DPDT	Black
-027	C	Momentary	DPDT	Black
-028	None	Momentary	DPDT	Black
-029	A	Momentary	DPDT	Red
-030	B	Momentary	DPDT	Red
-031	C	Momentary	DPDT	Red
-032	None	Momentary	DPDT	Red

FIGURE 106-9. Switches, push, 2 circuit and DPDT, alternate and momentary action, 2 amperes, dripproof (MIL-S-8805/99) - Continued.

Supersedes page 106.12
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.

SECTION 107


SWITCHES, ROTARY
(Applicable specifications: MIL-S-3786, MIL-S-6807, and MIL-S-15291)

FIGURE NO.	SWITCH CHARACTERISTICS						PAGE
	Style	Specification sheet No. or specification No.	Section size, excluding terminals (inches)	Type of construction	Current rating (amperes)	Shaft	
107-1	SR01 SR02 SR03 SR09 SR10	MIL-S-3786/1 MIL-S-3786/2 MIL-S-3786/3 MIL-S-3786/9 MIL-S-3786/10	2.094 max dia 1.594 max dia 1.375 max dia 2.344 max dia 2.328 max dia	Open	1/2	Single	107.2
107-2	SR14 SR15	MIL-S-3786/14 MIL-S-3786/15	1.750 square 2.531 square max	Open	1/2	Single	107.3
107-3	SR05	MIL-S-3786/5	1.047 max dia	Open	1/5	Single	107.4
107-4	SR31	MIL-S-3786/31	1.05 max dia	Open	1/4	Single (lever actuated)	107.6
107-5	SR28	MIL-S-3786/28	1.328 max dia	Open	1	Single	107.8
107-6	SR19	MIL-S-3786/19	.500 dia	Closed	1/10	Single	107.9
107-7	SR20	MIL-S-3786/20	.500 dia	Closed	1/5	Single	107.10
107-8	SR25	MIL-S-3786/25	1.60 dia	Closed	1/5	Single (key operated)	107.11
107-9	SR35	MIL-S-3786/35	.562 dia	Closed	1/5	Single	107.12
107-10	SR37	MIL-S-3786/37	.600 dia	Closed	1/5	Single	107.14
107-11	SR36	MIL-S-3786/36	1.350 dia (15°) 1.190 dia (18° & 22-1/2°)	Closed	1/4	Single	107.16
107-12	SR13	MIL-S-3786/13	.800 max dia (including terminals)	Closed	1/2	Single	107.20
107-13	SR04-1 SR04-2 SR04-3	MIL-S-3786/4	1.306 max dia (including terminals)	Closed	2	Single Concentric ADD-A-POT	107.23
107-14	---	MIL-S-6807	1.950 max dia (including terminals)	Closed	5	Single	107.29
107-15	SR41	MIL-S-3786/41	.765 max dia	Closed	1/2	Single	107.30
107-16	SR40	MIL-S-3786/40	1.781 square max	Open	Low level & 1/2	Single	107.32

NOTES:
1. For the styles listed under MIL-S-3786, the following variations are considered standard:
   (a) Operating-shaft length, diameter, shape, and special construction.
   (b) Deck-to-deck spacing dimensions.
   (c) Optional assemblies, such as spring return and push-to-turn actions.
   (d) Terminal angles.
   (e) Bushing thread size and diameter, and thread length.
   (f) Addition of a shield.
2. Standard switches are to be established for MIL-S-15291.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (milliamperes)			
	28 Vdc	115 Vrms		300 Vrms
		SR01 & 03	SR02, 09, & 10	
Resistive:				
At atmospheric pressure - - - - - -	500	225	250	50
At reduced barometric pressure- - -	350	100	100	---
Inductive (2.8 Henries):				
At atmospheric pressure - - - - - -	50	---	---	---




STYLE	PROCUREMENT DOCUMENT	DIMENSIONS			
		A max	B max	C max	D nom
SR01	MIL-S-3786/1	2.094 (53.19)	2.328 (59.13)	1.188 (30.20)	.750 (19.05)
SR02	MIL-S-3786/2	1.594 (40.49)	1.750 (44.45)	1.188 (30.20)	.500 (12.70)
SR03	MIL-S-3786/3	1.375 (34.93)	1.625 (41.28)	1.062 (26.97)	.500 (12.70)
SR09	MIL-S-3786/9	2.344 (59.54)	2.062 (52.37)	1.312 (33.32)	.500 (12.70)
SR10	MIL-S-3786/10	2.328 (59.13)	2.625 (66.68)	1.312 (33.32)	.500 (12.70)

NOTES:
1. For shipboard applications, switches must withstand the high impact shock test of MIL-S-3786.
2. Mounting brackets are recommended for switches that protrude over 3.50 inches (88.90 mm) behind panel or have more than five sections.
3. These switches are identified by a type designation (see MIL-S-3786).

FIGURE 107-1. SR01, SR02, SR03, SR09, and SR10 switches, rotary, open construction, 1/2 ampere, single shaft (MIL-S-3786/1, /2, /3, /9, and /10).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)	
	28 Vdc	115 Vac, 400 Hz
Resistive	5	5
Inductive	5	---
Lamp	2	---
Power factor, 50%	---	3




Number of wafers	Part number	
	Shock method I	Shock methods I and II
1	MS25002-1	MS25002-12
2	MS25002-2	MS25002-22
3	MS25002-3	MS25002-32
4	MS25002-4	MS25002-42
5	MS25002-5	MS25002-52
6	MS25002-6	MS25002-62

FIGURE 107-14. Switches, rotary, closed construction, 5 amperes, single shaft (MIL-S-6807).


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (milliamperes)	
	28 Vdc	115 Vrms, 60 Hz
Resistive:		
At atmospheric pressure	125 to 500	75 to 500
At reduced barometric pressure	50	20
Inductive (2.8 Henries):		
At atmospheric pressure	50 to 250	---
At reduced barometric pressure	10	---



INCHES	MM	INCHES	MM
.125	3.18	.700	17.78
.300	7.62	.750	19.05
.312	7.92	.765	19.43
.375	9.52	.800	20.32
.670	17.02		

"E" CONSTRUCTION STYLE
(EXPLOSION-PROOF, CLOSED CONSTRUCTION WITHOUT SEALED SHAFT AND BUSHING)



"F" CONSTRUCTION STYLE
(EXPLOSION-PROOF, CLOSED CONSTRUCTION WITH SEALED SHAFT AND BUSHING)

FIGURE 107-15. SM41 switches, rotary, closed construction, 1/2 ampere, single shaft (MIL-S-3786/41).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER: Consists of "M3786/41" followed by a dash and a four-character code. The four-character code used in the following example identifies a switch of construction style E, 30° angle of throw, 1 pole per deck, temperature-life characteristic B, three positions; the switch has two decks with nonshorting switching characteristics and three decks with shorting switching characteristics. (NOTE: Switches with both nonshorting and shorting decks have the nonshorting decks in front (nearer the panel).)

EXAMPLE: M3786/41- A B C D

- A — CONSTRUCTION STYLE, ANGLE OF THROW, AND NUMBER OF POLES PER DECK (see table I)
- B — TEMPERATURE-LIFE CHARACTERISTIC AND NUMBER OF POSITIONS (see table II)
- C — NUMBER OF DECKS WITH NONSHORTING SWITCHING CHARACTERISTICS (see table III)
- D — NUMBER OF DECKS WITH SHORTING SWITCHING CHARACTERISTICS (see table IV)

TABLE I. Code characters for construction style, angle of throw, and number of poles per deck.

	Poles per deck					Angle of throw
	1	2	3	4	6	
CONSTRUCTION STYLE E						
Code - - -	A	B	C	D	E	30°
Code - - -	F	G	--	--	--	36°
Code - - -	H	J	--	K	--	45°
Code - - -	L	M	N	--	--	60°
CONSTRUCTION STYLE F						
Code - - -	P	Q	R	S	T	30°
Code - - -	U	V	--	--	--	36°
Code - - -	W	X	--	Y	--	45°
Code - - -	Z	8	9	--	--	60°

TABLE II. Code letters for temperature-life characteristic and number of positions.

	Number of positions												Temperature-life characteristic
	2	3	4	5	6	7	8	9	10	11	12	C 1/	
Code - - -	A	B	C	D	E	F	G	H	J	K	L	M	B
Code - - -	N	P	Q	R	S	T	U	V	W	X	Y	Z	C

1/ Switch is continuous rotation type (no stops), and number of positions is dependent on angle of throw: 12 positions for 30° angle of throw; 10 positions for 36° angle of throw; 8 positions for 45° angle of throw; and 6 positions for 60° angle of throw.

TABLE III. Code letters for number of decks with nonshorting switching characteristics.

Code	Number of decks with nonshorting switching	Code	Number of decks with nonshorting switching	Code	Number of decks with nonshorting switching
A - - -	0	E - - -	4	J - - -	8
B - - -	1	F - - -	5	K - - -	9
C - - -	2	G - - -	6	L - - -	10
D - - -	3	H - - -	7		


TABLE IV. Code letters for number of decks with shorting switching characteristics.


Code	Number of decks with shorting switching	Code	Number of decks with shorting switching	Code	Number of decks with shorting switching
A - - -	0	E - - -	4	J - - -	8
B - - -	1	F - - -	5	K - - -	9
C - - -	2	G - - -	6	L - - -	10
D - - -	3	H - - -	7		

FIGURE 107-15. SR41 switches, rotary, closed construction, 1/2 ampere, single shaft (MIL-S-3786/41) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD (At atmospheric pressure)	ELECTRICAL RATINGS (milliamperes)		
	28 Vdc	115 Vrms	300 Vrms
Resistive - - - - - - - - - - -	500	125	50
Inductive (2.8 Henries) - - -	50	—	—





1. Common terminal #1.
2. Common terminal #2.
3. Common terminal #3.
4. Common terminal #4. Common #1 (only) required for one pole switch. Commons #1 and #2 (only) required for two pole switch. Commons #1, #2, #3 and #4, required for four pole switch.

PRINTED CIRCUIT BOARD PIN TERM.

INCHES	MM	INCHES	MM	INCHES	MM	INCHES	MM	INCHES	MM
.001	.03	.031	.79	.250	6.35	.531	13.49	.797	20.24
.003	.08	.040	1.02	.300	7.62	.563	14.30	1.000	25.40
.007	.18	.050	1.27	.310	7.87	.578	14.68	1.375	34.92
.010	.25	.060	1.52	.312	7.92	.688	17.48	1.438	36.53
.015	.38	.125	3.18	.375	9.52	.755	19.18	1.750	44.45
.020	.51	.216	5.49	.392	9.96				

FIGURE 107-16. SR40 switches, rotary, open construction, low level and 1/2 ampere (MIL-S-3786/40).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER: Consists of "M3786/40" followed by a dash and a three-character code. The three-character code used in the following example identifies a switch of construction type S, 30° angle of throw, with nonshorting switching characteristic; 3 decks, 1 pole per deck, solder-lug terminals, and has 10 positions.

EXAMPLE: M3786/40- M C K

CONSTRUCTION TYPE, ANGLE OF THROW, AND SWITCHING CHARACTERISTIC (see table I)

NUMBER OF DECKS, NUMBER OF POLES PER DECK, AND TYPE OF TERMINALS (see table II)

NUMBER OF POSITIONS (see table III)

TABLE I. Code letters for construction type, angle of throw, and switching characteristic.

	Construction type		Angle of throw	Switching characteristic
	N	S		
Code - - -	A	G	11.25°	S
Code - - -	B	H	15°	S
Code - - -	C 1/	J 1/	22.5°	S
Code - - -	D 1/	K 1/	30°	S
Code - - -	E	L	22.5°	NS
Code - - -	F	M	30°	NS

1/ Adjacent terminals must be connected together in pairs to obtain shorting characteristic.

TABLE II. Code characters for number of decks, number of poles per deck, and type of terminals.

	Number of decks										Poles per deck	Type of terminals
	1	2	3	4	5	6	7	8	9	10		
Code - - -	A	B	C	D	E	F	G	H	J	K	1	Solder lug
Code - - -	L	M	N	P	Q	R	-	-	-	-	2	Solder lug
Code - - -	S	T	U	V	-	-	-	-	-	-	4	Solder lug
Code - - -	W	-	-	-	-	-	-	-	-	-	1	Printed circuit (PC)
Code - - -	-	X	Y	Z	2	-	-	-	-	-	1	Rear deck PC 1/
Code - - -	3	-	-	-	-	-	-	-	-	-	2	Printed circuit
Code - - -	-	4	5	6	-	-	-	-	-	-	2	Rear deck PC 1/
Code - - -	7	-	-	-	-	-	-	-	-	-	4	Printed circuit
Code - - -	-	8	-	-	-	-	-	-	-	-	4	Rear deck PC 1/

1/ Multi-deck switches with PC terminals on the rear deck have solder lug terminals on all other decks.

TABLE III. Code characters for number of positions.

Code	Number of positions	Code	Number of positions	Code	Number of positions
A - - -	1/ Continuous	M - - -	12 (with stops)	Y - - -	23 (with stops)
B - - -	2 (with stops)	N - - -	13	Z - - -	24
C - - -	3	P - - -	14	2 - - -	25
D - - -	4	Q - - -	15	3 - - -	26
E - - -	5	R - - -	16	4 - - -	27
F - - -	6	S - - -	17	5 - - -	28
G - - -	7	T - - -	18	6 - - -	29
H - - -	8	U - - -	19	7 - - -	30
J - - -	9	V - - -	20	8 - - -	31 (with stops)
K - - -	10	W - - -	21		
L - - -	11(with stops)	X - - -	22 (with stops)		

1/ Switch is continuous rotation type (no stops), and number of positions is dependent on angle of throw: 12 positions for 30° angle; 16 positions for 22.5° angle; 24 positions for 15° angle; and 32 positions for 11.25° angle.

FIGURE 107-16. SR40 switches, rotary, open construction, low level and 1/2 ampere (MIL-S-3786/40) - Continued.

Source: https://assist.dla.mil -- Downloaded: 202640-26T07:41Z
Check the source to verify that this is the current version before use.

SECTION 110

SWITCHES, SENSITIVE

(Applicable specification: MIL-S-8805)

TABLE 110.I. Switches, sensitive, characteristics.

Figure number	Applicable specification sheet MIL-S-8805	Operation	Circuit	Electrical ratings (28 Vdc resistive) (amperes)	General remarks
110-1	/1	Momentary	SPDT	2	
110-2	/2	Momentary	SPDT	5	
110-3	/4	Momentary	SPDT	7	
110-4	/5	Latching - reset button	4 circuit	15	
110-5	/7	Momentary	2 circuit	10	
110-6	/8	Momentary	SPDT	4	Hermetic seal
110-7	/11	Momentary	2 circuit	10	
110-8	/14	Latching - reset button	2 circuit	10	
110-9	/15	Momentary	4 circuit	15	
110-10	/16	Latching - reset button	4 circuit	15	
110-11	/17	Latching - reset button	6 circuit	15	
110-12	/18	Momentary	6 circuit	15	
110-13	/19	Momentary	2 circuit	40	
110-14	/27	Momentary	SPST, SPDT	10	
110-15	/28	Momentary	SPDT	7.5	
110-16	/29	Momentary	SPDT double break	10	
110-17	/31	Momentary	DPDT	10	
110-18	/32	Momentary	SPDT	7	Watertight seal
110-19	/34	Latching - reset button	2 circuit	40	
110-20	/39	Momentary	2PDT 4PDT	7	Plunger - resilient seal
110-21	/40	Momentary	2PDT 2 circuit 4 circuit	4,10 15 15	Plunger - resilient seal
110-22	/41	Momentary	2PDT	5	Plunger - hermetic seal
110-23	/42	Momentary	SPDT	6	Plunger - watertight seal
110-24	/43	Momentary	2PDT 4PDT	7	Pin and roller plunger - resilient seal
110-25	/44	Momentary	SPDT	5	Resilient seal
110-26	/45	Momentary	SPDT	5	Resilient seal
110-27	/47	Momentary	SPDT	25	Hermetic seal
110-28	/48	Roller lever - self return	2PDT 2 circuit 4 circuit	5,10 15 15	Resilient seal
110-29	/49	Rotary linkage lever (nonself-return)	2PDT 2 circuit 4 circuit	4,10 15 10,15	Resilient seal
110-30	/65	Momentary	2PDT	5	Plunger - resilient seal
110-31	/68	Momentary	SPDT	7	Hermetic seal

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.

TABLE 110.I. Switches, sensitive, characteristics - Continued.

Figure number	Applicable specification sheet MIL-S-8805	Operation	Circuit	Electrical ratings (28 Vdc resistive) (amperes)	General remarks
110-32	/70	Momentary	2PDT	7	Pin and roller
			4PDT		plunger-hermetic seal 1/
110-33	/72	Momentary	SPDT	7	Plunger-hermetic seal 1/
110-34	/73	Momentary	SPDT	7	Plunger-hermetic seal 1/
110-35	/74	Momentary	SPDT	7	Plunger-hermetic seal 1/
110-36	/76	Momentary	2 circuit	5	
110-37	/77	Momentary	4 circuit	10	
110-38	/78	Momentary	6 circuit	10	
110-39	/80	Momentary	2PDT	5	Plunger-hermetic seal
110-40	/84	Momentary	6 circuit	10	Watertight seal
110-41	/85	Rotary -	2PDT	4	Resilient seal
		nonself-return	4PDT		
110-42	/90	Momentary	SPDT	10	
110-43	/101	Momentary	2 circuit	5	
110-44	/100	Momentary	2PDT	10	Pin and roller
			4PDT	7	Plunger-resilient seal 2/
110-45	/104	Momentary	4PDT	7	Pin and roller
					Plunger-resilient seal 2/

1/ Minimum current applicable.
2/ Low level circuit and icing applicable.

Supersedes page 110.2
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


Electrical ratings.

Load	Sea level, 28 Vdc		70,000 feet, 28 Vdc	
	NO or NC	2 circuit	NO or NC	2 circuit
	amperes	amperes	amperes	amperes
Resistive - - - -	8	5	8	5
Inductive - - - -	5	3	3	2
Motor - - - - - -	5	---	---	---


Operating characteristics:


Actuating force:	8 ounces maximum
Pretravel:	.035 inch maximum
Overtravel:	.004 inch minimum
Movement differential:	.010 inch minimum

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




ROLLER PLUNGER






PIN PLUNGER

INCHES	MM
.015	.38
.030	.76
.120	3.05
.250	6.35
.500	12.70
.626	15.90
.794	20.17
1.030	26.16
1.375	34.92
1.781	45.24




2PDT



4PDT

FIGURE 110-44. Switches, sensitive, plunger, resilient seal.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



INCHES	MM
.350	8.89
.800	20.32
.925	23.50
1.030	26.16
1.200	30.48
1.315	33.40

WIRE LEADS: M22759/7-20, 72^{+2}_{-0} inches long.

FIGURE 110-44. Switches, sensitive, plunger, resilient seal - Continued.

Procurement document: MIL-S-8805/100.

Electrical ratings. 1/

Load	Sea level 28 Vdc		80,000 ft. 28 Vdc	
	2 PDT	4 PDT	2 PDT	4 PDT
	Amperes	Amperes	Amperes	Amperes
Resistive	10	7	10	7
Inductive	4	2	4	2
Motor	6	4	6	4
Lamp	3	2	2	1

1/ Low level circuit applicable.

Operating characteristics:


Actuating force:	9 +3 pounds.
Full overtravel force:	30 pounds maximum.
Releasing force:	5 pounds minimum.
Pretravel:	.070 inch maximum.
Movement differential:	.035 inch maximum.
Overtravel:	.250 inch minimum.


TABLE 110.XXVI. Part numbers and configuration.

Part number M8805/100-	Actuator	Lead wires
011	Pin plunger	Six wire leads brought out in two rows of three leads each.
012	Pin plunger	Six wire leads brought out from the bottom of the switch.
013	Roller plunger	Six wire leads brought out in two rows of three leads each.
014	Roller plunger	Six wire leads brought out from the bottom of the switch.
015	Pin plunger	Twelve wire leads brought out in two rows of six each.
016	Pin plunger	Twelve wire leads brought out from bottom of switch.
017	Roller plunger	Twelve wire leads brought out in two rows of six each.
018	Roller plunger	Twelve wire leads brought out from bottom of switch.


Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.

INCHES	MM	INCHES	MM
.015	.38	.895	22.73
.030	.76	1.000	25.40
.120	3.05	1.100	27.94
.375	9.52	1.125	28.58
.475	12.06	1.375	34.92
.525	13.34	1.719	43.66
.850	21.59	2.0	50.80
		72.0	1828.80






M8805/104-001
PIN PLUNGER




M8805/104-002
ROLLER PLUNGER

FIGURE 110-45. Switches, sensitive, plunger, resilient seal.

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the currentversion before use.





CIRCUIT SCHEMATIC

INCHES	MM
.100	2.54
.700	17.78
.850	21.59
1.200	30.48

M8805/104-003,004
AXIAL LEAD UNITS

WIRE LEADS: M22710/7-20, 72^{+2}_{-0} inches long.

FIGURE 110-45. Switches, sensitive, plunger, resilient seal - Continued.

Procurement document: MIL-S-8805/104.

Operating characteristics:

Actuating force:	9 +3 pounds.
Full overtravel force:	30 pounds maximum.
Releasing force:	5 pounds minimum.
Pretravel:	.050 inch maximum.
Movement differential:	.030 inch maximum.
Overtravel:	.125 inch minimum.

Electrical ratings. 1/

Load	28 Vdc		115 Vac, 400 Hz	
	Sea level	80,000 ft.	Sea level	80,000 ft.
	Amperes	Amperes	Amperes	Amperes
Resistive	7	7	1	1
Inductive	3	3	1	1
Motor	4	4	1	1
Lamp	2	1	1	1

1/ Low level circuit applicable.

TABLE 110.XXVII. Part numbers.

Part number M8805/104	Actuator	Wire exit
-001	Pin plunger	Side
-002	Roller plunger	
-003	Pin plunger	Bottom
-004	Roller plunger	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

SECTION 111A

SWITCHES, THERMOSTATIC


(Applicable specifications: MIL-S-24236 and MIL-S-28827)

FIGURE NO.	SWITCH CHARACTERISTICS			PAGE
	Specification sheet number	Circuitry	Electrical rating	
111-1	MIL-S-24236/11	SPST	1 ampere	111.2
111-2	MIL-S-24236/13	SPST	1 ampere	111.4
111-3	MIL-S-24236/19	SPST	1 ampere	111.6
111-4	MIL-S-24236/20	SPST	2 amperes	111.8
111-5	MIL-S-24236/2	SPST	5 amperes	111.10
111-6	MIL-S-24236/1	SPST	5 amperes	111.12
111-7	MIL-S-24236/24	SPDT	2 amperes	111.20
111-8	MIL-S-24236/25	SPST	2 amperes	111.23
111-9	MIL-S-24236/26	SPST-SPDT	2 amperes	111.26
111-10	MIL-S-28827/1	SPDT	1 ampere	111.28


Supersedes Section 111 (pages 111.1 thru 111.23) of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS			ENDURANCE
	Sea level		70,000 ft	
	28 V	115 V, 60 Hz	28 V	
	(ampere)	(ampere)	(ampere)	(cycles)
Resistive - - -	1.0	1.0	1.0	10,000
Inductive - - -	.5	.5	.5	10,000
Lamp- - - - - -	.2	.2	.2	10,000



CONFIGURATION 1



CONFIGURATION 2




CONFIGURATION 3

INCHES	MM
.11	2.79
.14	3.56
.320	8.13
.36	9.14
.362	9.19
.39	9.91
.415	10.54
.422	10.72
.445	11.30
.50	12.70
.75	19.05
1.25	31.75
11.5	292.10
12.5	317.60

FIGURE 111-1. Switches, thermostatic (MIL-S-24236/11).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



CONFIGURATION 4

INCHES	MM	INCHES	MM
.17	4.32	.565	14.35
.20	5.08	.69	17.53
.320	8.13	11.5	292.10
.535	13.59	12.5	317.50

PART NUMBER: Consists of "M24236/11" followed by a dash and a four-letter code as shown in the following example:

M24236/11- A A CD

CONFIGURATION AND CONTACT ACTION (see table I)
PROBE LENGTH (see table II)
HIGH TEMPERATURE SETTING (to nearest 25°F, table III; to nearest 5°F, table IV)

TABLE I. Configuration and contact action.

	Configuration				Contact action
	1	2	3	4	
Code - - - -	A	C	E	G	Open on increasing temperature
Code - - - -	B	D	F	H	Close on increasing temperature

TABLE II. Probe length.

Code	Dimension A (inches)
A - - - - -	1.5 (38.10)
B - - - - -	2.0 (50.80)
C - - - - -	2.5 (63.50)
D - - - - -	3.0 (76.20)
E - - - - -	4.0 (101.60)

TABLE III. High temperature setting to the nearest 25°F.

Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)
A - - -	0	F - - -	125	L - - -	250
B - - -	25	G - - -	150	M - - -	275
C - - -	50	H - - -	175	N - - -	300
D - - -	75	J - - -	200	P - - -	325
E - - -	100	K - - -	225	Q - - -	350


TABLE IV. High temperature setting to the nearest 5°F.

Code	Temperature (°F)
A - - -	-10
B - - -	-5
C - - -	0
D - - -	+5
E - - -	+10

FIGURE 111-1. Switches, thermostatic (MIL-S-24236/11) - Continued.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		ENDURANCE (cycles)
	28 Vdc	115 Vac, 60 Hz	
Resistive - -	0.6	1.0	10,000



INCHES	MM
.015	.38
.021	.53
.080	2.03
.130	3.30
.263	6.68
.575	14.61
12.000	304.80

CONFIGURATION 1



CONFIGURATION 2

FIGURE 111-2. Switches, thermostatic (MIL-S-24236/13).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER: Consists of "M24236/13" followed by a dash and a three-letter code as shown in the following example:

M24236/13- A H C

CONFIGURATION AND CONTACT ACTION (see table I)

TEMPERATURE SETTING TO WITHIN 20°F (see table II)

TEMPERATURE SETTING TO WITHIN 5°F (see table III)

TABLE I. Configuration and contact action.

	Configuration		Contact action
	1	2	
Code - - - -	A	C	Open on increasing temperature
Code - - - -	B	D	Close on increasing temperature

TABLE II. High temperature setting to within 20°F.

Code	Temperature (°F)	Code	Temperature (°F)
A - - -	-30	L - - -	170
B - - -	-10	M - - -	190
C - - -	10	N - - -	210
D - - -	30	P - - -	230
E - - -	50	Q - - -	250
F - - -	70	R - - -	270
G - - -	90	S - - -	290
H - - -	110	T - - -	310
J - - -	130	U - - -	330
K - - -	150	V - - -	350


TABLE III. High temperature setting to within 5°F.

Code	Temperature (°F)
A - - -	0
B - - -	+5
C - - -	+10
D - - -	+15

FIGURE 111-2. Switches, thermostatic (MIL-S-24236/13) - Continued.

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS (amperes)		ENDURANCE (cycles)
	28 Vdc	115 Vac, 60 Hz	
Resistive - - - - -	0.5	1.0	10,000



CONFIGURATION 1

CONFIGURATION 2

INCHES	MM
.040	1.02
.060	1.52
.070	1.78
.093	2.36
.110	2.79
.112	2.84
.136	3.45
.156	3.96
.168	4.27
.170	4.32
.189	4.80
.203	5.16
.215	5.46
.250	6.35
.281	7.14
.290	7.37



CONFIGURATION 3

CONFIGURATION 4

NOTE: All configurations are of grounded construction. Configuration 3 has an isolated mounting stud.

FIGURE 111-3. Switches, thermostatic (MIL-S-24236/19).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER: Consists of "M24236/19" followed by a dash and a three-letter code as shown in the following example:

M24236/19- A H C

CONFIGURATION AND CONTACT ACTION (see table I)
HIGH TEMPERATURE SETTING TO WITHIN 20°F (see table II)
HIGH TEMPERATURE SETTING TO WITHIN 5°F (see table III)

TABLE I. Configuration and contact action.

	Configuration				Contact action
	1	2	3	4	
Code - - -	A	C	E	G	Close on increasing temperature
Code - - -	B	D	F	H	Close on decreasing temperature

TABLE II. Temperature setting to within 20°F.

Code	Temperature (°F)	Code	Temperature (°F)
A - - -	-30	L - - -	170
B - - -	-10	M - - -	190
C - - -	10	N - - -	210
D - - -	30	P - - -	230
E - - -	50	Q - - -	250
F - - -	70	R - - -	270
G - - -	90	S - - -	290
H - - -	110	T - - -	310
J - - -	130	U - - -	330
K - - -	150	V - - -	350


TABLE III. Temperature setting to within 5°F.

Code	Unit
A - - -	0
B - - -	+5
C - - -	+10
D - - -	+15

FIGURE 111-3. Switches, thermostatic (MIL-S-24236/19) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS		ENDURANCE
	28 Vdc	115 Vac, 60 Hz	
	(amperes)	(amperes)	(cycles)
Resistive - - -	2.0	2.0	250,000
Inductive - - -	1.0	1.5	250,000
Lamp	1.0	0.5	250,000



INCHES	MM	INCHES	MM
.003	.08	.171	4.34
.005	.13	.218	5.54
.007	.18	.300	7.62
.010	.25	.426	10.82
.015	.38	.453	11.51
.031	.79	.550	13.97
.063	1.60	.660	16.76
.078	1.98	.937	23.80
.104	2.64	1.477	37.52
.125	3.18	1.497	38.02

FIGURE 111-4. Switches, thermostatic (MIL-S-24236/20).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER: Consists of "M24236/20" followed by a dash and a four-letter code. The four-letter code used in the following example identifies a switch of configuration A which closes on increasing temperature at 140 ±4°F and closes on decreasing temperature 2 to 5°F below the actual closing temperature. EXAMPLE:

M24236/20- A GF B

CONFIGURATION AND CONTACT ACTION (see table I)

OPERATING TEMPERATURE (see tables II and III)

TEMPERATURE DIFFERENTIAL (see table IV)

TABLE I. Configuration and contact action.

	Configuration						Contact action
	A	A1	B	B1	C	C1	
Code - - -	A	C	E	G	J	L	Close on increasing temperature
Code - - -	B	D	F	H	K	M	Close on decreasing temperature
Code 1/- -	N	Q	S	U	W	Y	Open on increasing temperature
Code 1/- -	P	R	T	V	X	Z	Open on decreasing temperature

1/ Available tolerance is ±5°F only (see table III).

TABLE II. Temperature setting to the nearest 25°F.

Code	Temperature	Code	Temperature
	°F		°F
A - - -	0	K - - -	225
B - - -	25	L - - -	250
C - - -	50	M - - -	275
D - - -	75	N - - -	300
E - - -	100	P - - -	325
F - - -	125	Q - - -	350
G - - -	150	R - - -	375
H - - -	175	S - - -	400
J - - -	200		

TABLE III. Temperature setting to the nearest 5°F.

	Unit					Tolerance
	-10	-5	0	+5	+10	
Code - - -	A 1/	B	C	D	E	±3°F
Code - - -	F	G	H	J	K	±4°F
Code - - -	L	M	N	P	Q	±5°F

1/ Available to 250°F only.

TABLE IV. Temperature differential.

Code	Available differential	Operating temp. range
A - - -	2 - 4°F	-10° to +250°F
B - - -	2 - 5°F	
C - - -	3 - 7°F	+251° to +400°F

FIGURE 111-4. Switches, thermostatic (MIL-S-24236/20) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

INCHES	MM
.060	1.52
.360	9.14
.390	9.91
.50	12.70
.670	17.02
.990	25.15

LOAD	ELECTRICAL RATINGS		ENDURANCE
	28 V	115 V, 60 Hz	
	(amperes)	(amperes)	(cycles)
Resistive - - -	5.0	2.0	100,000
Inductive - - -	2.5	1.0	100,000
Lamp- - - - - -	1.0	0.5	100,000

INCHES	MM
1.000	25.40
1.010	25.65
1.115	28.32
1.135	28.83
12.00	304.80

NOTE: Do not use in applications where basic switch will be exposed to pressures over 250 psig.




FIGURE 111-5. Switches, thermostatic (MIL-S-24236/2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER: Consists of "M24236/2" followed by a dash and a six-letter code as shown in the following example:

M24236/2- A B G F E N

- CONFIGURATION AND CONTACT ACTION (see table I)
- PROBE LENGTH (see table II)
- HIGH TEMPERATURE SETTING (to nearest 25°F, see table III)
- HIGH TEMPERATURE SETTING (to nearest 5°F and its tolerance, see table IV)
- LOW TEMPERATURE SETTING (to nearest 25°F, see table III)
- LOW TEMPERATURE SETTING (to nearest 5°F and its tolerance, see table IV)

TABLE I. Configuration and contact action.

	Configuration				Contact action
	1	2	3	4	
Code - - -	A	C	E	G	Open on increasing temperature
Code - - -	B	D	F	H	Close on increasing temperature

TABLE II. Probe length.

Code	Dimension A ±.030 (.76) (inches)
A - - -	1.50 (38.10)
B - - -	2.00 (50.80)
C - - -	2.50 (63.50)
D - - -	3.00 (76.20)
E - - -	4.00 (101.60)

TABLE III. Temperature settings to within ±5°F.

Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)
A - - -	-75	J - - -	125	S - - -	325
B - - -	-50	K - - -	150	T - - -	350
C - - -	-25	L - - -	175	U - - -	375
D - - -	0	M - - -	200	V - - -	400
E - - -	25	N - - -	225	W - - -	425
F - - -	50	P - - -	250	X - - -	450
G - - -	75	Q - - -	275	Y - - -	475
H - - -	100	R - - -	300	Z - - -	500


TABLE IV. Temperature settings to within 5°F.

	Tolerance						Unit
	±3°F	±5°F	±8°F	±10°F	±15°F	±25°F	
Code - - -	A	F	L	R	W	2	-10
Code - - -	B	G	M	S	X	3	-5
Code - - -	C	H	N	T	Y	4	0
Code - - -	D	J	P	U	Z	5	+5
Code - - -	E	K	Q	V	1	6	+10

FIGURE 111-5. Switches, thermostatic (MIL-S-24236/2) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATINGS			ENDURANCE
	Sea level		80,000 feet	
	28 V	115 V, 60 Hz	28 V	
	(amperes)	(amperes)	(amperes)	(cycles)
Resistive - - -	5.0	2.0	5.0	100,000
Inductive - - -	2.5	1.0	2.5	100,000
Lamp- - - - - -	1.0	0.5	1.0	100,000



INCHES	MM	INCHES	MM	INCHES	MM	INCHES	MM
.005	.13	.071	1.80	.295	7.49	.560	14.22
.007	.18	.140	3.56	.300	7.62	.640	16.26
.010	.25	.187	4.75	.325	8.25	.937	23.80
.021	.53	.243	6.17	.395	10.03	1.190	30.23
.045	1.14	.250	6.35	.437	11.10	1.260	32.00
.070	1.78	.280	7.11	.468	11.89		

FIGURE 111-6. Switches, thermostatic (MIL-S-24236/1).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



CONFIGURATION B
(MOUNTING BRACKETS NOT FURNISHED)

CONFIGURATION B1

CONFIGURATION B2

CONFIGURATION B3

CONFIGURATION B4

INCHES	MM	INCHES	MM	INCHES	MM
.005	.13	.187	4.75	.500	12.70
.007	.18	.250	6.35	.531	13.49
.010	.25	.280	7.11	.560	14.22
.015	.38	.295	7.49	.640	16.26
.021	.53	.300	7.62	.680	17.27
.071	1.80	.325	8.26	.937	23.80
.125	3.18	.395	10.03	1.190	30.23
.140	3.56	.468	11.89	1.260	32.00

FIGURE 111-6. Switches, thermostatic (MIL-S-24236/1) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

CONFIGURATION A

Operating points				Part No. M24236/1-	Operating points				Part No. M24236/1-
Open on incr temp	Close on decr temp	Open on decr temp	Close on incr temp		Open on incr temp	Close on decr temp	Open on decr temp	Close on incr temp	
(°F)	(°F)	(°F)	(°F)		(°F)	(°F)	(°F)	(°F)	
60 ±5	35 ±5	---	---	0105	115 ±5	80 ±7	---	---	0130
60 ±8	40 ±5	---	---	0100	165 ±5	145 ±5	---	---	0131
70 ±8	50 ±5	---	---	0110	180 ±5	160 ±5	---	---	0132
75 ±8	45 ±8	---	---	0115	215 ±5	195 ±5	---	---	0133
80 ±5	60 ±7	---	---	0120	---	---	180 ±6	170 ±7	0135
90 ±8	70 ±5	---	---	0125	---	---	275 ±10	325 ±12	0140

CONFIGURATION A1

Operating points		Part No. M24236/1-	Operating points		Part No. M24236/1-
Open on increasing temperature	Close on decreasing temperature		Open on increasing temperature	Close on decreasing temperature	
(°F)	(°F)		(°F)	(°F)	
35 ±5	15 ±5	0200	158 ±5	131 ±5	0320
37	20	0205	160 ±3	150	026
45	32	0210	160 ±5	140	0321
60	30	0214	160	145	0325
50	35	0215	167	158	0330
50	40	0220	170	158	0329
55	40	0230	170	160	0331
60	40	0250	173 ±3	149	0335
60	45	0255	173 ±5	158	0336
60	50	0245	176	160	0340
65	50	0260	180	135	0345
70	40	0262	180	170	0350
75	60	0265	185	165	0355
77	72	0590	185	170	0356
85	65	0270	190	170	0360
95	85	0275	194	176	0365
120	100	0280	200	160	0370
125	110	004	200	180	0371
125	120	0281	200	185	0372
128	112	0285	210 ±8	175	0375
131 ±3	120	024	212 ±8	192	0380
135 ±5	110 ±10	0290	230 ±5	205	0379
140	130 ±5	0295	230	220	0381
145	135	025	235	215	032
147	132	0300	250 ±8	210 ±8	0383
150	120	0304	265	180 ±5	0385
150	135	0305	270	250 ±6	0 90
150	140	0306	272	220 ±6	0 95
165	135	0310	275	200 ±6	0-100
158	123	0315	380 ±12	310 ±10	0405

Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-	Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-
(°F)	(°F)		(°F)	(°F)	
17 ±5	31 ±5	027	50 ±5	65 ±5	0435
19	36	0410	62	77	0440
28	38	0415	80	95	0450
28	45	0420	85	95	0451
32 ±9	54 ±9	0425	86	112	0455
40 ±5	60 ±5	0430	86	120	0460

FIGURE 111-6. Switches, thermostatic (MIL-S-24236/1) - Continued.

Source: https://assist.dla.mil -- Downloaded: 202640-26T07:41Z
Check the source to verify that this is the current version before use.

CONFIGURATION A1					
Operating points		Part No. M24236/1-	Operating points		Part No. M24236/1-
Open on decreasing temperature	Close on increasing temperature		Open on decreasing temperature	Close on increasing temperature	
(°F)	(°F)		(°F)	(°F)	
95 ±5	115 ±7	0465	144 ±5	158 ±5	0507
110 ±8	130 ±6	0470	149 ±8	165 ±6	0510
120 ±5	130 ±5	028	150 ±5	160 ±5	0515
120	140	0475	151	167	0520
120	160	0480	165	185	0523
125 ±7	150	0485	170	200	0525
130 ±5	140	0476	174	194	0530
130 ±8	145 ±6	0490	175	190	0535
131 ±5	151 ±3	0495	176	185	0540
133	158 ±5	003	180	200	0649
140	150	0486	180	210 ±6	0545
145	155	0496	185	200 ±5	0550
135	175	0500	192	219	0555
155	175	0501	200	250	0560
138	153	0506	230 ±8	260	0565
138 ±8	153 ±6	0505			

CONFIGURATION A2					
Operating points		Part No. M24236/1-	Operating points		Part No. M24236/1-
Open on increasing temperature	Close on decreasing temperature		Open on increasing temperature	Close on decreasing temperature	
(°F)	(°F)		(°F)	(°F)	
80 ±5	60 ±5	0600	150 ±5	141 ±5	0640
80	65	0605	158	140	0645
90	75	0610	175	160	0650
100	85	0611	181	165	0655
120	111	0615	185	120	0660
130	110	0620	212 ±9	185 ±9	0665
131	116 ±7	0625	225 ±8	150 ±5	0670
140	105 ±7	0630	239 ±5	221 ±5	0675
145	130 ±5	0635	250 ±8	220 ±6	0680
145	135 ±5	0636	480 ±25	420 ±25	0684
Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-	Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-
(°F)	(°F)		(°F)	(°F)	
45 ±5	73 ±5	0685	140 ±5	155 ±5	0710
80	100 ±5	0686	140	160	0715
85	105 ±7	0690	145	160	0720
95	100 ±5	0687	160	180	0725
111	120	0695	170	185	0730
116	125	0700	175	225	0735
120	130	0701	240	255	0736
140	150 ±7	0705	200	280	0740

FIGURE 111-6. Switches, thermostatic (MIL-S-24236/1) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

CONFIGURATION A3					
Operating points		Part No. M24236/1-	Operating points		Part No. M24236/1-
Open on increasing temperature	Close on decreasing temperature		Open on increasing temperature	Close on decreasing temperature	
(°F)	(°F)		(°F)	(°F)	
50 ±5	30 ±5	0800	225 ±10	195 ±8	0830
80	55	0805	230 ±5	210 ±5	0835
158	140	001	239	221	002
170	140	0815	240	227	0836
170	150	0810	248 ±14	194 ±10	0840
190	170	0818	299 ±8	280 ±6	0845
197	177	0820	302 ±12	202 ±6	0850
212 ±8	176	0825			
Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-	Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-
(°F)	(°F)		(°F)	(°F)	
40 ±10	60 ±5	0855	165 ±5	195 ±5	0883
100 ±5	120	0860	175 ±5	205	0884
105	120	0865	180 ±6	210	0885
130	160	0871	185 ±5	210	0886
140	165	0872	195 ±5	220	0887
149	158 ±4	0870	200 ±8	230 ±8	0888
150	175 ±5	0876	205	230	0889
155	170	0875	210	240	0891
155	185	0881	220	250	0892
160	185	0882	248	266 ±6	0890
165	180	0880			

CONFIGURATION B					
Operating points		Part No. M24236/1-	Operating points		Part No. M24236/1-
Open on increasing temperature	Close on decreasing temperature		Open on increasing temperature	Close on decreasing temperature	
(°F)	(°F)		(°F)	(°F)	
75 ±5	55 ±5	0895	212 ±8	194 ±5	0935
100 ±8	85	0900	224 ±4	See 1/	0940
125 ±5	100	0905	229 ±3	199 ±5	0945
160 ±3	See 1/	0915	275 ±8	235 ±6	0948
160 ±5	40 ±5	0910	290 ±8	250 ±6	0949
176 ±3	See 1/	0920	350 ±12	310 ±10	0950
194 ±15	175 ±15	0925	420 ±15	350 ±10	0955
205 ±3	See 1/	0930			
Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-	Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-
(°F)	(°F)		(°F)	(°F)	
115 ±5	130 ±5	0960	See 2/	88 ±3	0985
173	203	0965	See 2/	124 ±3	0990
180	200	0970	See 2/	153 ±5	0995
215 ±8	250 ±8	0975	See 2/	176 ±5	1000
215 ±8	245 ±8	0980	See 2/	205 ±4	1005

1/ 9-14 below open.
2/ 9-14 below close.

FIGURE 111-6. Switches, thermostatic (MIL-S-24236/1) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

CONFIGURATION B1

Operating points: Open on increasing temperature	Operating points: Close on decreasing temperature	Part No. M24236/1-
(°F)	(°F)	
25 ±5	10 ±5	1100
30	20	1105
43	28	1110
45	30	1115
50	30	1116
50	35	1120
50	40	1121
55	40	1125
See 1/	60 ±3	1130
60 ±5	40 ±7	1135
65	50 ±5	1140
70	40	1145
70	55	1150
75	35 ±10	1155
77	37 ±5	1159
78	58	1160
80	70	1165
90	80	1170
95	60	1175
95	81	1180
96	85	1185
99	90	1195
115	100	1200
115 ±4	105 ±4	1205
130 ±5	115 ±5	1210
135	120	1215
135	126	1220
140	120	1225
140	125	1230
145	135 ±4	1235
150	130 ±5	1240
150	135 ±5	1245
155	100 ±10	1250
155	140 ±5	1255
158	138 ±5	1260
160	120 ±7	1265
160	140 ±6	1270

Operating points: Open on increasing temperature	Operating points: Close on decreasing temperature	Part No. M24236/1-
(°F)	(°F)	
160 ±5	150 ±5	1275
164	149	006
165	155	1280
170	130 ±10	1290
172	159 ±5	1295
175	150	1296
178	158	1305
180	160	1310
180	165	1315
185	175	1320
190	175	1325
190	180	1330
194	180	1335
196	176	1340
198	170 ±7	1345
200	180 ±5	1350
200	185 ±5	1355
205	182 ±7	1360
205 ±6	230 ±8	1365
207 ±8	192 ±5	1370
212	150	1375
215	195	1380
220	176	1385
220	200	1395
230	210 ±6	1400
239 ±6	160 ±12	1405
239 ±8	209 ±6	1410
240	220	1415
240	230	1420
250	230	1425
260	230	1430
260 ±5	248 ±5	1431
274 ±7	194 ±15	1435
275 ±7	245 ±10	1440
280 ±8	250 ±6	1445
320 ±7.	305 ±7	1451
400 ±10	350 ±10	005

Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-
(°F)	(°F)	
32 ±5	77 ±5	1456
35	50	1460
45	55	1465
50	68	1475
50 ±6	65	1470
55 ±5	65	1480
See 2/	66 ±3	1485
See 2/	87 ±3	1490
68 ±6	95 ±5	1495
See 2/	97 ±3	1500

Open on decreasing temperature	Close on increasing temperature	Part No. M24236/1-
(°F)	(°F)	
70 ±5	100 ±5	1505
70	105	1510
80	100	1515
85	95	1520
96	105	1525
105	120	1530
See 2/	115 ±3	1535
115 ±5	130 ±5	1540
See 2/	124 ±3	1545
140 ±5	160 ±5	1550

See footnotes at end of configuration B1.

FIGURE 111-6. Switches, thermostatic (MIL-S-24236/1) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

CONFIGURATION B1					
Operating points		Part No. M24236/1-	Operating points		Part No. M24236/1-
Open on decreasing temperature	Close on increasing temperature		Open on decreasing temperature	Close on increasing temperature	
(°F)	(°F)		(°F)	(°F)	
140 ±5	165 ±5	1555	185 ±5	215 ±6	1585
140 ↓	180 ±5	1560	190 ↓	210 ↓	1590
165 ↓	175 ±4	1285	200 ↓	250 ↓	1595
146 ↓	160 ±5	1565	210 ±8	240 ↓	1600
See 3/	156 ±3	1570	230 ±8	265 ↓	1605
156 ±6	176 ±5	1575	255 ±8	300 ↓	1610
174 ±5	194 ↓	1580	305 ±10	330 ±10	1611
185 ±5	195 ↓	1581			

1/ 3-7 above close.
2/ 2-6 below close.
3/ 1-4 below close.

CONFIGURATION B2					
Operating points		Part No. M24236/1-	Operating points		Part No. M24236/1-
Open on increasing temperature	Close on decreasing temperature		Open on decreasing temperature	Close on increasing temperature	
(°F)	(°F)		(°F)	(°F)	
70 ±5	61 ±5	1700	75 ±5	125 ±5	1725
160 ↓	140 ↓	1705	96 ±5	110 ±5	1730
162 ↓	153 ↓	1706	125 ±5	140 ±5	1735
200 ↓	180 ↓	0391	145 ±5	160 ±5	0390
248 ±8	218 ±6	1710	240 ±8	260 ±6	1755
255 ±8	220 ↓	1715			
325 ±12	285 ↓	1720			
482 ±25	420 ±25	1723			

CONFIGURATION B3		
Operating points		Part No. M24236/1-
Open on increasing temperature	Close on decreasing temperature	
(°F)	(°F)	
75 ±8	55 ±5	1800
252 ±9	203 ±9	1805
325 ±12	275 ±12	1810

FIGURE 111-6. Switches, thermostatic (MIL-S-24236/1) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER (if not in tabulation): Shall consist of "M24236/1" followed by a dash and a five-letter code. The five-letter code used in the following example identifies a temperature switch of configuration A which opens on increasing temperature at 65° ±5°F and closes on decreasing temperature at 25° ±5°F EXAMPLE:




TABLE I. Configuration and contact action.

	Configuration									Contact action
	A	A1	A2	A3	B	B1	B2	B3	B4	
Code -	A	C	E	G	J	L	N	Q	S	Open on increasing temperature
Code -	B	D	F	H	K	M	P	R	T	Open on decreasing temperature

TABLE II. Temperature setting to the nearest 25°F.

Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)
A - - -	-75	J - - -	125	S - - -	325
B - - -	-50	K - - -	150	T - - -	350
C - - -	-25	L - - -	175	U - - -	375
D - - -	0	M - - -	200	V - - -	400
E - - -	25	N - - -	225	W - - -	425
F - - -	50	P - - -	250	X - - -	450
G - - -	75	Q - - -	275	Y - - -	475
H - - -	100	R - - -	300	Z - - -	500


TABLE III. Temperature setting to the nearest 5°F.

	Tolerance						Units
	±3°F	±5°F	±8°F	±10°F	±15°F	±25°F	
Code - - -	A	F	L	R	W	2	-10
Code - - -	B	G	M	S	X	3	-5
Code - - -	C	H	N	T	Y	4	0
Code - - -	D	J	P	U	Z	5	+5
Code - - -	E	K	Q	V	1	6	+10

FIGURE 111-6. Switches, thermostatic (MIL-S-24236/1) - Continued.


Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS			ENDURANCE
	Sea level		80,000 feet	
	28 V	115 V, 60 Hz	28 V	
	(amperes)	(amperes)	(amperes)	(cycles)
Resistive - - -	2.0	2.0	2.0	100,000
Inductive - - -	1.0	1.0	1.0	100,000
Lamp- - - - - -	0.5	0.5	0.5	100,000




CONFIGURATION A

(MOUNTING BRACKETS NOT FURNISHED)



CONFIGURATION A1




CONFIGURATION A2


INCHES	MM
.005	.13
.007	.18
.021	.53
.039	.99
.055	1.40
.070	1.78
.140	3.56
.160	4.06
.164	4.17
.265	6.73
.285	7.24
.328	8.33
.350	8.89
~~.405~~	~~10.29~~
.468	11.89
.500	12.70
.560	14.22
.640	16.26
.800	20.32
.937	23.80
1.140	28.96
1.200	30.48
1.260	32.00

FIGURE 111-7. Switches, thermostatic (MIL-S-24236/24).


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




Configuration A3 (stud mounted)



Configuration B
(MOUNTING BRACKETS NOT FURNISHED)



Configuration B1



Configuration B2



WIRING DIAGRAM

Below low temperature setting, circuit 1-2 is open.
Above high temperature setting, circuit 2-3 is open.

FIGURE 111-7. Switches, thermostatic (MIL-S-24236/24) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER: Consists of "M24236/24" followed by a dash and a five-letter code. The five-letter code used in the following example identifies a switch of configuration A which actuates at 65 ±6°F and deactuates at 25 ±6°F. EXAMPLE:




TABLE I. Configuration.

	Configuration						
	A	A1	A2	A3	B	B1	B2
Code - - -	A	B	C	D	E	F	G

TABLE II. Temperature setting to the nearest 25°F.

Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)
A- - -	-75	F- - -	50	L- - -	175	[illegible]- - -	300
B- - -	-50	G- - -	75	M- - -	200	[illegible]- - -	325
C- - -	-25	H- - -	100	N- - -	225	T- - -	350
D- - -	0	J- - -	125	P- - -	250	U- - -	375
E- - -	25	K- - -	150	Q- - -	275	V- - -	400


TABLE III. Temperature setting to the nearest 5°F.

	Unit					Tolerance
	-10	-5	0	+5	+10	
Code - - -	A	B	C	D	E	±4°F
Code - - -	F	G	H	J	K	±6°F
Code - - -	L	M	N	P	Q	±8°F
Code - - -	R	S	T	U	V	±10°F
Code - - -	W	X	Y	Z	1	±12°F

FIGURE 111-7. Switches, thermostatic (MIL-S-24236/24) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		ENDURANCE
	28 Vdc	115 Vac, 60 Hz	(cycles)
Res stive - - - -	2.0	2.0	250,000
Ind ctive - - - -	1.0	1.5	250,000
Lar - - - - - - -	1.0	0.5	250,000



INCHES	MM
.360	9.14
.390	9.91
.394	10.01
.665	16.89
.990	25.15
1.010	25.65
12.00	304.80

PART NUMBER: Consists of "M24236/25" followed by a dash and a five-letter code as shown in the following example:

M24236/25- A GF B C

- CONFIGURATION AND CONTACT ACTION (see table I)
- LOSING TEMPERATURE (see tables II and III)
- EMPERATURE DIFFERENTIAL (see table IV)
- ROBE LENGTH (see table V)

FIGURE 111-8. Switches, thermostatic (MIL-S-24236/25).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




TABLE I. Configuration and contact action.

	Configuration				Contact action
	A	B	C	D	
Code - - -	A	C	E	G	Close on increasing temperature
Code - - -	B	D	F	H	Close on decreasing temperature

TABLE II. Temperature setting to the nearest 25°F.

Code	Temperature (°F)	Code	Temperature (°F)
A - - -	0	K - - -	225
B - - -	25	L - - -	250
C - - -	50	M - - -	275
D - - -	75	N - - -	300
E - - -	100	P - - -	325
F - - -	125	Q - - -	350
G - - -	150	R - - -	375
H - - -	175	S - - -	400
J - - -	200		

FIGURE 111-8. Switches, thermostatic (MIL-S-24236/25) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

TABLE III. Temperature setting to the nearest 5°F.

	Tolerance			Unit
	* ±3°F	±4°F	±5°F	
Code - - -	A	F	L	-10
Code - - -	B	G	M	-5
Code - - -	C	H	N	0
Code - - -	D	J	P	+5
Code - - -	E	K	Q	+10

*Available to 250°F only.

TABLE IV. Temperature differential.

Code	Available differential	Closing temperature range
A - - -	2-4°F	-10°F to +250°F
B - - -	2-5°F	
C - - -	3-7°F	+251°F to +400°F

TABLE V. Probe length.

Code	Length ±.030 (.76)	Code	Length ±.030 (.76)
	inches (mm)		inches (mm)
A - - -	1.5 (38.10)	F - - -	4.0 (101.60)
B - - -	2.0 (50.80)	G - - -	4.5 (114.30)
C - - -	2.5 (63.50)	H - - -	5.0 (127.00)
D - - -	3.0 (76.20)	J - - -	5.5 (139.70)
E - - -	3.5 (88.90)	K - - -	6.0 (152.40)

FIGURE 111-8. Switches, thermostatic (MIL-S-24236/25) - Continued.

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the currentversion before use.

LOAD	ELECTRICAL RATINGS (amperes)		ENDURANCE (cycles)
	28 Vdc	115 Vac, 60 Hz	
Resistive - - - - - -	2.0	2.0	50,000
Inductive - - - - - -	1.0	1.0	50,000
Lamp- - - - - - - -	0.5	0.5	50,000





FIGURE 111-9. Switches, thermostatic (MIL-S-24236/26).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



INCHES	MM
.045	1.14
.051	1.30
.170	4.32
.250	6.35
.438	11.13
.440	11.18
.562	14.27
.625	15.88
.890	22.61
2.113	53.67
2.520	64.01

OPERATING TEMPERATURE DIFFERENTIAL: 10°F to 55°F.

PART NUMBER: Consists of "M24236/26" followed by a dash and a three-letter code as shown in the following example:

M24236/26- A H C

CONFIGURATION AND CONTACT ACTION (see table I)
TEMPERATURE SETTING TO WITHIN 25°F (see table II)
TEMPERATURE SETTING TO WITHIN 5°F (see table III)

TABLE I. Configuration and contact action.

	Configuration				Contact action
	A	B	C	D	
Code - - -	A	D	G	K	SPST, close on temperature rise
Code - - -	B	E	H	L	SPST, open on temperature rise
Code - - -	C	F	J	M	SPDT

TABLE II. Operating temperature setting to the nearest 25°F.

Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)
A - - -	100	H - - -	275	Q - - -	450
B - - -	125	J - - -	300	R - - -	475
C - - -	150	K - - -	325	S - - -	500
D - - -	175	L - - -	350	T - - -	525
E - - -	200	M - - -	375	U - - -	550
F - - -	225	N - - -	400	V - - -	575
G - - -	250	P - - -	425	W - - -	600


TABLE III. Temperature setting to the nearest 5°F.

	Tolerance				Temperature (°F)
	±8°F	±10°F	±12°F	±15°F	
Code - - -	A	F	L	R	-10
Code - - -	B	G	M	S	- 5
Code - - -	C	H	N	T	0
Code - - -	D	J	P	U	+ 5
Code - - -	E	K	Q	V	+10

FIGURE 111-9. Switches, thermostatic (MIL-S-24236/26) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.


LOAD	ELECTRICAL RATING (amperes) 28 Vdc	ENDURANCE (cycles)
Resistive	.080 to 1.0	25,000



CONFIGURATION I

CONFIGURATION II

INCHES	MM
.35	8.89
.38	9.65
.68	17.27
.75	19.05
.813	20.65
1.65	41.91
1.85	46.99
3.00	76.20



ELECTRICAL RECEPTACLE

FIGURE 111-10. Switches, thermostatic (MIL-S-28827/1).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

PART NUMBER: Consists of "M28827/1" followed by a dash and a five-letter code as shown in the following example:

M28827/1- A CD AB

- CONFIGURATION AND SETTING MODE (see table I)
- HIGH TEMPERATURE SETTING (first code, within 20°F; second code, within 2°F (see table II)
  or
  DIFFERENTIAL SETTING (first code, low end; second code, high end) (see table III)
- LOW TEMPERATURE SETTING (first code, within 20°F; second code, within 2°F (see table II)
  or
  DIFFERENTIAL SETTING (first code, low end; second code, high end) (see table III)

TABLE I. Configuration and setting modes.

	Configuration		High setting	Low setting
Code - - - -	A	J	At temperature with applicable tolerance of table II	At temperature with applicable tolerance of table II
Code - - -	B	K	At temperature with applicable tolerance of table II	By maximum or minimum temperature of table II
Code - - -	C	L	At temperature with applicable tolerance of table II	Differential (see table III)
Code - - -	D	M	By maximum or minimum temperature of table II	At temperature with applicable tolerance of table II
Code - - -	E	N	By maximum or minimum temperature of table II	By maximum or minimum temperature of table II
Code - - -	F	P	By maximum or minimum temperature of table II	Differential (see table III)
Code - - -	G	Q	Differential (see table III)	At temperature with applicable tolerance of table II
Code - - -	H	R	Differential (see table III)	By maximum or minimum temperature of table II

TABLE II. Temperature settings.

TEMPERATURE SETTINGS TO WITHIN 20 °F							
Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)
A - - -	100	F - - -	200	L - - -	300	R - - -	400
B - - -	120	G - - -	220	M - - -	320	S - - -	420
C - - -	140	H - - -	240	N - - -	340	T - - -	440
D - - -	160	J - - -	260	P - - -	360	U - - -	460
E - - -	180	K - - -	280	Q - - -	380	V - - -	480
						W - - -	500

TEMPERATURE SETTINGS TO WITHIN 2°F									
	Maximum, minimum, or ±5°F tolerance	±10°F tolerance	±25°F tolerance	Temperature		Maximum, minimum, or ±5°F tolerance	±10°F tolerance	±25°F tolerance	Temperature
Code - -	A	L	W	0	Code - -	F	R	2	10
Code - -	B	M	X	2	Code - -	G	S	3	12
Code - -	C	N	Y	4	Code - -	H	T	4	14
Code - -	D	P	Z	6	Code - -	J	U	5	16
Code - -	E	Q	1	8	Code - -	K	V	6	18

TABLE III. Differential temperature settings.

Code	Temperature (°F)	Code	Temperature (°F)	Code	Temperature (°F)
A - -	0	E - -	20	J - -	40
B - -	5	F - -	25	K - -	45
C - -	10	G - -	30	L - -	50
D - -	15	H - -	35	M - -	60
				N - -	75

FIGURE 111-10. Switches, thermostatic (MIL-S-28827/1) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

SECTION 112

SWITCHES, TOGGLE
(Applicable specifications: MIL-S-3950, MIL-S-8834, and MIL-S-8805)

FIGURE AND SPEC NUMBER	MS NUMBER (see NOTE)	SWITCH CHARACTERISTICS			PAGE
		Dash No. for:		Circuit characteristics	
		3 Position	2 Position		
112-1 - MIL-S-3950	MS24523	21,27,31	22,23,26,29,30	One pole	112.3
112-2 - MIL-S-3950	MS24524	21,27,31	22,23,26,29,30	Two pole	112.4
	MS24525	21,27,31	22,23,26,29,30	Four pole	
	MS27406	1,2,3	---	Four pole	
	MS27407	1,2,3	---	Two pole	
112-3 - MIL-S-3950	* MS24658	21,27,31	22,23,26,28,29, 30,32	One pole	112.5
112-4 - MIL-S-3950	* MS24659	21,27,31	22,23,26,28,29, 30,32	Two pole	112.6
	* MS24660	21,27,31	22,23,26,28,29, 30,32	Four pole	
	* MS27408	1,2,3	---	Two pole	
	* MS27409	1,2,3	---	Four pole	
112-5 - MIL-S-3950	MS27722	21,27,31	22,23,26,28,29, 30,32	One pole	112.7
	MS27784	21,27,31	22,23,26,28,29, 30,32	One pole	
112-6 - MIL-S-3950	MS27723	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Two pole	112.8
	MS27724	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Four pole	
112-7 - MIL-S-3950	MS27785	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Two pole	112.9
	MS27786	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Four pole	
112-8 - MIL-S-3950	* MS27782	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Two pole	112.10
	* MS27783	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Four pole	
112-9 - MIL-S-3950	* MS27788	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Two pole	112.11
	* MS27789	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Four pole	
112-10 - MIL-S-3950	* MS27781	21,27,31	22,23,26,28,29, 30,32	One pole	112.12
	* MS27787	21,27,31	22,23,26,28,29, 30,32	One pole	
112-11 - MIL-S-3950	MS27734	21,27,31	22,23,26,28,29, 30,32	One pole	112.13
112-12 - MIL-S-3950	MS27735	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Two pole	112.14
	MS27736	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Four pole	
112-13 - MIL-S-3950	* MS27737	21,27,31	22,23,26,28,29, 30,32	One pole	112.15
112-14 - MIL-S-3950	* MS27738	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Two pole	112.16
	* MS27739	1,2,3,21, 27,31	22,23,26,28,29, 30,32	Four pole	
112-15 - MIL-S-8834	MS14001	212,272,312	222,232,242, 262,282,292,302	One pole	112.17
	MS14002	212,272,312	222,232,242, 262,282,292,302	Two pole	
	MS14003	212,272,312	222,232,242, 262,282,292,302	Four pole	


Source: https://assist.dla.mil -- Downloaded: 202640-26T07:41Z
Check the source to verify that this is the current version before use.

FIGURE AND SPEC NUMBER	MS NUMBER (see NOTE)	SWITCH CHARACTERISTICS			PAGE
		Dash No. for:		Circuit characteristics	
		3 Position	2 Position		
112-16 - MIL-S-8834	* MS21026	211,271,311	221,231,241,281	One pole	112.18
	* MS21027	211,271,311,371	221,231,241,281,381	Two pole	
112-17 - MIL-S-8834	MS21346	211,271,311	221,231,241,281	One pole	112.19
	MS21347	211,271,311	221,231,241,281	Two pole	
112-18 - MIL-S-8834	MS21350	---	321	One pole	112.20
	MS21351	---	321	One pole	
112-19 - MIL-S-8834	MS21352	331,341,351	321	Two pole	112.21
	MS21353	331,341,351	321	Two pole	
112-20 - MIL-S-8834	MS21354	211,271,311	221,231,241,281	One pole	112.22
	MS21355	211,271,311	221,231,241,281	Two pole	
112-21 - MIL-S-8834	MS21356	211,271,311	221,231,241,281	One pole	112.23
	MS21357	211,271,311	221,231,241,281	Two pole	
112-22 - MIL-S-8834	* MS24612	212,272,312	222,232,242, 262,282,292,302	One pole	112.24
	* MS24613	212,272,312	222,232,242, 262,282,292,302	Two pole	
	* MS24614	212,272,312	222,232,242, 262,282,292,302	Four pole	
112-23 - MIL-S-8834	MS24655	211,271,311	221,231,241,281	One pole	112.25
	MS24656	211,271,311	221,231,241,281	Two pole	
112-24 - MIL-S-8834	MS25306	212,272,312	222,232,242, 262,282,292,302	One pole	112.26
	MS25307	212,272,312	222,232,242, 262,282,292,302	Two pole	
	MS25308	212,272,312	222,232,242, 262,282,292,302	Four pole	
112-25 - MIL-S-8834	MS90310	211,271,311	221,231,241,281	One pole	112.27
	MS90311	211,271,311	221,231,241,281	Two pole	
112-26 - MIL-S-8805/26	*	005,006,007, 008,009,010	001,003	Two pole	112.28
		011,012,013, 014	---	Three pole	
		---	002,004	Four pole	
112-27 - MIL-S-8805/92	*	005,006,007, 008,009,010, 011,012,013, 014,015,016, 017,018	001	Two pole	112.30
		019	---	Three pole	
		---	002,003,004	Four pole	
112-28 - MIL-S-8805/93	*	001 thru 007	---	Two pole	112.32
		008 thru 014	---	Four pole	
		015 thru 021	---	Six pole	
		022 thru 028	---	Eight pole	

NOTE: The part number consists of the MS number followed by the dash number; however, an asterisk (*) indicates that the "MS" part number will require an additional letter, or an "M" part number is applicable, as shown in the figure.

Supersedes page 112.2
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)					
				28 Vdc and 115 Vac, 400 Hz Load			115 Vac, 60 Hz Load		
	Opposite keyway side	Center	Keyway side	Lamp	Resistive	Inductive	Lamp	Resistive	Inductive
-212	ON	OFF	ON	7	25	15	7	20	15
-222	ON	NONE	OFF						
-232	ON	NONE	ON						
-242	ON	OFF	NONE						
-262	ON	NONE	MOM-ON						
-272	MOM-ON	OFF	MOM-ON						
-282	NONE	OFF	MOM-ON						
-292	ON	NONE	MOM-OFF						
-302	OFF	NONE	MOM-ON						
-312	ON	OFF	MOM-ON						

1/ Applicable terminal numbers are marked on the switch.

PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-15. MS14001, MS14402, and MS14003 toggle switches, positive break, environmentally sealed, solder lug, .469 mounting bushing (MIL-S-8834).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



KEYWAY SIDE →

A LOCKED IN THREE POSITIONS	B LOCKED IN CENTER POSITION	C LOCKED IN KEYWAY SIDE	E LOCKED OUT OF CENTER POSITION
F LOCKED IN CTR POS MOM. EITHER SIDE	G LOCKED OUT OF KEYWAY SIDE, MOM. KEYWAY SIDE	H LOCKED OUT OF SIDE OPP KEYWAY, MOM. EITHER SIDE	J LOCKED OUT OF & INTO SIDE OPP KEYWAY
K LOCKED IN CTR POS, MOM. KEYWAY SIDE	L LOCKED OUT OF SIDE OPP KEYWAY, MOM. KEYWAY SIDE		


Number	Locking comb.	1/ Circuit with toggle lever in			Current capacity (amperes)						Minimum current capacity per pole 5 mV ac-dc
					Resistive load			Inductive load			
		Opposite keyway side	Center	Keyway side	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	
											(μA)
211	A	ON	OFF	ON	5	2	3	1	1	2	25
221	C,E	ON	NONE	OFF							
231	C,E	ON	NONE	ON							
241	J,B	ON	OFF	NONE							
271	F,H	MOM-ON	OFF	MOM-ON							
281	K	NONE	OFF	MOM-ON							
311	G,K,L	ON	OFF	MOM-ON							
2/ 371	F,H	MOM-ON	OFF	MOM-ON							
2/ 381	K	NONE	OFF	MOM-ON							

1/ Applicable terminal numbers are marked on the switch.
2/ MS21027 only.

PART NUMBER: Consists of the applicable MS number followed by the locking combination letter and the three-digit number as shown in the tabulation.

FIGURE 112-16. MS21026 and MS21027 toggle switches, positive break, lever lock, miniature, toggle sealed, solder lug, .469 mounting bushing (MIL-S-8834).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)						Life low current level switching 5 mV
				Resistive load			Inductive load			
	Opposite keyway side	Center	Keyway side	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	(μA)
-211	ON	OFF	ON	5	2	3	1	1	2	25
-221	ON	NONE	OFF							
-231	ON	NONE	ON							
-241	ON	OFF	NONE							
-271	NON-ON	OFF	NON-ON							
-281	NONE	OFF	NON-ON							
-311	ON	OFF	NON-ON							

1/ Applicable terminal numbers are marked on the switch.


PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-17. MS21346 and MS21347 toggle switches, positive break, miniature, toggle sealed, integrated wire terminals, .469 mounting bushing (MIL-S-8834).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



(6.36)
MS 21350 (.250 MOUNTING BUSHING)



(11.91)
MS 21351 (.469 MOUNTING BUSHING)


Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)						Life low current level switching 5 mV
				Resistive load			Inductive load			
	Opposite keyway side	Center	Keyway side	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	
										(mA)
-321	NONE	ON	NON-ON	5	2	3	1	1	2	25

1/ Applicable terminal numbers are marked on the switch.


PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-18. MS21350 and MS21351 toggle switches, positive break, special circuit, miniature, toggle sealed, solder lug, single pole (MIL-S-8834).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



(6.35)
MS 21352 (.250 MOUNTING BUSHING)



(11.91)
MS 21353 (.469 MOUNTING BUSHING)

Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)						Life low current level switching 5 mV
				Resistive load			Inductive load			
				28 Vdc	115 Vac		28 Vdc	115 Vac		
	Opposite keyway side	Center	Keyway side		60 Hz	400 Hz		60 Hz	400 Hz	
										(μA)
-321 -331 -341 -351	NONE ON MOM-ON ON	ON ON ON ON	MOM-ON ON MOM-ON MOM-ON	5	2	3	1	1	2	25


1/ Applicable terminal numbers are marked on the switch.

PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-19. MS21352 and MS21353 toggle switches, positive break, special circuit, miniature, toggle sealed, solder lug, double pole (MIL-S-8834).

Supersedes page 112.21
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)						Life low current level switching 5 mV
				Resistive load			Inductive load			
				28 Vdc	115 Vac		28 Vdc	115 Vac		
	Opposite locking tab side	Center	Locking tab side		60 Hz	400 Hz		60 Hz	400 Hz	
										(μA)
-211	ON	OFF	ON	5	2	3	1	1	2	25
-221	ON	NONE	OFF							
-231	ON	NONE	ON							
-241	ON	OFF	NONE							
-271	MOM-ON	OFF	MOM-ON							
-281	NONE	OFF	MOM-ON							
-311	ON	OFF	MOM-ON							

1/ Applicable terminal numbers are marked on the switch.

PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-20. MS21354 and MS21355 toggle switches, positive break, miniature, toggle sealed, printed circuit board terminals, .250 mounting bushing (MIL-S-8834).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)						Life low current level switching 5 mV
				Resistive load			Inductive load			
				28 Vdc	115 Vac		28 Vdc	115 Vac		
	Opposite keyway side	Center	Keyway side		60 Hz	400 Hz		60 Hz	400 Hz	(μA)
-211	ON	OFF	ON	5	2	3	1	1	2	25
-221	ON	NONE	OFF							
-231	ON	NONE	ON							
-241	ON	OFF	NONE							
-271	MOM-ON	OFF	MOM-ON							
-281	NONE	OFF	MOM-ON							
-311	ON	OFF	MOM-ON							


1/ Applicable terminal numbers are marked on the switch.

PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-21. MS21356 and MS21357 toggle switches, positive break, miniature, toggle sealed, printed circuit board terminals, .469 mounting bushing (MIL-S-8834).

Supersedes page 112.23
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



KEYWAY SIDE →

A LOCKED IN THREE POSITIONS	B LOCKED IN CENTER POSITION	C LOCKED IN KEYWAY SIDE	E LOCKED OUT OF CENTER POSITION
F LOCKED IN CTR POS MOM. EITHER SIDE	G LOCKED OUT OF KEYWAY SIDE, MOM. KEYWAY SIDE	H LOCKED OUT OF SIDE OPP KEYWAY, MOM. EITHER SIDE	J LOCKED OUT OF & INTO SIDE OPP KEYWAY
K LOCKED IN CTR POS, MOM. KEYWAY SIDE	L LOCKED OUT OF SIDE OPP KEYWAY, MOM. KEYWAY SIDE	M LOCKED OUT OF SIDE OPP KEYWAY, MOM. KEYWAY SIDE	N LOCKED OUT OF & INTO SIDE OPP KEYWAY, MOM KWY SIDE


Number	Available locking combinations	1/ Circuit with toggle lever in			Current capacity (amperes)					
					28 Vdc and 115 Vac, 400 Hz			115 Vac, 60 Hz		
		Opposite keyway side	Center	Keyway side	Load			Load		
					Lamp	Resistive	Inductive	Lamp	Resistive	Inductive
212	A	ON	OFF	ON	7	25	15	7	20	15
222	C,E	ON	NONE	OFF						
232	C,E	ON	NONE	ON						
242	J,B	ON	OFF	NONE						
252	L	ON	NONE	MOM-ON						
262	F,H	MOM-ON	OFF	MOM-ON						
272	K	NONE	OFF	MOM-ON						
282	L	ON	NONE	MOM-OFF						
292	L	OFF	NONE	MOM-ON						
302	G,K,M,N	ON	OFF	MOM-ON						

1/ Applicable terminal numbers are marked on the switch.

PART NUMBER: Consists of the applicable MS number followed by the locking combination letter and the three-digit number as shown in the tabulation.

FIGURE 112-22. MS24612, MS24613, and MS24614 toggle switches, positive break, lever lock, environmentally sealed, screw terminals, .469 mounting bushing (MIL-S-6834).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)						Life low current level switching 5 mV
				Resistive load			Inductive load			
	Opposite locking tab side	Center	Locking tab side	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	28 Vdc	115 Vac 60 Hz	115 Vac 400 Hz	(μA)
-211	ON	OFF	ON	5	2	3	1	1	2	25
-221	ON	NONE	OFF							
-231	ON	NONE	ON							
-241	ON	OFF	NONE							
-271	MOM-ON	OFF	MOM-ON							
-281	NONE	OFF	MOM-ON							
-311	ON	OFF	MOM-ON							


1/ Applicable terminal numbers are marked on the switch.


PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-23. MS24655 and MS24656 toggle switches, positive break, miniature, toggle sealed, solder lug, .250 mounting bushing (MIL-S-8834).

Supersede; page 112.25
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.






Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)					
				28 Vdc and 115 Vac, 400 Hz			115 Vac, 60 Hz		
				Load			Load		
	Opposite keyway side	Center	Keyway side	Lamp	Resistive	Inductive	Lamp	Resistive	Inductive
-212	ON	OFF	ON	7	25	15	7	20	15
-222	ON	NONE	OFF						
-232	ON	NONE	ON						
-242	ON	OFF	NONE						
-262	ON	NONE	MOM-ON						
-272	MOM-ON	OFF	MOM-ON						
-282	NONE	OFF	MOM-ON						
-292	ON	NONE	MOM-OFF						
-302	OFF	NONE	MOM-ON						
-312	ON	OFF	MOM-ON						

1/ Applicable terminal numbers are marked on the switch.

PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-24. MS25306, MS25307, and MS25308 toggle switches, positive break, environmentally sealed, screw terminals, .469 mounting bushing (MIL-S-8834).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.



Dash number	1/ Circuit with toggle lever in			Current capacity (amperes)						Minimum current capacity per pole 5 mV ac-dc
				Resistive load			Inductive load			
								115 Vac		
	Opposite keyway side	Center	Keyway side	28 Vdc	50 Vdc	115 Vac, 60 and 400 Hz	28 Vdc	60 Hz	400 Hz	(μA)
-211	ON	OFF	ON	5	2	3	1	1	2	25
-221	ON	NONE	OFF							
-231	ON	NONE	ON							
-241	ON	OFF	NONE							
-271	NON-ON	OFF	NON-ON							
-281	NONE	OFF	NON-ON							
-311	ON	OFF	NON-ON							

1/ Applicable terminal numbers are marked on the switch.

PART NUMBER: Consists of the applicable MS number followed by the dash number as shown in the tabulation.

FIGURE 112-25. MS90310 and MS90311 toggle switches, miniature, toggle sealed, solder lug, .469 mounting bushing (MIL-S-8834).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS		
	Sea level		50,000 feet
	28 Vdc	115 Vac, 60 Hz	28 Vdc
	amperes	amperes	amperes
Resistive - - -	5	5	5
Inductive - - -	3	6	2.5
Lamp- - - - - -	2.4	1.5	2.4

INCHES	MM
.060	1.52
.115	2.92
.36	9.14
.470	11.94
.500	12.70
.720	18.29
.860	21.84
.990	25.15
1.125	28.58
1.160	29.46





FIGURE A FIGURE B FIGURE C



STANDARD LEVER TAB LEVER

FIGURE 112-26. Switch assemblies, sensitive, toggle lever (with integral leaf), 5 amperes, unsealed (MIL-S-8805/26).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

TABLE I. Part numbers and characteristics.

Dash No.	Figure	Locking combination	Circuit configuration (see table II)	Switch action		
				Opposite keyway	Center	Keyway
-001	A	D	1	Main	None	Main
-002	C	D	4	Main	None	Main
-003	C	F	4	Main	None	Main
-004	C	G	4	Main	None	Main
-005	A	E	2	Mom	Main	Mom
-006	A	A	2	Main	Main	Main
-007	A	D	2	Main	Main	Main
-008	A	E	2	Main	Main	Main
-009	A	F	2	Main	Main	Main
-010	A	G	2	Main	Main	Main
-011	A	J	2	Main	Main	Main
-012	A	K	2	Main	Main	Main
-013	A	L	2	Main	Main	Main
-014	A	M	2	Main	Main	Main
-015	A	N	2	Main	Main	Main
-016	A	B	2	Mom	Main	Main
-017	A	E	2	Mom	Main	Main
-018	A	P	2	Mom	Main	Main
-019	B	A	3	Main	Main	Main

TABLE II. Circuit configuration.

Circuit configuration	Switch pole number	Circuit closed with toggle lever in		
		Opposite keyway side	Center	Keyway side
1	1	C-NC	None	C-NO
1	2	C-NC	None	C-NO
2	1	C-NO	C-NC	C-NC
2	2	C-NC	C-NC	C-NO
3	1	C-NO	C-NC	C-NC
3	2	C-NC	C-NC	C-NO
3	3	C-NO	C-NC	C-NC
4	1	C-NC	None	C-NO
4	2	C-NC	None	C-NO
4	3	C-NC	None	C-NO
4	4	C-NC	None	C-NO

OPERATING CHARACTERISTICS:
Coincidence of operating and releasing points: All poles transfer within 10 degrees of lever travel.
Locking arrangement: Positive locking is accomplished and prevents motion of the toggle lever until the locking mechanism is manually released.
Locking mechanism release: The force required to release the locking mechanism is 3 to 5 pounds.


PART NUMBER: Consists of "M8805/92" followed by the dash number shown in table I.

FIGURE 112-27. Switch assemblies, sensitive, lever lock, 5 amperes, unsealed (MIL-S-8805/92) - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.

LOAD	ELECTRICAL RATINGS (amperes)		
	Sea level		50,000 feet
	28 Vdc	115 Vac, 60 Hz	28 Vdc
Resistive - - - -	7.0	7.0	4.0
Inductive - - - -	4.0	7.0	2.5
Lamp- - - - - - -	2.5	2.0	2.5

INCHES	MM
.003	.08
.13	3.30
.240	6.10
.50	12.70
.670	17.02
.720	18.29
.930	23.62
1.15	29.21
1.16	29.46
1.17	29.72
1.30	33.02



Part No. MS805/93-				Operation
Type I 2PDT	Type II 4PDT	Type III 6PDT	Type IV 8PDT	
001	008	015	022	Maint-off-maint
002	009	016	023	Mom-off-maint
003	010	017	024	Maint-off-mom
004	011	018	025	Mom-off-mom
005	012	019	026	Maint-none-maint
006	013	020	027	Mom-none-maint
007	014	021	028	Maint-none-mom

FIGURE 112-28. Switch assemblies, sensitive, lever, unsealed, 7 amperes (MIL-S-8805/93)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.




FIGURE 112-28. Switch assemblies, sensitive, lever, unsealed, 7 amperes (MIL-S-8805/93) - Continued.

Source: https://assist.dla.mil -- Downloaded: 202610-26T07:41Z
Check the source to verify that this is the current version before use.




FIGURE 202-15. Panel seal.

Intended use: Panel seal for 4 lamp, illuminated, push switch MIL-S-22885/9, and 4 lamp modular indicator light in accordance with MIL-S-22885/10.

Procurement document: MIL-S-22885/13.

Part number: M22885/13-02.

Supersedes page 202.17
of 23 March 1976

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:41Z
Check the source to verify that this is the current version before use.