INCH-POUND

MIL-B-52706A(ME)
29 June 1992
SUPERSEDING
MIL-B-52706(ME)
27 April 1971

MILITARY SPECIFICATION

BRIDGE, FLOATING: RAFT SECTION, LIGHT TACTICAL, SUPERSTRUCTURE COMPONENTS

This specification is approved for use within the USA Belvoir Research, Development and Engineering Center, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers the panel and curb components comprising the superstructure for the raft section of the light tactical floating bridge.

1.2 Classification. The components shall be of the following types and classes, as specified (see 6.2):

Type I - Panel
  Class 1 - Deck
  Class 2 - Articulator
  Class 3 - Ramp, Female
  Class 4 - Ramp, Male
  Class 5 - Filler, Deck
  Class 6 - Filler, Articulator and Ramp
Type II - Curb
  Class 1 - Deck
  Class 2 - Articulator and Ramp

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research, Development and Engineering Center, ATTN: STRBE-TSE, Fort Belvoir, VA 22060-5606 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 5420

AMSC N/A
DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. The following specifications and standards form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

SPECIFICATIONS

FEDERAL

PPP-B-601	- Boxes, Wood, Cleated-Plywood.

MILITARY

MIL-T-704	- Treatment and Painting of Materiel.
MIL-C-52950	- Crates, Wood, Open and Covered.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-130	- Identification Marking of U.S. Military Property.
MIL-STD-889	- Dissimilar Metals.

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Standardization Documents Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Government drawings. The following Government drawings form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those cited in the solicitation.

DRAWINGS

ME

TA13216E9590	- Panel Assembly, Deck.
TA13216E9604	- Panel Assembly, Articulator.
TA13216E9613	- Panel Assembly,, Ramp, Female.
TA13216E9615	- Panel, Ramp, Male.
TA13216E9616	- Panel, Filler, Deck Panel.
TA13216E9617	- Panel, Filler, Articulator and Ramp Panels.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

TA13216E9618	- Curb Assembly, Deck Panel.
TA13216E9620	- Curb Assembly, Articulator and Ramp Panels.

(Copies of drawings required by contractors in connection with specific acquisition functions should be obtained from the USA Belvoir Research, Development and Engineering Center, ATTN: STRBE-JBS, Fort Belvoir, VA 22060-5606.)

2.2 Non-Government publications. The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Qualification Standard for Welding and Brazing Procedures, Welders, Brazers, and Welding and Brazing Operators.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

D 3953	- Strapping, Flat Steel and Seals.
D 4675	- Selection and Use of Flat Strapping Materials.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

AMERICAN WELDING SOCIETY (AWS)

A5.1	- Covered Carbon Steel Arc Welding Electrodes.
A5.10	- Bare Aluminum and Aluminum Alloy Welding Electrodes and Rods.
A5.18	- Carbon Steel Filler Metals for Gas Shielded Arc Welding.
D1.1	- Structural Welding Code - Steel.
D1.2	- Structural Welding Code - Aluminum.

(Application for copies should be addressed to the American Welding Society, 550 N.W. LeJeune Road, P.O. Box 351040, Miami, FL 33135.)

NATIONAL MOTOR FREIGHT TRAFFIC ASSOCIATION INC., AGENT (NMFTA)

National Motor Freight Classification Rules.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

(Application for copies should be addressed to the American Trucking Association, Inc., ATTN: Traffic Order Section, 2200 Mill Road, Alexandria, VA 22314.)

UNIFORM CLASSIFICATION COMMITTEE AGENT (UCC)

Uniform Freight Classification Rules

(Application for copies should be addressed to the Uniform Classification Committee, ATTN: Tariff Publishing Officer, Room 1106, 222 South Riverside Plaza, Chicago, IL 60606.)

(Non-Government standards and other publications are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description.

3.1.1 Type I, class 1. The type I, class 1, deck panel assembly, shall be as shown on TA13216E9590 and as specified herein.

3.1.2 Type I, class 2. The type I, class 2, articulator panel assembly, shall be as shown on TA13216E9604 and as specified herein.

3.1.3 Type I, class 3. The type I, class 3, female ramp panel assembly, shall be as shown on TA13216E9613 and as specified herein.

3.1.4 Type I, class 4. The type I, class 4, male ramp panel, shall be as shown on TA13216E9615 and as specified herein.

3.1.5 Type I, class 5. The type I, class 5, deck panel filler panel, shall be as shown on TA13216E9616 and as specified herein.

3.1.6 Type I, class 6. The type I, class 6, articulator and ramp panels filler panel, shall be as shown on TA13216E9617 and as specified herein.

3.1.7 Type II, class 1. The type II, class 1, deck panel curb assembly, shall be as shown on TA13216E9618 and as specified herein.

3.1.8 Type II, class 2. The type II, class 2, articulator and ramp panels curb assembly, shall be as shown on TA13216E9620 and as specified herein.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

3.1.9 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the panel and curb components. Any data (e.g., shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available upon request, for inspection by the contracting officer or the designated representative.

3.2 First article. Unless otherwise specified (see 6.2), a sample shall be subjected to first article inspection (see 6.3) in accordance with 4.3.

3.3 Materials. The materials shall be as specified herein and on the drawings. Materials not specified shall be selected by the contractor, and shall be subjected to all provisions of this specification.

3.3.1 Material deterioration prevention and control. The panel and curb components shall be fabricated from compatible materials, inherently corrosion resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable operating and storage environments to which the panel and curb components may be exposed.

3.3.1.1 Dissimilar metals. Dissimilar metals shall not be used in intimate contact with each other unless protected against galvanic corrosion. Dissimilar metals and methods of protection are defined and detailed in MIL-STD-889.

3.3.1.2 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with component and subcomponent, and shall make information available upon request to the contracting officer or designated representative.

3.3.2 Recovered materials. For the purpose of this requirement, recovered materials are those materials which have been collected from solid waste and reprocessed to become a source of raw materials, as distinguished from virgin raw materials. The components, pieces and parts incorporated in the panel and curb components may be newly fabricated from recovered materials to the maximum extent practicable, provided the panel and curb components produced meets all other requirements of this specification. Used, rebuilt or remanufactured components, pieces and parts shall not be incorporated in the panel and curb components.

3.3.3 Cadmium plating. Cadmium plating or cadmium plated parts shall not be used.

3.4 Welding electrodes.

3.4.1 For steel. Welding electrodes for steel shall conform to AWS A5.1 or A5.18, classification E60 or E70 series, size as required.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

3.4.2 For aluminum. Welding electrodes for aluminum shall conform to AWS A5.10, classification ER4043, size as required.

3.5 Identification marking. The component shall be metal-die stamped as shown on the applicable drawing. Die stamping shall be legible after painting.

3.6 Treatment and painting. The portions of the item normally painted internally and externally shall be cleaned, treated, and painted in accordance with MIL-T-704, type F and G, as applicable. Unless otherwise specified (see 6.2) top coat shall be camouflage green 383. If required the item shall then be overcoated in accordance with the Government furnished camouflage patterns with the colors specified in the camouflage patterns.

3.7 Stenciling. The nomenclature, Federal stock number, weight, and cube shall be stenciled on each component. The letters "NET WT" shall precede the numerals in the weight and the letter "CU" shall precede the cubic displacement. Markings shall be Gothic-type capitals and Arabic numerals 0.75 inch high. Stenciling shall conform to MIL-STD-130.

3.8 Government-loaned property. Unless otherwise specified (see 6.2), the following property in the quantities indicated will be loaned by the Government (see 6.4):

Item	Description	Identification	Quantity
1	Inspection Equipment for Bridge, Floating, Aluminum, Light Tactical Superstructure.	Quality Assurance Pamphlet, P715-121	1
2	QA Pamphlet 'Care, Operation Maintenance of Inspection Equipment for Light Tactical Superstructure'.	P715-121	1

3.9 Government-furnished-property. When specified (see 6.2), the following property in the quantity indicated will be furnished by the Government (see 6.5).

Item No.	Description	Quantity
1	Camouflage paint pattern	As required

3.10 Workmanship.

3.10.1 Steel fabrication. Steel may be cut by shearing, sawing, or flame cutting. Burned surfaces of flame-cut material shall be ground or machined to remove cooling checks. All bends shall be made by use of metal dies or fixtures to insure uniformity in size and shape. All burrs shall be removed.

3.10.2 Aluminum fabrication. Aluminum used in the fabrication of the component shall be free from kinks and sharp bends. Straightening of material shall be done by methods that will not cause injury to the metal. Surfaces and

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

edges of all finished members shall be smooth and free from kinks, bends, and winds. All bends of a major character shall be made with metal dies or fixtures to insure uniformity of size and shape. Sharp instruments shall not be used for marking bend lines. Aluminum shall not be cut by methods using heat. Aluminum less than 3/8 inch thick may be cut by shearing; aluminum 3/8 inch thick and over shall be cut by routing or by high-speed saws. Shearing and sawing shall be done neatly and accurately.

3.10.3 Riveted connections.

3.10.3.1 Rivet holes. Holes for countersunk rivets shall be of such depth and angle that the rivet head shall fill the hole without projection or recession.

3.10.3.2 Riveting. Components shall be bolted in position before riveting. Jigs or frames shall be used to maintain alignment and tolerance. Rivets shall be free from slag or scale when driven. Countersunk rivets shall be flush with the surrounding surface. Heads of driven rivets shall be uniform in shape and concentric with the rivet shank axis, and shall have full bearing on the surfaces of the joined members. Rivets shall fill the holes in the joined members. Caulking or redriving of rivet heads shall not be permitted. Rivet tension shall not be created by driving in incorrectly fitted members. A rivet with a head deficient in size, not uniform in shape, off-center, loose, burned, or misshapen in any way shall be considered defective. Defective rivets shall be removed without injury to the joined metal. Automatic or squeeze-type riveters shall be permitted for driving rivets, where practicable, provided the pressure employed does not cause distortion of the material. In lieu of automatic or squeeze-type rivet machines, pneumatic rivet hammers may be used.

3.10.3.2.1 Steel rivets. Steel rivets may be driven hot or cold. Hot steel rivets shall be heated uniformly throughout their length and driven while at a light cherry color. Hot steel rivets in aluminum shall be driven at random in order to prevent overheating of the aluminum.

3.10.3.2.2 Aluminum rivets. Aluminum rivets shall be driven cold, as-received.

3.10.4 Welders and welding.

3.10.4.1 Welders and welding operators. Before assigning any welder or welding operator to manual welding work covered by this specification, the contractor shall obtain certification that the welder has passed qualification tests as prescribed by either AWS D1.1, D1.2 or the ASME code for the materials joined and the type of welding operation to be performed and that such qualification is effective as defined. Contractors who only make horizontal welds need not qualify welders for "all position welding". The contractor is responsible for determining that automatic welding equipment operators are capable of producing quality welds in accordance with AWS and ASME codes. In the event of evidence of poor welds, the Government reserves the right to require retesting of any welder or welding operator (see 6.6).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

3.10.4.2 Welding. The surfaces of parts to be welded shall be free from dirt, scale, paint, grease, and other foreign matter. Welding shall be done by the shielded metal-arc or gas metal-arc (MIG) process. All welded parts shall be free from slag, flux, welded spatter, cracks and other imperfections that may reduce the effectiveness of the part. Work shall be positioned for flat welding when practicable. Before welding over previously deposited weld metal, all traces of slag shall be removed and the deposit and adjoining base metal shall be wire brushed clean. Welding and welds shall be in accordance with either ASME or AWS code.

3.10.4.2.1 Steel welding. Where embrittlement of the joined metal may result, preheating or annealing or both shall be employed.

3.10.4.2.2 Aluminum welding. Aluminum members to be welded may be preheated for welding to a temperature of not more than 400 °F. Aluminum welds may be filed, wire brushed, or chipped but shall not be hammered.

3.10.5 Interchangeability. Components of like description shall be fabricated to be duplicates within the tolerances specified and shall be interchangeable.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items shall meet all requirements of sections 3 and 5. The inspections set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to accept defective material.

4.1.2 Component and material inspection. The contractor is responsible for ensuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards, as applicable.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Inspection of packaging (see 4.6).

4.3 First article inspection.

4.3.1 Examination. The first article shall be examined in accordance with 4.4.2.1 and for defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for examination and tests shall be in accordance with MIL-STD-105. Sample size shall be determined by using MIL-STD-105, table I and table IIa. A lot shall be accepted when 0 defects are found and rejected when 1 or more defects are found.

4.4.2 Examination.

4.4.2.1 Individual. Unless otherwise specified (see 3.8), Government-loaned inspection equipment shall be used in accordance with Government-loaned QA pamphlet to inspect dimensions indicated on the applicable drawings under 'Major - 100 percent inspection'. Nonconformance to any of these dimensions shall constitute failure of this examination and shall be cause for rejection.

4.4.2.2 Samples. Samples selected in accordance with 4.4.1 shall be examined for the defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.5 Inspection procedure.

4.5.1 Examination. The panel or curb components, as applicable, shall be examined as specified herein for the following defects:

101. Dimensions not as specified (see 3.1).
102. Materials not as specified (see 3.3).
103. Materials not resistant to corrosion and deterioration, or treated to be resistant to corrosion and deterioration of the applicable operating and storage environments (see 3.3.1).
104. Dissimilar metals as defined in MIL-STD-889 are not effectively insulated from each other (see 3.3.1.1).
105. Contractor does not have documentation available for identification of materials, material finishes, or treatment (see 3.3.1.2).
106. Used, rebuilt or remanufactured components, pieces, and parts incorporated in the panel or curb components (see 3.3.2).
107. Cadmium plating/plated parts used (see 3.3.3).
108. Welding electrodes not as specified (see 3.4).
109. Identification marking not as specified (see 3.5 and 3.7).
110. Treatment and painting not as specified (see 3.6).
111. Workmanship not as specified (see 3.10).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

112. Riveting not as specified (see 3.10.3.2).
113. Welders and welding operators not certified as specified (see 3.10.4.1).
114. Welding not as specified (see 3.10.4.2).

4.6 Inspection of packaging.

4.6.1 Quality conformance inspection of pack.

4.6.1.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.6.1.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.6.1.3 Examination. Samples selected in accordance with 4.6.1.2 shall be examined for the following defects. Presence of one or more defects shall be cause for rejection.

115. Deck panels not packed as specified for level A (see 5.1.1.1.1).
116. Pins and retainers not in place as specified for level A (see 5.1.1.1.1).
117. Strapping not as specified for level A (see 5.1.1.1.1).
118. Articulator panels, ramp panels, filler panel, deck, articulator and ramp not packed as specified for level A (see 5.1.1.1.2 thru 5.1.1.1.5).
119. Deck panel curbs not packed in a crate, and not bundled as specified for level A (see 5.1.1.2.1).
120. Articulator and ramp panel curbs not packed together in a box, and not blocked, braced, or anchored as specified for level A (see 5.1.1.2.2).
121. Marking missing, illegible, incorrect, or incomplete (see 5.2).

5. PACKAGING

5.1 Packing. Packing shall be level A or C as specified (see 6.2).

5.1.1 Level A.

5.1.1.1 Panels (type I).

5.1.1.1.1 Deck panels (class 1). The deck panels (with pins and retainers in place) shall be packed as a bundle in quantities of two. The panels shall be shipped as a bundle or the bundled panels shall be consolidated into a secured lift. Each bundle shall be secured with not less than two flat steel straps conforming to ASTM D 3953, type 1 or 2, zinc-coated, size as applicable and ASTM D 4675. Secured lifts shall be strapped with not less than three straps specified above, with two straps applied girthwise and with one strap applied lengthwise at the center of the lift.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:09Z
Check the source to verify that this is the currentversion before use.

5.1.1.1.2 Articulator panels (class 2). The components comprising each articulator panel (with pins and retainers in place) shall be bundled together. The panel shall be shipped as a bundle or the bundles shall be consolidated into a secured lift. Each bundle and lift shall be secured as specified in 5.1.1.1.1.

5.1.1.1.3 Ramp panels; female (class 3) and male (class 4). The ramp panels of like description (with the pin and retainer in place on the female (class 3) panels) shall be packed as a bundle in quantities of two. The panels shall be shipped as a bundle or the bundles shall be consolidated into a secured lift. Each bundle and lift shall be secured as specified in 5.1.1.1.1.

5.1.1.1.4 Filler panel, deck (class 5). The panels shall be packed as a bundle in quantities of two. The panels shall be positioned top against top. The angles on each panel shall be protected against damage with a nominal 2-inch by 4-inch wood filler strip, extending the full length of each angle. The two panels shall be secured together with bolts, flat washers top and bottom, and nuts. The bolts shall go through the holes in the angles and matching drilled holes in the wood filler strip. Bolts shall be the same diameter as the holes. The panels shall be shipped as a bundle or the bundles shall be consolidated into a secured lift. Lifts shall be secured as specified in 5.1.1.1.1.

5.1.1.1.5 Filler panel, articulator and ramp (class 6). The panels shall be packed as specified in 5.1.1.1.4.

5.1.1.2 Curbs (type II).

5.1.1.2.1 Deck panel curbs (class 1). The curbs (with the pins and retainers in place) shall be packed in a close-fitting crate conforming to MIL-C-52950 in quantities of eight. Prior to placing in the crate, the curbs shall be bundled together in the manner most convenient for packing. The bundle shall be secured as specified in 5.1.1.1.1.

5.1.1.2.2 Articulator and ramp panel curbs (class 2). The curbs (with the pins and retainers in place) shall be packed together in a close-fitting box conforming to PPP-B-601, overseas type, style optional, in quantities of 12. The contents shall be blocked, braced, and anchored within the box in a manner to prevent free movement. Box closure shall be in accordance with the appendix to the box specification. Strapping shall be in accordance with ASTM D 3953, type 1 or 2, zinc-coated, size as applicable and ASTM D 4675.

5.1.1.3 Components procured separately. Items of like description procured separately from either the panels or curbs shall be packed together as specified in 5.1.1.2.2.

5.1.2 Level C. The components shall be packed in a manner to assure carrier acceptance and safe delivery to destination at lowest ratings in compliance with Uniform Freight Classification Rules or National Motor Freight Classification Rules.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

5.2 Marking. In addition to any special marking specified in the contract or purchase order (see 6.2), boxes, bundles, or secured lifts shall be marked in accordance with MIL-STD-129.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The panels and curbs are intended for use in raft section which is a component of the aluminum light tactical floating bridge.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Type and class of component required (see 1.2).
c. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
d. When a first article is required for inspection and approval, and the number of units required (see 3.2, 4.3 and 6.3).
e. When camouflage patterns shall be provided (see 3.6).
f. When Government-loaned property is required (see 3.8).
g. Level of packing required (see 5.1).
h. Any special marking required (see 5.2).

6.3 First article. When a first article inspection is required, the panel and curb components should be preproduction models. The first article should consist of one or more units. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, approval of the first article test results and disposition of the first articles. Invitation for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract. Bidders should not submit alternate bids unless specifically requested to do so in the solicitation.

6.4 Government-loaned-property. The contracting officer should arrange to loan the property listed in 3.8.

6.5 Government-furnished-property. The contracting officer should arrange to furnish the property listed in 3.9.

6.6 Consideration of data requirements. ,The following data requirements should be considered when this specification is applied on a contract. The applicable Data Item Descriptions (DID's) should be reviewed in conjunction with the specific acquisition to ensure that only essential data are requested/provided and that the DID's are tailored to reflect the requirements of

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

the specific acquisition. To ensure correct contractual application of the data requirements, a Contract Data Requirements List (DD FAR Supplement 27.475-1) exempts the requirement for a DD Form 1423.

Reference paragraph	DID Number	DID Title	Suggested Tailoring
a. 3.8.1.1	DI-MISC-80875	Welding Procedures	
b. 3.8.1.1	DI-MISC-80876	Welding Procedure Qualification Test Report	

6.7 Subject term (key word) listing.

Bridge components
Curb
Curb assembly
Panel
Panel assembly
Raft section components

6.8 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 5420-A374

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER MIL-B-52706A(ME)	2. DOCUMENT DATE (YYMMDD) 920629

3. DOCUMENT TITLE
Bridge, Floating: Raft Section, Light Tactical Superstructure Components

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (if applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME Gerry Harlow	b. TELEPHONE (Include Area Code) (1) Commercial (703) 704-3469 (2) AUTOVON 654-3469
ADDRESS (Include Zip Code) Army Belvoir RDE Center ATTN: STRBE-TSE Fort Belvoir, VA 22060-5606	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340

DD Form 1426, OCT 89 Previous editions are obsolete

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.