INCH-POUND

MIL-E-52714C(ME)
26 June 1992
SUPERSEDING
MIL-E-52714B(ME)
23 August 1984

MILITARY SPECIFICATION

EQUIPMENT, CABLE REINFORCEMENT, FOR PANEL BRIDGE: M-2 (BAILEY TYPE)

This specification is approved for use within the USA Belvoir Research, Development, and Engineering Center, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers all structural components necessary to post-tension and reinforce 100 to 180 foot spans of M-2 panel bridge in its triple-single configuration.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. The following specifications and standards form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research, Development and Engineering Center, ATTN: STRBE-TSE, Fort Belvoir, VA 22060-5606 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 5420

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

PPP-B-601	-	Boxes, Wood, Cleated-Plywood.
PPP-B-621	-	Boxes, Wood, Nailed and Lock-Corner.

MILITARY

MIL-C-104	-	Crates, Wood; Lumber and Plywood Sheathed, Nailed and Bolted.
MIL-P-116	-	Preservation, Methods of.
MIL-T-704	-	Treatment and Painting of Materiel.
MIL-C-3774	-	Crates, Wood: Open (12,000 and 16,000 Pound Capacity).
MIL-C-16173	-	Corrosion Preventive Compound, Solvent Cutback, Cold Application.

STANDARDS

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	-	Marking for Shipment and Storage.
MIL-STD-163	-	Steel Mill Products, Preparation for Shipment and Storage.
MIL-STD-889	-	Dissimilar Metals.
MIL-STD-1186	-	Cushioning, Anchoring, Bracing, Blocking, and Water-Proofing; with Appropriate Test Methods.

(Unless otherwise indicated, copies of federal and military specifications and standards are available from the Standardization Documents Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Other Government drawings. The following other Government drawings form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those in effect on the date of the solicitation.

DRAWINGS

ME

TA13217E2170	-	Equipment, Cable Reinforcement, for Panel Bridge, M2 (Bailey Type).

(Copies of drawings required by contractors in connection with specific acquisition functions should be obtained from the USA Belvoir Research, Development and Engineering Center, ATTN: STRBE-JBS, Fort Belvoir, VA 22060-5606.)

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:09Z
Check the source to verify that this is the currentversion before use.

2.2 Non-Government publications. The following documents form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Qualification Standard for Welding and Brazing Procedures, Welders, Brazers, and Welding and Brazing Operators.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

AMERICAN WELDING SOCIETY (AWS)

AWS A 5.1 - Covered Carbon Steel Arc Welding Electrodes.
AWS A 5.18 - Carbon Steel Filler Metals for Gas Shielded Arc Welding.
AWS D 1.1 - Structural Welding Code - Steel.

(Application for copies should be addressed to the American Welding Society, 550 N.W. LeJeune Road, P.O. Box 351040, Miami, FL 33135.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

D 3951 - Standard Practice for Commercial Packaging.
D 3953 - Strapping, Flat Steel and Seals
D 4675 - Selection and Use of Flat Strapping Materials

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

(Non-Government standards and other publications are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description. The cable reinforcing equipment shall be in accordance with TA13217E2170 and as specified herein. The contractor shall furnish any or all of the components on the data list, as specified (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T04:09Z
Check the source to verify that this is the current version before use.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to ensure correct fit, assembly, and operation of the cable reinforcement equipment. Any data (e.g. shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available upon request, for inspection by the contracting officer or the designated representative.

3.2 First article. Unless otherwise specified (see 6.2), a sample shall be subjected to first article inspection (see 6.3) in accordance with 4.3.

3.3 Material. Material shall be as specified herein and on drawings. Material not specified shall be selected by the contractor and shall be subject to all provisions of this specification.

3.3.1 Material deterioration prevention and control. The cable reinforcement equipment shall be fabricated from compatible materials, inherently corrosion resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable storage and operating environments to which the cable reinforcement equipment may be exposed.

3.3.1.1 Dissimilar metals. Dissimilar metals shall not be used in intimate contact with each other unless protected against galvanic corrosion. Dissimilar metals and methods of protection are defined and detailed in MIL-STD-889.

3.3.1.2 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with components and subcomponents, and shall make information available, upon request, to the contracting officer or designated representative.

3.3.1.3 Recovered materials. For the purpose of this requirement, recovered materials are those materials which have been collected from solid waste and reprocessed to become a source of raw materials, as distinguished from virgin raw materials. The components, pieces and parts incorporated in the cable reinforcement equipment may be newly fabricated from recovered materials to the maximum extent practicable, provided the cable reinforcement equipment produced meets all other requirements of this specification. Used, rebuilt or remanufactured components, pieces and parts shall not be incorporated in the cable reinforcement equipment.

3.3.1.4 Cadmium plating. Cadmium plating and cadmium plated items shall not be used.

3.4 Welding electrodes. Welding electrodes shall conform to AWS A 5.1 or A 5.18, classification and size as required.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

3.5 Cable. When tested as specified in 4.5.2, the cable shall not show any slippage of the buttons or threaded end on the cable.

3.6 Identification marking. The cable reinforcement equipment shall be metal die stamped as shown on the drawings. Die stamping shall be legible after painting.

3.7 Stenciling. Each component, except pins, bolts, and washers shall be stenciled with the National Stock Number, nomenclature, and contract number. Stenciling shall be in accordance with MIL-T-704 and shall be Gothic capitals and numerals, 2 inches high where space permits. Stenciling on small components shall be as large as practicable.

3.8 Treatment and painting. All parts of the cable reinforcement equipment shall be cleaned, treated, and painted in accordance with MIL-T-704, type F, with topcoat color camouflage green 383. Pins, bolts, nuts, threaded surfaces, and cables shall not be painted but shall be coated with a preservative conforming to MIL-C-16173, grade 2.

3.9 Performance. The cable reinforcement equipment shall operate without evidence of material defects (i.e., cracks, open joints, weld deterioration), permanent deformation or damage.

3.10 Government-furnished property. When specified (see 6.2), the following property in the quantities indicated will be furnished by the Government (see 6.2):

Item no.	Nomenclature	National Stock Number	Quantity for each
1.	Bridge, Fixed, Steel Bailey Type M-2.	5420-00-530-3784	1
2.	Bridge Erection Set, Fixed Bridge, Bailey Type, M-2.	5420-00-530-3785	1
3.	Truck, Dump, 5 Ton, 6 x 6, M51 (or equivalent).	2320-00-835-8336	30
4.	Trailer, Basic Utility, Pole Type, 2-1/2 Ton, 2 Wheel (or equivalent).	2330-00-697-8102	9

3.11 Workmanship.

3.11.1 Steel fabrication. Steel used in the fabrication of the cable reinforcement equipment shall be free from kinks and sharp bends. The straightening of material shall be done by methods that shall not cause injury to the metal. Shearing and chipping shall be done neatly and accurately. Corners shall be square and true. Flame cutting may be employed instead of shearing or sawing. Burned surfaces of flame-cut material shall be ground or

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

machined sufficiently to remove ash and cooling checks. All bends of a major character shall be made with metal dies or fixtures in order to ensure uniformity of size and shape.

3.11.2 Bolted connections. Boltholes shall be accurately punched or drilled and shall have the burrs removed.

3.11.3 Welders and welding.

3.11.3.1 Welders and welder operators. Before assigning any welder or welding operator to welding work covered by this specification, the contractor shall obtain certification that the welder has passed qualification tests as prescribed by either of the following listed codes for the materials joined and the type of welding operations to be performed and that such qualification is effective as defined by the particular code: ASME, Boiler and Pressure Vessel Code, Section IX; AWS D 1.1, Structural Welding Code - Steel. Contractors who only make horizontal welds need not qualify welders for "all position welding". In the event of evidence of poor welds, the Government reserves the right to require retesting of any welder or welding operator. The test results shall be made available for review by the contracting officer or his representative.

3.11.3.2 Welding. The surfaces of parts to be welded shall be free from scale, paint, grease, and other foreign matter. Welding shall be done by the shielded metal-arc or gas metal-arc (MIG) process and shall conform to the provisions of either AWS or ASME Code. All welded parts shall be free from cracks and other imperfections that may reduce the effectiveness of the part. Work shall be positioned for flat welding when practicable. Before welding over previously deposited weld metal, all traces of slag shall be removed, and the deposit and adjoining base metal shall be wire-brushed clean.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.2 Component and material inspection. The contractor is responsible for ensuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards, as applicable.

4.1.3 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the quality assurance provisions (QAP) shown on the drawings. The drawings specify the characteristics requiring QAP inspection, the sampling plan, and the basis for acceptance and rejection (see 6.6 and 6.7).

4.2 Classification of inspections. Inspections specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Inspection of packaging (see 4.6)

4.3 First article inspection.

4.3.1 Examination. The first article cable reinforcement equipment shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Tests. The first article cable reinforcement equipment or separately procured components shall be tested as specified in 4.5.2. Failure of any test shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Sampling for examination. Sampling for examination shall be in accordance with MIL-STD-105. Sample size shall be determined by using MIL-STD-105, table I and table IIa. A lot shall be accepted when zero defects are found and rejected when one or more defects are found.

4.4.2 Examination. Samples selected in accordance with 4.4.1 shall be examined for defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.5 Inspection procedure.

4.5.1 Examination. The cable reinforcement equipment shall be examined as specified herein for the following defects:

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:09Z
Check the source to verify that this is the current version before use.

Major

101. Components missing or not as specified (see 3.1).
102. Any part or component not in accordance with the QAP requirements as shown on the drawings (see 3.1.1).
103. Any drawing requirement, other than those identified by QAP data, not as specified (see 3.1.1).
104. Material not as specified (see 3.3).
105. Materials not resistant to corrosion and deterioration or treated to be resistant to corrosion and deterioration of the applicable storage and operating environments (see 3.3.1).
106. Dissimilar metals as defined in MIL-STD-889 are not effectively insulated from each other (see 3.3.1.1).
107. Contractor does not have documentation available for identification of materials, material finishes or treatment (see 3.3.1.2).
108. Used, rebuilt or remanufactured components, pieces, or parts incorporated in the cable reinforcement equipment (see 3.3.1.3).
109. Cadmium plating/plated parts used (see 3.3.1.4).
110. Workmanship not as specified (see 3.11.1 and 3.11.2).
111. Bolted connections not as specified (see 3.11.2).
112. Qualification of welders not as specified (see 3.11.3.1).
113. Welders and welding operators not certified as specified (see 3.11.3.1).
114. Welding and welds not as specified (see 3.11.3.2).

Minor

201. Identification markings incorrect or missing (see 3.6).
202. Stenciling incorrect or missing (see 3.7).
203. Treatment and painting not as specified (see 3.8).

4.5.2 Proof load. Place the cable shown on drawing 13217E2181 in a test frame and apply a proof load of 135,000 pounds to each button and the threaded end. Any slippage of the buttons or the threaded end shall constitute failure of this test.

4.6 Inspection of packaging.

4.6.1 First article inspection.

4.6.1.1 Examination. Examine the first article pack for the defects specified in 4.6.2.3. Presence of one or more defects shall be cause for rejection.

4.6.1.2 Test. The first article pack of crated equipment for level A shall be subjected to the rail-impact test in accordance with MIL-STD-1186, appendix A. At the conclusion of the first article pack test, the pack shall be examined. Any shifting of contents, loosening or breakage of holddowns, ties,

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

stays, blocking or bracing, or any visual damage to the components shall constitute failure of the first article pack and shall be cause for rejection.

4.6.2 Quality conformance inspection of pack.

4.6.2.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.6.2.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105. Sample size shall be determined by using MIL-STD-105, table I and table IIa. A lot shall be accepted when zero defects are found and rejected when one or more defects are found.

4.6.2.3 Examination. Samples selected in accordance with 4.6.2.2 shall be examined for the following defects. Presence of one or more defects shall be cause for rejection.

115. Threaded and unprotected metal surfaces requiring the application of a preservative in accordance with the referenced document, not coated with preservative for level A or commercial (see 5.2.1 and 5.2.2).
116. Wire rope not preserved and packed in accordance with the referenced document for level A (see 5.2.1.2).
117. Consolidation not as specified for level A (see 5.2.1.3).
118. Blocking, bracing, and anchoring not in accordance with the referenced documents for level A (see 5.3.1).
119. When procured as complete kits and as individual components not packed in a box or crate as specified for level A (see 5.3.1.1).
120. Marking missing, illegible, incorrect, or incomplete for level A or commercial (see 5.4).

5. PACKAGING

5.1 First article pack. The contractor shall furnish a first article pack for examination and test within the time frame specified, to prove, prior to starting production packaging that the applied preservation, packing, and marking comply with the packaging requirements of this specification. Examination and test shall be as specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.4). The first article pack may be accomplished utilizing either the first article equipment or the production equipment. If the first article model is utilized, any preservation and packing shall be removed by the contractor at no expense to the Government when requested by the Government to facilitate comparison between the first article model equipment and the production equipment.

5.2 Preservation. Preservation shall be, level A or commercial as specified (see 6.2).

5.2.1 Level A (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

5.2.1.1 Threaded and unpainted surfaces. Threaded and unpainted surfaces of components such as bolts, nuts, chord plates, pull rods or any other similar type components requiring the application of a contact preservative in accordance with MIL-P-116, shall be coated with type P-1 preservative. The preservative shall conform to the applicable specification listed in and shall be applied in accordance with MIL-P-116.

5.2.1.2 Wire rope. The wire rope furnished on reels shall be preserved in accordance with the level A requirements of MIL-STD-163.

5.2.1.3 Consolidation. Nuts, bolts, and any other loose components requiring the protection of a container to prevent loss or to aid in accomplishing the packing specified herein shall be consolidated together in close-fitting boxes conforming to PPP-B-621, class 2, style optional or PPP-B-601, overseas type, style optional. Box closure shall be in accordance with the appendix to the applicable box specification. Boxes to be packed in a crate shall not require strapping.

5.2.2 Commercial. Threaded and unpainted surfaces shall be preserved as specified in 5.2.1.1. Additional preservation of the equipment shall be as required to afford protection against deterioration and damage in accordance with ASTM D 3951.

5.3 Packing. Packing shall be level A or commercial as specified (see 6.2).

5.3.1 Level A.

5.3.1.1 When procured as complete kits.

5.3.1.1.1 Wire rope. Wire rope, preserved as specified in 5.2.1.2 shall be packed in accordance with the level A requirements of MIL-STD-163 and shall be shipped separate from but at the same time as the crate containing the other erection equipment components (see 5.3.1.1.3).

5.3.1.1.2 Pull rods. Three pull rods shall be placed together in a close-fitting box conforming to PPP-B-621, class 2, style 2, or PPP-B-601, overseas type, style A or B. Blocking and bracing shall be provided within the box to prevent movement or damage to the threaded surfaces. Box closure shall be in accordance with the appendix to the applicable box specification. Strapping shall not be required. The required pull rods for the kit shall then be packed in the crate with the other components specified in 5.3.1.1.3.

5.3.1.1.3 Other components. The kit components except for the wire rope contained on reels, preserved as specified in 5.2, shall be packed in a crate conforming to MIL-C-3774, type I, style A or MIL-C-104, type I, class 1 or 2, style A. The components shall be arranged within the crate, in a manner to provide maximum compactness, low center of gravity, and in a manner that void spaces are held to a minimum. Blocking, bracing, and anchoring of the contents shall be in accordance with the crate specification and MIL-STD-1186.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

5.3.1.2 When procured as individual components. Individual components procured as replacements or spares, except for the wire rope contained on reels shall be packed together in close-fitting boxes conforming to PPP-B-601, overseas type, style optional; PPP-B-621, class 2, style optional or in a crate conforming to MIL-C-3774, type I, style A, as applicable to the weight and quantities of components procured. Only components of like description shall be packed together in the same container. Blocking, bracing and anchoring of the contents to prevent movement or damage shall be in accordance with the crate specification and MIL-STD-1186. Closure shall be in accordance with the crate or applicable box specification. Strapping shall be in accordance with ASTM D 3953, type 1 or 2, zinc-coated, size as applicable, and ASTM D 4675.

5.3.2 Commercial. The equipment components, preserved as specified in 5.2, shall be packed in accordance with ASTM D 3951.

5.4 Marking. In addition to any special marking specified in the contract or purchase order, marking shall be in accordance with MIL-STD-129.

5.4.1 Military. Marking for military levels of protection (level A) shall be in accordance with MIL-STD-129.

5.4.2 Commercial. Marking shall be in accordance with ASTM D 3951. In addition, weight and cube data shall be marked on the shipping container.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory).

6.1 Intended use. The cable reinforcement equipment is intended for use as a rapid means of post tensioning the triple-single configuration of the M-2 panel bridge. The bridge is reinforced using the king/queen post principle. The reinforced bridge is capable of supporting a class 60 load over spans between 100 and 170 feet and class 50 load over the 180 foot span.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
c. Designation of equipment desired (see 3.1).
d. When a first article is not required for inspection and approval and the number of units required (see 3.2).
e. When the property listed in 3.10 will be furnished by the Government.
f. Degree of preservation and degree of packing required (see 5.2 and 5.3).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

6.3 First article. When a first article inspection is required, the items(s) should be a preproduction model. The first article should consist of one or more units. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, approval of the first article test results and disposition of the first article. Invitation for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract. Bidders should not submit alternate bids unless specifically requested to do so in the solicitation.

6.4 First article pack. Any changes or deviations of production packs from the approved first article pack will be subject to the approval of the contracting officer. Approval of the first article pack will not relieve the contractor of his obligation to preserve, pack, and mark the equipment or components when procured separately, in accordance with this specification.

6.5 Government-furnished property. The contracting officer should arrange to furnish the property listed in 3.10.

6.6 Quality assurance provisions (QAP) record. The contracting officer should require the contractor to maintain records of all QAP inspections. A suggested paragraph is as follows:

"The contractor shall maintain complete records of all examinations and tests performed to verify the requirements of classified QAP characteristics. The records shall include, as a minimum, lot size, sample size, drawing requirements, actual measurement, number, and type of deficiencies found, quantity approved, quantity rejected, corrected action taken when applicable."

6.7 Definitions.

6.7.1 Quality assurance provisions (QAP). A QAP is a contractual requirement that supplements section 4 of the specification. QAP indicates the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

6.8 Subject term (key word) listing.

Bailey bridge
Cable reinforcement bridge
Panel bridge

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:09Z
Check the source to verify that this is the current version before use.

6.9 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 5420-0208

Review activity:
DLA - CS

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER MIL-E-52714C(ME)	2. DOCUMENT DATE (YYMMDD) 920626

3. DOCUMENT TITLE
Equipment, Cable Reinforcement, for Panel Bridge: M-2 (Bailey Type)

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (if applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME Gerry Harlow	b. TELEPHONE (Include Area Code) (1) Commercial (703) 704-3469 (2) AUTOVON 654-3469
c. ADDRESS (Include Zip Code S Army Belvoir RDE Center ATTN: STRBE-TSE Fort Belvoir, VA 22060-5606	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340

DD Form 1426, OCT 89 Previous editions are obsolete

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.