MILITARY SPECIFICATION

HULL ASSEMBLY, WELDED, FOR BRIDGE/FERRY TRANSPORTER

1. SCOPE

1.1 This specification covers the welded aluminum-alloy hull, without machinery, for the Mobile Floating Assault Bridge/Ferry (MAB) Transporter covered in MIL-T-52703 .

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS

Federal

NN-P-530	- Plywood, Flat Panel.
QQ-S-781	- Strapping, Steel, Flat and Seals.
PPP-T-60	- Tape: Pressure-Sensitive Adhesive, Waterproof, for Packaging.

Military

MIL-P-116	- Preservation, Methods of.
MIL-B-121	- Barrier Material, Greaseproofed, Waterproofed, Flexible.
MIL-T-704	- Treatment and Painting of Materiel.
MIL-W-5044	- Walkway Compound, Nonslip and Walkway Matting, Nonslip.
MIL-W-45205	- Welding, Gas Metal-Arc and Gas Tungsten-Arc Aluminum Alloys, Readily Weldable for Structures, Excluding Armor.
MIL-W-45210	- Welding, Resistance, Spot: Weldable Aluminum Alloys.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

MIL-R-45774	- Radiographic Inspection, Soundness Requirements for Fusion Welds in Aluminum and Magnesium Missile Components.
MIL-T-52703	- Transporter: Welded Hull, For Mobile Floating Assault Bridge/Ferry.

STANDARDS

Federal

FED. STD. No. 595	- Colors.

Military

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-453	- Inspection, Radiographic.
MIL-STD-1261	- Welding Procedures for Constructional Steels.

DRAWINGS

ME

DL13207E3300	- Hull Assembly, Welded, For Bridge/Ferry Transporter.

(Copies of specifications, standards, and drawings required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

NATIONAL BUREAU OF STANDARDS

Handbook H28 - Screw-Thread Standards for Federal Services.

(Application for copies should be addressed to the Superintendent of Documents, U. S. Government Printing Office, Washington, D. C. 20402.)

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:09Z
Check the source to verify that this is the currentversion before use.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS

Boiler and Pressure Vessel Code, Welding Qualifications.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, N. Y. 10017.)

AMERICAN WELDING SOCIETY

Standard Qualification Procedure.

(Application for copies should be addressed to the American Welding Society, 345 East 47th Street, New York, N. Y. 10017.)

3. REQUIREMENTS

3.1 Description. The hull assembly shall be in accordance with Data List DL13207E3300 and as specified herein. The completed hull assembly forms the chassis, body, and cab of the transporter specified in MIL-T-52703 .

3.1.1 Drawings. The drawings forming a part of this specification are engineering design drawings. No deviation from the prescribed dimensions or tolerances is permissible without the prior approval of the contracting officer. Any data (e.g., shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the supplier or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative. All dimensions shown on the drawings are based on temperatures of 68° F. through 70° F.

3.2 First article (first-produced hull assembly). The supplier shall furnish one or more hull assemblies for examination and testing within the time frame specified, to prove prior to starting production, that his production equipment and methods will produce hull assemblies that comply with the requirements of this specification. Examination and tests shall be those specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.3).

3.3 Initial production. When specified, the supplier shall furnish to the Government one or more hull assemblies for inspection as specified in 4.4.

3.4 Materials. Materials shall be as specified herein and as shown on the applicable drawings. The surfaces of the materials shall be free of foreign matter, scale, rust, oxidation or corrosion.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

3.5 Threads. All threads shall conform to Handbook H28 or as specified on the applicable drawings.

3.6 Hull watertightness. The hull shall be watertight when tested before painting as specified in 4.7.2.

3.7 Cab watertightness. The cab shall be watertight when tested before painting as specified in 4.7.2.

3.8 Wheel well air retention. The wheel wells consist of the four wheel well compartments as shown on Drawing 13207E3220, with the wheel well cover assemblies shown on Drawing 13207E3256 bolted in place. The wheel sells shall be airtight when tested before painting as specified in 4.7.2.

3.9 Operational requirements. The hull assembly shall perform as specified herein, and as specified in MIL-T-52703 , when operationally tested as a part of the transporter.

3.10 Treatment and painting. The hull assembly including the interiors of the wheel well assemblies and cab assembly, shall be cleaned, treated, and painted in accordance with MIL-T-704, type B, lusterless, except the finish coat on the hull interior shall be semigloss white, to range between color No. 27875 and No. 27778 of FED. STD. No. 595. The primer and finish coat shall not be applied until after the hull assembly has successfully passed the required water and air tests specified in 4.7.2. The nonslip coating shall be applied to all areas designated on the drawings. The nonslip coating shall conform to MIL-W-5044, type II, olive drab, color X34087. The finish coat of the eight superstructure supports located on top of the fenders shall conform to yellow, lusterless, No. 33538, of FED. STD. No. 595. Dissimilar metals shall be isolated as specified on the drawings.

3.11 Government-loaned property. The following property, in the quantities listed, will be loaned by the Government (see 6.4):

Item No.	Qty	Description	Identification
1*	1	Gage, Locating, Spline Device	Dwg 13207E6117
2*	1	Gage, Locating, Holddown	Dwg 13207E6118
3**	1	Gage, Locating, Engine-Transmission Mounting	Dwg 13207E6120
4	1 (with each chest)	QA Pamphlet "Care, Operation and Maintenance of Inspection Equipment for Bridge/Ferry Unit, Interior Bay, and End Bay, Amphibious: Mobile Floating Assault Bridge/Ferry Unit"	AMSMO-FB-P715-106

* - with chest No. 8, Dwg. No. 13207E6139.
** - with chest No. 9, Dwg. No. 13207E6140.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

3.12 Workmanship.

3.12.1 Metal fabrication. The parts fabrication, subassembly, and final assembly shall be made with production fixtures, tooling, and jigs to assure the specified configuration, alinement, and location of all components. Aluminum-alloy materials shall not have scratches or scribe lines exceeding a total of 5 percent of the stock thickness, or be water stained. Aluminum-alloy materials shall not be heated for forming or be flame cut. All edges of the components shall be smooth and free of slivers, burrs, and sharp edges. All components shall be accurately and completely formed to the drawing requirements prior to the bolting, riveting, or welding phases of assembly or installation. Joints, butts, and splices shall be limited to those specifically shown on the drawings. Specific precautions shall be employed in forming the chines and skids, to assure correct fitting in the bow and stern bend regions. Unless otherwise specified on the drawings, sheet or plate buckling distortions shall not exceed 3/32-inch per 12-inches of the span between frames or stiffening members.

3.12.2 Aluminum welds. All aluminum fusion welding shall be in accordance with MIL-W-45205, utilizing the inert gas metal-arc process (see 6.5). The weld types, materials, sizes, and quality of soundness shall be in full accordance with the weld requirements specified on the applicable drawings. Class "A" welds shall be stamped to identify the individual welder responsible for the specific welding. Prior to the production fabrication of any MIL-W-45205, class "A" aluminum weldment, the supplier shall prepare and submit to the contracting officer for approval, surface preparation, cleaning, and welding procedures in accordance with MIL-W-45205. When approved by the contracting officer, such procedures shall be the minimum weld quality procedures acceptable to the Government for class "A" welds. Prior to the production fabrication of any MIL-W-45205, class "B" aluminum weldment, the supplier shall prepare surface preparation, cleaning, and welding procedures in accordance with MIL-W-45205 and shall make such procedures available to the Government upon request. All aluminum resistance welding procedures and workmanship specimens shall be in accordance with MIL-W-45210.

3.12.3 Steel welds. The weld types, materials, sizes, and quality of soundness shall conform to the weld requirements specified on the applicable drawings. Prior to the production fabrication of any steel weldment, the supplier shall prepare welding procedures and workmanship specimens in accordance with the requirements of MIL-STD-1261, and shall make such procedures available to the Government upon request.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

3.12.4 Welders. Before the assignment of any welder to welding work covered by this specification, the supplier shall provide the contracting officer with certification that the welder has passed the prescribed qualification tests of the following listed codes, for the specific welding procedures, positions, materials, material thickness, and equipment to be used for the hull fabrication, and that such qualification is effective and current as defined by the particular code:

Steel welding - Standard Qualification Procedure of the American Welding Society.
Aluminum alloy welding - Welding Qualification of the ASME.

3.12.5 Weld repairs. All areas of defective or unacceptable welds shall be repaired in accordance with the weld repair procedures specified in MIL-W-45205, MIL-W-45210, and MIL-STD-1261, as applicable. Repair of any defective weld shall be limited to two re-welds.

3.12.5 Bolt torque. Screw (bolt) installation torque values shall be as specified on the drawings.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements.

4.1.1 Component and material inspection. The supplier is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards.

4.1.2 Disassembly inspection. Hull assemblies failing any test shall be cause for disassembly as applicable in the presence of a Government representative, to the extent necessary to determine the cause of the failure. Each disassembled part shall be examined in detail for compliance with this specification and referenced drawings in regard to materials, dimensions, tolerances, and workmanship. Parts not complying with such requirements shall be rejected. Reassembly with accepted material or components and retesting shall be the responsibility of the supplier.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

4.2 Classification of inspection. Inspection shall be classified as follows:

(a) First-produced hull inspection (see 4.3).
(b) Initial production inspection (see 4.4).
(c) Quality conformance inspection (see 4.5).
(d) Inspection comparison (see 4.6).
(e) Inspection of preparation for delivery (see 4.8).

4.3 First-produced hull inspection.

4.3.1 In-process inspection. During fabrication and assembly of the first-produced hull assembly, the Government shall conduct an in-process inspection in addition to the suppliers inspection, to evaluate workmanship and materials for compliance with the drawings and applicable specifications. Nonconformance to any applicable drawing or referenced specification shall be cause for rejection of the part, component, subassembly, or hull assembly, as applicable.

4.3.2 Examination. The first-produced hull assembly shall be examined as specified in 4.7.1. Presence of one or more defects shall be cause for rejection.

4.3.3 Tests. The first-produced hull assembly shall be tested as specified in 4.7.2. Failure of the test shall be cause for performing the disassembly inspection specified in 4.1.2. Successful completion of all tests specified in 4.7.2 shall result in provisional acceptance of the first-produced hull assembly pending final testing of the hull assembly when incorporated into a transporter conforming to MIL-T-52703 and acceptance of the transporter by the Government. Such transporter testing shall be within the time frame specified and shall be those tests specified to be conducted by the transporter supplier. Upon successful completion of all hull assembly supplier and transporter supplier testing, the first-produced hull assembly incorporated into the transporter will be subjected to the Government conducted tests specified in MIL-T-52703 . Failure of any transporter test shall be cause for rejection of the hull assembly or transporter, as applicable.

4.4 Initial production inspection. When specified (see 3.3), one or more initial production hull assemblies will be selected at random by the Government from the first 10 hull assemblies being produced from production tooling, and will be examined as specified in 4.7.1 and tested as specified in 4.3.3 to determine conformance to this specification. Upon successful completion of this inspection, the provisionally accepted

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:09Z
Check the source to verify that this is the current version before use.

hull assembly(s) when incorporated into a transporter (MIL-T- 52703), will be tested by the Government as specified in MIL-T- 52703 , to determine conformance to the requirements of this specification and to MIL-T- 52703 . The inspection will be performed at a site selected by the Government. Acceptance of the initial production assembly(s) shall not exclude the remaining hull assemblies from the quality conformance inspection and acceptance provisions specified in section 4.

4.4.1 Inspection failure. Failure of an initial production hull assembly to meet any requirement specified herein during and as a result of the examination and tests specified in 4.4 shall be cause for rejection of the initial production hull assembly(s), and shall be cause for refusal by the Government to continue provisional acceptance of production hull assemblies until acceptable evidence has been provided by the supplier that corrective action has been taken to eliminate the defects. Correction of such defects shall be accomplished by the supplier at no cost to the Government on hull assemblies provisionally accepted and produced under the contract. Any defects found as a result of the initial production inspection will be considered prima facie evidence that all hull assemblies provisionally accepted prior to the completion of initial production inspection are similarly deficient, unless evidence to the contrary is furnished by the supplier, and such evidence is acceptable to the contracting officer.

4.5 Quality conformance inspection.

4.5.1 Examination. Each hull assembly shall be examined as specified in 4.7.1. Presence of one or more defects shall be cause for rejection.

4.5.2 Tests. Each hull assembly shall be subjected to the tests specified in 4.7.2. Failure of any test shall be cause for rejection. Successful completion of all tests specified in 4.7.2 shall result in provisional acceptance of the hull assembly pending final testing of the hull assembly when incorporated into a transporter conforming to MIL-T-52703 and acceptance of the transporter by the Government. Such transporter testing shall be within the time frame specified and shall be those tests specified to be conducted by the transporter suppliers. Failure of any transporter test shall be cause for rejection of the hull assembly or transporter, as applicable.

4.6 Inspection comparison. When initial production inspection is specified the Government may select hull assemblies at any time during the contract production period and subject these hull assemblies to the examination and testing specified in 4.4 to determine that the quality of the

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:09Z
Check the source to verify that this is the currentversion before use.

selected hull assembly is equal to the quality standards established during initial production inspection. The inspection will be performed by the Government at a site selected by the Government. Hull assemblies will be selected at random from those which have been provisionally accepted by the Government and will not include the previously inspected first-produced hull assembly and initial production hull assembly(s).

4.6.1 Failure criteria. Failure of any assembly due to incorrect workmanship, materials, or nonconformance to requirements when inspected as specified in 4.6 may be considered cause for refusal by the Government to continue acceptance of hull assemblies until objective evidence furnished by the supplier reveals that corrective action has been taken to eliminate the condition which caused the failure and such evidence is acceptable to the contracting officer.

4.7 Inspection procedure.

4.7.1 Examination. Each hull assembly shall be examined for the following defects. All dimensions identified on the drawings by the symbol ⟨I⟩ shall be gaged by the Government-loaned inspection equipment to determine acceptability in accordance with Quality Assurance Pamphlet, AMSMO-FB-P715-106. The gages are calibrated at 68° F. to 70° F.

101. Nonconformance to geometric features identified on the drawings by symbol ⟨I⟩ .
102. Dimensions, tolerances, or geometric conditions not as specified. Components not true to dimension or alinement, containing twists, buckling, or other conditions.
103. Components incorrectly or incompletely assembled, including fitting and bearing conditions not as specified.
104. Components missing, incorrectly located, or not as specified.
105. Materials not as specified, including heat treatment, surface conditions, welding materials, protective coatings, sealing materials, and platings.
106. Screw (bolt) torque not as specified.
107. Gasket bonding or installation incomplete or not as specified.
108. Cleaning, treatment, and painting not as specified.
109. Nonslip coating incomplete or not as specified.
110. Sealing compound application incomplete, incorrectly applied, or not as specified.
111. Workmanship not as specified.

4.7.1.1 Aluminum weld examination. All areas affected by the welding processes shall be examined prior to painting for evidence of defects, including base metal cracks adjacent to or behind welds, arc strikes,

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:09Z
Check the source to verify that this is the currentversion before use.

cracks in weld metal, undercutting, lack of fusion, porosity, lack of penetration, lack of prescribed fit, incorrect cleaning or preparation for welding, inclusions, incorrect weld size, reduction of adjacent material thickness, or nonadherence to the welding procedures specified in 3.12.2. Weld quality shall be examined and compared against the approved welding specimens submitted (see 6.5). Subassembly welds shall be examined before final installation, wherever feasible. All aluminum welds shall be visually examined with the aid of a 5X magnifying glass. Welds identified on the drawings with the symbol "RT" shall be radiographically examined in accordance with MIL-STD-453 over a minimum of 15 percent of the cumulative weld lengths on each of the first five produced hull assemblies and one of every subsequent 10 hull assemblies on a random choice basis at the discretion of the Government, and a minimum of 2 percent of the cumulative weld lengths on each of the other production hull assemblies unless otherwise approved by the contracting officer. Evidence of weld defects in excess of that exhibited by the Government-approved welding specimens or the radiographic soundness requirements shall constitute failure of this examination. Weld areas to be radiographed shall be chosen at random on each hull assembly at the discretion of the Government. When radiographic examination indicates that the applicable weld quality requirements have not been met, the Government may require additional radiographic examination of adjacent or other weld areas including examination of hull assemblies examined since the last hull assembly which was radiographed a minimum of 15 percent of the "RT" identified weld areas. Other class A or class B aluminum welds may be radiographed at random at the discretion of the Government.

4.7.1.2 Steel weld examination. All areas of welded assemblies affected by the welding processes shall be examined prior to plating, painting, or installation for evidence of defects, including base metal cracks adjacent to or behind welds, cracks in weld metal, undercutting, lack of fusion, porosity, lack of penetration, lack of prescribed fit, incorrect cleaning or preparation for welding, inclusions, incorrect weld size, reduction of adjacent material thickness, or nonadherence to the welding procedures specified in 3.12.3. Weld quality shall be examined and compared against the approved welding specimens submitted (see 6.5). All steel welds shall be visually examined with the aid of a 5X magnifying glass. Steel welds identified on the drawings with the symbol "RT" shall be radiographically examined in accordance with MIL-STD-453, for 100 percent of the indicated weld lengths, unless otherwise approved by the contracting officer. Steel welds should meet the radiographic soundness requirements noted on the applicable drawings. Evidence of weld defects in excess of that exhibited by the approved welding specimens, or the radiographic soundness requirements noted on the applicable drawings shall constitute failure of this examination.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

4.7.1.3 Weld repair examination. All weld repair areas shall be visually examined with the aid of a 5X magnifying glass. Weld repair areas shall be radiographically examined in accordance with MIL-STD-453, for 100 percent of the repaired weld lengths. Weld repairs which evidence defects in excess of that exhibited by the weld specimens or the radiographic soundness requirements shall constitute failure of this examination.

4.7.2 Tests.

4.7.2.1 Test procedures. The completed hull assembly shall be subjected to the following water and airtightness tests before painting. Prior to any tests, all hull openings shown on the drawings within the test draft depth, shall be temporarily sealed to prevent leakage during the tests.

4.7.2.2 Watertightness. The completed hull assembly (with or without cab assembly) shall be immersed in clear water to a static fore and aft draft of 50 inches (measured from the bottom sheet) by loading the eight gunwale-mounted superstructure support blocks. The hull shall remain immersed to this draft for 30 minutes. Evidence of water entry into the hull during this test period constitutes failure of this test. CAUTION: A hull assembly when immersed 50 inches is relatively unstable when deck loaded, and exerts an upward force of approximately 95,000 pounds.

4.7.2.3 Cab watertightness. The cab door hinges, side window overlaps and other cab openings shown on the drawings shall be taped to prevent entry of water. The cab compartment shall be installed on the hull and shall be externally sprayed with water. A 1/2-inch ID hose with nozzle shall be used, with a water pressure of 30 psi and shall be held between 5 feet and 6 feet away from the cab. A medium spray shall be applied for 3 minutes at a downward angle of 45 degrees plus or minus 5 degrees each to the top, front, back, and the two sides of the cab assembly (a total of 15 minutes). Leakage of water into the cab attributable to nonconforming materials, dimensions, tolerances, or incorrect workmanship constitutes failure of this test.

4.7.2.4 Wheel well air retention. With the hull assembly immersed as specified in 4.7.2.2, each wheel well with the deck assemblies bolted on as specified, shall be air pressurized to 1.8 psig, and the air supply line closed. At the end of 5 minutes, the air pressure within each wheel well shall be measured. Inability of any wheel well to retain a minimum pressure of 1.3 psig shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:09Z
Check the source to verify that this is the current version before use.

4.8 Inspection of preparation for delivery.

4.8.1 Quality conformance inspection of pack.

4.8.1.1 Unit of product. For the purpose of inspection, a completed hull processed for shipment shall be considered a unit of product.

4.8.1.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.8.1.3 Examination. Samples selected in accordance with 4.8.1.2 shall be examined for the following defects. Acceptable Quality Level (AQL) shall be 2.5 percent defective.

112.	Materials and procedures not as specified. Each incorrect material or procedure shall constitute one defect.
113.	Holding devices and spline assembly not cleaned and coated with preservative as specified.
114.	Coated surfaces of the holding devices and spline assembly not covered with barrier material and the barrier material not secured with tape as specified.
115.	Exposed machined surfaces of the wheel-suspension supports not cleaned and coated with preservative as specified.
116.	Preserved areas of wheel-suspension supports not covered with barrier material and the barrier material not secured with tape as specified.
117.	Hull drains not left open.
118.	Hull drain plugs not secured to the hull as specified.
119.	Openings into the hull not sealed or covered as specified, using tape or barrier material as applicable.
120.	The air grill, rear control station, and capstan openings not closed with plywood panels as specified and the plywood panels not secured in place with tape as specified.
121.	Cab windshields and windows not protected with plywood panels as specified.
122.	Plywood panels not secured in place as specified.
123.	Banding not applied as specified.
124.	Unbolted deck hatches not secured with wire as specified.
125.	Marking missing, illegible, incomplete, or incorrect.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:09Z
Check the source to verify that this is the currentversion before use.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.

5.1.1 Levels A and B. Not applicable (see 6.6).

5.1.2 Level C.

5.1.2.1 Holding devices (13207E1783) and superstructure spline assembly (13207E2542). The holding devices and unpainted surfaces of the superstructure spline assembly shall be cleaned using method C-1, dried, and then coated with type P-6 preservative, in accordance with MIL-P-116. Barrier material conforming to MIL-B-121, type I, grade A, class 2, secured with tape conforming to PPP-T-60, type IV, shall be used to cover the holding devices and the superstructure spline assembly.

5.1.2.2 Wheel-suspension supports. Exposed machined surfaces of the wheel-suspension supports shall be cleaned using method C-1, dried, and then coated with type P-6 preservative in accordance with MIL-P-116. Preserved areas of the wheel-suspension supports shall be covered with barrier material conforming to MIL-B-121, type I, grade A, class 2, which shall be secured with tape conforming to PPP-T-60, type IV.

5.1.2.3 Hull drains. Hull drains shall be left open. The chained plugs shall be taped securely to the hull.

5.1.2.4 Openings. All openings (except hull drains) into the hull and cab which would permit entrance of water, snow, or dust shall be sealed with waterproof tape conforming to PPP-T-60, type IV. Openings within the wheel wells, for the marine drive assembly, and all other holes greater than 5 inches in diameter shall be covered with heavy waterproof barrier material secured with waterproof tape specified herein. The air grill, rear control station, and capstan openings shall be closed with 1/4-inch plywood panels conforming to NN-P-530, exterior grade, sealed with waterproof tape conforming to PPP-T-60, type IV, and wired securely in place. The cab windshields and windows shall be covered on the outside with 1/4-inch thick plywood panels, conforming to NN-P-530, exterior grade, with 1 inch thick waterproof cushioning material secured between the panels and the windshield and window frames, and secured with the waterproof tape specified herein and by a minimum of two bands of steel banding conforming to QQ-S-781, type I, class B, around the cab. The banding shall be applied in a manner to prevent opening of the cab doors. The nonbolted deck hatches shall be secured with wiring from the inside of the hull.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:09Z
Check the source to verify that this is the current version before use.

5.2 Marking. Marking shall be in accordance with MIL-STD-129.

5.3 Loading. The hull assembly shall be loaded for rail transportation in accordance with Drawing 13207E4615. The hull assembly shall be loaded for highway transportation in accordance with Drawing 13207E4614.

6. NOTES

6.1 Intended use. The hull assembly is intended for use as a sub-assembly of the bridge/ferry superstructure transporter, welded hull (MIL-T-52703), used for military floating bridges and ferries.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Time frame required for submission of the first-produced hull assembly (see 3.2), and number required.
(c) When initial production inspection is required and number of hull assemblies to be furnished, when applicable (see 3.3).
(d) Time frame required for submission of provisionally accepted first-produced hull assembly for transporter testing (see 4.3.3).
(e) Time frame required for submission of production hull assemblies for transporter testing (see 4.5.2).
(f) Level of preservation and packaging required (see 5.1).

6.3 First-produced hull assembly. Any changes or deviations of production hull assemblies from the approved first-produced hull assembly during production will be subject to the approval of the contracting officer. Approval of the first-produced hull assembly will not relieve the supplier of his obligation to furnish hull assemblies conforming to this specification.

6.4 Government-loaned property. The contracting officer should arrange to loan the inspection equipment specified in 3.11 and should include the terms for the care, use, and maintenance, and storage of such equipment. The use of such equipment shall be limited to final acceptance inspections only.

6.5 Bid samples.

6.5.1 Aluminum welding specimens. At the time of invitation for bids or request for proposal the contracting officer should require each bidder to submit as part of his bid, aluminum fusion welding specimens prepared by using the specific equipment and procedures proposed for production fabrication in accordance with 3.12.2 for class "A" welds, and which meet the soundness requirements of MIL-R-45774, class II. Each specimen will

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

include a minimum of 12 linear inches of welds and will include the weld start and stop areas. The specimens should represent the sizes and types of welds specified in table I. The specimens upon receipt will become the property of the Government and each will be permanently identified as follows:

(a) The identity of the bidder.
(b) The bid or proposal number.
(c) The bid or proposal date.
(d) The specimen number, weld type and size, parent and filler metal and welding equipment identification.

When approved by the contracting officer these specimens will represent the minimum acceptable quality characteristics for class "A" aluminum fusion welds, as identified "RT" on the applicable drawings.

Table I. Welding Specimen Types and Sizes

Specimen No.	Weld Type and Size	Parent Metal	Filler Metal
1	1/8" Fillet	1/8" - 5456H343 to 3/16" - 5456H111	5556 per MIL-E-16053, or 5556, 5183, or 5356 per QQ-R-566.
2	1/8" Butt	1/8" - 5456H343 to 1/8" - 5456H343	5556 per MIL-E-16053, or 5556, 5183, or 5356 per QQ-R-566.
3	3/16" Fillet	3/16" - 5456H343 to 3/16" - 5456H111	5556 per MIL-E-16053, or 5556, 5183, or 5356 per QQ-R-566.
4	3/16" Butt	3/16" - 5456H343 to 3/16" - 5456H343	5556 per MIL-E-16053, or 5556, 5183, or 5356 per QQ-R-566.
5	1/4" Fillet	1/4" - 5456H111 to 1/4" - 5456H111	5556 per MIL-E-16053, or 5556, 5183, or 5356 per QQ-R-566.
6	1/4" Butt	1/4" - 5456H111 to 1/4" - 5456H111	5556 per MIL-E-16053, or 5556, 5183, or 5356 per QQ-R-566.
7	3/8" 60° Groove	3/8" - 5456H111 to 1/2" - 5456H111	5556 per MIL-E-16053, or 5556, 5183, or 5356 per QQ-R-566.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.

6.5.1.1 Radiographs. Each aluminum fusion welding specimen submitted should be accompanied by radiographs in accordance with MIL-STD-453, that fully disclose the soundness and freedom from defects of the weld and weld affected area of each specimen submitted. These radiographs upon receipt will become the property of the Government and will be permanently identified as follows:

(a) The identity of the bidder.
(b) The bid or proposal number.
(c) The bid or proposal date.
(d) The welding specimen number depicted by the radiographs.
(e) The direction and orientation of the source of radiation.

6.6 It is anticipated that the hull assembly will be shipped only from a supplier to the point where final assembly of the complete transporter will occur. Hazards of overseas shipment and indeterminate storage will not be encountered, eliminating the need for levels A and B preservation and packaging. Configuration and characteristics of the hull assembly are such that packing for shipment is not required.

Custodian:

Army - ME

Preparing activity:

Army - ME

Project No. 5420-A236

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:09Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION: HULL ASSEMBLY, WELDED, FOR BRIDGE/FERRY TRANSPORTER

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:09Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE ARMY
U. A. ARMY MOBILITY EQUIPMENT COMMAND
RESEARCH, DEVELOPMENT AND ENGINEERING DIRECTORATE
ATTN: AMSME-RZG
FORT BELVOIR, VIRGINIA 22060

OFFICIAL BUSINESS

POSTAGE AND FEES PAID

DEPARTMENT OF THE ARMY
U. S. ARMY MOBILITY EQUIPMENT COMMAND
RESEARCH, DEVELOPMENT AND ENGINEERING DIRECTORATE
ATTN: AMSME-RZG
FORT BELVOIR, VIRGINIA 22060

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:09Z
Check the source to verify that this is the current version before use.