MIL-M-50901 (MU)
22 February 1971
SUPERSEDING
(See 6.8)

MILITARY SPECIFICATION

MINE, ANTI-PERSONNEL, M26
PRIMER AND DELAY ASSEMBLY FOR

1. SCOPE

1.1 This specification covers the parts and loading, assembling and packing for Primer and Delay Assembly for use with Mine, Anti-Personnel, M26.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550	-	Ammunition and Special Weapons, General Specification for
MIL-I-45607	-	Inspection Equipment, Acquisition, Maintenance and Disposition of
MIL-P-20444	-	Primer, Percussion, M42, Loading, Assembling and Packing

STANDARDS

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109	-	Quality Assurance Terms and Definitions
MIL-STD-286	-	Propellants, Solid: Sampling, Examination and Testing

FSC: 1345

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

MIL-STD-1168 - Lot Numbering of Ammunition

MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

US ARMY MUNITIONS COMMAND

7548101 - Box, Packing, Ammunition, for Detonator, Stab, M28, M32, M50, T37E3, or Detonator, Electric, T65

7548103 - Box, Set-up, Packing, Ammunition, Outer, for Small Explosive Components

7548104 - Box, Set-up, Packing, Ammunition, Inner, for Small Explosive Components

8840311 - Primer and Delay Assembly

PUBLICATIONS

ARMY

ET-8840311 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activitiy or as directed by the Contracting Officer.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS

ASTM B 117-64 - Standard Method of Salt Spray (Fog) Testing

ASTM E 18-67 - Standard Methods of Test for Rockwell Hardness and Rockwell Superficial Hardness of Metallic Materials

(Application for copies should be addressed to: American Society for Testing and Materials, 1916 Race Street, Philadelphia, Pa. 19103)

2.2 Other publications.-The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on the date of invitation for bids or request for proposal shall apply.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

CODE OF FEDERAL REGULATIONS

Title 49 - Transportation, Parts 0-190

(The Code of Federal Regulations is available from the Superintendent of Documents, U. S. Government Printing Office, Washington, D. C. 20402. Orders should specify, "49 CFR 0-190 (latest revision)".)

3. REQUIREMENTS

3.1 Material.-Materials and parts shall be in accordance with the applicable drawings and specifications.

3.2 Moisture content of eimite igniter.-The moisture content of the eimite igniter at the loading station at the time of loading shall not exceed 0.4 percent when tested as specified in 4.4.1. When the alternate method as specified in 4.4.1 is used, the moisture content shall not exceed 0.6 percent.

3.3 Mechanical properties.-Cold-working or heat-treating (including quenching-and-tempering, normalizing, normalizing-and-tempering, annealing, and stress-relieving) operations, shall be performed in such a manner as to produce the specified properties uniformly throughout the entire lot. The contractor shall determine the detailed procedures to produce parts meeting the required mechanical properties. These procedures shall be documented and submitted with the first article sample to the Contracting Officer. (See 4.2.4) Changes in these procedures shall also be documented and submitted to the Contracting Officer.

3.4 Workmanship.-All parts and assemblies shall be fabricated, loaded and assembled in a thorough, workmanlike manner. They shall be free of burrs, sharp edges, cracks, dirt, grease, rust and other foreign matter. The cleaning method used shall not be injurious to any part, nor shall the parts be contaminated by the cleaning agents. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required markings shall be neat and sharply defined.

3.5 First article testing.-This specification makes provisions for first article testing. Submission of first article quantity by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection.

4.2.1 Submission.-The contractor shall submit a first article quantity as designated by the Contracting Officer for evaluation in accordance with the provisions of 4.2.2. (See 6.1) The first article sample shall consist of twenty-five (25) of each part and four-hundred (400) completed primer and delay

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

assemblies. All parts and assemblies submitted shall have been produced by the contractor (or furnished by a supplier) using the same production processes, procedures and equipment as will be used in fulfilling the contract. All assemblies and parts, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of conformance. A first article quantity, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer.

4.2.2 Inspections to be performed.-Assemblies and parts will be subjected by the Government to any or all the examinations or tests specified in this specification and any or all requirements of the applicable drawings. After Classification of defects inspections have been performed as specified in 4.3.2.1 to 4.3.2.5, the following quantities shall be subjected to the indicated tests. All tests shall be performed as specified in 4.4.

4.2.2.1 Firing of primer and delay assembly at ambient temperature (See Dwg. 8840311).-One-hundred and twenty-five (125) primer and delay assemblies shall be subjected to this test. If any assembly, after functioning has the cup protruding thru the crimp which secures the cup in the shell case, the lot shall be rejected. Rejection shall be as specified in 4.2.3.

4.2.2.2 High temperature, low temperature and water-immersion firing of primer and delay assembly (See Dwg 8840311).-One-hundred and fifty (150) primer and delay assemblies shall be subjected to these tests. Fifty assemblies shall be tested in each phase. Rejection shall be as specified in 4.2.3.

4.2.2.3 Delay time of primer and delay assembly at ambient temperature (See Dwg 8840311).-One-hundred and twenty-five (125) primer and delay assemblies shall be subjected to this test. If three (3) or more assemblies fail to comply with the delay time requirement specified on the applicable drawing, the lot shall be rejected.

4.2.2.4 Salt spray test of sleeve (See Dwg 9258106).-The twenty-five (25) sleeves shall be subjected to this test..

4.2.2.5 Hardness of sleeve (See Dwg 9258106).-The twenty-five sleeves shall be subjected to this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

4.2.3 Rejection.-Unless otherwise specified, if any primer and delay assembly fails to comply with any of the applicable requirements, the first article quantity shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article quantity or portion thereof. Until a first article quantity is accepted, the contractor is in no way authorized by the Government to resume regular production unless otherwise directed by the Contracting Officer.

4.2.4 Mechanical properties.-Documentation detailing all equipment, operations, and procedures to be used during the term of this contract, and affecting one or more of the mechanical properties, shall be submitted as part of first article inspection. Changes in the established procedures or equipment during the course of the contract shall be documented and submitted, with test data, as specified in 6.5. Documentation shall include actual chemical and metallurgical analyses of material, including wrought materials, (hardness, grain size and grain structure with photographs). Documentation covering normalizing, tempering, stress-relieving and annealing, when any of these operations are used, shall provide the shortest and longest time at the temperature for each item, size and type of furnace or oven. This documentation, with actual test data, shall be signed by a responsible agent of the prime contractor and submitted to the technical agency specified in 6.5.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168. Each inspection lot shall contain:

a. Parts of one lot interfix number from one manufacturer.
b. Primer assemblies of one lot interfix number from one manufacturer. (See 4.3.3.5).
c. Eimite powder from one lot.
d. Delay composition from one batch or blend of batches which results in homogeneity of all delay mixture used in the lot.
e. Delay assemblies (Dwg. C-8840328) of one lot interfix number from one manufacturer.

4.3.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (See 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Cup, closure (See Dwg 8840313 covering a detail of Dwg 8840311.

Categories	Defects	Method of Inspection	Code Number
Critical: None defined			
Major	AQL 0.65 Percent (See 4.3.3.1)		
101.	Inside diameter	Gage	01001
102.	Diameter of hole	Gage	01002
103.	Outside diameter	Gage	01003

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

Minor	AQL 1.50 Percent (See 4.3.3.1)		
201.	Total height	Gage	01004
202.	Thickness of wall	Gage	01005
203.	Burrs	Visual	01006

4.3.2.2 Disc (See Dwg 8840314 covering a detail of Dwg. 8840311).

Categories	Defects	Method of Inspection	Code Number
Critical:	None defined		
Major:	None defined		
Minor	AQL 1.00 Percent (See 4.3.3.1)		
201.	Diameter	Gage	02001
202.	Thickness	Gage	02002

4.3.2.3 Case, shell (See Dwg 8840315 covering a detail of Dwg 8840311).

Categories	Defects	Method of Inspection	Code Number
Critical:	None defined		
Major	AQL 1.00 Percent		
101.	Total length	Gage	03001
102.	Largest inside diameter	Gage	03002
103.	Outside diameter of body	Gage	03003
104.	Depth of primer cavity	Gage	03004
105.	Diameter of primer cavity	Gage	03005
106.	Concentricity of body with large outside diameter	Gage	03006
Minor	AQL 2.50 Percent		
201.	Depth of second largest inside diameter	Gage	03007
202.	Largest outside diameter	Gage	03008
203.	Length of flange	Gage	03009
204.	Diameter of hole in primer cavity	Gage	03010
205.	Evidence of poor workmanship (See 3.4)	Visual	03011

4.3.2.4 Sleeve (See Dwg 9258106 covering a detail of Dwg. 8840311).

Categories	Defects	Method of Inspection	Code Number
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

Major	AQL 0.65 Percent		
101.	Large outside diameter, min.	Gage	04001
102.	Groove diameter, min	Gage	04002
103.	Burrs	Visual	04003
Minor	AQL 4.00 Percent		
201.	Small outside diameter, min.	Gage	04004
202.	Inside diameter, max.	Gage	04005
203.	Concentricity of inside diameter with the outside diameter	Gage	04006
204.	Concentricity of small outside diameter	Gage	04007
205.	Concentricity of groove with inside diameter	Gage	04008
206.	Total length, min	Gage	04009
207.	Radius of groove, max.	Gage	04010
208.	Evidence of poor workmanship (See 3.4)	Visual	04011

4.3.2.5 Primer and delay assembly (See Dwg 8840311).

Categories	Defects	Method of Inspection	Code Number
Critical:	None defined		
Major	AQL 1.00 Percent		
101.	Weight of eimite	Balance	05001
102.	Outside diameter, max	Gage	05002
103.	Depth of primer, max	Gage	05003
104.	Shell case cracked or distorted	Visual	05004
105.	Primer assembly missing	Visual	05005
106.	Delay element inverted	Visual	05006
107.	Primer above flush	Gage	05007
108.	Sealant missing at joint of primer and pocket	Visual	05008
109.	Sealant missing around crimp or over flash hole	Visual	05009
110.	Crimp of shell case holding delay element, missing or incomplete	Visual	05010
111.	Thickness of Disc, max.	Gage	05011
Minor	AQL 1.00 Percent		
201.	Total length	Gage	05012
202.	Evidence of poor workmanship (See 3.4)	Visual	05013

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

4.3.2.6 Box, set-up, inner (prior to sealing) (See Dwg. 7548104).

Categories	Defects	Method of Inspection	Code Number
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Delay missing	Visual	06001
102.	Cushion missing	Visual	06002
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.4)	Visual	06003

4.3.2.7 Box, set-up, inner (See Dwg. 7548104).

Categories	Defects	Method of Inspection	Code Number
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Box damaged to the extent that contents are exposed	Visual	07001
Minor	AQL 1.50 Percent		
201.	Contents loose	Manual	07002
202.	Marking misleading or unidentifiable	Visual	07003
203.	Label missing or badly wrinkled (when applicable	Visual	07004

4.3.2.8 Box, set-up, outer (prior to insertion into barrier bag) (See Dwg. 7548103).

Categories	Defects	Method of Inspection	Code Number
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Box damaged to the extent that contents are exposed	Visual	08001
102.	Sealing strip incomplete, badly wrinkled, or missing	Visual	08002

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection	Code Number
Minor	AQL 1.50 Percent		
201.	Contents loose	Manual	08003
202.	Marking misleading or unidentifiable, including incorrect color code	Visual	08004
203.	Label missing or badly wrinkled (when applicable)	Visual	08005

4.3.2.9 Sealed barrier bag (See Dwg 7548103).

Categories	Defects	Method of Inspection	Code Number
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Waterproofness destroyed by separation of heat seal, or rip, tear or puncture	Visual	09001
Minor	AQL 0.65 Percent		
201.	Marking misleading or unidentifiable, including incorrect color code	Visual	09002

4.3.2.10 Box, packing, wooden (unsealed) (See Dwg. 7548101).

Categories	Defects	Method of Inspection	Code Number
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Incorrect number of cartons	Visual	10001
102.	Fillers missing	Visual	10002
Minor:	None defined		

4.3.2.11 Box, packing, wooden (See Dwg 7548101).

Categories	Defects	Method of Inspection	Code Number
Critical:	None defined		
Major	AQL 1.00 Percent		
101.	Hardware missing, broken or loose	Visual-Manual	11001
102.	Strapping missing, broken or loose	Visual-Manual	11002
103.	Contents exposed	Visual	11003

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

104.	Board broken or split	Visual	11004
105.	DOD symbol misleading or unidentifiable	Visual	11005
Minor	AQL 2.50 Percent		
201.	Hardware improperly engaged	Visual-Manual	11006
202.	Contents loose	Manual	11007
203.	Strapping improperly assembled	Visual	11008
204.	Marking misleading or unidentifiable, including incorrect color code	Visual	11009
205.	Car seal missing, unsealed, or improperly positioned	Visual	11010

4.3.3 Testing.

4.3.3.1 Dimensional control of stamped parts.-In place of the normal sampling associated with the Classification of Defects, and with the approval of the Contracting Officer, a sample of at least ten (10) parts may be dimensionally inspected to qualify the tool used in the stamping process for use in production. In addition, a random sample of five (5) parts shall be selected from the last portion of each hour's production for dimensional inspection as a control of the tool during production.

If any defective parts are found during qualification of the tool, the tool producing the defective part shall not be used in production.

If any defective parts are found when inspection is performed for control of the tool, the tool producing the defective part shall be removed from production. Further, that portion of production since the last tool control check shall be returned to the contractor for corrective action.

All tools removed from production because of some fault, may, after reworking, be returned to production providing they pass the qualification test above. The contractor may request a change of inspection frequency providing he presents objective evidence to the Contracting Officer to substantiate the request.

4.3.3.2 Moisture content of eimite igniter (See 3.2) Major defect (Code No. 12001).-The contractor shall provide adequate controls to insure compliance with the applicable requirement. The moisture content of each lot of eimite shall be determined at the loading station at the time of loading. This determination shall be made at least once each eight (8) hours of production. Sampling of the eimite shall be in accordance with MIL-STD-286. In addition, if the moisture content fails

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

to comply with the requirement specified on the applicable drawing, and loading has not begun, the eimite lot shall be rejected until corrective action has been taken as verified by repeating the moisture content determination. If loading has begun, assemblies loaded with the non-conforming eimite shall be rejected. This determination shall be performed as specified in 4.4.1.

4.3.3.3 Functioning and delay time test of primer and delay assembly (ambient temperature) (See Dwg 8840311) Major defect (Defect Code for failure to function - 13001; for delay time failure - 14001; for protrusion of the cup from the shell case - 15001).-Eighty (80) primer and delay assemblies shall be selected from each lot and subjected to this test. If a total of two (2) or more primer and delay assemblies fail to fire or fail to comply with the delay time requirement specified on the applicable drawing, the lot shall be rejected. In addition, if a total of two (2) or more primer and delay assemblies after functioning have the cup protrude thru the crimp securing the cup in the shell case, the lot shall be rejected. The test shall be performed as specified in 4.4.2, using equipment in accordance with 4.3.4.

4.3.3.4 High temperature, low temperature and water-immersion firing of primer and delay assembly (see Dwg. 8840311) Major defects.

4.3.3.4.1 High temperature (Code No. 16001).-Forty (40) assemblies shall be selected from each lot and subjected to this test. The test shall be performed as specified in 4.4.3.1, using equipment in accordance with 4.3.4. Rejection shall be as specified in 4.3.3.4.4.

4.3.3.4.2 Low temperature (Code No. 17001).-Forty (40) assemblies shall be selected from each lot and subjected to this test. The test shall be performed as specified in 4.4.3.2, using equipment in accordance with 4.3.4. Rejection shall be as specified in 4.3.3.4.4.

4.3.3.4.3 Water-immersion.-Twenty-five (25) assemblies shall be selected from each lot and subjected to this test. The test shall be performed as specified in 4.4.3.3, using equipment in accordance with 4.3.4. This test will be conducted for informational purpose only.

4.3.3.4.4 Rejection.-If two or more assemblies fail in the combined high and low phases, the lot shall be rejected.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

4.3.3.5 Check test for deterioration of primers (See MIL-P-20444) Major defect (Code No. 18001).-If the total time between original acceptance of any primer lot and the assembly of that lot into the shell case of the primer and delay assembly exceeds two years, or if the primers have been subjected to adverse conditions, however brief, at any time since previous tests, the primer lot shall be subjected to, and must satisfactorily pass, the check test for deterioration specified in MIL-P-20444 immediately before the primer lot is assembled into the shell case. This test shall be performed by the contractor on primers selected by the Government Inspector at the facility assembling the primer into the shell case. (See 6.4)

4.3.3.6 Sleeve hardness (See dwg. 9258106) Major defect (Code No. 19001).-Five (5) sleeves shall be selected from each heat treatment batch and subjected to this test. If any sleeve fails to comply with the requirement specified on the applicable drawing, the batch represented by the failing part shall be rejected.

4.3.3.7 Salt Spray Test of Sleeve (See Dwg 9258106) Major defect (Code No. 20001).-Fifteen (15) sleeves from each shifts production shall be subjected to the salt spray test as specified on the applicable drawing. If any sleeve fails to comply with the specified requirement, the quantity represented by the sample shall be rejected. The test shall be performed as specified in 4.4.3.4.

4.3.4 Inspection equipment.-Equipment Tabulation (ET) number 8840311 and Equipment Lists (EL's) referenced thereon identify the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3. Supply and maintenance of the equipment listed on the EL's shall be in accordance with MIL-I-45607.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey, and whenever inspection equipment drawings are needed.

4.4 Test methods and procedures.

4.4.1 Moisture content of eimite igniters.-The percentage of total moisture shall be determined in accordance with MIL-STD-286, Method 102.1.3. The electric Hygrometer Method specified in 101.4 may be used as an alternative method for moisture determinations at the loading station at the time of loading.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

4.4.2 Firing and delay time of primer and delay assembly (ambient temperature).-The primer and delay assemblies selected shall be temperature-conditioned at 72 degrees Fahrenheit (72°F) + 4°F for 24 + ½ hours prior to testing. After conditioning, the assemblies shall be placed in a fixture specified on the Equipment List and fired. Observation shall be made for firing and delay time as specified on Dwg 8840311 and for protrusion of the cup through the crimp securing the cup in the shell case. All test results shall be recorded. (See 6.5)

4.4.3 High temperature, low temperature and water-immersion.

4.3.3.1 High temperature.-The primer and delay assemblies selected shall be temperature-conditioned at 160°F + 4°F for 24 + ½ hours prior to testing. After conditioning, the assemblies shall be placed in a fixture specified on the Equipment List and fired. All test results shall be recorded. (See 6.5)

4.4.3.2 Low temperature.-The primer and delay assemblies selected shall be temperature-conditioned at -65°F + 4°F for 24 + ½ hours prior to testing. After conditioning, the assemblies shall be placed in a fixture specified on the Equipment List and fired. All test results shall be recorded. (See 6.5)

4.4.3.3 Water-immersion.-The primer and delay assemblies selected shall be immersed in water 12 inches + 1 inch in depth; water temperature 72°F + 4°F for 24 + ½ hours prior to testing. After immersion, the assemblies shall be placed in a fixture specified on the Equipment List and fired. All test results shall be recorded. (See 6.5)

4.4.3.4 Salt spray test.-This test shall be performed on the sleeves as specified in TT-C-490. The number of hours and the percentage of sodium chloride solution shall be as indicated on the applicable drawing. Examination shall be made for any evidence of corrosion on the plated areas. If any sleeve fails to comply with the specified requirement, it shall be classified defective and corrective action taken as specified in TT-C-490.

4.4.3.5 Hardness of sleeve.-The sleeve shall be subjected to the Rockwell Hardness that in accordance with ASTM test method E 18-67. This is a non-destructive test. Parts so tested may be returned to the lot.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.

5.1.1 Level C.-The primer and delay assemblies shall be preserved and packaged in accordance with Dwgs 7548103 and 7548104.

5.2 Packing.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

5.2.1 Level C.-The primer and delay assemblies, preserved and packaged as specified in 5.1.1, shall be packed in accordance with Dwg. 7548101.

5.3 Marking.-Marking shall be in accordance with Dwgs. 7548101, 7548103 and 7548104, Code of Federal Regulations, Title 49, Parts 171-179.

5.4 Shipping.-When components from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of first article samples.

6.2 Inspection code numbers.-The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. These code numbers shall be listed on drawings of equipment designs submitted by the contractor (See 6.3.5).

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Equipment lists.-Equipment lists indicate the availability of inspection equipment designs by showing in the "Part Number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the "Part Number"

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications: Mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number. When an equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, with the approval of the Government, design alternate inspection equipment to facilitate his operations. Such contractor-prepared designs (See 6.3.4) or commercial equipment selections must be approved by the Government prior to fabrication or procurement of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes and operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to Specification MIL-D-1000, Category A, Form 3. Legibility and reproducibility shall permit conventional making of clearly understandable, high-contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

6.3.5 Submission of contractor design.-All submitted designs shall contain a reference to the applicable 5-digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND13. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract. Submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished, normally, within one month after receipt.

6.4 Cost of check test.-The Contracting Officer will arrange for the contractor to be reimbursed for the expense incurred in the performance of the check test for deterioration of the primer assemblies. The tests shall be conducted at Government expense without cost to the contractor who loaded the primer assemblies or to the contractor assembling the primer assemblies into the shell case; and shall not constitute a basis for rejection against either contractor except where deterioration has occurred as a direct result of carelessness in handling, storage, etc., permitted while the primer assembly lot was under the jurisdiction of either contractor.

6.5 Submission of test data.-In addition to the normal distribution of records, when the primer and delay assembly is procured by the US Army Munitions Command, one (1) copy of all test data and ammunition data cards shall be forwarded to: Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND3.

6.6 Submission of results of contractor-conducted examinations and tests.-Unless otherwise specified by the Contracting Officer, the contractor shall forward requested records of examinations or tests to Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND3.

6.7 Check test for deterioration of primer and delay assemblies (not applicable to new production).-The following test (See 6.6.1) is designed to prevent the loading of Primer and Delay assemblies which have deteriorated, into a major ammunition item. The test shall be performed on Primer and Delay assemblies from each lot which has been stored under normal conditions for more than two years. If the specification for the ammunition item into which the Primer and Delay assemblies are loaded does not

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use.

require that the check test be performed, the Contracting Officer should insert a provision for the performance of the check test in that contract. The Contracting Officer will arrange for the contractor to be reimbursed for expenses incurred in the performance of the check test for possible deterioration of Primer and Delay assemblies.

6.7.1 Firing and delay time test of primer and delay assembly (ambient temperature).-Eighty (80) primer and delay assemblies shall be selected from each lot and subjected to this test. If three (3) or more assemblies fail to fire or fail to comply with the delay time specified on the applicable drawing, the lot shall not be used in production.

6.8 Supersession data.-This specification includes the requirements of, and supersedes, Purchase Specification AEI-427, dated 8 February 1967.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project No: 1345-A319

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:43Z
Check the source to verify that this is the current version before use