MILITARY SPECIFICATION

CIRCUIT CARD ASSEMBLY, CASE INTERCONNECT

This specification is approved for use by the US Army Armament, Munitions and Chemical Command and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification establishes the requirements for manufacture and acceptance of the Case Interconnect Circuit Card Assembly: 9355699, used in the Mortar Ballistics Computer (MBC): M23. Throughout this specification this assembly is referenced as “Interconnect”-

2. APPLICABLE DOCUMENTS.

2.1 Government documents.

2.1.1 Specification and standards. Unless otherwise specified, the following specifications and "stardards of the issue “listed in that issue of the Department of Defense index of Specifications and Standards (DoDISS) specified in the solicitation form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-F-13926	-	Fire Control Materiel; General Specification Governing the Manufacture and Inspection
MIL-I-45607	-	Inspection Equipment, Acquisition Maintenance and Disposition of

STANDARDS

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes

FSC 1220

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commander, US Army Armament Research and Development Center, Attn: AMSMC-QA, Dover, New Jersey 07801-5001 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T03:35Z
Check the source to verify that this is the current version before use.

MIL-STD-109	-	Quality Assurance Terms and Definitions
MIL-STD-454	-	Electronic Equipment, General Requirements for
MIL-STD-1521	-	Technical Reviews and Audits for Systems, Equipments, and Computer Programs
MIL-STD-45662	-	Calibration System Requirements

(Copies of specifications and standards required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal.

DRAWINGS

9355699	Circuit Card Assembly, Case Interconnect
11785850	Computer Set, Ballistics, Mortar: M23

PACKAGING DATA SHEETS

9355699	Packaging of Circuit Card Assembly, Case Interconnect: 9355699

(Copies of drawings and packaging data sheets required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.2 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence."

3. REQUIREMENTS

Item definition. The interconnect provides the Mortar Ballistic Computer (MBC) with electrical interconnection between the following:

a. Keyboard Assembly.

b. Interconnect Circuit Card Assembly.

c. Battery: BB-588/U, BA-5588/U, or BA1588/U.

Source: https://assist.dla.mil -- Downloaded: 20260-23T03:35Z
Check the source to verify that this is the current version before use.

The connector contacts are listed in Table I.

TABLE I. Case interconnect circuit card assembly connector Contacts.

Connector	Pin	Signal Name
XA5	Al	HBO *
XA5	A2	HB1*
XA5	A3	HB2*,
XA5	A4	HB3*
XA5	A5	HB4 *
XA5	A6	HB5*
XA5	A7	HB6 *
XA5	A8	GND
XA5	A9	MSGLED
XA5	A10	ONLED
XA5	All	ELLO
XA5	B1	LBO*
XA5	B2	LB1 *
XA5	B3	LB2*
XA5	B4	LB3 *
XA5	B5	LB4*
XA5	B6	LB5 *
XA5	B7	LB6*
XA5	B8	ON*
XA5	B9	SEQLED
XA5	B10	BATLE D
XA5	Bll	ELHI
XA6A2	1	GND
XA6A2	2	GND
XA6A2	3	GND
XA6A2	4	LLBO*
XA6A2	5	LB1 *
XA6A2	6	LB2*
XA6A2	7	LB3 *
XA6A2	8	LB4 *
XA6A2	9	HB5*
XA6A2	10	HB1*
XA6A2	11	HB4 *
XA6A2	12	HB3*
XA6A2	13	HBo *
XA6A.2	14	HB2 *
XA6A2	15	MS GLE D
XA6A2	16	ELLO
XA6A2	17	HB6 *
XA6A2	18	ELHI
XA6A2	19	ONLED
XA6A2	20	LB5*
XA6A2	21	LB6 *
XA6A2	22	BATP OS

Source: https://assist.dla.mil -- Downloaded: 2026l0-23T03:35Z
Check the source to verify that this is the currentversion before use.

TABLE I. Case interconnect circuit card assembly connector contacts.-Continued

XA6A2	23	BATPOS
XA6A2	24	ON*
XA6A2	25	SEQLED
XA6A2	26	BATLED
	El	BAT
	E2	BATRTN

3.2 Performance. The interconnect shall meet the requirements specified herein unless otherwise specified.

3.2.1 Functional. The resistance between the connector contacts listing in Table II shall be less than 7.5 Ohms.

TABLE II. Connector contacts; resistance.

XA5-A1	to	XA6A2-13
XA5-A2	to	XA6A2-10
XA5-A3	to	XA6A2-14
XA5-A4	to	XA6A2-12
XA5-A5	to	XA6A2-11
XA5-A6	to	XA6A2-9
XA5″A7	to	XA6A2-17
XA5-A8	to	XA6A2-1 to XA6A2 to XA6A2 3 to ‘2
XA5″A9	to	xA6A2-15
XA5-A10	to	XA6A2-19
XA5-A1l	to	XA6A2-16
XA5-B1	to	XA6A2-4
XA5-B2	to	xA6A2-5
XA5-B3	to	XA6A2-6
XA5-B4	to	XA6A2-7
XA5-B5	to	XA6A2-8
XA5-B6	to	XA6A2-20
XA5-B7	to	XA6A2-21
XA5-B6	to	XA6A2-24
XA5-B9	to	XA6A2-25
XA5-B10	to	XA6A2-26
XA5-B1l	to	XA6A2-18
XA6A2-22	to	XA6A2-23 to El

3.2.2 Physical characteristics. The physical characteristics shall be as prescribed by the drawings, specifications, and QAP’s.

3.2.3 Reliability. When specified in the contract, a special sample shall be subjected to reliability testing. The manufacturing and production techniques emloyed in the fabrication of the interconnect shall not degrade the inherent rellablllty. (see 4 and 6)

Source: https://assist.dla.mil -- Downloaded: 2026l0-23T03:35Z
Check the source to verify that this is the current version before use.

3.3 Environmental. The interconnect shall meet the requirements specified herein unless otherwise specified.

3.3.1 Room ambient temperature. The requirements of this specification shall be met with the interconnect thermally stabilized at room ambient temperature of +16°C to +32°C (+60°F to +90°F), unless otherwise specified in the requirements paragraph.

3.3.2 Environmental stress screen (ESS) temperature. The interconnect shall meet the requirements of 3.2.1 after having been exposed to a minimum of ten temperature cycles at temperatures of -57°C and +71°C (-71°F and +160°F).

3.3.3 Environmental stress screen (ESS) vibration. The interconnect shall meet the requirements of 3.2.1 after having been subjected to a random or pseudorandom vibration which includes frequency content from 100 Hz to 1000 Hz and up to a 3g RMS in two axis for a period of 10 minutes plus or minus 15 seconds.

3.4 Fabrication. The interconnect shall be manufactured in accordance with drawing 9355699.

3.5 First article. When specified in the contract, a sample shall be subjected to first article inspection (See 4 and 6).

3.6 Workmanship. The workmanship requirements of MIL-F-13926 and MIL-STD-454 shall be met. All components shall be fitted properly and firmly in their respective positions. All electrical connections shall be mechanically secure and electrically sound. There shall be no evidence of corrosion, burrs, roughness, sharp edges or other defects which could adversely affect its use or suitability for the purpose intended.

3.7 Materials. Materials shall be in accordance with drawings, material specifications and general specifications forming a part of this specification.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T03:35Z
Check the source to verify that this is the current version before use.

4.1.1 General provisions. The component and subassembly inspection requirements of MIL-F-13926 and MIL-STD-454 form a part of the Quality Assurance Provisions of this specification. Definitions of inspection terms shall be as listed in MIL-STD-109.

4.2 First article (initial production) approval. The requirement for first article approval and the responsibility (Government or contractor) for first article testing shall be as specified in the contract. The sample for first article approval test shall consist of three (3) interconnect plus three (3) each of all items covered by QAP. The three interconnect shall be tested as specified herein for all the requirements of this specification. The items covered by QAP shall be tested, as specified thereon, for all characteristics delineated on the QAP. The samples shall be manufactured in the same manner, using the same materials, equipment, processes, and procedures as will be used in the production of the balance of the contract quantity. All parts and materials, including packaging and packing, shall be obtained from the same source of supply as will be used in the production of the balance of the contract quantity.

4.2.1 Government testing. When the Government is responsible for conducting first article approval test, the contractor prior to submitting sample to the Government, shall inspect the sample to insure that it conforms to all requirements of the contract and submit a record of this inspection with the sample, including certificates of conformance for all materials.

4.2.2 Contractor testing. When the contractor is responsible for conducting first article approval tests, the sample shall be inspected by the contractor for all the requirements of the contract. The sample and a record of this inspection, including certificates of conformance for all materials, shall be submitted to the Government for approval. The Government reserves the right to witness any or all of the contractor’s inspections.

4.3 Inspection provisions.

4.3.1 Submission of product. Unless otherwise specified by the contracting officer, inspection lot size, lot formation, and presentation of lots shall be in accordance with “Submission of Product” provision of MIL-STD-105.

4.3.2 Examination and tests.

4.3.2.1 Components and subassemblies. All components and subassemblies shall be inspected in accordance with the inspection provisions contained in Quality Assurance Provisions (QAP’s) listed in the Technical Data Package (TDP). In the absence of QAP's, the applicable Quality Assurance Provisions of MIL-F-13926 shall apply.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T03:35Z
Check the source to verify that this is the current version before use.

4.4 Sampling.

4.4.1 Envitonmental/performance. The interconnect shall be inspected to the requirements in Table III.

TABLE III. Classification of defects.

No.	Characteristics	Requirement	Test procedure
100% Inspection			
1.	Functional	3.2.1	4.6.3
2.	ESS temperature	3.3.2	4.6.1
3.	ESS vibration	3.3.3	4.6.2
MAJOR: AQL 1.0% Defective			
101.	Workmanship	3.6	4.6.4

4.4.2 Special sampling. One interconnect shall be selected at random as a special sample from each lot or each 100 produced which ever occurs first. The sample shall meet the requirements and tests in Table IV.

TABLE IV. Classification of defects.

No.	Characteristics	Requirement	Test procedure
201.	Fabrication	3.4	Applicable Drawing/ Visual
202.	Materials	3.7	Applicable Drawing/ Visual

NOTE: The tests in Table IV shall be conducted at room ambient temperature (as specified in 3.3.1).

4.4.3 Failure of sample. Should any one item of a special sampling fail to meet the specified test requirements, acceptance of the represented inspection lot will be suspended by the Government until necessary corrections have been made by the contractor and resubmitted items have been approved in accordance with “Acceptance and Rejection” as specified in MIL-STD-105.

4.5 Inspection equipment. Except as otherwise provided for by the contract, the contractor shall supply ans maintain inspection equipment in accordance with the applicable requirements of MIL-I-45607.

4.5.1 Government furnished inspection equipment. Where the contract providesfor Government furnished test equipment, supply and maintenance of test equipment shall be in accordance with the applicable requirements specified in MIL-I-45607.

Source: https://assist.dla.mil -- Downloaded: 20260-23T03:35Z
Check the source to verify that this is the current version before use.

4.5.2 Contractor furnished inspection equipment.

4.5.2.1 Government design. All inspection equipment specified by drawing number in specification or QAP forming a part of the contract shall be supplied by the contractor in accordance with technical data included in the Technical Data Package List (TDPL).

4.5.2.2 Contractor design. In the absence of Government inspection equipment design, the contractor shall design and supply inspection equipment compatible with the “Test Methods and Procedures" specified in 4.6 of this specification and with the component inspection procedures specified in “Examination” and "Test Facilities" requirements of MIL-F-13926. Since tolerance of test equipment is normally considered to be within 10% of the product tolerance for which it is intended, this inherent error in the test equipment design must be considered as part of the prescribed product tolerance limit. Thus, concept, construction, materials dimensions, and tolerance used in the design of test equipment shall be so selected and controlled as to insure that the test equipment will reliably indicate acceptability of a product which does not exceed 90% of the prescribed tolerance limit, and permit positive rejection when non-conforming. Construction shall be such as to facilitate routine calibration of test equipment.

4.5.2.3 Inspection equipment design requirements.

4.5.2.3.1 Temperature testing. The volume of the test chamber shall conform to the test facilities requirements of MIL-F-13926. The air temperature at the control sensor shall be in accordance with the specified requirements within plus or minus 2.5% (1.4°C). The temperature gradient across the cross-sectional area occupied by the test item shall not exceed 0.50F per foot in any direction. The heat source of the test chamber shall be so located that radient heat, if used, will not fall directly on the test item. Thermocouples or equivalent temperature sensors utilized to determine or control the specified chamber temperature shall be centrally located within the test chamber within the supply airstream, or in the return airstream, whichever provides the specified test condition at the item under test and shall be baffled or otherwise protected against radiation effects.

4.5.2.3.2 Fabrication, setup and calibration. Design and fabrication of test equipment shall be such that it incorporates the features of rigidity, stability, and ease of maintenance. Setup and calibration equipment necessary for certification of the testing equipment accuracy shall be furnished and will become a part of the testing equipment. Operating and calibration instruction shall be prepared and submitted to the procuring activity.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T03:35Z
Check the source to verify that this is the current version before use.

4.6 Test methods and procedures. Unless otherwise specified in the contract, the following procedures shall be utilized to conduct specified tests. If the contractor chooses to use alternate test procedures, a detailed description of the set-up and procedure shall be submitted to the government procuring agency for approval prior to use.

4.6.1 ESS temperature. Testing equipment utilized in the test shall conform to the requirements of 4.5.2.3.1. The interconnect shall be placed in the test chamber and the temperature of the chamber reduced 10°C (18°F) per minute plus or minus l°C (1.8°F) from room ambient temperature (as specified in 3.3.1) to -57°C (-71°F) . The interconnect shall be maintained at this temperature for a minimum of 20 minutes. upon completion of the 20 minute exposure, the temperature of the chamber shall be raised 10°C (18°F) per minute plus or minus 1°C (1.8°F) to +71°F (+160°C). The interconnect shall remain at this temperature for a minimum of 20 minutes. Upon completion of the 20 minute exposure the temperature of the chamber shall be reduced 10°C (18°F) per minute plus or minus 1°C (1.8°F) to room ambient temperature (as specified in 3.3.1). The above procedure shall be conducted a minimum of ten times. Upon completion of the cycles the interconnect shall then be removed from the chamber and subjected to the test in 4.6.3. It shall meet the requirements of 3.2.1.

4.6.2 ESS vibration. Conduct the vibration test with the interconnect positioned on an appropriate adapter affixed to a vibrating machine that is capable of providing the amplitudes and frequencies specified in 3.3.3. Unless otherwise specified, the test equipment shall be in accordance with the “Test Facilities” requirements of MIL-F-13926. The applied motion shall be in two separate planes for the time period specified. Upon completeion of the vibration sweep the interconnect shall be removed from the vibration adapter and shall be subjected to the test in 4.6.3. It shall meet the requirements of 3.2.1.

4.6.3 Functional tests. This test is to be conducted utilizng a certified Ohm meter. Measure the resistance between the connector contacts listed in Table II. All measured resistances shall meet the requirements of 3.2.1.

4.6.4 Workmanship. The interconnect shall be subjected to a visual and tactile examination for evidence of faulty workmanship. The interconnect shall conform to the requirements of 3.6.

Source: https://assist.dla.mil -- Downloaded: 2026l0-23T03:35Z
Check the source to verify that this is the currentversion before use.

4.7 Reliability testing. The requirement for reliability test approval and the responsibility (Government or contractor) for reliability testing shall be as-specified in the contract." The sample for reliability test shall consist of 3 interconnects. The samples shall be manufactured in the same manner, using the same materials, equipment, processes, and procedures as will be used in the production of the balance of the contract quantity. All parts and materials, including packaging and packing, shall be obtained from the same source of supply as will be used in the production of the balance of the contract quantity.

4.7.1 Government testing. When the Government is responsible for conducting reliability tests, the contractor prior to submitting the sample to the Government, shall inspect the sample to assure-that it conforms to all requirements of the contract-and submit a record of this inspection with the sample, including certificates of conformance for all materials.

4.7.2 Contractor testing. When the contractor is responsible for conducting reliability tests, the sample shall be inspected and tested by-the contractor for all the requirements of the cpontract. The sample and a record of these inspections and tests, including certificates of conformance for all materials, shall be submitted to the Government for approval. The Governemnt reserves the right to witness any or all of the contractors reliability tests and inspections.

5. PREPARATION FOR DELIVERY

5.1 Delivery requirements. Handling, packaging, packing, shipping, and marking of the Case Interconnect Circuit Card Assembly, 9355699 shall be in accordance with Packaging Data Sheet 9355699. The level of protection shall be as specified in the procurement document.

6. NOTES

6.1 Intended use. The interconnect described herein is intended for use in the MBC. See drawing 11785850.

6.2 Ordering data. Procurement documents shall specify the following:

a. Title, number and date of this specification.

b. Provisions for first article testing.

c. Provisions for reliability testing.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T03:35Z
Check the source to verify that this is the current version before use.

d. Applicable Packaging Data Sheet.

e. Applicable levels of preservation, packing, and marking (see 5.1).

f. Applicable stock numbers.

Custodian:
Army-AR

Preparing activity:
Army-AR

(Project 1220-A307)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T03:35Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON D. C.
POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commander
US Army Armament Munitions &
Chemical Command
ATTN: AMSMC-QA
Dover, NJ 07801-5001

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T03:35Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-C-70497 (AR)	

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ USER
	☐ MANUFACTURER
	☐ OTHER *(Specify)*: _____

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 1426 PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil – Downloaded: 2026-10-23T06:35Z
Check the source to verify that this is the current version before use.