MIL-T-83256 (USAF)
AMENDMENT 2
29 November 1971
SUPERSEDING
AMENDMENT 1
14 April 1971

MILITARY SPECIFICATION

TRUCK, FIRE FIGHTING, STRUCTURAL A/S32P-12;
750 GPM, 4 BY 2 CHASSIS

This amendment forms a part of Military Specification MIL-T-83256 (USAF) dated 10 February 1970.

Page 2, paragraph 2.1, military standards: Add:

"MIL-STD-281 Automobiles, Trucks, Truck-Tractors, Trailers and Trailer Dollies, Preservation and Packaging of".

Page 7, paragraph 3.6.1, item b: Delete "Starting and".

Page 7, paragraph 3.6.2, item a: Delete and substitute:

"a. Negotiate, in both directions, a 15° ramp connecting two horizontal surfaces. The ramp length shall be at least 1.2 times the wheelbase of the truck. The truck shall be capable of being driven forward, or backed from one horizontal surface across the ramp toe, ascend or descend the ramp, cross the ramp crest and proceed on the other horizontal surface without any portion of the truck scraping any of the three surfaces".

Page 8, paragraph 3.6.3:

(1) Item a, line 1: Delete "through any three" and substitute "through each of any three".

*(2) Item b: Delete and substitute:

"b. Discharging water at a rate of 125 gpm through each of the two 1-1/2-inch preconnect discharge outlets separately or simultaneously while selectively pumping from draft, hydrant, or the installed water tank supply."

Page 10, paragraph 3.7.2.5, first sentence: Delete "charged and dry, without electrolyte" and substitute "charged and wet".

Page 12, paragraph 3.8.3, last sentence: Delete and substitute "Drains shall be located inside the pump compartment and shall discharge onto the ground from a point below the bottom of the truck frame."

FSC 4210

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:43Z
Check the source to verify that this is the current version before use.

*Page 13, paragraph 3.8.5:

(1) Item c, second sentence: Delete.

(2) Add:

"f. Outlets of not less than 1-1/2-inch NPT in the discharge manifold for lines leading to preconnect hose. Valve controls shall be at the pump control panel."

*Pages 14 and 15, paragraph 3.9.2:

(1) Third sentence: Delete "Four 2-1/2-inch diameter discharge gages" and substitute "Six 2-1/2-inch diameter discharge gages".

(2) Item c: Delete "Four" and substitute "Six".

(3) Add:

"u. Lights adjacent to each of the two preconnect discharge valve controls which, when operated by weatherproof switches in each of the 1-1/2-inch preconnect hose storage areas, will automatically indicate which hose is withdrawn from the hose bed

"v. A pressure computer to calculate proper pump pressures for various hose lays."

*Page 15, paragraph 3.9.3: Add "The 1-1/2-inch hose shall be preconnected to pump feeder lines extending through the forward wall of each storage area."

Pages 17 and 18, paragraph 3.10:

(1) Item c (3): Delete.

*(2) Item u: Delete "brass or".

*Page 19, paragraph 3.11, beginning of sentence: Add "Unless otherwise specified (see 6.2),".

Page 19, paragraph 3.11.1:

(1) Ninth sentence: Delete and substitute "The tanks shall be fabricated of 304L, 316L, 321, or 347 stainless steel."

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:43Z
Check the source to verify that this is the current version before use.

(2) Last sentence: Delete and substitute "The tanks shall withstand an internal static pressure of 5 psi without leaking, and shall be so designed that at least 90 percent of their rated agent capacities can be discharged during pumping operations with the truck headed in either direction on a 20-percent side slope."

Page 21, paragraph 3.13.1, item a: Add "with a removable bottom cover".

*Page 27, paragraph 4.5.1: Add:

"e. Pumping tests . . . . . See 4.6.12 thru 4.6.12.3."

*Page 27, paragraph 4.5.2: Delete and substitute:

"4.5.2 Sampling plan and tests. One truck shall be selected at random from each fifty, or fraction thereof produced, and subjected to the following tests as described under 4.6:

a. One-hundred-mile road test . . . . . See 4.6.5

b. High temperature pumping . . . . . See 4.6.12.4

c. Agent discharge . . . . . See 4.6.13."

Page 29, paragraph 4.6.12.4, first sentence: Delete and substitute "With the pump compartment bottom cover removed, the properly instrumented truck shall be placed in a hot chamber and subjected to an ambient temperature of 125° ±2°F for a period of at least 24 hours."

*Page 30, paragraph 4.6.13, item b: Delete and substitute:

"b. A water discharge rate of 125 gpm through each of the two 1-1/2-inch preconnect discharge outlets separately or simultaneously while selectively pumping from draft, hydrant, or the installed water tank supply".

Page 30, paragraph 4.6.14: Delete and substitute:

"4.6.14 Agent tank exhaustion. It shall be demonstrated that at least 90 percent of the water tank and foam liquid tank capacities can be discharged during pumping operations while the truck is headed in either direction on a 20-percent side slope."

Page 33: Add:

"4.7 Inspection of preparation for delivery. Preservation, packaging, packing, and marking shall be examined to determine compliance with the requirements of section 5 herein."

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:43Z
Check the source to verify that this is the current version before use.

Page 33, paragraph 5.1: Delete and substitute:

"5.1 Preservation, packaging, packing, and marking. Preservation, packaging, packing, and marking shall be in accordance with MIL-STD-281, level A, B, or C, as specified (see 6.2)."

*Page 34, paragraph 6.2: Add:

"i. Stored agent system requirements (see 3.11)

"j. Applicable levels of preservation, packaging, and packing (see 5.1)."

*The margins of this specification are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This has been done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

Custodian:
Air Force - 11

Reviewer:
Air Force - 84

Preparing activity:
Air Force - 11

Project No. 4210-F091

*U.S. GOVERNMENT PRINTING OFFICE: 1971-714-161/4199

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:43Z
Check the source to verify that this is the current version before use.