A-A-53439
29 April 1988

COMMERCIAL ITEM DESCRIPTION

CHAMBER, X-RAY FILM PROCESSING

The General Services Administration has authorized the use of this Commercial Item Description.

This Commercial Item Description covers a manually operated dental portable darkroom for processing dental x-ray film without plumbing or electricity.

Salient characteristics:

The x-ray film processing chamber shall be a non-automatic, plastic, dental chairside portable darkroom for processing (hand developing) intra-oral dental x-ray film without plumbing or electricity.

The processing chamber shall consist of a sturdy molded structural plastic body with a detachable molded structural plastic base. The base shall fit snugly into the body so as to prevent the entry of light into the unit. The body and the base shall be easily separated and easily cleaned.

The processing chamber shall be box-shaped with two diverging sides to provide normal arm positioning and an anterior-posterior dimension of not less than 10 inches (25.40 cm). Overall dimensions with base shall be approximately 17 inches long, by 11 inches deep, by 11 inches high (43.18 cm by 27.94 cm by 27.94 cm).

Each diverging side at the front of the body shall have hand-holes approximately 4.5 inches (11.4 cm) in diameter which are equipped with replaceable nylon reinforced neoprene rubber hand-entry frames which shall grip the wrists gently, yet effectively prevent entry of light into the unit.

The body shall have rectangular opening at the top approximately 11.5 inches by 4.5 inches (29.0 cm by 11.4 cm) which shall be covered by a removable see-through amber light-filtering panel which shall provide easy entry from above. The amber panel shall completely filter out normal room lighting.

AMSC N/A FSC 6525

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:19Z
Check the source to verify that this is the current version before use.

The base shall have a recessed holding tray for discarded film packets, and four recessed retainers to prevent spillage of four approximately 8 ounce (236 cc) plastic processing jars.

The processing chamber shall be supplied with four processing jars, a developer jar, a fixer jar, and two rinse water jars. The developer and fixer jars shall each be equipped with easy-to-operate hinged stainless steel closure lids which are of the "pop-top" type, are air tight, and will prevent oxidation of the solutions so as to prolong solution life. The two water jars shall have screw caps to prevent spillage if and when the processing chamber is transported to an alternate workplace.

The processing chamber shall be furnished with four hook and pile fasteners to secure bottom of base to counter top or table to prevent slippage of unit. The fasteners shall allow for easy removal for chamber cleaning or use at another location.

The processing chamber shall be supplied with three film clips for film drying.

All parts of the processing chamber shall be resistant to x-ray developer and fixer chemicals. The chamber finish shall be free of pits, burrs, sharp edges, scratches, stains, or other appearance defects.

Each processing chamber shall be supplied with one set of instructions for use.

Workmanship. The x-ray processing chamber shall be free from defects which detract from its appearance or impair its serviceability.

Unit. Each (EA). One chamber, as specified, constitutes one unit.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:19Z
Check the source to verify that this is the current version before use.

Quality Assurance Provisions.

Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Records. Records of examinations and tests performed by or for the contractor shall be maintained by the contractor and made available to the Government upon the Government's request, at any time, or from time to time, during the performance of the contract and for a period of three years after delivery of the supplies to which such records relate.

Inspection. Inspection, as used herein, is defined as both examination (such as visual or auditory investigation without the use of special laboratory appliances or procedures) and testing (determination by technical means of physical and chemical properties) of the item.

Tests. Tests shall be conducted to determine compliance with specification requirements. Where feasible, the same sample shall be used for the determination of two or more test characteristics.

Sampling for examination. Sampling for examination shall be conducted in accordance with MIL-STD-105, with an AQL of 1.0 (percent defective) and an inspection level of II. The unit of product for examination purposes shall be one x-ray processing chamber as specified in this description.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:19Z
Check the source to verify that this is the current version before use.

Defects.

Any component missing, broken, or not as specified.

Anterior-posterior dimension of chamber less than 10 inches (25.40 cm).

Developer and fixer jars do not have stainless steel closure lids.

Amber light-filtering panel is not removable.

The chamber body and base are not easily separated.

Chamber finish not free of pits, burrs, sharp edges, scratches, stains, or other appearance defects.

Instructions for use not furnished.

Sampling for tests. Sampling for tests including dimensional test, shall be conducted in accordance with MIL-STD-105, with an AQL of 2.5 (percent defective) and inspection level of S-3. The unit of product for test purposes shall be one x-ray film processing chamber.

Tests.

Light-Tightness Test

The body of the processing chamber shall be attached to the base in the specified manner. Both hands of the operator shall be then inserted through the two hand holes of the chamber along with three unexposed intra-oral film packets. The chamber shall then be inspected for visible light leakage around the neoprene rubber hand entry frames.

After hand insertion into chamber, the film jackets shall then be removed from the unexposed intra-oral film and the film developed completely to final rinse. The fully developed film shall then be checked for signs of light leakage during processing.

Any visible evidence of light leakage, or evidence of light leakage onto processed film, shall constitute a major defect.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:19Z
Check the source to verify that this is the current version before use.

Contractor certification. The contractor shall certify that the product offered meets the salient characteristics of this description and conforms to the producers' own drawings, specifications, standards, and quality assurance practices. The Government reserves the right to require proof of such conformance prior to first delivery and thereafter as may be otherwise provided for under the provisions of the contract.

Regulatory requirements.

Federal Food, Drug and Cosmetic Act. If the product covered by this document has been determined by the U.S. Food and Drug Administration to be under its jurisdiction, the offeror/contractor shall comply, and be responsible for compliance by its subcontractors/suppliers, with the requirements of the Federal Food, Drug and Cosmetic Act, as amended, and regulations promulgated thereunder. In addition, the offeror/contractor shall comply, and be responsible for compliance by its subcontractors/suppliers, with the requirements of all other applicable Federal, State, and local statutes, ordinances, and regulations.

Recovered materials. The offeror/contractor is encouraged to use recovered material in accordance with Public Law 94-580, as amended, and as implemented by Federal Acquisition Regulation Subpart 23.4 to the maximum extent practical.

Preservation, packaging, packing, labeling, and marking. Unless otherwise specified, preservation, packaging, and packing shall be to a degree of protection to preclude damage to containers and/or contents thereof under normal shipping conditions, handling, etc., involving shipment from the supply source to the receiving activity, plus reshipment from receiving activity, and shall conform to applicable carrier's rules and regulations. Intermediate and exterior package quantities and labeling and marking shall be as specified in the contract and/or order.

NOTE: The following National Stock Number is covered by this document:

6525-01-125-6593

Ordering data. Intermediate/exterior package quantities, labeling, and marking must be specified in the contract and/or order.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:19Z
Check the source to verify that this is the current version before use.

MILITARY INTERESTS:

Custodians:

Army - MD
Navy - MS
Air Force - 03

PREPARING ACTIVITY:

DoD - MB

Agent:

DLA-DM

CIVIL AGENCY COORDINATING ACTIVITIES:

VA-OSS
PHS
FDA-MPQAS

Project No. 6525-1231

PGC 40909

Location: CID/CHAMBER/H13-25

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:19Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEFENSE LOGISTICS AGENCY

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO 4966 WASHINGTON D C

POSTAGE WILL BE PAID BY THE DEFENSE LOGISTICS AGENCY

Commander
Defense Personnel Support Center
Attn: DPSC-RSTS
2800 South 20th Street
Philadelphia, PA 19101

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:19Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
A-A-53439	CHAMBER, X-RAY FILM PROCESSING

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
	☐ USER
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ MANUFACTURER
	☐ OTHER *(Specify)* _____

5. PROBLEM AREAS

a. Paragraph Number and Wording

b. Recommended Wording

c. Reason/Rationale for Recommendation

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

Source: https://assistdocs.mil – Downloaded: 2026-10-26T09:19Z
Check the source to verify that this is the current version before use.