11 February 1972
Superseding
MIL-P-10653C(EL)
16 February 1970

MILITARY SPECIFICATION

POWER SUPPLY
(PLATE SUPPLY-TIMER UNIT PE-244( ))

1. SCOPE

1.1 This specification covers one type of power supply for providing filtered power and timing pluses; designated as Plate Supply-Timer Unit PE-244( ). (See 6.1 and 6.4.)

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-P-116	Preservation, Methods of
MIL-T-152	Treatment, Moisture-and-Fungus-Resistant, of Communications, Electronic, and Associated Electrical Equipment
MIL-V-173	Varnish, Moisture-and-Fungus-Resistant (For the Treatment of Communications, Electronic, and Associated Electrical Equipment)
MIL-C-3885	Cable Assemblies and Cord Assemblies, Electrical (For Use in Electronic, Communications, and Associated Electrical Equipment)
MIL-S-10956	Sound Ranging Set GR-8, Packaging and Packing of

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

MIL-P-11268	Parts, Materials, and Processes Used in Electronic Communication Equipment
MIL-M-13231	Marking of Electronic Items
MIL-F-14072	Finishes for Ground Signal Equipment.

STANDARDS

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-252	Wired Equipment, Classification of Visual and Mechanical Defects
MIL-STD-454	Standard General Requirements for Electronic Equipment
MIL-STD-461	Electromagnetic Interference Characteristics, Requirements for Equipment
MIL-STD-810	Environmental Test Methods

DRAWINGS

ELECTRONICS COMMAND

SC-A-46439	List of Accessories for Package Tester.
SC-DL-182740	Plate Supply-Timer Unit PE-244( ).
SC-A-678013	Burn-in (Debugging) Procedure.

(Copies of specifications, standards, and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity, or as directed by the contracting officer. Both the title and number or symbol should be stipulated when requesting copies.)

3. REQUIREMENTS

3.1 First articles.- The contractor shall furnish first articles for approval as required by the invitation for bids and contract. (See 4.3 and 6.2(c).)

3.2 Construction.- Construction of the equipment shall be in accordance with Drawing and Data List SC-DL-182740.

3.3 Parts, materials, and processes; general.- In addition to the requirements of this specification, the requirements of MIL-P-11268, including the selection requirements therein, shall apply.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

3.4 Cable assemblies.- Power and audio-frequency cable and cord assemblies used for voltages up to and including 600 volts AC, or equivalent DC, shall be in accordance with MIL-C-3885.

3.5 Performance requirements.-

3.5.1 Voltage ratings.- The microphone voltage (+100 volts) represents the voltage supplied to Microphone T-23( ). Amplifier voltage (+300 volts) represents the voltage used to power the amplifier and supply current for writing the signals on the chart paper of Recorder BC-1337( ). The high voltage is used to supply current to the time marking styli of the recorder. The operating values shown in Table I for the power supply shall be minimum requirements for the battery source voltage when set as indicated. The microphone voltage shall not exceed +105 volts. (See 4.7.1).

Table I.- Minimum Voltage Requirements

Battery source supply voltage	10.5	12.5
High voltage	265	315
Amplifier voltage (+300 volts)	260	295
Microphone voltage (+100 volts)	95	95

3.5.2 Power supply ripple and frequency of DC to DC converter.- (see 4.7.2)

3.5.2.1 Power supply ripple.- The ripple voltage including noise pulses shall not exceed one (1) volt peak-to-peak at the +100 volt and +300 volt outputs of the power supply. (See 4.7.2.1)

3.5.2.2 Power supply oscillator frequency.- The fundamental frequency of the converter oscillator shall be 2.1 ±0.6K Hz. (See 4.7.2.2)

3.5.3 Timer interval unit.- (See 4.7.3)

3.5.3.1 Crystal oscillator stability.- The crystal oscillator shall have a frequency of 1000 ±0.2K Hz. (See 4.7.3)

3.5.3.2 Frequency dividers.- The timing pulses (100 Hz, 10 Hz and 1 Hz) at the output of the timer shall not deviate more than ±200 parts in 1,000,000. (See 4.7.3)

3.5.4 Operation.- Continuous operation for a period of 30 minutes. The recording obtained shall be clear and legible when tested in accordance with 4.7.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

material. contents cushioned etc.: with polystyrene (10058-1111)

3.6 Finish, protective. - The power supply shall be given protective finish in accordance with MIL-F-14072. This includes finish of hardware, such as handles, hinges, screws, etc, and necessary touch up after mounting. The final paint film on type I surfaces shall be green color (olive drab), semigloss enamel matching a color chip provided by the procuring agency. (See 6.3.)

3.7 Marking.-

3.7.1 General.- Marking shall conform to MIL-M-13231. (See 4.4.) Front panel markings shall be group 1 as described in that specification.

3.7.2 Visibility.- Wherever practicable, parts shall be so mounted that their identification markings will be readily visible with minimum disassembly of the equipment.

3.7.3 Serial numbers.- The power supplies shall be serial numbered.

3.8 Tropicalization.-

3.8.1 Overall treatment (moisture and fungus proofing treatment (MFP)).- When overall tropicalization treatment of equipment is a contractual requirement, a moisture and fungus resistant coating of varnish conforming to MIL-V-173 shall be applied in accordance with MIL-T-152. The moisture-fungus resistant coating shall be applied after the equipment has been cleaned to remove such contaminants as corrosion products, dust, fingerprints, lubricating oils, mold release agents, sand, and solder fluxes. When tape is used on parts of equipment that are masked against treatments, the tape shall be an electrical grade. In the application of the MFP coating, care shall be taken to assure that the coating does not affect circuit constants and thereby degrade performance.

3.9 Interchangeability.- Like units, assemblies,subassemblies, and replaceable parts shall conform to requirement 7 of MIL-STD-454. (See 4.8)

3.10 Burn-in (debugging).- The power supply shall be capable of meeting the requirements of this specification after being subjected to the burn-in (debugging) cycle of Drawing SC-A-678013. (See 4.9.

3.11 Service conditions.- After a warmup period of 10 minutes, the power supply shall meet the specified performance requirements of this specification when subjected to the following conditions:

3.11.1 Temperature.-

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

3.11.1.1 Low temperature.- During testing as specified in 4.10.1, the power supply shall meet the performance requirements of this specification.

3.11.1.2 High temperature.- During testing as specified in 4.10.2, the power supply shall meet the performance requirements of this specification.

3.11.2 Rain.- After testing as specified in 4.11, the power supply shall meet the performance requirement of 3.5.4.

3.11.3 Altitude (elevation).- The power supply shall meet full specification requirements as tested in accordance with 4.12.

3.11.4 Dust.- After testing as specified in 4.13, the power supply shall meet full specification performance.

3.11.5 Humidity (moisture-resistance).- During testing as specified in 4.14, the power supply shall meet the performance requirement of 3.5.4.

3.11.6 Bounce (vibration) and shock.- The power supply shall meet the requirements of table II.

Table II Bounce (vibration) and Shock

Requirement	Insp Para	Performance after test
Bounce (vibration)	4.15	Full specification performance with the exception that the total excursion in the resonance survey test of panel may exceed twice the amplitude of the input. Minor mechanical damage is permissible
Shock; bench handling	4.16	Full specification performance. Minor mechanical damage is permissible
Shock; drop	4.17	The equipment shall be operable. Minor mechanical damage is permissible

3.11.7 Orientation.- During testing as specified in 4.18, the power supply shall meet full specification performance.

3.12 Electromagnetic interference.- The power supply shall meet the electromagnetic interference requirements as tested in accordance with 4.19.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

late or voltage as specified herein.

3.13 Tools and running spare parts.- Tools and running spare parts shall be furnished as specified by the contract. Running spare parts shall be identical to corresponding parts in the equipment furnished on the order. (See 6.2(d).)

3.14 Workmanship.- The power supply shall be manufactured and assembled in accordance with requirement 9 of MIL-STD-454 and the applicable portions of the following paragraphs:

(a) In MIL-P-11268:

General requirements for plastic material and plastic parts.
Wiring and cabling, including:
Slack.
Protection.
Clearance.
Splicing.
Connections, general
Grounding, general.
Shielding on wire and cable.
Soldering and brazing.
Cleaning of units.
General requirements for securing of parts.
Process for welding.
Cleaning after welding.
Controls.
Self-tapping screws.
Cleaning prior to welding.

(b) In this specification:

Para 3.2 Construction.
Para 3.4 Cable assemblies.
Para 3.6 Finish.
Para 3.7 Marking.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.- Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the government. The government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

4.1.1 Contractor quality assurance. The contractor shall provide and maintain a means of determining product conformance in accordance with the requirements specified herein or elsewhere in the contract. The Government, at its option, may perform any evaluation deemed necessary to assure the adequacy of the means employed and the effectiveness of the contractor's quality assurance methods and systems.

4.1.2 Government verification.- All quality assurance operations required of the contractor shall be subject to Government verification at scheduled or unscheduled intervals. Verification will consist of the following:

a. Surveillance of the contractor's operations to determine that practices, methods and procedures of the contractor's quality assurance system are being applied and are, in fact, accomplishing the objectives of total compliance of the product with the requirements of this specification and the contract.

b. Government product inspections to determine compliance of the product with the specification and contract requirements.

4.1.3 Accomodation and assistance.- The Government quality assurance representative shall have the right of access to any area the work is being performed. The Government quality assurance representative shall be afforded unrestricted opportunity to verify conformance of the product with specification requirements. The contractor shall make his inspection equipment and records available for use by the Government quality assurance representative for verification purposes. The contractor's personnel shall be made available for operation of such inspection equipment as required.

4.2 Classification of inspections. - Inspections shall be classified as follows:

(a) First article inspection. (Does not include preparation for delivery.) (See 4.3.)

(b) Inspections covered by subsidiary documents. (See 4.4.)

(c) Quality conformance inspections.

(1) Quality conformance inspection of equipment before preparation for delivery. (See 4.6)

(2) Quality conformance inspection of preparation for delivery. (See 4.21)

4.3 First article inspection. - This inspection shall consist of the inspections

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

specified in subsidiary documents covering the items listed in 4.4, and the inspections specified for group A, group B, and group C (see tables V, VI and VII, respectively). First article inspection shall be performed in the order shown in table III according to the number of samples specified in the contract or order.

Table III Order of Environmental Testing

Inspection (Note 1)	Number of units				
	Two	Three			
	Unit 1	Unit 2	Unit 1	Unit 2	Unit 3
Non-damaging (Note 2)					
Low temperature	1		1		
High Temperature	2		2		
Rain	3		3		
Altitude (elevation)		1		1	
Dust		2			1
Potentially damaging					
Humidity (moisture resistance)	4			2	
Bounce (vibration)		3			2
Shock; bench handling		4			3
Shock; drop		5			4

Note 1: Other inspections may precede, follow, or be interspersed between the non-damaging tests.

Note 2: The order of non-damaging tests and the choice of which units are subjected to the non-damaging tests may be varied if convenient, except that the bounce (vibration) test shall be performed on the unit used for the shock tests.

4.4 Inspection covered by subsidiary documents.- The following shall be inspected under the applicable subsidiary documents as part of the inspection of equipment before preparation for delivery:

Item	Where required
Finish	3.6
Marking	3.7

4.5 Equipment verification review.- The contractor shall perform an Equipment

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

Verification Review (EVR), consisting of a complete technical audit of the equipment on order against the drawings cited for construction. (See 3.2) The EVR shall consist of the following:

4.5.1 An audit to establish that "as-built" equipment (unit, assembly, module, or part) is in accordance with the cited end product drawings.

4.5.2 An audit to establish that "as-built" configuration of unit, assembly, module, or part meet the acceptance requirements (other than equipment specification performance) specified for each unit, assembly, module, or part. The audit shall record all acceptance test methods used together with resulting verification test data.

4.5.3 The contractor shall compile an EVR report(s) containing the following information:

(a) Identification of unit, assembly, module, or part and details proving compliance with 4.5.1 and 4.5.2 above.

(b) Discrepancies noted.

(c) Corrective action taken.

4.5.4 The contractor shall make available to the Government copies of his EVR report(s) no later than 15 days prior to the submission of the first production unit or lot. The results of the EVR shall be subject to inspection by authorized Government personnel at the time the first unit or production lot is offered for acceptance. Government inspection will be to the depth and extent necessary to demonstrate that the "as-built" hardware is in accordance with the cited drawings. Copies of the EVR reports shall be made available to the Government personnel during the inspection. The contractor shall provide the following:

(a) Segregation of units, assemblies, modules, and parts to permit reviewing personnel access for detailed inspection.

(b) As required, responsible personnel from each functional department available for discussions in their respective areas.

(c) Adequate administrative support for the EVR.

4.6 Quality conformance inspection of equipment before preparation for delivery.- Every equipment shall be subjected to burn-in (debugging) (see 3.10) prior to conformance inspection. The contractor shall perform the inspection specified in 4.4 and 4.6.1 through 4.6.4. This does not reliever the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements. Failure to meet any requirement as a result of burn-in (debugging) shall be classified as a defect and recorded as such.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

The Government will review and evaluate the contractor's inspection procedures and examine the contractor's inspection records as an element of Government verification (see 4.1.2).

4.6.1 Group A inspection.- Equipment shall be assembled into discrete lots for quality conformance inspection, utilizing the criteria of MIL-STD-105 for determination of lot composition. Unless otherwise specified, the lot size shall be determined from table IV, as related to production rates necessary to meet delivery schedules of the contract. The lot size shall be adjusted throughout the life of the contract as necessary to provide for changes in contract delivery schedule and production rates. Each unit of each lot of equipment shall be inspected for conformance to all the examinations and tests required in table V. The quality conformance of each lot shall then be subjected to an audit (see 6.7), utilizing the procedures of MIL-STD-105, under the general inspection levels and the Acceptable Quality Level (AQL) indicated in table V. Group A inspection shall be performed in any order satisfactory to the Government, except that the operational inspection (4.7.4) shall be last.

Table IV Lot Formation

Production Rate	Size of Lot
500 or more per month	One week's production
51 to 499 per month	Two week's production
0 to 50 per month	One month's production

Table V Group A Inspection

Inspection	Reqt Para	Insp Para	AQL	
			Major	Minor
Visual and mechanical	3.14	4.20	1.5 dphu*	6.5dphu
Electrical				
Voltage ratings	3.5.1	4.7.1	1.5 dphu	
Power supply ripple	3.5.2.1	4.7.2.1	for	
Frequency of DC to DC converter	3.5.2.2	4.7.2.2	group	
Operation	3.5.4	4.7.4	1%	

*Defects per hundred units
Defects in all characteristics other than visual and mechanical are considered major

Source: https://assist.dla.mil -- Downloaded: 202610-17T14:19Z
Check the source to verify that this is the currentversion before use.

4.6.2 Group B inspection.- This inspection, including sampling, shall conform to Table VI and to procedures for special inspection levels of MIL-STD-105. Group B inspection shall be performed on production lots of product that have passed group A inspection. The AQL shall be 15 percent defective and inspection level shall be S-3 for narmal and tightened inspection and S-2 for reduced inspection. (See 4.6.1 for lot formation)

Table VI. - Group B Inspection.-

Inspection	Reqt Para	Insp Para	AQL
Crystal oscillator stability Frequency dividers	3.5.3.1 3.5.3.2	4.7.3 4.7.3	15% for group

4.6.3 Group C inspection.- This inspection shall consist of the tests specified in table VII and shall be performed on sample units of product that have been subjected to and passed group A and group B inspection requirements. Sample units shall be selected in accordance with 4.6.3.1.

Table VII. - Group C Inspection.-

Inspection (Note 1)	Reqt Para	Insp Para
Group 1		
Electromagnetic interference (Note 2)	3.12	4.19
Low temperature	3.11.1.1	4.10.1
High temperature	3.11.1.2	4.10.2
Rain	3.11.2	4.11
Humidity (moisture resistance)	3.11.5	4.14
Group 2		
Altitude (elevation)	3.11.3	4.12
Dust	3.11.4	4.13
Bounce (vibration)	3.11.6	4.15
Shock; bench handling	3.11.6	4.16
Shock; drop	3.11.6	4.17
Orientation	3.11.7	4.18
Group 3		
Equipment verification review (Note 3)	3.2	4.5

Note 1: The order of inspection shall be in accordance with table III.
Note 2: Electromagnetic interference shall only be performed during first article testing and on the first production lot.
Note 3: Equipment verification review shall only be performed on the first production lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

4.6.3.1 Sampling for group C inspection.- One sample unit shall be selected at random for each group of inspections in Table VII from every twenty units or fraction thereof produced. The first samples selected shall be at the start of the contract from the first quality conformance inspection production lot. (See 4.6.3)

4.6.3.2 Sampling for inspection of solderless-terminal-lug connections.- Five specimens of each combination of wire and terminal shall be prepared each week for inspection. A specimen is a 1-foot length of wire on which a terminal lug has been applied, using the same tools and procedures used in crimping the terminal lugs in production.

4.6.3.3 Noncompliance.- The contractor shall immediately report in writing each group C failure occurrence, including details of the failure and characteristics affected. The contractor shall immediately investigate the cause of failure and further report the results of investigation and details of the proposed corrective action on the processes and materials, as applicable, and on all units of product which are manufactured under the same conditions and which the Government considers subject to the same failure. Reports shall be forwarded through the Government procurement quality assurance representative to the responsible technical activity designated in the contract. After corrective action has been taken, additional sample units shall be subjected to group C inspection (all inspections, or the inspections which the sample failed, at the option of the technical activity) and group A and group B inspections may be reinstituted. However, final acceptance and shipment will be withheld until group C reinspection results have shown that the corrective action was effective and approved by the technical activity. (See "Delivery and Conditional Acceptance of Contract Items Subject to Group C Inspection: provisions elsewhere in the contract.)

4.6.4 Reinspection of conforming group C sample units.- Unless otherwise specified, sample units which have been subjected to and passed group C inspection may be accepted on the contract or order provided all damage is repaired and the sample units are resubjected to and pass group A inspection.

4.7 Performance tests.-

4.7.1 Power supply operating values.- Connect the power supply to a Recorder BC-1337 and adjust both for normal operation. Connect loads simulating Microphone T-23( ) to the microphone binding posts of the recorder. Make a recording of an impressed signal. While the recorder is in operation, voltage measurements shall meet the requirements of 3.5.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

4.7.2 Power supply ripple and frequency of DC to DC converter.- The tests (4.7.2.1 and 4.7.2.2) below will be performed with the equipment connected and operating as in 4.7.1 above.

4.7.2.1 Power supply ripple.- Using an oscilloscope (Hewlett Packard 180A or equal) check the ripple content for compliance to 3.5.2.1.

4.7.2.2 Frequency of DC to DC converter.- Measure this frequency using an electronic counter (Hewlett Packard model 5532A or equal). The results shall conform to the requirements of 3.5.2.2

4.7.3 Timer stability.- By means of an electronic counter (Hewlett Packard Model 5532A or equal) test the timer outputs for compliance with 3.5.3.1 and 3.5.3.2. The tests shall be made at -31.7°C(-25°F), -17.8°C(0°F), 0.0°C(32°F), 43.3°C(110°F), 55.0°C(131°F), and 65.6°C(150°F).

4.7.4 Operation.- Connect the power supply to Recorder BC-1337( ) and apply a DC voltage of 11.5 volts. Connect loads simulating six microphones to the microphone binding posts. Make a recording every 5 minutes for a duration of 30 seconds by impressing a 15 Hz signal. This will be accomplished by closing the paper loading door when signals are to be recorded and opening the door when signals are not to be recorded (see 3.5.4). The 15 Hz signal shall not be applied when the door is opened.

4.8 Inspection for interchangeability.- The dimensions listed below shall be gaged or measured to determine compliance with the physical interchangeability requirement of 3.9. When a listed dimension is not within specified or design limits, it shall be considered a major defect.

(a) External and internal dimensions of cases, covers, and insertable subassemblies, when such dimensions affect mating of parts.

(b) Dimensions of cavities, when such dimensions affect insertion of items.

(c) Location of hinges and fasteners on separable parts or assemblies which must mate, such as cases, covers, and mountings.

(d) Location of connectors, locking pins, fasteners, slides, and mountings which receive mating parts of plug-in assemblies and major units; and location of the mating parts on the plug-in assembly or major unit.

(e) Size and form of special threads.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

4.9 Burn-in (debugging).- All units submitted for acceptance shall be subjected to burn-in (debugging) in accordance with Drawing SC-A-678013.(see 3.10)

4.10 Temperature test.-

4.10.1 Low temperature.- The power supply shall be tested in accordance with Method 502, Procedure I, of MIL-STD-810. Prior to testing, the power supply shall meet full specification performance. The storage temperature shall be -34.4°C (-30°F) and the operating temperature shall be -31.7°C (-25°F). The storage temperature shall be maintained for 24 hours. Batteries may be placed outside the test chamber (see 3.11.1.1).

4.10.2 High temperature.- The power supply shall be tested in accordance with Method 501, Procedure II, of MIL-STD-810. Prior to testing, the power supply shall meet full specification performance. The operating temperature shall be 65.6°C (150°F) and the storage temperature shall be 71.1°C (160°F). Batteries may be placed outside the test chamber (see 3.11.1.2).

4.11 Rain test.- The power supply shall be dried at 65.6° ± 2.8°C (150°±5°F) for 48 hours. Then condition the power supply for 4 hours at 25° ± 2.8°C (77°±5°F) and 40 to 60 percent relative humidity. Prior to testing, the power supply shall meet the performance requirement of 3.5.4. Test the power supply, in its transit case, in accordance with Method 506, Procedure I, of MIL-STD-810. Final measurements shall be made within 1 hour after the rain has been discontinued. (See 3.11.2)

4.12 Altitude (elevation) test.- The power supply shall be tested in accordance with Method 500, Procedure I, of MIL-STD-810. Prior to testing the power supply shall meet full specification performance. The requirement of 3.5.3.1 shall be performed only at ambient temperature (see 3.11.3).

4.13 Dust test.- The power supply, in its transit case, shall be tested in accordance with Method 510, Procedure I, of MIL-STD-810. Prior to testing the power supply shall meet full specification performance. The requirement of 3.5.3.1 shall be performed only at ambient temperature (see 3.11.4).

4.14 Humidity (moisture-resistance) test.- The power supply shall be tested in accordance with Method 507, Procedure II of MIL-STD-810. Prior to testing, the power supply shall meet the performance requirement of 3.5.4. Measurements shall be made at the end of the 2nd and 4th cycles. Do not move the power supply from the humidity chamber for measurements, and do not leave power on after measurements have been completed. If any power supply fails to meet the specified performance during cycling, it shall be realigned or readjusted once and the test continued. No

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

repair or replacement of parts shall be permitted. If the power supply still fails to meet the specified performance during cycling, or fails subsequently, it does not pass the test. In addition, if the power supply fails to meet specified requirements after final conditioning and adjustment, it does not pass the test. (See 3.11.5)

4.15 Bounce (vibration) test.- The power supply shall be tested in accordance with Method 514, Procedure XI, of MIL-STD-810. Prior to testing the power supply shall meet full specification performance. The requirement of 3.5.3.1 shall be performed only at ambient temperature. Package tester accessories shall be selected from those listed on Drawing SC-A-46439 (see 3.11.6).

4.16 Shock test; bench handling.- The power supply shall be tested in accordance with Method 516, Procedure V, of MIL-STD-810. Prior to testing the power supply shall meet full specification performance. The requirement of 3.5.3.1 shall be performed only at ambient temperature (see 3.11.6).

4.17 Shock test; drop.- The power supply shall be tested in accordance with Method 516, Procedure II, of MIL-STD-810. Prior to testing the power supply shall meet full specification performance (see 3.11.6).

4.18 Orientation test.- The power supply shall be inclined for a minimum of 5 minutes in each plane (forward, backward, left, and right) to an angle of 20 + 3, -1 degrees. The requirement of 3.5.3.1 shall be performed only at ambient temperature (see 3.11.7).

4.19 Electromagnetic interference test.- The power supply shall be tested for electromagnetic interference in accordance with Test Method RE02 of Table AII-MIL-I-11748, Class III b, of MIL-STD-461 (see 3.12).

4.20 Visual and mechanical inspection.- The power supply shall be examined for the defects listed in MIL-STD-252 and Table VIII.

Table VIII. - Classification of Visual and Mechanical Defects

Classification	Defect
Major	Outer case too large, or too small. Improper or loose fitting panels and covers. Controls loose or too tight. Improper fit of printed circuit boards Components not interchangeable. Loose binding posts, cable plugs, and/or jacks. Running spare parts not interchangeable with the corresponding part in use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

Classification	Defect
Minor	Loose fasteners. Shock mounts improperly mounted, or loose. Markings missing, imcomplete and/or illegible. Loose cabling. Rough edges on brazed, soldered and/or welded joints. Flux residue. Improper finish and/or tropicalization.

4.21 Quality conformance inspection of preparation for delivery.- Preparation for delivery shall be inspected in accordance with MIL-P-116 to determine conformance to the requirements of Section 5.

5. PREPARATION FOR DELIVERY

5.1 Preservation, packing, packaging, and marking.- Preservation, packing, packaging, and marking shall be in accordance with MIL-S-10956(EL).

6. NOTES

6.1 Intended use.- Plate Supply - Timer Unit PE-244 ( ) is part of Sound Ranging Set GR-8( ) and provides filtered power and timing pulses to Recorder BC-1337( ).

6.2 Ordering data.- Procurement documents should specify the following:

(a) Title, number, and date of this specification and any amendment thereto.

(b) Level of packaging and level of packing required for shipment. (Level A, level B, or level C.)

(c) Number of first articles to be submitted for approval. (See 3.2.)

(d) Quantity of tools and running spare parts required. (See 3.13)

(e) Submission of the statement of treatment before first article approval. This statement should be submitted to the contracting officer.

(f) One (1) each Recorder BC-1337 ( ) will be loaned to the successful bidder for testing as indicated in the bid request and contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

6.3 Color.- The color chip furnished by the procuring agency will be color chip No. X-24087, and may be obtained upon request to Commanding General, Aberdeen Proving Ground, ATTN: Coating and Chemical Laboratory, Aberdeen, Maryland 21005. (See 3.6.)

6.4 Nomenclature.- The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design; for example: PE-244 W. The contractor should apply for nomenclature in accordance with the applicable clause in the contract. (See 1.1.)

6.5 Group C inspection.- Approval to ship may be withheld, at the discretion of the government inspector, pending a decision from the contracting officer on the adequacy of corrective action. (See 6.3.3)

6.6 Verification inspection.- Verification by the government will be limited to the amount deemed necessary to determine compliance with the contract and will be limited in severity to the definitive quality assurance provisions established in this specification and contract. The amount of verification inspection by the government will be adjusted to make maximum utilization of the contractor's quality control system and the quality history of the product.

6.7 Audit.- An audit (see 4.6.1) is an assessment of the effectiveness of an act, a performance, or a process.

Custodian
Army-EL

Preparing Activity
Army-EL
Project Number 6115-A300

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

To detach this form, cut along this line

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION MIL-P-10653D(EL) POWER SUPPLY (PLATE SUPPLY-TIMER UNIT PE-244 ())

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

ESC-FM 1068-68

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.

voltage deviation and transient recovery time shall be recorded by means of

FOLD

Department of the Army
Headquarters
U.S.Army Electronics Command
Fort Monmouth, New Jersey 07703

POSTAGE AND FEES PAID

OFFICIAL BUSINESS

Commanding General
U.S.Army Electronics Command
ATTN: AMSEL-PP-MD
Fort Monmouth, New Jersey 07703

To detach this form, cut along this line

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:19Z
Check the source to verify that this is the current version before use.