MIL-T-10767F

INTERIM AMENDMENT 1 (EL)
29 December 1971

MILITARY SPECIFICATION
INTERIM AMENDMENT

TOWERS (Components of)

This Interim Amendment is issued for use by the Department of the Army with Military Specification MIL-T-10767F dated 21 May 1968.

Page 1

1.1: Replace "Tower AB-216/U" with "Tower AB-216( )/U." At end of paragraph add "(See 6.1 and 6.3)."

Page 2

2.1: Delete Military Specification "MIL-B-43291 Boxes; Fiberboard; Corrugated Double-Wall, Weather Resistant."

Page 3

3.1: At end of paragraph add "(See 4.25)."

3.2: Replace "Preproduction Samples" with "First Article Samples" and "preproduction" with "first article."

Page 4

3.2.1: Replace all reference to "preproduction" with "first article."

3.2.2: Replace all reference to "preproduction" with "first article."

3.2.3: Replace all reference to "preproduction" with "first article."

3.3.1: At end of paragraph add "(See 4.4)."

3.3.2: Change "marking" to "markings."

3.4: At end of paragraph add "(See 4.4 and 4.7). When spot or other intermittent welds are used to hold a part, the number of welds shall be at least two."

3.5: At end of paragraph add "(See 4.4)."

Page 6

3.21.1: Delete "SC-DL-168884" and replace with "SC-DL-168733."

3.22: Replace "(See 4.16)" with "(See 4.6 and 4.16)."

Source: https://assist.dla.mil -- Downloaded: 202610-17T14:24Z
Check the source to verify that this is the current version before use.

Page 7

3.24.4: Replace "(See 4.21)" with "(See 4.6 and 4.21)."

3.26: Replace "(See 4.12)" with "(See 4.6 and 4.12)."

3.29: Add "Paragraph 3.1 Construction" to the list.

Page 8

4.1, Lines 2 and 4: Replace "supplier" with "contractor."

4.1.1: Add Paragraph 4.1.1:

"4.1.1 Contractor Quality Assurance. - The contractor shall provide and maintain a means of determining product conformance in accordance with the requirements specified herein or elsewhere in the contract. The Government, at its option, may perform any evaluation deemed necessary to assure the adequacy of the means employed and the effectiveness of the contractor's quality assurance methods and systems."

4.1.2: Add Paragraph 4.1.2:

"4.1.2 Government verification. - All quality assurance operations required of the contractor shall be subject to Government verification at scheduled or unscheduled intervals. Verification will consist of the following:

a. Surveillance of the contractor's operations to determine that practices, methods, and procedures of the contractor's quality assurance system are being applied and are, in fact, accomplishing the objectives of total compliance of the product with the requirements of this specification and the contract.

b. Government product inspections to determine compliance of the product with the specification requirements and the contract."

4.1.3: Add Paragraph 4.1.3:

"4.1.3 Accomodation and assistance. - The Government quality assurance representative shall have the right of access to any area of the contractor's or his subcontractor's premises where any part of the work is being performed. The Government quality assurance representative shall be afforded unrestricted opportunity to verify conformance of the product with specification requirements. The contractor shall make his inspection equipment and records available for use by the Government quality assurance representative for verification purposes. The contractor's personnel shall be made available for operation of such inspection equipment as required."

4.2 (a): Replace "Preproduction" with "First Article."

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:24Z
Check the source to verify that this is the current version before use.

4.3: Delete Paragraph 4.3 entirely and replace with the following:

"4.3 First article inspection. - This inspection shall consist of the inspections specified in subsidiary documents covering the items listed in 4.4, and the inspections specified for group A, group B, and group C (see tables I, II, and III, respectively). The order of first article inspection shall be the same as that specified for group A, group B, and group C inspection. Group A and group B will therefore be performed on all units, and group C on designated units."

Page 9

4.5: Delete the last two sentences from the paragraph. At the end of the sentence on the seventh line add "as an element of Government verification." At the end of the paragraph add "(See 4.1.2 and 6.4)."

Table IA: Add the following table immediately after table I:

Table IA Lot Formation

Production Rate	Size of Lot
500 or more per month	One week's production
51 to 499 per month	Two week's production
0 to 50 per month	One month's production

Page 10

4.5.1: Delete Paragraph 4.5.1 entirely and replace with the following:

"Paragraph 4.5.1 Group A inspection. - Equipment shall be assembled into discrete lots for quality conformance inspection, utilizing the criteria of MIL-STD-105 for determination of lot composition. Unless otherwise specified, the lot size shall be determined from table IA, as related to production rates necessary to meet delivery schedules of the contract. The lot size shall be adjusted throughout the life of the contract as necessary to provide for changes in contract delivery schedules and production rates. Each unit of each lot of equipment shall be inspected for conformance to all the examinations and tests required in table I. The quality conformance of each lot shall then be subjected to an audit, utilizing the procedures of MIL-STD-105, under the general inspection levels and the Acceptable Quality Level (AQL) indicated in table I. Group A inspection shall be performed in any order satisfactory to the Government."

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:24Z
Check the source to verify that this is the current version before use.

INTERIM AMENDMENT 1 (EL)

4.5.2: Delete the last sentence and replace with the following: "Group B inspection shall be performed on production lots of product that have passed group A inspection. (See 4.5.1 for lot formation)."

4.5.2.1: In table replace "Special Inspection Plan" with: "Special Inspection Level."

4.5.3: Delete Paragraph 4.5.3 and replace with the following:

"4.5.3 Group C inspection. - This inspection shall consist of the tests specified in table III and shall be performed on units of product that have been subjected to and passed group A and group B inspection requirements. Sample units shall be selected in accordance with 4.5.3.1."

Table III:ADD to TABLE III

Inspection	Rqr. Para.	Insp. Para.
Equipment Verification Review*	3.1	4.25

*The EVR is to be performed once on the initial production lot.

4.5.3.1: Change title from "Sampling for inspection" to "Sampling for group C inspection."

4.5.3.2: Delete entirely and replace with the following:

"Paragraph 4.5.3.2 Noncompliance. - All quality conformance inspection shall be halted, including group A and group B inspections upon the occurrence of any group C failure. The contractor shall immediately report in writing each group C failure occurrence, including details of the failure and characteristics affected. The contractor shall immediate investigate the cause of failure and further report the results of investigation and details of the proposed corrective action on the processes and materials, as applicable, and on all units of product which are manufactured under the same conditions and which the Government considers subject to the same failure. Reports shall be forwarded to the responsible technical activity designated in the contract with a copy to the Government procurement quality assurance representative. After corrective action has been taken, additional sample units shall be subjected to group C inspection (all inspections, or the inspections which the sample failed, at the option of the technical activity)

Source: https://assist.dla.mil -- Downloaded: 202610-17T14:24Z
Check the source to verify that this is the current version before use.

and group A and group B inspections may be reinstituted. However, final acceptance and shipment will be withheld until group C reinspection results have shown that the corrective action was effective and approved by the technical activity. (See "Delivery and Conditional Acceptance of Contract Items Subject to Group C Inspection" provisions elsewhere in the contract.)."

4.5.4, Lines 3 and 4: Delete "or order."

Page 15

4.24.2(a), Lines 1 and 4: Replace "10" with "13."

Page 16

4.25: Add Paragraph 4.25:

"Paragraph 4.25 Equipment Verification Review. - The contractor shall perform an Equipment Verification Review (EVR), consisting of a complete technical audit of the equipment on order against the drawings cited for construction (para. 3.1). The EVR shall consist of the following:

4.25.1 An audit to establish that "as built" equipment (unit, assembly, module, or part) is in accordance with the cited end product drawings.

4.25.2 An audit to establish that "as built" configuration of unit, assembly, module, or part meet the acceptance requirements (other than equipment specification performance) specified for each unit, assembly, module, or part. The audit shall record all acceptance test methods used together with resulting verification test data.

4.25.3 The contractor shall compile an EVR report (s) containing the following information:

(a) Identification of unit, assembly, module, or part and details proving compliance with 4.25.1 and 4.25.2 above.

(b) Discrepancies noted.

(c) Corrective action taken.

4.25.4 The contractor shall make available to the Government copies of his EVR report(s) no later then 15 days prior to the submission of the first-production unit or lot. The results of the EVR shall be subject to inspection by authorized Government personnel at the time the first unit or production lot is offered for acceptance.

Source: https://assist.dla.mil -- Downloaded: 202610-17T14:24Z
Check the source to verify that this is the currentversion before use.

Government inspection will be to the depth and extent necessary to demonstrate that the "as built" hardware is in accordance with the cited drawings. Copies of the EVR reports shall be made available to the Government personnel during the inspection. The contractor shall provide the following:

(a) Segregation of units, assemblies, modules, and parts to permit reviewing personnel access for detailed inspection.

(b) As required, responsible personnel for each functional department available for discussions in their respective areas.

(c) Adequate administrative support for the EVR.

Page 17

5.1.1.3.2: At the end of the paragraph add "For Army Procurements, all unit, supplementary and intermediate containers shall either be weather-resistant or overwrapped with waterproof barrier materials."

Page 18

Table VII: Delete the eighth container down in the table "Box, Fiberboard, Corrugated Double Wall, Weather Resistant." Under Column For Level B add "(NOTE D)" under the class specified on the third, fourth, sixth, and seventh containers down in the table. Under the table add, "NOTE D. For Army procurements, shipping containers for level B shall be Class 2,3 or overseas."

Page 19

6.2 (b): Delete "Equipment required" and replace with "Type required."

6.2 (g): At end of sentence add "(See 3.28)."

6.2 (h): At end of sentence add "(See 3.28)."

Page 20

6.6: Add Paragraph 6.6

"6.6 Group C inspection. - Approval to ship may be withheld, at the discretion of the Government, pending the decision from the contracting officer on the adequacy of corrective action. (See 4.5.3.2)."

Custodian:
Army-EL

Preparing Activity:
Army-EL

Project No. 5445-A010

Source: https://assist.dla.mil -- Downloaded: 202610-17T14:24Z
Check the source to verify that this is the current version before use.