MIL-T-10767F
21 May 1968
SUPERSEDING
MIL-T-10767E
20 June 1962

MILITARY SPECIFICATION

TOWERS (Components of)

* This specification is mandatory for use by all departments and agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers the following components comprising a 78-foot sectionalized, guyed, rectangular-type tower, designated as Tower AB-216/U and components for extending it to a height of 204 feet.

Component	Reference Paragraph
Platform Section, Tower MT-1156( )/U	3.7
Bracket, Scaffold, Tower MT-1157( )/G	3.8
Clevis, upset, insulator type	3.9
* Davit, Tower Erection MX-1215( )/U	3.10
Bar, digging	3.11
Roller, Aerial Cable MX-1216( )/U	3.12
Guy MX-1201( )/U	3.13
Ground Rod MX-148/G	3.14
Modified guy anchor	3.15
Hoist line assembly	3.16
Tag line assembly	3.17
Antenna stabilizer assembly	3.18
Guy spacer assembly	3.19
Block, snatch	3.20
Coupler assembly	3.20.1
Support, Antenna AB-296( )/G	3.21
Antenna support platform assembly	3.21.1
Tensiometer assembly	3.22
Plate, Base, Tower Section AB-556( )/U	3.23
Tower Section AB-207( )/U	3.24
Platform	3.24.2
Stairway	3.24.3
Interlock clips	3.24.4
Guy attachment straps	3.24.5
Capstan E-12( )/U	3.25
Guy winch assembly	3.26
Anchor rod	3.27

FSC 5445

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:24Z
Check the source to verify that this is the current version before use.

2. APPLICABLE DOCUMENTS

* 2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

QQ-S-781	Strapping, Flat; Steel
PPP-T-97	Tape; Pressure-Sensitive Adhesive, Filament Reinforced
PPP-B-585	Boxes, Wood, Wirebound
PPP-B-591	Boxes, Fiberboard, Wood-Cleated
PPP-B-601	Boxes, Wood, Cleated-Plywood
PPP-B-621	Boxes, Wood, Nailed and Lock-Corner
PPP-B-636	Box, Fiberboard
PPP-B-640	Boxes, Fiberboard, Corrugated, Triple-Wall
PPP-C-650	Crates, Wood, Open and Covered
PPP-S-760	Strapping, Nonmetallic, (And Connectors)

MILITARY

MIL-C-104	Crates, Wood, Lumber and Plywood Sheathed, Nailed and Bolted
MIL-P-116	Preservation, Methods of
MIL-W-8604	Welding of Aluminum Alloys: Process for
MIL-M-13231	Marking of Electronic Items
MIL-F-14072	Finishes for Ground Signal Equipment
MIL-B-43291	Boxes; Fiberboard; Corrugated Double-Wall, Weather Resistant

STANDARDS

MILITARY

MIL-STD-22	Welded-Joint Designs
MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-110	Gages, plug, plain cylindrical, Go
MIL-STD-112	Gages, ring, plain, Go

Source: https://assist.dla.mil -- Downloaded: 20260-17T14:24Z
Check the source to verify that this is the current version before use.

MIL-STD-129	Marking for Shipment and Storage
MIL-STD-252	Wired Equipment, Classification of Visual and Mechanical Defects
MIL-STD-454	Standard General Requirements for Electronic Equipment

DRAWINGS

SIGNAL CORPS

SC-D-14158	Ground Rod MX-148/G
SC-C-33443	Modification of guy anchor
SC-DL-47184	Plate, Base, Tower Section AB-556( )/U
SC-D-57276	Gage for Diagonal Distance of Tower Sections
SC-D-57277	Gage for Mating Holes of Tower Sections
SC-DL-168681	Tower Section AB-207( )/U
SM-B-168704	Clip Assembly
SC-DL-168733	Antenna Support Platform Assembly
SC-DL-168734	Coupler Assembly
SM-C-168855	Guy Spacer Assembly
SC-C-168860	Guy Winch Assembly
SM-B-168877	Rope Assemblies
SC-DL-168879	Tensiometer Assembly
SC-DL-168880	Guy MX-1201( )/U
SC-DL-168881	Roller, Aerial Cable MX-1216( )/U
SC-DL-168884	Support, Antenna AB-296( )/G
SC-DL-168885	Platform Section, Tower MT-1156( )/U
SC-DL-168891	Capstan E-12( )/U
SC-DL-168892	Davit, Tower Erection MX-1215( )/U
SM-B-168896	Block, Snatch
SC-DL-168898	Bracket, Scaffold, Tower MT-1157( )/G
SC-DL-173534	Antenna Stabilizer Assembly

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer. Both the title and number or symbol should be stipulated when requesting copies).

3. REQUIREMENTS

* 3.1 Construction.- The equipment shall be constructed in accordance with the requirements of this specification and of the applicable drawings (including requirements for parts, materials and processes thereon).

* 3.2 Preproduction samples.- The contractor shall furnish preproduction samples for approval, if required by the invitation for bids and contract (see 4.3 and 6.2(d)).

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:24Z
Check the source to verify that this is the current version before use.

3.2.1 Fabrication and assembly.- Preproduction samples shall be fabricated by the contractor and shall meet all requirements specified for the equipment on contract. The preproduction samples shall be assembled using parts, materials, and processes that will be employed in production, and shall be fabricated and assembled in a manner similiar to that to be used in production.

* 3.2.2 Approval and use.- Approval of preproduction samples shall not be construed as a waiver of any specified requirement. After being released to the contractor (see 3.2.3), preproduction samples to be offered as units on contract shall be refabricated by the contractor if necessary to meet specified requirements.

3.2.3 Reference standards.- After preproduction samples have been approved, they shall be kept intact in custody of the Government inspector until released by him. They shall be used as reference standards to resolve any differences of opinion regarding interpretation of requirements.

3.3 Marking.-

3.3.1 General.- Marking shall conform to Specification MIL-M-13231.

3.3.2 Visibility.- Wherever practicable, parts and assemblies shall be so mounted that their identification marking will be readily visible with minimum disassembly of the equipment.

3.3.3 Serial numbers.- Tensiometer shall be serial numbered in accordance with Specification MIL-M-13231.

* 3.3.4 Installation caution notice.- Each tower shall be provided with an installation caution notice plate conforming to Specification MIL-M-13231. Category (a), (b), or (c) material and process shall be used. The legend shall be marked on the plate with white or aluminum letters on a red background, as follows: "CAUTION- THIS EQUIPMENT SHALL NOT BE INSTALLED CLOSER THAN TWICE ITS HEIGHT FROM POWER LINES". The plate shall be attached to the Davit, Tower Erection MX-1215( )/U in the vicinity of the nameplate.

* 3.4 Welding.- Wherever practicable, welded joints shall conform to Standard MIL-STD-22 and shall be such that grinding on the finished weld will be unnecessary. All welds shall conform to Specification MIL-W-8604.

3.5 Finish.- The equipment shall be finished in accordance with Specification MIL-F-14072 and the applicable equipment drawings. This provision shall be followed on exterior surfaces except the male and female connecting surfaces, spring loaded pins, and face of grounding lug. These portions shall be masked to insure free movement of the pins and unimpaired electrical contact of the grounding lug, respectively.

Source: https://assist.dla.mil -- Downloaded: 202610-17T14:24Z
Check the source to verify that this is the current version before use.

3.6 Interchangeability.- Like units, assemblies, subassemblies, and replaceable parts shall be physically and functionally interchangeable, without modification of such items or of the equipment (see 4.8). Individual items shall not be hand-picked for fit or performance; however, matched pairs or sets, when permitted, may be interchangeable as such. Reliance shall not be placed on any unspecified dimension, rating, characteristic, et cetera.

3.7 Platform Section, Tower MT-1156( )/U.- Platform Section, Tower MT-1156( )/U shall be constructed in accordance with Drawing SC-DL-168885 (see 4.6).

3.8 Bracket, Scaffold, Tower MT-1157( )/G.- Bracket, Scaffold, Tower MT-1157( )/G shall be constructed in accordance with Drawing SC-DL-168898 (see 4.6).

* 3.9 Clevis, upset, insulator type.- The clevis shall be heavy type J-725 Joslyn Manufacturing and Supply Company, Chicago, Ill or equal. The clevis shall be capable of withstanding a tensile load of 1,500 pounds without evidence of permanent deformation and a tensile load of 5,500 pounds without fracture (see 4.6 and 4.9).

* 3.10 Davit, Tower Erection MX-1215( )/U.- Davit, Tower Erection MX-1215( )/U shall be constructed in accordance with Drawing SC-DL-168892. The davit shall be rotating type, capable of being easily attached to, or detached from, Tower Section AB-207( )/U by two men, while being installed as part of the tower. The davit shall be capable of hoisting a 200-pound load without evidence of permanent deformation when used as a complete assembly. The davit shall be capable of hoisting a 500-pound load without evidence of permanent deformation when used as a short davit (see 4.6 and 4.10).

3.11 Bar, Digging.- Each digging bar shall be No. T405, 8 feet long as supplied by Joslyn Company, or equal (see 4.6).

3.12 Roller, Aerial Cable MX-1216( )/U.- Roller, Aerial Cable MX-1216( )/U shall be constructed in accordance with Drawing SC-DL-168881 (see 4.6). (When installing the tower, this roller is used for trolleying a guy down a previously installed guy).

* 3.13 Guy MX-1201( )/U.- Guy MX-1201( )/U shall be constructed in accordance with Drawing SC-DL-168880. The guy shall be capable of withstanding a minimum tensile load of 5,500 pounds without failure of the cable or slipping of the connectors (see 4.6 and 4.11).

3.14 Ground Rod MX-148/G.- Ground Rod MX-148/G shall be constructed in accordance with Drawing SC-D-14158 (see 4.6).

3.15 Modified guy anchor.- The modified guy anchor shall be constructed in accordance with Drawing SC-C-33443 (see 4.6).

* 3.16 Hoist line assembly.- The hoist line assembly shall be constructed in accordance with Drawing SM-B-168877, GP I. The hoist line shall have a minimum breaking strength of 2,400 pounds (see 4.6 and 4.13).

Source: https://assist.dla.mil -- Downloaded: 202640-17T14:24Z
Check the source to verify that this is the current version before use.

* 3.17 Tag line assembly.- The tag line assembly shall be constructed in accordance with Drawing SM-B-168877, GP II. The tag line shall have a minimum breaking strength of 2,400 pounds (see 4.6 and 4.13).

3.18 Antenna stabilizer assembly.- The antenna stabilizer assembly shall be constructed in accordance with Drawing SC-DL-173534 (see 4.6).

* 3.19 Guy spacer assembly.- The guy spacer assembly shall be constructed in accordance with Drawing SM-C-168855. The guy spacer shall have a minimum breaking strength of 5,500 pounds, and the hooks shall withstand a tensile load of 5,500 pounds without permanent deformation (see 4.6 and 4.14).

3.20 Block, snatch.- The snatch block shall be constructed in accordance with Drawing SM-B-168896 (see 4.6).

3.20.1 Coupler assembly.- The coupler assembly shall be constructed in accordance with Drawing SC-DL-168734 (see 4.6).

* 3.21 Support, Antenna AB-296( )/G.- Support, Antenna AB-296( )/G shall be constructed in accordance with Drawing SC-DL-168884 (see 4.6).

* 3.21.1 Antenna Support Platform Assembly.- The antenna support platform assembly shall be constructed in accordance with Drawing SC-DL-168884. The platform assembly shall be capable of supporting a 360 pound load (see 4.6 and 4.15).

* 3.22 Tensiometer assembly.- Each tensiometer and case shall be constructed in accordance with Drawing SC-DL-168879. Each tensiometer shall be accurate to ± 5 percent (see 4.16).

* 3.23 Plate, Base, Tower Section AB-556( )/U.- Plate, Base, Tower Section AB-556( )/U shall be constructed in accordance with Drawing SC-DL-47184. The base plate assembly shall be capable of withstanding a compressive load of 15,500 pounds without evidence of permanent deformation (see 4.6 and 4.17).

3.24 Tower Section AB-207( )/U.- Tower Section AB-207( )/U shall be constructed in accordance with Drawing SC-DL-168681 (see 4.6).

* 3.24.1 Column load.- Tower Section AB-207( )/U shall be capable of supporting a compressive load of 48,000 pounds distributed equally on the four legs without evidence of permanent deformation. The welded joint between the vertical leg and joint foot bushing shall withstand a minimum tensile load of 4,500 pounds without failure (see 4.18).

* 3.24.2 Platform.- The removable platform for Tower Section AB-207( )/U shall be capable of supporting a load of 1,080 pounds without evidence of permanent deformation (see 4.19).

Source: https://assist.dla.mil -- Downloaded: 202640-17T14:24Z
Check the source to verify that this is the currentversion before use.

* 3.24.3 Stairway.- The stairway for Tower Section AB-207( )/U shall be capable of supporting an 800 pound load on any and each step but not simultaneously (see 4.20).

* 3.24.4 Interlock Clip.- The interlock clip shall be constructed in accordance with Drawing SM-B-168704. The clip pin shall be capable of withstanding a minimum shear load of 4,500 pounds without failure (see 4.21).

* 3.24.5 Guy Attachment Strap.- The guy attachment straps for Tower Section AB-207( )/U shall be mounted so as to be free to swivel on the section leg. The strap shall be capable of withstanding an 8,000 pound tensile load without evidence of distortion of the guy attachment hole (see 4.22).

* 3.25 Capstan E-12( )/U.- Capstan E-12( )/U shall be constructed in accordance with Drawing SC-DL-168891. The capstan shall be capable, with one man operation, of raising a 500 pound load to a height of 200 feet in 60 minutes (see 4.6 and 4.23).

* 3.26 Guy Winch Assembly.- The guy winch assembly shall be constructed in accordance with Drawing SM-C-168860. The winch shall be capable of applying a 1,000 pound tensile load to the guy with no damage to the cable covering. The winch shall allow a minimum takeup of 3 feet and have a positive method of locking. The winch shall be capable of withstanding an 8,000 pound tensile load without evidence of permanent deformation (see 4.12).

3.27 Anchor rod.- Each anchor rod shall be Chance No. 191072, or equal (see 4.6).

3.28 Technical literature, tools and running spare parts.- Technical literature, tools and running spare parts shall be furnished if specified in the contract. Running spare parts shall be identical to corresponding parts in the equipment furnished on the order (see 6.2).

* 3.29 Workmanship.- The equipment shall be manufactured and assembled in accordance with requirement 9 of Standard MIL-STD-454 and the applicable portions of the following paragraphs herein:

3.3	Marking
3.3.1	Marking, general
3.3.2	Visibility
3.3.3	Serial numbers
3.3.4	Installation Caution Notice
3.4	Welding
3.5	Finish
3.6	Interchangeability

4. QUALITY ASSURANCE PROVISIONS

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:24Z
Check the source to verify that this is the current version before use.

* 4.1 Responsibility for inspection.- Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements.

* 4.2 Classification of inspection.- Inspection shall be classified as follows:

(a) Preproduction inspection (does not include preparation for delivery) (see 4.3).

(b) Inspection covered by subsidiary documents (see 4.4).

(c) Quality conformance inspection:

(1) Quality conformance inspection of equipment before preparation for delivery (see 4.4 and 4.5).

(2) Quality conformance inspection of preparation for delivery (see 4.24).

4.3 Preproduction inspection.- This inspection will be performed by the Government unless otherwise specified in the contract. It shall consist of the inspection specified in the subsidiary documents covering the items listed in 4.4, and the inspection specified for group A, group B, and group C. (See tables I, II, and III, respectively). The preproduction inspection shall be performed in any order which is satisfactory to the procuring agency.

* 4.4 Inspection covered by subsidiary documents.- The following shall be inspected under the applicable subsidiary documents as part of the inspection of equipment before preparation for delivery:

Item	where required
Marking	3.3
Welding	3.4
Finish	3.5

Source: https://assist.dla.mil -- Downloaded: 202610-17T14:24Z
Check the source to verify that this is the current version before use.

* 4.5 Quality conformance inspection of equipment before preparation for delivery.- The contractor shall perform the inspection specified in 4.4 and 4.5.1 through 4.5.4. This does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's inspection records. In addition the Government, at its discretion, may perform all or any part of the specified inspection, to verify the contractor's compliance with specified requirements (see 6.4). Test equipment for Government verification inspection shall be made available by the contractor.

* TABLE I. Group A Inspection

Inspection	Req par.	Insp par.	AQL major in percent	AQL minor in percent
Visual and mechanical				
Anchor rod	3.29-3.27	4.6	1	4
Antenna stabilizer assembly	3.29-3.18	4.6	1	4
Antenna support platform assembly	3.29-3.21.1	4.6	1	4
Bar, digging	3.29-3.11	4.6	1	4
Block, snatch	3.29-3.20	4.6	1	4
Bracket, Scaffold, Tower MT-1157()/G.	3.29-3.8	4.6	1	4
Capstan E-12( )/U	3.29-3.25	4.6	1	4
Clevis, upset, insulator type	3.29-3.9	4.6	1	4
Coupler assembly	3.29-3.20.1	4.6	1	4
Davit, Tower Erection MX-1215( )/U	3.29-3.10	4.6	1	4
Ground Rod MX-148/G	3.29-3.14	4.6	1	4
Guy MX-1201( )/U	3.29-3.13	4.6	1	4
Guy attachment straps	3.29-3.24.5	4.6	1	4
Guy spacer assembly	3.29-3.19	4.6	1	4
Guy winch assembly	3.29-3.26	4.6	1	4
Hoist line assembly	3.29-3.16	4.6	1	4
Interlock clips	3.29-3.24.4	4.6	1	4
Modified guy anchor	3.29-3.15	4.6	1	4
Plate, Base, Tower Section AB-556()/U	3.29-3.23	4.6	1	4
Platform	3.29-3.24.2	4.6	1	4
Platform Section, Tower MT-1156()/U	3.29-3.7	4.6	1	4
Roller, Aerial Cable MX-1216( )/U	3.29-3.12	4.6	1	4
Stairway	3.29-3.24.3	4.6	1	4
Support, Antenna AB-296( )/G	3.29-3.21	4.6	1	4
Tag line assembly	3.29-3.17	4.6	1	4
Tensiometer assembly	3.29-3.22	4.6	1	4
Tower Section AB-207( )/U	3.29-3.24	4.6	1.5 DPHU	1.5 DPHU

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:24Z
Check the source to verify that this is the current version before use.

* 4.5.1 Group A inspection.- Each unit of each lot of equipment shall be inspected for conformance to all the inspection and test requirements of table I. Each lot will be subject to verification, utilizing the procedures of Military Standard MIL-STD-105, and the AQL's indicated in table I. Group A inspection shall be performed in any order which is satisfactory to the Government.

* 4.5.2 Group B inspection.- This inspection, including sampling, shall conform to table II and to the special procedures for small-sample inspection of Standard MIL-STD-105. Group B inspection shall be performed on inspection lots that have passed Group A inspection and on samples selected from units that have been subjected to and met the Group A inspection.

* 4.5.2.1 Group B sampling plans.- The Group B sampling plans, for the AQL's listed in table II, shall be as follows:

AQL	Special Inspection Plan
6.5%	S-4
10.0%	S-3

TABLE II. Group B Inspection

Inspection	Req. par.	Insp. par.	AQL in percent
Tensile			
Clevis, upset, insulator type	3.9	4.9	10
Guy MX-1201( )/U	3.13	4.11	10
Guy attachment straps	3.24.5	4.22	10
Guy spacer assembly	3.19	4.14	10
Guy winch assembly	3.26	4.12	10
Hoist line assembly	3.16	4.13	10
Tag line assembly	3.17	4.13	10
Load			
Antenna support platform assembly	3.21.1	4.15	10
Capstan E-12( )/U	3.25	4.23	10
*Davit, Tower Erection MX-1215( )/U	3.10	4.10	10
Plate, Base, Tower Section AB-566()/U	3.23	4.17	10
Platform	3.24.2	4.19	10
Stairway	3.24.3	4.20	10
Accuracy			
Tensiometer	3.22	4.16	6.5
Shear Load			
Interlock clips	3.24.4	4.21	10
Interchangeability	3.6	4.8	10

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:24Z
Check the source to verify that this is the current version before use.

4.5.2.2 Order of inspection within Group B.- Group B inspection shall be performed in any order which is satisfactory to the Government.

* 4.5.3 Group C inspection.- This inspection shall be as specified in table III, and shall be performed on sample units that have been subjected to and met Group A and Group B inspection. Sample units shall be selected in accordance with paragraph 4.5.3.1.

TABLE III. Group C Inspection

Inspection	Req. par.	Insp. par.
Tower Section AB-207( )/U Column load	3.24.1	4.18

* 4.5.3.1 Sampling for inspection.- One sample shall be selected at random for the inspection specified for Table III from every 25 tower sections or fraction thereof produced. The first samples selected shall be at the start of the contract from the first quality conformance inspection production lot (see 4.5.3).

* 4.5.3.2 Noncompliance.- The contractor shall immediately report in writing each group C failure occurrence, including details of the failure and characteristics affected. The contractor shall immediately investigate the cause of failure and further report the results of investigation and details of the proposed corrective action on (i) the process and materials, as applicable, and (ii) all units of product which were manufactured under the same conditions and which the Government considers subject to the same failure. Reports shall be forwarded to the responsible technical activity designated in the contract through the Quality Assurance Representative. After corrective action has been taken, additional sample units shall be subjected to group C inspection (all inspections, or the inspections which the sample failed, at the option of the Government) and Groups A and B inspection may be reinstituted; however, final acceptance and shipment will be withheld until the group C reinspection results have shown that the corrective action was effective.

* 4.5.4 Reinspection of conforming Group B and Group C sample units.- Unless otherwise specified, sample units which have been subjected to and passed both Group B and Group C inspection may be accepted on contract or order provided all damage is repaired and the sample units are resubjected to and pass Group A inspection.

4.6 Visual and mechanical inspection.- Equipment shall be examined for the defects listed in Standard MIL-STD-252 and table IV.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:24Z
Check the source to verify that this is the current version before use.

TABLE IV. Classification of visual and mechanical defects

Classification	Defect
Major	Loose nuts and screws. Welding, such as scabs, blisters, pock marks and other harmful defects. Riveting, rivet too close to edge of material riveted. Painting, color not as specified, unsatisfactory adhesion, film thickness less than ½ specified thickness. Marking, missing, illegible or incorrect. Parts, missing or improperly assembled. Item not within requirements of drawing.
Minor	Scratches, cuts, abrasions, peeling or chipping. Useless holes or slots.

* 4.7 Welding inspection.- Welding shall be inspected in accordance with Specification MIL-W-8604 (see 3.4).

* 4.8 Inspection for dimensional interchangeability.- The dimensions of Tower Section AB-207( )/U listed below shall be gaged or measured to determine conformance to the physical interchangeability requirements of 3.6. When a listed dimension is not within specified or design limits, it shall be considered a major defect.

(a) The diagonal distance between alternate legs of the tower section shall be gaged in accordance with Drawing SC-D-57276, "Gage for Diagonal Distance of Tower Sections".

(b) The distance between adjacent legs of the tower section, and also the dimension of the mating holes of these legs, shall be gaged in accordance with Drawing SC-D-57277, "Gage for Mating Holes of Tower Sections".

(c) The female ends of the tower section legs shall be gaged with "Gage, Plug, Plain Cylindrical (Go) No. 7447468" listed in Standard MIL-STD-110.

(d) The male ends of the tower section legs shall be gaged with "Gage, Ring, Plain (Go) No. 7492640" listed in Standard MIL-STD-112.

* 4.9 Clevis, upset, insulator type.- The clevis shall be proven capable of meeting the requirements of 3.9. The test load shall be applied and measured by a tensile test machine. The sample shall be tested while attached to fixtures of the same diameter as the components attached to the clevis during service.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:24Z
Check the source to verify that this is the current version before use.

* 4.10 Davit, Tower Erection MX-1215( )/U.- The davit shall be proven capable of meeting the requirements of 3.10 while attached to two Tower Sections AB-207( )/U, erected one above the other. The lower tower section shall be mounted on four Tower Section Base Plates AB-556( )/U.

* 4.11 Guy MX-1201( )/U.- Samples of guy assemblies shall be proven capable of meeting the requirements of 3.13. End fittings shall be attached to the samples in accordance with the applicable drawing, and the sample length shall conveniently fit into the test apparatus used. The test load shall be applied and measured by a tensile test machine. Samples shall be tested while attached to fixtures of the same diameter as the components attached to the guys during service.

* 4.12 Guy winch assembly.- The guy winch assembly shall be proven capable of meeting the requirements of 3.26. Tensile loads shall be applied and measured by a tensile test machine.

* 4.13 Hoist and tag line assemblies.- Samples of the hoist and tag line assemblies shall be proven capable of meeting the requirements of 3.16 and 3.17. The fittings on the samples shall be in accordance with the applicable drawing, and the sample length shall conveniently fit into the test apparatus used. The test load shall be applied and measured by a tensile test machine.

* 4.14 Guy Spacer Assembly.- Samples of the guy spacer assembly shall be proven capable of meeting the requirements of 3.19. The fittings on the samples shall be in accordance with the applicable drawing, and the sample length shall conveniently fit into the test apparatus used. The test load shall be applied and measured by a tensile test machine. Samples shall be tested while attached to fixtures of the same diameter as the components attached to the guy spacers during service.

* 4.15 Antenna Support Platform Assembly.- The platform assembly, when mounted on Support, Antenna AB-296( )/G, shall be proven capable of meeting the load requirement of 3.21.1.

* 4.16 Tensiometer.- The tensiometer shall be proven capable of meeting the requirements of 3.22. The tensiometer shall be tested on 5/16 inch diameter cable at 250 pounds, 500 pounds, 750 pounds and 1,000 pounds. The load shall be applied to the cable by, and the tensiometer reading shall be compared to the indicator of, a tensile test machine.

* 4.17 Plate, Base, Tower Section AB-556( )/U.- The base plate assembly shall be proven capable of meeting the requirements of 3.23. The compressive test load shall be applied on top of the adjusting nuts.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:24Z
Check the source to verify that this is the current version before use.

* 4.18 Column load.- An assembled tower section shall be proven capable of meeting the compressive load requirement of 3.24.1. A sample weld shall be proven capable of meeting the tensile load requirement of 3.24.1, using a tensile test machine to apply and measure the load.

* 4.19 Platform.- The removable platform for Tower Section AB-207( )/U, when mounted on a tower section, shall be proven capable of meeting the load requirement of 3.24.2.

* 4.20 Stairway.- The stairway for Tower Section AB-207( )/U, when mounted on a tower section, shall be proven capable of meeting the load requirement of 3.24.3.

* 4.21 Interlock clip.- The interlock clip shall be proven capable of meeting the shear load requirement of 3.24.4 when mounted in the normal functional position.

* 4.22 Guy Attachment Strap.- The guy attachment strap shall be proven capable of meeting the tensile load requirement of 3.24.5. The test load shall be applied and measured by a tensile test machine. The strap shall be tested while attached to fixtures of the same diameter as the components attached to the strap during service.

* 4.23 Capstan E-12( )/U.- Capstan E-12( )/U shall be proven capable of meeting the requirements of 3.25 when tested in its normal functional position.

* 4.24 Quality conformance inspection of preparation for delivery.- The contractor shall perform the inspection specified by 4.24.1 and 4.24.2. This does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's inspection records. In addition, the Government, at its discretion, may perform all or any part of the specified inspection to verify the contractor's compliance with specified requirements (see 6.4).

* 4.24.1 Preservation and packaging.- Preservation and packaging shall be inspected in accordance with Specification MIL-P-116. Classification of defects shall be as shown on table V.

* TABLE V. Preservation and packaging and marking

Major defects
1. Use of improper or defective material.
2. Quantity in unit package not as specified.
3. Incorrect packaging method applied.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:24Z
Check the source to verify that this is the current version before use.

4. Cushioning or padding omitted.
5. Cushioning inadequate for the physical and mechanical protection of the item.
6. Unsealed, punctured or improperly sealed barrier bag, wrap or envelope.
7. Stock number omitted, incorrect or illegible.
8. Nomenclature omitted, incorrect or illegible.
9. Marking of quantity of items in package omitted, incorrect or illegible.
10. Different stock numbered items in same unit package.

Minor defects

1. Item not properly blocked or braced within the unit package to prevent movement.
2. Packaging material damaged.
3. Conforming wraps are not snug-fitting and contain voids.
4. Any item of required marking information other than listed under major defects 7 thru 9 omitted, incorrect, or illegible.

* 4.24.2 Packing and Marking of exterior containers.- Packing and marking of exterior containers shall be given visual inspection in accordance with Table VI to determine conformance to Section 5 and the approved process sheet (see contract). This inspection shall conform to the procedure for small-sample inspection of Standard MIL-STD-105. Inspection level S-4 shall be used. (Note: Other statistical sampling procedures may be employed if approved by the contracting officer).

(a) Major defects.- For sample sizes up to 10 inclusive, as determined by reference to Standard MIL-STD-105, each sample size as given shall be used, and for these sample sizes the acceptance number shall be zero. For sample sizes greater than 10 the acceptance number shall be determined by the AQL of 4.0 percent defective.

(b) Minor defects.- For sample sizes up to 5 inclusive, as determined by reference to Standard MIL-STD-105, each sample size as given shall be used, and for these sample sizes the acceptance number shall be zero. For sample sizes greater than 5 the acceptance number shall be determined by the AQL of 10.0 percent defective.

* TABLE VI. Packing and marking

Major defects

1. Use of improper or defective material.
2. Quantity in pack not as specified.
3. Gross weight in excess of specified amount.
4. Box closure not as specified.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:24Z
Check the source to verify that this is the current version before use.

5. Type, grade, class and style of the shipping container not as specified.
6. Strapping omitted.
7. Strapping inadequate or incorrectly applied.
8. Items not adequately blocked, braced or cushioned within the shipping container to prevent movement or damage.
9. Shipping documents or packing list omitted.
10. Stock number omitted, incorrect or illegible.
11. Nomenclature omitted, incorrect or illegible.
12. Marking of quantity of items in pack omitted, incorrect or illegible.
13. Destination marking omitted, incorrect or illegible.
14. Service designation (color marking) omitted.
15. Set or assembly markings omitted.
16. Specified special marking and labeling such as MAP labels, shipment digit markings, etc. omitted, incorrect or illegible.
17. Overseas code marking omitted, incorrect or illegible.

Minor defects
1. Unsealed carton.
2. Defective taping or sealing of carton.
3. Any other box defect which may be considered minor by definition of Standard MIL-STD-105.
4. Any item of required marking information other than 10 thru 17 listed under major defects omitted, incorrect or illegible.

* 4.24.2.1 Inspection lot.- A lot for visual inspection of the pack shall be all completed packs which are identical and will be submitted for acceptance at one time.

* 5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.- Preservation and packaging shall be level A or C, as specified.

5.1.1 Level A.-

5.1.1.1 Cleaning.- Cleaning shall be accomplished in accordance with process C-1 of MIL-P-116.

5.1.1.2 Drying.- Drying shall be accomplished in accordance with the applicable procedure of MIL-P-116.

5.1.1.3 Unit packaging.- Unit packaging shall be in accordance with the methods prescribed in MIL-P-116 and as specified herein.

5.1.1.3.1 Technical literature.- Each technical literature shall be packaged method 1C-1.

Source: https://assist.dla.mil -- Downloaded: 202640-17T14:24Z
Check the source to verify that this is the currentversion before use.

5.1.1.3.2 Towers, components of.- Packaging shall be developed in accordance with method III employing kinds and types of materials which when applied will afford adequate protection against corrosion, deterioration and damage during world-wide shipment, handling and open storage. When fiberboard unit package containers are used they shall conform to the requirements of PPP-B-636, type CF, class weather-resistant. All cushioning used in unit containers shall be fabricated of material equal to the weather-resistant requirements of the unit container. Closure shall be in accordance with the appendix of the box specification.

5.1.2 Level C.- Each Tower Component shall be preserved and packaged in a manner that will afford adequate protection against corrosion, deterioration and damage during shipment from the supply source to the first receiving activity.

5.2 Packing.- Packing shall be level A, B or C as specified.

5.2.1 Level A.- Tower components packaged as specified in 5.1, shall be packed in containers selected from Table VII based upon the most economical container required to provide minimum, adequate protection for the packaged item for this packing level of protection.

5.2.1.1 Strapping and reinforcing.- Metal strapping conforming to QQ-S-781, type 1, class B shall be applied to wood and wood-cleated shipping containers in accordance with the requirements of the applicable box specification or appendix thereto. Fiberboard shipping containers shall be reinforced by pressure-sensitive filament tape banding or non-metallic strapping conforming to PPP-T-97, type IV and PPP-S-760, type II respectively; selection of the material and application shall be in accordance with the appendix of the applicable box specification.

5.2.2 Level B.- Tower component packaged as specified in 5.1, shall be packed as specified in 5.2.1 except that Level B containers of Table VII shall apply.

5.2.3 Level C.- Tower component shall be packed in shipping containers in a manner that will afford adequate protection against damage to the package and its contents during shipment from the supply source to the first receiving activity. Shipping containers shall comply with the rules and regulations of the common carrier as applicable to the mode of transportation.

5.3 Marking.- In addition to any special marking required by the contract or order, interior packages and exterior shipping containers shall be marked in accordance with MIL-STD-129.

5.4 Inspection.- Inspection of military packaging shall be in accordance with MIL-P-116.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:24Z
Check the source to verify that this is the current version before use.

TABLE VII

CONTAINER REQUIREMENTS

Container	Specification	For Level A	For Level B	Max. Gross Wt. Limitation (lbs)
Boxes, Wood, Nailed and Lock-Corner, Style 4	PPP-B-621	Class 2	Class 1	200 (Note A)
Boxes, Wood, Nailed and Lock-Corner, Style 7	PPP-B-621	Class 2	Class 1	1000 (Note B)
Box, Wirebound, Style 2 or 3	PPP-B-585	Class 3	Class 1	200
Box, Wood Cleated Fiberboard	PPP-B-591	Class II	Class 1	200 (Note A)
Box, Cleated Plywood	PPP-B-601	Overseas Type	Domestic Type	200 (Note A)
Boxes, Fiberboard, Corrugated, Triple Wall, Style E	PPP-B-640	Class 2	Class 1	200 (Note A)
Box, Fiberboard, Type CF	PPP-B-636	Class Weather-resistand	Class Domestic	(Note C)
Box, Fiberboard, Corrugated Double Wall, Weather Resistant	MIL-B-43291	Type CF	--	Table II
Crates, Wood, Open and Covered	PPP-C-650	Style B, Type V Covered	Style B, Type V Covered	Table I (Note B)
Crates, Wood	MIL-C-104	Type, Class, Style As applicable	Type, Class, Style As applicable	30,000 (Note B)

NOTE A. When the weight of a single item together with the shipping container exceeds 200 pounds, the maximum gross weight limitation of the container specification shall apply. In addition, skids, or pallet bases shall be applied in accordance with the requirements of the container specification, or if not specified in the specification, in a manner which will adequately support the item and facilitate the use of material handling equipment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:24Z
Check the source to verify that this is the current version before use.

NOTE B. Style 7 containers conforming to PPP-B-621 shall be considered for use only when the weight of a single item exceeds 400 pounds. Covered crates conforming to PPP-C-650 shall be used only when the weight of a single item exceeds 1000 pounds. Sheathed crates conforming to MIL-C-104 shall be used only when the weight of a single item exceeds 4000 pounds.

NOTE C. The maximum gross weight limitations for Special Requirements as cited in PPP-B-636 shall apply.

6. NOTES

6.1 Intended use.- Tower AB-216( )/U is intended for use as a 78-foot sectionalized guyed rectangular type utility tower with components for extending it to a height of 204 feet. It provides for easy accessibility and mounting of Microwave antenna and Radio Relay equipment.

6.2 Ordering data.- Procurement documents should specify the following:

(a) Title, number, and date of this specification and any amendments thereto.

* (b) Equipment required.

(c) Level of packaging and level of packing required for shipment. (Level A, level B, level C.)

(d) Preproduction inspection - Two sample units of each item cited in Section 1 are generally required for test purposes (see 3.2).

(e) Marking and shipping of samples.

(f) Place of final inspection.

(g) Technical literature required.

(h) Quantity of tools and running spare parts required.

6.3 Nomenclature.- The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design, for example, AB-216W/U. The contractor should apply for nomenclature in accordance with the applicable clause in the contract (see 1.1).

* 6.4 Verification inspection.- Verification by the Government will be limited to the amount deemed necessary to determine compliance with the contract and will be limited in severity to the definitive quality assurance provisions established in this specification and the contract. The amount of verification inspection by the Government will be adjusted to make maximum utilization of the contractor's quality control system and the quality history of the product.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:24Z
Check the source to verify that this is the current version before use.

* 6.5 The margins of this specification are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

Custodian:
Army-EL

Navy-YD

Air Force-84

Preparing Activity:
Army-EL

Reviewing Activity:
Army-SM

Project No. 5445-0004

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:24Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION
MIL-T-10767F TOWERS (COMPONENTS OF)

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A
☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

ESC-FM 1068-68

To detach this form, cut along this line

Source: https://assist.dla.mil -- Downloaded: 202610-17T14:24Z
Check the source to verify that this is the current version before use.