MILITARY SPECIFICATION

GENERATOR SETS, DIESEL ENGINE, STATIONARY, ALTERNATING CURRENT, 30 THROUGH 500 KW (FOR FLOATING DRYDOCKS)

This amendment forms a part of Military Specification MIL-G-17264C, 19 October 1961, and has been approved by the Department of Defense and is mandatory for use by the Departments of the Army, the Navy, and the Air Force.

Page 6, paragraph 3.7, delete dynamic force formula and substitute:

"$F = \frac{Wl}{32.2}\left(\frac{4\pi^2\theta}{180T^2}\right)$"

Page 6, paragraph 3.7.1, line 8: Delete "have" and substitute: "having".

Page 10, paragraph 3.9, line 7: Delete "protective" and substitute: "protected".

Page 11, paragraph 3.9.3.2, line 6: Delete "affected" and substitute: "effected".

Page 12, paragraph 3.12, line 19: Delete "positionel" and substitute: "positioned".

Page 20, paragraph 4.6: Delete and substitute:

"4.6 Tests. Tests shall include all special tests on the first complete generator set of each type as well as the first engine and generator; and routine tests on duplicate sets, engines, and generators. Tests shall be listed in table III and performed as specified herein. Tests shall also include a special paralleling test of all generator sets after installation on the floating drydock in the presence of the factory supervisor."

Page 22, paragraph 4.6.3: Delete subparagraph (a) and substitute:

"(a) Parallel operation. Each generator set shall be tested after installation on board the drydock, in the presence of the factory supervisor, for satisfactory parallel operation with the other generator sets on the dock. This test shall be a continuous 2-hour test with all generator sets synchronized, and each operating at rated voltage and approximately 20 percent of rated load at rated power factor. Adjust the governors and voltage reactive droop compensation for equal kw and kvar load division. No further adjustment of governors, voltage regulator, or rheostats shall be made for the duration of the test. Vary the load from 20 to 100 percent of the combined ratings of the generators, at about rated power factor, in four approximately equal steps. Maintain 75 to 100 percent load for 90 minutes. Then reduce load in four approximately equal steps

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:53Z
Check the source to verify that this is the current version before use.

to 20 percent and vary again from 20 to 100 percent and back to 20 percent. At each load point, record speed, voltage, current, kw load, kvar load, and field current of each generator."

Page 25, paragraph 6.2(i) : Delete:

Custodians:
Army—MO
Navy—Docks

Preparing activity.
Navy—Docks
Project No. 6115-0047

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:53Z
Check the source to verify that this is the current version before use.