MILITARY SPECIFICATION

MODIFICATION KIT: RADIO RELAY EQUIPMENT AN/GRC-201

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE.

1.1 This specification covers the requirements for one type modification kit to be installed in the AN/TRC-97C Radio Set to provide low noise receiver performance, universal power utilization, and pulse-code modulation/time division multiplex (pcm/tdm). When this kit is installed, the AN/TRC-97C Radio Set will be identified as the AN/GRC-201 Radio Set.

2. APPLICABLE DOCUMENTS.

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of the specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-P-15024	- Plate, Tags and Bands For Identification of Equipment.
MIL-E-16400	- Electronic Interior Communication and Navigation Equipment, Naval Ship and Shore, General specification.
MIL-E-17555	- Electronic and Electrical Equipment, Accessories, and Repair Parts; Packaging and Packing of.
MIL-E-21981	- Electronics Type Designations, Identification Plates and Markings, Requirements For.
MIL-R-28704	- Radio Relay Equipment, Transhorizon (Tropospheric Scatter) AN/TRC-97

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.

FSC 5820

Source: https://assist.dla.mil -- Downloaded: 202610-20T22:33Z
Check the source to verify that this is the current version before use.

MIL-STD-470	- Maintainability Program Requirements (For Systems and Equipments).
MIL-STD-481	- Configuration Control-Engineering Changes, Deviations and Waivers (Short Form).
MIL-STD-785	- Reliability Program for Systems and Equipment Development and Production.
MIL-STD-810	- Environmental Test Methods.
MIL-STD-1472	- Human Engineering Design Criteria for Military Systems, Equipment and Facilities.

(Copies of specifications and standards required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 First article. Prior to submission of any complete production units for acceptance, the contractor shall furnish three first articles which shall be installed in the Government-loaned radio sets (see 3.10) for testing under the direction and supervision of the cognizant Government inspector to determine conformance to this specification. The first articles shall be identical to production units which the contractor will subsequently produce in fulfillment of the contract. Approval of the first articles by the activity concerned shall not relieve the contractor of the responsibility to supply kits conforming to this specification. Examination and testing shall be as specified herein. Any changes or deviations of the production units from the first articles shall be subject to the approval of the contracting officer and shall conform to the requirements of MIL-STD-481. The first articles may become a part of the total quantity to be supplied under the contract, provided complete refurbishing and inspection have been accomplished.

3.2 Materials and parts. Materials and parts not covered by applicable specifications shall be of best commercial quality. In the selection of materials and parts, fulfillment of major design objectives shall be the prime consideration. In all cases, the meeting of general material requirements as to nonflammability, fungus-resistance and nontoxicity as required by MIL-E-16400 shall be met. The following factors shall govern:

(a) Materials and parts approved in MIL-E-16400 shall be given first consideration.

(b) When use of materials or parts in accordance with MIL-E-16400 will not fulfill the design objective because of size, weight, performance, or other reasons, use of other materials must be approved by the contracting officer.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:33Z
Check the source to verify that this is the current version before use.

(c) High strength-to-weight ratio structural materials shall be utilized in construction to minimize weight. Materials shall withstand the severe environmental requirements specified herein without deterioration. Protective coatings and finishes shall be utilized in materials subject to deterioration.

3.3 Design and construction. The kit shall be designed and constructed so that when it has been installed, the AN/GRC-201 Radio Set will conform to the requirements specified herein. The radio set shall be readily transportable and capable of providing two-way multichannel communication. While the primary purpose of the radio set is to utilize the tropospheric scatter mode of operation, it shall also be capable of transmitting and receiving in the line-of-sight mode. The baseband intermediate frequency and radio frequency parts shall be designed so that the bandwidth capability may be extended up to 24 channels of pcm/tdm by the use of bandpass plug-in filters or other suitable, replaceable assemblies in accordance with MIL-E-16400. The primary requirements of this kit are that it shall be reliable, maintainable, and suitable for operation and maintenance to the current levels of the AN/TRC-97C Radio Set.

3.3.1 Power sources. The radio set shall be designed to operate and maintain performance specified herein from power sources having the following characteristics:

(a)	Potential (steady state):	120/208 volts (V) ± 10 percent
(b)	Phase:	3-phase, 4-wire, wye
(c)	Fluctuation in potential:	± 2 percent
(d)	Rate of change of voltage:	2.5 percent per second
(e)	Frequency (steady state):	50, 60, or 400 hertz (Hz) ± 5 percent
(f)	Fluctuation in frequency:	± 1 percent
(g)	Rate of change of frequency:	2.5 percent per second

3.3.2 Electrical supply variations. The radio set shall not be required to deliver performance specified herein during periods where electrical power source varies from specific steady state value by more than the tolerance value when used with a power generating source provided solely for power supply for the radio set. Operation of the radio set, though degraded, shall still be possible with voltage variations of up to ±30 percent and frequency variations of ±15 percent. The radio set shall not sustain damage or alteration of characteristics when such variations are experienced in the power source for periods of 10 seconds with a frequency of one every 5 minutes. In the event of

Source: https://assist.dla.mil -- Downloaded: 202610-20T22:33Z
Check the source to verify that this is the current version before use.

variations in excess of ±30 percent in voltage or ±15 percent in frequency, or complete power source failure, the radio set shall "fail safe."

3.3.3 Power consumption. Under normal operating conditions, the radio set shall require not more than 7.5 kilowatts of 0.8 power factor primary power.

3.3.4 Pulse-code modulation channel capacity. The 12-channel pcm/tdm radio set shall provide facilities for 1,152,000 bits per second (b/s) pcm/tdm signals in a format identical to that used by the TD-660A/G Multiplexer, TD-206 Restorers, and the TD-204 Cable Combiner. The radio set shall regenerate the pcm signals but not convert pcm signals to audio or vice versa. An independent orderwire (ow) or service channel of 300 to 3400 Hz shall be included. Also, direct current (dc) from the receive cable interface shall be looped back to the transmit cable interface to provide a closed circuit enabling the TD-204 Cable Combiner to power the TD-206 Restorers.

3.3.5 Frequency response. The frequency response shall be as follows measured at the shelter interface:

ow: 700 Hz and 1300 Hz, +2.0 decibels (dB) to -2.0 dB;

300, 400, and 2500 Hz, +3.0 dB to -3.0 dB;

3000 Hz, +2 dB to -10 dB, all relative to 1 kilohertz (kHz).

pcm/tdm: 2,304,000 b/s (cable system)

3.3.6 Pulse code modulation input. The pcm input of the exciter shall be compatible with the output of the pcm digital data modem. An ow or service channel circuit shall be incorporated whose input shall be independent of that provided by the pcm multiplexer signal and whose ringing tone is different from all other ringing tones or alarm tones in the radio set.

3.3.7 Modulating frequencies. The modulating frequencies shall be as follows:

ow service channel: 300 Hz to 4 kHz

pcm multiplex channel: 576,000 b/s for 12 channels

1,152,000 b/s for 24 channels

3.3.8 Frequency deviation. The frequency deviation shall be as follows:

ow: ± 31.1 kHz peak at -15 dB referred to 1 milliwatt (mW).

Source: https://assist.dla.mil -- Downloaded: 202640-20T22:33Z
Check the source to verify that this is the currentversion before use.

pcm multiplex	For 12 or 24 channels, ± 375 peak for 1 V peak-to-peak input at pcm baseband.

3.3.9 Receiver. The receiver shall be a low noise receiver capable of receiving and demodulating signals from either the tropospheric scatter or line-of-sight modes of operation. The receiver shall utilize a parametric amplifier-tunnel diode preamplifier with appropriate preselection to obtain a noise figure measured at the antenna terminals of 2.8 dB or better and shall not be limited by special maintenance or operating features. The receiver noise figure shall automatically be 11 dB or less if the low-noise device fails (fail-safe operation). These input noise figures apply provided the input noise figure of the AN/TRC-97C Radio Set before modification is 5.1 dB or less.

3.3.10 Diversity combiner. The receiver shall be capable of dual diversity operation. Diversity action shall be achieved by means of a predetection maximal ratio combiner. The dual diversity output shall be constant within 1 dB with the receiver input signals at any point within their normal range of operation.

3.3.11 Bandwidth. The bandwidth shall be 1.5 kHz.

3.3.12 Receiver output. The output circuits of the receiver for the 12- or 24-channel baseband shall have the capability of feeding the pcm digital data modem a composite pcm plus ow signal. The receiver ow system shall accept the radio sensory ow from the digital data modem at a -4 dB referred to 1 mW level and transfer the signals through the ow hybrid to the receiver handset and ring facilities. The pcm baseband output signals to the digital data modem shall be 1 V peak-to-peak at 50 ohms.

3.3.13 Receiver monitor. The receiver monitor shall provide a means to identify the receiver(s) which are contributing to the output of the diversity combiner. This indication shall include the operation of a local indicator and shall provide a facility for each receiver for operation of a monitor to a remote location.

3.3.14 Maximum signal. The receiver shall operate normally and meet the intermodulation requirement with the radio set operating as a line-of-sight terminal and a like radio set as the other terminal to a distance of 1 nautical mile. Reception of signals in excess of this level shall not affect the maximum usable signal of the receiver at any time.

3.3.15 Recorder output. A monitor circuit and output amplifier for driving a suitable recorder shall be provided for each receiver and combiner to permit monitoring the received signal level.

Source: https://assist.dla.mil -- Downloaded: 20260-20T22:33Z
Check the source to verify that this is the current version before use.

3.3.16 Metering. All critical circuits, and circuits normally used in tuning the receiver, shall be metered.

3.3.17 Output impedance. The output impedance for the ow shall be 600 ohms ±10 percent, including the drop repeater, and 50 ohms ±10 percent for the pcm baseband.

3.3.18 Output level. The output level shall be -15 dB referred to 1 mW for the ow and 1 V peak-to-peak for the pcm baseband.

3.3.19 Antenna group. The antenna group shall be designed to provide maximum flexibility in operating as a line-of-sight terminal antenna group and space dual diversity compatible with the AN/TRC-112 Radio Set antenna system. The reflector shall provide for orientation of the feed system at both the vertical position and 45 degrees from the vertical position. All other antenna requirements shall continue to be met.

3.3.20 Pulse-code modulation digital data modem (ddm). The ddm provides for transmission of 12 or 24 audio channels using pcm signals in a format identical to that used by the TD-660 Multiplexer and the TD-204 ( )/G Cable Combiner. The ddm shall regenerate the pcm signals but shall not convert the pcm signals to audio or vice versa. The ddm shall interface the radio transmitter and receiver into the special purpose electrical CX-11230 Cable Assembly. The ddm shall be compatible with pulse form TD-206 ( )/G Restorers placed at 1/4-mile intervals in the cable system with the TD-204 ( )/G Cable Combiner at the distant end of the cable system. The ddm shall regenerate the pcm signals from the cable and radio and make format changes for compatible operation. Provisions shall be made for insertion of an ow signal with the pcm (except to the radio transmitter) and extraction of the ow from the received signals. Provisions shall also be made for dc from the receive cable to be loop locked to the transmit cable through a closed loop in the TD-204 Cable Combiner to power the TD-206 Restorers. The ddm shall provide for pcm signals plus ow from the radio receiver, to the cable system, from the cable system, and to the radio transmitter.

3.3.20.1 From radio receiver signal. This signal is a summation of the pcm and ow signal components. The signal is summed and shaped in the mode transmitter, then gaussian noise is added and shaped in the radio receiver and sent to the ddm. The components shall have the following characteristics:

(a) Pulse-code modulation component

Voltage	1 V peak-to-peak ±1 dB
Bit Rate	1,152,000 b/s ± 25 pules per minute (ppm) for 24 channels
	576,000 b/s ±12 ppm for 12 channels

Source: https://assist.dla.mil -- Downloaded: 20260-20T22:33Z
Check the source to verify that this is the current version before use.

Data Format	Full baud binary before filtering effects of radio.

(b) Orderwire component. Variable frequency of 300 to 3400 Hz sine wave with peak-to-peak amplitude equal to 175 ± 2.5 percent of pcm peak-to-peak amplitude.

3.3.20.2 To cable system signal. This signal is a summation of the pcm, ow, and dc components. The pcm signal shall be regenerated in the ddm formatted to a 2,304,000 b/s diphase summed with the ow and dc signals then sent to the cable system. The components shall have the following characteristics:

(a) Pulse-code modulation component

Impedance:	50 ohms.
Voltage:	1.8 ± V height of 1 pulse following a string of zeros above and relative to the zero level.
Pulse Droop:	Approximately 20 percent
Bit Rate:	2,034,000 b/s ± 50 ppm
Bit Error Rate:	With a data rates 2,304,000 b/s ± 50 ppm, shall be less than $1/10^5$ (equivalent to less than one click per minute on any audio channel) when peak signal to root mean square (rms) noise ratio of pcm from radio is 19.0 dB and when ow component is present. Noise insertion for frame and bit synchronization tests at "from radio" point shall maintain bit synchronization at a signal to noise of 12.5 dB.

(b) Orderwire component.

Impedance:	880 ohms ± 10 percent
Voltage:	1.5 V rms minimum and 2.2 V rms nominal.
Frequency Response:	Frequencies relative to 1 kHz shall be -0.5 dB ±1 dB for 300 and 1700 Hz.

Source: https://assist.dla.mil -- Downloaded: 202610-20T22:33Z
Check the source to verify that this is the current version before use.

(c) Direct current component: 40 milliamperes nominal dc complying.

3.3.20.3 From cable system signal. This signal is a summation of the pcm, ow, and dc components. The received pcm signal from the cable shall be regenerated to the proper bit rate and sent to the radio transmitter. The ow shall be recovered from the cable system and sent to the radio ow system. The components shall have the following characteristics:

(a) Pulse-code modulation component

Impedance:	50 ohms
Voltage:	20 to 50 millivolt peak-to-peak
Pulse Shape:	Pulses are distorted by CX 11230 Cable characteristics. This pulse shape is specified at input to cable. Cable input is equivalent to ddm or TD-204 Cable Combiner to cable signals.
Bit Rate:	2,303,000 b/s ± 50 ppm
Data Format:	Equivalent to ddm or TD-204 Cable Combiner to cable signal.

(b) Orderwire component

Impedance:	880 ohms ± 10 percent
Voltage:	0.15 to 15 V rms test tone at 1 kHz
Frequency Response:	Frequency relative to 1 kHz shall be -0.5 db ± 1 dB for 300 and 1700 Hz

(c) Direct current component. 40 mA nominal dc complying used for pulse restorer power from TD-204 Cable Combiner and lock.

3.3.20.4 To radio transmitter signal. This signal shall be pcm only and shall be a regenerated signal from the cable system with the following characteristics:

(a)	Impedance:	50 ohms ± 10 percent
(b)	Voltage:	"One" 0.9 to 1.3 V
		"Zero" 0 to 0.2 V

Source: https://assist.dla.mil -- Downloaded: 20260-20T22:33Z
Check the source to verify that this is the current version before use.

(c) Width 24 channel 0.868 microsecond ± 1 percent

(d) Bit Representation: Full band binary

(e) Bit Error Rate: With data rate of 1,152,000 b/s and with a signal noice of 33 dB at "from cable signal" input, the error rate shall be less than 1 x 10^6 bits transmitted.

3.3.21 Alarm signals. A major alarm signal shall be provided which summarizes all detected failures and shall activate the MUX ALARM on the radio set. Alarm signals for the from cable, to cable, from radio, and to radio shall operate red (alarm) and green (normal) lamps on the ddm. A control signal shall be provided signifying that the pcm component of the signal from the radio is not present so that the radio ow can be transferred directly to the radio ow system.

3.3.22 Radio recovered ow. This signal shall be recovered from the radio receiver and the antilog ow signal sent back to the radios ow system and shall have the following characteristics:

(a) Impedance: 600 ohms ± 2 percent

(b) Voltage: -4 dB referred to 1 mW

(c) Frequency Response: Reference to 1 kHz ± 1 dB for 300 Hz and ± 2 dB for 3000 Hz.

(d) Residual Noise: At least 39 dB below the -4 dB referred to 1 mW signal level.

3.3.23 Orderwire to cable insertion. This signal shall be transferred from the radio set ow THRW OW to the pcm cable system in the pcm mode and shall have the following characteristics:

(a) Impedance: 600 ohms ± 2 percent

(b) Voltage: -4 dB referred to 1 mW

(c) Frequency Response: Reference to 1 kHz ± 1 dB for 300 Hz and ± 2 dB for 3000 Hz.

3.3.24 Cable recovered ow. This signal shall be recovered from the composite pcm signal which is present on the receive cable. The antilog ow signal is then sent back to the radio ow system. This signal shall have the following characteristics:

Source: https://assist.dla.mil -- Downloaded: 20261O-20T22:33Z
Check the source to verify that this is the currentversion before use.

(a) Impedance: 600 ohms ± 10 percent

(b) Voltage: -4 dB referred to 1 mW

(c) Frequency Response: -0.5 ± 1 dB, 300 to 1700 Hz with respect to 1 kHz.

3.3.25 Radio repeat mode. The ddm shall provide for a repeat mode whereby the pcm signal can be retransmitted when the radio set is configured as a through repeater.

3.3.26 Cable loop back. Provision shall be made for a cable loop back test within the ddm.

3.3.27 Modular construction. The kit shall be designed and constructed to utilize modular construction techniques whenever possible. The number of removable subunits employed shall be consistent with good engineering practice. A subunit shall not be construed to mean a chassis but units or circuitry within a chassis. All modular assemblies performing identical assemblies, such as amplifying circuits or low voltage power supplies, shall be identical and interchangeable with like modular assemblies throughout the set. Every effort shall be made to minimize the number of modular assemblies employed to accomplish a specific function.

3.3.28 Human factors engineering. The kit shall be human engineered from a maintenance and operational point of view in accordance with MIL-STD-1472.

3.4 Reliability. Reliability shall be in accordance with MIL-STD-785 and shall be compatible with the operational levels of the AN/TRC-97C Radio Set. Reliability shall receive major emphasis during the design, fabrication, and construction of the kits. This shall be reflected in the assembly processes and the determination of operational techniques. The first article, production, and sample kits shall be subjected to the mechanical and electrical tests specified in Section 4. Mechanical wear shall be such that mechanical or functional performance is not affected. Abrasion of painted surfaces is allowable. Electrical performance of the AN/GRC-201 Radio Set shall not be degraded.

3.5 Maintainability. Maintainability shall be in accordance with MIL-STD-470 and shall be compatible with the operational levels of the AN/TRC-97C Radio Set. The AN/GRC-201 Radio Set shall be capable of being aligned, adjusted, and maintained, where practicable, without the use of external test equipment or tools. In circuit indicators, monitors, and alarms shall be utilized to the maximum extent possible. All replaceable components shall be individually replaceable. No loss of watertight integrity shall result from opening the case for field repair or replacement of components.

Source: https://assist.dla.mil -- Downloaded: 20260-20T22:33Z
Check the source to verify that this is the current version before use.

3.6 Transportability. The radio set shall be capable of being transported by fixed wing aircraft such as type C-123, by sling on rotary wing aircraft or by truck such as type M37, without deleterious effects of shock and vibration.

3.7 Weight. Weight of the radio set shelter package when loaded for transport shall not exceed 1,970 pounds for 12-channel equipment or 2,145 pounds for 24-channel equipment. Weight of the power accessory group shall not exceed 4,200 pounds.

3.8 Color and finish. Color and finish of all items of the kit shall be in accordance with MIL-R-28704.

3.9 Identification marking. Identification plates for the kit shall be in accordance with MIL-P-15024 and shall be of aluminum alloy when practicable. Drawings for identification plates shall be submitted for approval prior to commencement of first article tests. Nomenclature shall be requested in accordance with MIL-E-21981 and shall be submitted prior to commencement of first article testing. Subassemblies shall be identified with the following information rubber stamped or silk screened on a fixed surface, if available, or on a permanent tag affixed in such a manner as not to impair operation of the assembly and not be easily removeable:

(a) Nomenclature

(b) Approved item name

(c) Additional information required; NSN, drawing number, manufacturer's name and serial number.

3.10 Government-loaned property. Three AN/TRC-97 Radio Sets shall be loaned by the Government. The three first article kits shall be installed in these radio sets and the resulting AN/GRC-201 Radio Sets shall be subjected to the first article tests specified in Section 4. These Government-loaned radio sets may be retained by the contractor for the duration of the contract for use in sample testing of the production kits. They shall then be returned to the Government.

3.11 Workmanship. The kits covered by this specification shall be manufactured and finished in accordance with requirement 9 of MIL-STD-454.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. - Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may utilize his own or any other facilities suitable for the performance of the inspection

Source: https://assist.dla.mil -- Downloaded: 202610-20T22:33Z
Check the source to verify that this is the currentversion before use.

requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of inspection. - The inspection and test requirements specified herein are classified as follows:

(a) First article (see 4.3)

(b) Production inspection (see 4.4)

(c) Sample inspection (see 4.5

4.2.1 Tests, test equipment, and test procedures. - The contractor shall submit a list of proposed tests and written test procedures, including test equipment and tolerance limits to be used in testing first articles and production equipment, to the procuring activity for review and approval, at least 30 days prior to beginning tests.

4.3 First article inspection. - First article inspection shall consist of all examination and testing necessary to determine compliance with the requirements of this specification including environmental tests.

4.3.1 Inspection and test of kit. - The electrical parts and assemblies contained in the kit shall be tested in accordance with approved test procedures. An inspection report shall be maintained with all data recorded.

4.3.2 Inspection and test of AN/GRC-201 Radio Set. After the kit has been installed, the AN/GRC-201 Radio Set shall be subjected to the following tests:

(a) 48-hour continuous operation at room temperature but with input line voltage at 110 percent of nominal line voltage and frequency of 60 Hz.

(b) Humidity test specified in MIL-E-16400.

(c) The shock and vibration test specified in MIL-STD-810.

The following performance characteristics shall be measured during the above tests:

(a) Receiver noise figure

(b) Combiner performance

(c) Baseband output level

Source: https://assist.dla.mil -- Downloaded: 202610-20T22:33Z
Check the source to verify that this is the currentversion before use.

(d) Input level to modulator

(e) Orderwire performance, bandwidth and level

(f) Critical power supply voltages

The contractor shall make all changes in the kit required as a result of first article testing to meet the requirements of this specification.

4.4 Production inspection. - Production inspection shall be made on every kit offered for delivery. The inspection shall include examination and testing which will prove the workmanship and reveal the omissions and errors of the production process such as functional and performance tests at a limited number of points, tests which detect deviations from design, tests of adjustment, and tests which detect hidden defects of material. Production inspection shall include the following:

(a) Surface Examination

(b) Operating Test

4.5 Sample inspection. - Sample inspection shall be performed in accordance with MIL-E-16400 except that the reliability tests are not required. Kits to be subjected to sample inspection shall be selected from lots which have passed production inspection. The sampling shall conform to the procedures for special inspection levels of MIL-STD-105. The inspection level shall be S-4 for normal, tightened, and reduced inspection, with an acceptable quality level of 6.5 percent for each test required by MIL-E-16400.

4.5.1 Nonconformance and retest. - If a sample kit fails a test specified in 4.5, the contractor shall immediately investigate the cause of failure and shall report to the Government inspector the results thereof and details of the corrective action taken to correct kits which were manufactured with the same conditions, materials, processes, and so forth. The kits shall then be retested. The other kits in the production lot may be shipped in advance of completion of tests specified in 4.5.

4.5.2 Corrective action. - If corrective action results in a change of part(s), circuit layout or the mechanical arrangement, or if the Government inspector does not consider that the corrective action will enable the product to meet requirements specified herein, or if the contractor cannot determine the cause of failure, the matter shall be referred immediately to the contracting officer. It shall then be determined by the procuring activity whether correction should be made to the kits already delivered under the contract.

Source: https://assist.dla.mil -- Downloaded: 20261O-20T22:33Z
Check the source to verify that this is the current version before use.

4.5.3 Reinspection of sample units. - Sample kits which have been subjected to and passed production control or environmental inspections, or both, may be accepted on contract provided that they are resubjected to, and pass, production inspection after repair of all visible damage.

5. PREPARATION FOR DELIVERY

5.1 Preservation, packaging and packing. Preservation, packaging and packing shall be the level of shipment specified in the contract or order in accordance with MIL-E-17555 (see 6.2).

5.2 Marking. In addition to any special marking required by the contract or order, unit packages, intermediate packages, and shipping containers shall be marked in accordance with the requirements of MIL-STD-129.

6. NOTES

6.1 Intended use. These modification kits are intended for installation in Radio Set AN/TRC-97. After installation, the radio set will be identified as AN/GRC-201 Radio Set.

6.2 Ordering data. Purchasers should exercise any desired options offered herein, and procurement documents should specify the following:

6.2.1 Procurement requirements.

(a) Title, number, and date of this specification.

(b) Selection of applicable level of packaging and packing required (see 5.1).

6.2.2 Contract data requirements. Data conforming to Data Item Descriptions DI-H-1313, DI-H-1315, DI-R-3533, DI-R-3542, DI-R-4026, DI-E-4528, DI-E-4542, DI-R-4803, DI-T-4901, DI-T-4902, DI-T-4903 and DI-T-4904 will usually be required for delivery in connection with this specification. When so required, such data will be specified for delivery on a DD Form 1423 included in the contract.

6.3 First article. Invitations for bids should provide for the Government to reserve the right to waive the requirement for the first article testing for those bidders offering a product which has been previously procured or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending procurement.

Preparing activity:
Navy - MC
Project No. 5820-N675

Source: https://assist.dla.mil -- Downloaded: 20261O-20T22:33Z
Check the source to verify that this is the current version before use.