NOT MEASUREMENT SENSITIVE

MIL-R-29231A(YD)
JANUARY 20, 1991
SUPERSEDING
MIL-R-29231(YD)
13 April 1984

MILITARY SPECIFICATION

ROLLER, TANDEM, SELF-PROPELLED, WITH RETRACTABLE TRANSPORT WHEELS

This specification is approved for use by the Naval Facilities Engineering Command, Department of the Navy, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a diesel-engine-driven, self-propelled, tandem axle, static, steel roller equipped with pneumatic tired retractable transport wheels.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commanding Officer (Code 156), Naval Construction Battalion Center, Port Hueneme, CA 93043-5000, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 3895

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:23Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

VV-F-800 - Fuel Oil, Diesel.

MILITARY

MIL-R-3075 - Rollers, Motorized, Road, Diesel- or Gasoline-Engine-Driven, Packaging of.

STANDARDS

FEDERAL

FED-STD-595 - Colors.

MILITARY

* MS 51336 - Lunnett-Coupler, Drawbar, Ring.

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Standardization Documents Order Desk, Bldg. 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094)

* 2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those cited in the solicitation.

DEPARTMENT OF LABOR (DoL)
OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA)

Occupational Safety and Health Standards.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402.)

* 2.2 Non-Government publications. The following document(s) form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DoD adopted shall be the issue listed in the current DoDISS and the supplement thereto, if applicable.

SOCIETY OF AUTOMOTIVE ENGINEERS, INC. (SAE)

SAE Handbook.

(Application for copies should be addressed to the Society of Automotive Engineers, Inc., 400 Commonwealth Drive, Warrendale, PA 15096.)

TIRE AND RIM ASSOCIATION, INC. (TRA)

TRA Yearbook.

Source: https://assist.dla.mil -- Downloaded: 2026l0-20T22:23Z
Check the source to verify that this is the current version before use.

(Application for copies should be addressed to the Tire and Rim Association, Inc., 3200 West Market Street, Akron, OH 44313.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

D1557 - Moisture-Density Relations of Soils using 10-pound rammer and 18-inch drop.
D2487 - Classification of Soils for Engineering Purposes.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

* 2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

3.1 Description. The Roller shall consist essentially of a steel body and frame, two steel compaction drums, diesel engine, hydrostatic drive, sprinkler system, operator's station, retractable transport wheels, and all necessary controls and accessories to make a complete, serviceable unit.

3.2 First article. When specified (see 6.2), the contractor shall furnish one complete roller for first article inspection and approval (see 4.2.1 and 6.4).

3.3 Standard commercial product. The roller shall, as a minimum, be in accordance with the requirements of this specification and shall be the manufacturer’s standard commercial product. Additional or better features which are not specifically prohibited by this specification, but which are a part of the manufacturer’s standard commercial product, shall be included in the roller being furnished. A standard commercial product is a product which has been sold or is being currently offered for sale on the commercial market through advertisements or manufacturer’s catalogs, or brochures, and represents the latest production model.

* 3.4 Materials. Materials used shall be free from defects which would adversely affect the performance or maintainability of individual components or of the overall assembly. Materials not specified herein shall be of the same quality used for the intended purpose in commercial practice. Unless otherwise specified herein, all equipment, material, and articles incorporated in the work covered by this specification are to be new and fabricated using materials produced from recovered materials to the maximum extent possible without jeopardizing the intended use. The term "recovered materials” means materials which have been collected or recovered from solid waste and reprocessed to become a source of raw materials, as opposed to virgin raw materials. Unless otherwise specified, none of the above shall be interpreted to mean that the use of used or rebuilt products are allowed under this specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:23Z
Check the source to verify that this is the current version before use.

3.5 Interchangeability. All units of the same classification furnished with similar options under a specific contract shall be identical to the extent necessary to insure interchangeability of component parts, assemblies, accessories, and spare parts.

3.6 Safety. All rotating or reciprocating parts, and all parts subject to high operational temperatures, that are of such a nature or so located as to be or become a hazard to the operating personnel, shall be insulated, enclosed, or guarded. to the extent necessary to eliminate the hazard. The roller shall comply with OSHA regulations in effect at time of manufacture. The roller shall be equipped with a horn, distinguishable from the surrounding noise level, operable from the operator's station.

3.7 Weight. The roller shall have a shipping (metal) weight of not less than 8,000 pounds. The operating weight of the roller, when filled with water ballast, shall be not less than 10,000 pounds.

* 3.8 Dimensions. The roller shall conform to the dimensional requirements specified in Table I.

TABLE I. Dimensions

	Inches
Steering roll diameter(minimum)	34"
Steering roll width(minimum)	40"
Compression roll diameter(minimum)	48"
Compression roll width(minimum)	42"
Turning radius(maximum, inside)	168"
Ground clearance(minimum)	12"

* 3.9 Performance. The fully ballasted roller shall have a maximum operating speed of not less than 5 miles per hour in both forward and reverse directions while traveling up or down a 7 percent grade at any elevation from sea level to 5,000 feet above sea level. The roller shall be capable of compacting hot and cold mixed asphaltic concrete to a smooth compacted surface. The roller shall be required to compact fine and coarse grained soil as classified in accordance with ASTM D2487 to a density of 90 percent standard proctor as determined in accordance with ASTM D1557. The roller shall withstand the strains imposed upon it without any damage or deformation when operating at maximum speeds and as specified herein.

3.10 Body and Frame. The body and frame shall be fabricated of structural steel sections or steel plates with members joined, using one of the arc-welding processes. In order to withstand the stresses imposed, and to prevent permanent deformation or damage to the roller, the frame shall be braced and reinforced wherever necessary.

Source: https://assist.dla.mil -- Downloaded: 202610-20T22:23Z
Check the source to verify that this is the current version before use.

* 3.11 Engine. The engine furnished shall be of the diesel type having horsepower, torque, and speed characteristics to meet satisfactorily all the roller performance requirements specified herein. The engine shall be capable of meeting the performance requirements using diesel fuel conforming to W-F-800. The diesel engine shall start within 5 minutes and be ready for full load operation within 15 minutes in any ambient temperature from +125 degrees F to -20 degrees F. Glow plugs or fluid priming system shall be provided. When a fluid priming system is furnished, it shall be of the measured shot type with a storage capacity of at least 12 fluid ounces. The engine shall be furnished complete with at least the following accessories:

a. An instrument panel complete with a lubricating oil pressure gage, a fuel level gage, a cooling liquid-temperature indicator, a battery charge and discharge rate indicator, and an hour meter.
b. A fuel tank with sufficient capacity for 8 hours normal operation.
c. A 12-volt or 24-volt electric cranking system.
d. Battery(s).
e. A charging alternator wish a capacity rating compatible to the system.
f. A cooling-liquid high temperature safety warning device.
g. A lubricating oil low pressure safety warning device.
h. An engine housing so designed as to facilitate the maintenance of the engine.

3.12 Hydrostatic Drive. The roller shall have a high pressure hydraulic system to transmit power smoothly to the drive roll. Direction of travel shall be controlled by the use of a single lever. Neutral position of the forward/reverse lever shall be identified by a detent position. Movement of the roller shall be in the same direction as the movement of the forward\reverse lever.

* 3.13 Roller Drums. Roller drums shall be fabricated of steel plates with seams and. heads joined using one of the arc-welding processes. Roller drum surfaces shall be smooth. The roller drums shall be watertight and have provisions for filling and draining water ballast. The roller drums shall be equipped with heavy-duty axles and anti-friction bearings with seals to prevent entry of water and dirt.

* 3.14 Scrapers. Roller drums shall have scrapers, located in the front and rear of each roller drum. All scrapers shall extend across the full width of each roller drum, and shall be capable of preventing the accumulation of material on the roller drums when the roller drum operates in either the forward or reverse direction.

* 3.15 Sprinkler system. Roller shall be equipped with a self-contained sprinkler system for wetting and cleaning of the rolls. Sprinkler system shall consist essentially of a water tank, lines, cocoa mats, spray headers, and valves. Tanks shall have a capacity of not less than 100 gallons, a filler opening with cap having a diameter of not less than 1-1/2 inches, and a petcock for draining. Piping shall be rigidly affixed to the frame; flexible lines shall be supported at 2-foot intervals or less. Cocoa mats and spray headers shall be furnished on each roll and shall extend across the full width of each roll and shall completely wet the surface of the rolls. Individual regulating valves, located within easy reach of the operator, shall be

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:23Z
Check the source to verify that this is the current version before use.

provided for controlling the flow of water to each spray header. The complete system shall be assembled of rust proof materials.

3.16 Brakes. The hydrostatic drive shall provide dynamic braking during roller operation. A lever operated parking/emergency brake capable of holding the roller stationary on a 15 percent slope shall be provided.

3.17 Operator's platform and steps. An operator's platform with a removable operator's seat shall be provided. The seat shall be adjustable to either side of the operator's platform, and shall be located to permit operation of all controls from either seat position on the operator's platform. Dual seats, one on each side of the operator's platform, are acceptable. The seat shall be covered with a durable, waterproof covering. Steps and handholds shall be provided for access to the operator's platform. The operator's platform and steps shall be provided with an antiskid surface.

3.18 Controls. All controls necessary to operate the roller shall be provided and shall be located within reach of the operator from either seat position on the operator's platform. All controls, except brakes, shall be clearly identified for their intended operation and function with permanently-affixed identification plates made of corrosion-resistant material.

* 3.19 Steering. The roller shall have hydraulic power steering with steering wheel or lever type control.

3.20 Lighting system. A complete 12- or 24-volt lighting system as specified (see 6.2), shall be provided. The lighting system shall include at least the forward and two rearward directed sealed beam lights and two red lights at each end. Independent controls shall be provided for forward directed lights, rearward directed lights, front-mounted red lights, and rear-mounted red lights. Each control shall be clearly identified. Sealed beam floodlights shall conform to SAE J598 and shall be provided with lamp housings. Sealed beam lights shall be used to floodlight the work area and to permit safe travel at night. Panel lamps shall be provided on the instrument panel for night illumination of all instruments.

3.21 Retractable transport wheels. Hydraulically raised and lowered transport wheels shall be provided on the roller. The control lever shall be conveniently located at the operator's control station. Wheels and stub axles shall be easily removed to give maximum working clearance for the roller. Tire and wheel size shall conform to the tire and rim association (TRA) recommendation.

* 3.22 Towing tongue. A towing tongue shall be provided on the roller. The tongue shall be equipped with hydraulic devices to raise, lower and safely support roller during towed transport. The tongue shall be furnished with either a lunnette ring conforming to MS 51336 or a "U" shaped tongue with a material diameter and eye opening such that the "U" shaped tongue shall accommodate all hitches/couplers that would accept the MS 51336 lunnette ring.

3.23 Toolbox. Toolbox shall be provided to carry those tools and accessories required to operate the roller. Toolbox shall be constructed of sheet steel, shall have a hinged lid which shall open not less than 90 degrees,

Source: https://assist.dla.mil -- Downloaded: 202610-20T22:23Z
Check the source to verify that this is the current version before use.

and shall be equipped with a latching device of a type that shall keep the lid closed when the toolbox is subjected to vibration. The toolbox shall be securely fastened to the roller in a protected, but easily accessible location.

3.24 Lubrication. Means for lubrication shall be in accordance with the manufacturer's standard practice. The lubricating points shall be easily visible and accessible. Hydraulic lubrication fittings shall be in accordance with SAE J534. Where use of high pressure lubricating equipment, 1,000 pounds-force per square inch (psi) or higher, will damage grease seals or other parts, a suitable warning shall be affixed to the equipment in a conspicuous location.

3.25 Cleaning, treatment, and painting. Surfaces normally painted in good commercial practice shall be cleaned, treated, and painted as specified herein. Surfaces to be painted shall be cleaned and dried to insure that they are free from contaminants such as oil, grease, welding slag and spatter, loose mill scale, water, dirt, corrosion product, or any other contaminating substances. As soon as practicable after cleaning, and before any corrosion product or other contamination can result, the surfaces shall be prepared or treated to insure the adhesion of the coating system. The painting shall consist of at least one coat of primer and one finish coat. The primer shall be applied to a clean, dry surface as soon as practicable after cleaning and treating. Painting shall be with manufacturer's current materials according to manufacturer's current processes and the total dry film thickness shall be not less than 2.5 mils over the entire surface. The paint shall be free from runs, sags, orange peel, and other defects. Color of finish coat shall be as specified (see 6.2). The color shall conform to FED. STD. 595-Colors.

* 3.26 Identification plate. An identification plate will be furnished by the contracting officer for each roller. The contractor shall stamp all necessary data in the blank spaces of the plate provided for that purpose, and securely affix a plate to each roller in a conspicuous place with nonferrous screws, rivets, or bolts not less than l/8-inch in diameter. The applicable nomenclature contained in the contract item description shall be placed in the top blank. Point of contact for obtaining Navy Name Plates is: Naval Construction Battalion Center, Port Hueneme, CA 93043-5000 ATTN: CODE 15332, (805) 982-3297.

3.27 Workmanship.

3.27.1 Steel fabrication. The steel used in fabrication shall be free from kinks, sharp bends, and other conditions which would be deleterious to the finished product. Manufacturing processes shall not reduce the strength of the steel to a value less than intended by the design. Manufacturing processes shall be done neatly and accurately. All bends shall be made by controlled means to insure uniformity of size and shape.

3.27.2 Bolted connections. Bolt holes shall be accurately punched or drilled and shall have the burrs removed. Washers or lockwashers shall be provided in accordance with good commercial practice, and all bolts, nuts, and screws shall be tight.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:23Z
Check the source to verify that this is the current version before use.

3.27.3 Riveted connections. Rivet holes shall be accurately punched or drilled and shall have the burrs removed. Rivets shall be driven with pressure tools and shall completely fill the holes. Rivet heads, when not countersunk or flattened, shall be of approved shape and of uniform size for the same diameter of rivet. Rivet heads shall be full, neatly made, concentric with the rivet holes, and in full contact with the surface of the member.

3.27.4 Welding. Welding procedures shall be in accordance with a nationally recognized welding code. The surface of parts to be welded shall be free from rust, scale, paint, grease, or other foreign matter. Welds shall be of sufficient size and shape to develop the full strength of the parts connected by the welds. Welds shall transmit stress without permanent deformation or failure when the parts connected by the weld are subjected to proof and service loadings.

3.27.5 Castings. All castings shall be sound and free from patching, misplaced coring, warping, or any other defect which reduces the castings ability to perform its intended function.

4. QUALITY ASSURANCE PROVISIONS

* 4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and test) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this document where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

* 4.1.1 Responsibility for compliance. All items shall meet all requirements of sections 3 and 5. The inspection set forth in this document shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in this document shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, not does it commit the Government to accept defective material.

* 4.1.2 Component and material inspection. Components and materials shall be inspected in accordance with all the requirements specified herein and in applicable referenced documents.

* 4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.2.1).
b. Quality conformance inspection (see 4.2.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:23Z
Check the source to verify that this is the current version before use.

4.2.1 First article inspection. The first article inspection shall be performed on one roller when a first article is required (see 3.2 and 6.2). This inspection shall include the examination of 4.3, the tests of 4.4, and, when specified, the preproduction pack inspection of 4.6 (see 4.6 and 6.2). The first article may be either a first production item or a standard production item from the supplier's current inventory provided the item meets the requirements of the specification and is representative of the design, construction, and manufacturing technique applicable to the remaining items to be furnished under the contract.

4.2.2 Quality conformance inspection. The quality conformance inspection shall include the examination of 4.3, the tests of 4.5, and the packaging inspection of 4.6.

4.3 Examination. Each roller shall be examined for compliance with the requirements specified in section 3 of this specification. Any redesign or modification of the contractor's standard product to comply with specified requirements, or any necessary redesign or modification following failure to meet specified requirements shall receive particular attention for adequacy and suitability. This element of inspection shall encompass all visual examinations and dimensional measurements. Noncompliance with any specified requirements or presence of one or more defects preventing or lessening maximum efficiency shall constitute cause for rejection.

4.4 Tests. The first article roller shall be tested as specified in 4.4.1 through 4.4.2. Each production roller shall be subjected to the operational test of 4.5 to verify satisfactory performance and compliance with the requirements of this specification. Failure to pass one or more tests shall be cause for rejection.

4.4.1 Performance Test. The roller shall be weighed to determine conformance to 3.7. Operate the ballasted roller in both forward and reverse directions at maximum speed for not less than 4 hours up and down a 7-percent grade over a bituminous or asphalt road surface. Apply the parking brake with the engine running and the ballasted roller heading both up and down grade. Inability of the roller to operate as specified in 3.9, inability of the parking brake to hold the ballasted roller in a stopped position, malfunction of any control, or leakage of fuel, lubricants, coolants, or hydraulic fluid shall constitute failure of this test. Verify roller conformance to dimensions specified in Table I.

4.4.2 Compaction.

4.4.2.1 Asphalt. Roller shall compact either hot or cold mix asphaltic concrete. A test area having the minimum dimensions of not less than 7 feet by 15 feet shall be prepared. Area shall be paved with asphaltic concrete having a minimum thickness of not less than 3 inches. Roller shall make not more than five passes. The compacted asphalt shall be examined to determine conformance to the requirements of 3.9. Sprinkler system shall be operated during this test to prove compliance with the requirements of 3.15.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:23Z
Check the source to verify that this is the current version before use.

4.4.2.2 Soil. Roller shall compact both fine and coarse grained soils. Two test areas shall be prepared, each being not less than 7 feet by 30 feet. A single layer of soil at optimum moisture shall be spread over each area. Thickness of the fine grained soil shall be not less than 4 inches and not greater than 6 inches. Thickness of the coarse grained soil shall be not less than 6 inches and not greater than 8 inches. Roller shall nake not more than six passes over the fine grained soil and not more than four passes over the coarse grained soil. Each compacted soil shall be tested to ascertain compliance with the density requirements of 3.9. Scrapers shall be observed to determine conformance to 3.14.

4.5 Operational test. Each production roller shall be completely assembled, properly adjusted, and serviced for operation. Engine shall be started and subjected to a warmup period as recommended by the manufacturer. Roller shall be operated for not less than 30 minutes. Travel speed shall be determined, water tank filled and sprinkled system operated, and the transport mechanism(s) actuated to establish proof of compliance with 3.9, 3.15, and 3.21, respectively. All controls and switches shall be operated as many times as necessary to determine ease of operation, effectiveness, responsiveness, and that mechanisms actuated by the controls operate promptly, fully, and without restriction, malfunction, or excessive vibration. The power train, bearings, shafts, and other easily accessible moving parts shall be tactilely examined for excessive heating or abnormal operation insofar as is practicable. Failure to pass any phase of this test shall be cause for rejection.

4.6 Packaging inspection. The inspection of the preservation, packing, and marking shall be in accordance with the requirements of section 4 of MIL-R-3075. The inspection shall consist of the quality conformance inspection; and, when specified (see 6.2), a preproduction pack shall be furnished for examination and test within the time frame required (see 6.2).

5. PACKAGING

5.1 Preservation, packing, and marking. Presentation, packing, and marking shall be in accordance with the requirements of MIL-R-3075 with the level of preservation and the level of packing as specified (see 6.2).

6. NOTES

(This section contains information of general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The roller is intended for compaction of earth fill and bituminous road surfaces.

* 6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number, and date of this specification
b. Specifications, standards, and handbooks (see 2.1.1)
c. Issue of DODISS to be cited in the solicitation and, if required, the specific issue of the individual documents referenced (see 2.1.1).

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:23Z
Check the source to verify that this is the current version before use.

d. When first article is required for inspection and approval (see 3.2, 4.2.1, and 6.4)
e. Lighting system required (see 3.20)
f. Color of finish coat required (see 3.25)
g. When a preproduction pack inspection is required and time frame required for submittal (see 4.2.1 and 4.6)
h. Level of preservation and level of packing required (see 5.1)

6.3 First article. When a first article inspection is required (see 3.2 and 6.2), the item will be tested and should be a first production item or it may be a standard production item from the contractor's current inventory as specified in 4.2.1. The first article should consist of one unit, The contracting officer should include specific instructions in acquisition documents regarding arrangements for examination, test, and approval of the first article.

6.4 Pass. Driving the roller in one direction over the material being compacted, is defined as one pass. Driving the roller over the original path a second time in the same or opposite direction is defined as two passes.

* 6.5 Subject term (key word) listing.

Asphalt, compaction
Diesel, engine
Drive, hydrostatic
Drums
Pneumatic
Soil, compaction
Scraper

6.6 Changes from previous issue. The margins of this specification are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Goverment assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content.

Custodian:
Navy - YD

User activity:
Navy - MC

Preparing activity:
Navy - YD

(Project 3895-N315)

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:23Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER	2. DOCUMENT DATE *(YYMMDD)*
3. DOCUMENT TITLE		

4. NATURE OF CHANGE *(Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)*

5. REASON FOR RECOMMENDATION

6. SUBMITTER		
a. NAME *(Last, First, Middle Initial)*	b. ORGANIZATION	
c. ADDRESS *(Include Zip Code)*	d. TELEPHONE *(Include Area Code)* (1) Commercial (2) AUTOVON *(If applicable)*	7. DATE SUBMITTED *(YYMMDD)*

8. PREPARING ACTIVITY	
a. NAME	b. TELEPHONE *(Include Area Code)* (1) Commercial (2) AUTOVON
c. ADDRESS *(Include Zip Code)*	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:23Z
Check the source to verify that this is the current version before use.