MILITARY SPECIFICATION

CENTRAL MIXING PLANT, CONCRETE,

MOBILE, 250 CUBIC YARDS PER HOUR CAPACITY

This amendment forms a part of MIL-C-52600(ME) dated 12 February 1968.

Page 2

2.1, under SPECIFICATIONS, Military: Add
"MIL-L-2638 - Lacquer, Vinyl Resin, Gasoline and Water Resistant."

Page 7

2.2, under SOCIETY OF AUTOMOTIVE ENGINEERS, last line: Delete "485 Lexington Ave New York, N. Y. 10017" and substitute:"Two Pennsylvania Plaza, New York, N. Y. 10001."

Page 10

3.7.2: Add "Dissimilar metals are defined in MIL-T-704."

Page 13

Table II:
Line 4: Delete "18" and substitute "14".
Line 6: Delete "55,000" and substitute "65,000".
Line 10: After "Swing radius clearance" add "(SR, SAE J701)."
After line 10: Insert new line "Landing wheel clearance (LWC, SAE J701) 86 inches, min".

Page 15

After 3.9.13, add the following subparagraphs:

"3.9.13.1 Water supply unit. Unless otherwise specified, four water supply units shall be furnished with each plant. The water supply unit shall be mounted on a semitrailer and shall consist of a tank, gasoline-engine-driven pump, piping, and other components required for obtaining, transporting, storing, and delivering potable water to the plant water system for use during the manufacture of concrete.

"3.9.13.1.1 Tank. The tank shall have a single compartment with a capacity of 5,500 gallons plus 3 percent for expansion. The interior of the tank shall be clean and smooth to preclude any areas retaining water when the tank is drained. The tank shall be welded construction using high strength, low alloy

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:26Z
Check the source to verify that this is the current version before use.

steel sheets of not less than 12-gage (0.1046 inch) for the tank skin and baffles, and 10-gage (0.1345 inch) for the area above the fifth wheel plate. The tank shall have a round cross section, with a free draining straight bottom. External ring construction shall be provided. External rings shall be continuously welded to the exterior of the tank and secured to the full length frame. The tank shall be watertight and shall withstand an internal air pressure of 3 pounds per square inch (psi) without leaking.

"3.9.13.1.2 Manhole. The tank shall be fitted with a nominal 18-inch diameter steel manhole, manhole cover, and dust cover assembly. The assembly shall be welded to become an integral part of the tank and to effect a seal against moisture and dust penetration from external sources. The manhole cover and dust cover shall be hinged and welded to the manhole. The cover shall be provided with a locking device that effectively seals the cover. The device shall be secured with wingnut(s). The cover assembly shall be furnished with pressure vacuum vents to equalize internal and external air pressure during loading and unloading with cover assembly sealed. A single smooth, easily cleanable gasket, without seams or crevices, shall be utilized between the manhole and cover assembly. A lightweight, liquidtight, easy opening fill pipe, with corrosion-resistant external threads and corrosion-resistant security chain shall be furnished in the cover assembly. The fill pipe shall be provided with a removable sleeve screen. Fill pipe and screen shall permit flow of water at the rate of 250 gallons per minute (gpm). A corrosion-resistant warning plate shall be furnished at the fill opening and the discharge opening stating that the vents must be operable during loading and unloading operations.

"3.9.13.1.3 Baffles. Not less than three baffles shall be provided and shall be equally spaced in the linear dimension of the tank length. Baffles shall be flanged and dished or reinforced and shall have half-round drain openings at top and bottom of not less than 3-1/2-inch radius. Each baffle shall also be provided with a manhole opening, centrally located, not less than 18 inches in diameter.

"3.9.13.1.4 Skirting. Skirting down to the bottom of the frame rails of the semitrailer shall be provided the full length of the body on both sides. The top surface of skirting shall be reinforced and covered completely with 3/16-inch thick rubber or synthetic rubber blend ribbed material for use as a walkway.

"3.9.13.1.5 Catwalk and ladder. A catwalk, not less than 72 inches in length over the top of the tank shall be provided. The catwalk shall be of the grating type of construction and located on risers above the tank top. The catwalk shall be centrally located at the manhole. An access ladder or steps shall be provided for access to the top of the tank on curbside of vehicle at manhole location.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:26Z
Check the source to verify that this is the current version before use.

"3.9.13.1.6 Underslung cabinets. Underslung cabinets, constructed of steel not less than 16-gage (0.0598 inch) thickness, shall be provided on both sides of the semitrailer, approximately equal in size, and extending from the rear wheelhousing. Each cabinet shall be full flanged, flush-type construction. The right (curb) side cabinet shall house the manifold, pump, and pump engine. The left side cabinet shall be provided with two full-length, removable-type, metal shelves, not less than 12 inches wide. Wooden trays suitable for stowing strainers, couplings, and tools shall be provided. Doors shall be side hung and equipped with piano-type hinges. Cabinets shall have provisions for flushing, draining, and for ventilation through fixed louvers. The cabinets shall be stormproof. Cabinet doors shall be provided with check straps. The doors shall have latches and fittings for locking with a padlock.

"3.9.13.1.7 Hose tubes. Hose tubes of the dimensions required to stow the discharge hose shall be provided in the tank skirting. The hose tubes shall have drainage provisions and removable dusttight covers at both ends to facilitate cleaning. Theftproof locking devices shall be provided on each tube cover. Corrosion-resistant security chains shall be provided for dust-type covers and locking devices.

"3.9.13.1.8 Discharge hose and nozzle. Not less than 100 feet of 2-inch minimum inside diameter discharge hose, equipped with a delivery nozzle, shall be provided. Discharge hose shall be furnished in not more than six connecting units equipped with couplings and shall be stowed in hose tubes. The delivery nozzle shall be trigger-action operated and shall be equipped with a nominal 2-inch rigid spout.

"3.9.13.1.9 Pump. A centrifugal pump, having 2-inch minimum suction and discharge ports, shall be provided. The pump shall provide a flow rate of not less than 150 gpm at the discharge end of the delivery nozzle. The pump shall be driven by a direct-coupled air-cooled gasoline engine.

"3.9.13.1.10 Pump engine. The pump shall be powered by an industrial, air-cooled, 4 cycle gasoline engine. The engine shall be of a standard commercial design that has proven to be satisfactory in extensive use, and for which repair parts are readily available. The power and speed ratings of the engine shall be not less than the power and speed requirements of the pump.

"3.9.13.1.10.1 Engine accessories. The engine shall be furnished complete with all accessories required for operation, including a fuel tank of sufficient capacity for 4 hours of normal operation, a fuel line sediment bowl, a manual cranking system, and an externally adjustable governor capable of limiting the engine speed within the pump operating range.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:26Z
Check the source to verify that this is the current version before use.

"3.9.13.1.10.2 Engine mounting. The pump and engine shall be mounted on a common bedplate and the bedplate mounted on vibration-dampening pads. All controls shall be readily accessible to an operator standing on the ground by the semitrailer. Provisions for draining and filling crankcase, lubrication, adjustments, and cranking shall be readily accessible.

"3.9.13.1.10.3 Engine installation. The engine fuel tank shall be mounted outside the right side cabinet on the end wall, and provided with a recessed fill pipe and cap in the skirting. A spark-arresting muffler shall be mounted on the outside wall of the cabinet with the tailpipe pointing downward to the rear. The muffler and exhaust pipe shall be covered with a metal shield (bottom open) to guard against fuel drip from above. The exhaust pipe inside the cabinet shall be wrapped with asbestos. A fire partition shall be installed between the engine and the pump. Adequate ventilation shall be provided in the engine cabinet. This may include provision whereby the compartment doors must remain open when the engine is in operation, and instructions to this effect shall be provided.

"3.9.13.1.11 Piping and drainage. The piping system shall be not less than nominal 2-inch diameter tubing. Any portion of the discharge system, including the pump, which is not self-draining, shall be equipped with marked drain plugs located to assure complete removal of water.

"3.9.13.1.12 Tank outlet and valve. A manually operated tank outlet valve of flanged type and 2-inch diameter shall be provided for the compartment, attached to the flanged outlet welded to the bottom of the compartment. The outlet valve, when closed, shall effectively seal the compartment outlet, and shall be of a type permitting complete removal of the valve body. The outlet valve shall have a screen of the smallest possible mesh that will not restrict the flow of water through the discharge piping. The screen shall be readily removable from the exterior of the tank for cleaning purposes.

"3.9.13.1.13 Manifold. A manifold shall be provided, with manually operated valve and connection, for pressure discharge of the tank contents by use of the pump unit and hose assembly. The manifold shall be located in the right (curb) side underslung cabinet.

"3.9.13.1.14 Gage rod. One gage rod of stainless steel shall be furnished and shall be calibrated in increments of 25 gallons on three sides. The gage rod shall be stowed in the left side underslung cabinet."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:26Z
Check the source to verify that this is the current version before use.

Page 32

3.11.6.3, last line: Delete "or 3.11.6.3.4."

Page 33

3.11.6.3.4: Delete.

3.11.7.1, line 10: After "SAE J702", insert "and SAE J318,".

Page 35

3.11.9, line 1: Between "component" and "and" insert "semitrailer".

Page 38

3.12, end of sentence: Delete the period and add "or III C, as applicable."

Page 40

3.18, end of sentence: Delete the period and add "except that after cleaning, the interior surfaces of the water supply unit tank shall be coated with the 3-coat system of vinyl resin lacquer conforming to MIL-L-2638. The dry film thickness shall be not less than 1 mil for the type I coating, 2 mils for the type II coating, and 1 mil for the type III coating."

Page 46

Table VI, item 120: After "water system", add "and water supply unit." After "3.9.13", add "through 3.9.13.1.14."

Page 53

After 4.6.2.3.7, add the following subparagraph:

"4.6.2.3.7.1 Water supply units. The tank shall be completely filled. The pump shall be operated until the tank is approximately at 75 percent of rated capacity. The remaining water shall remain stored in the tank for 24 hours, then drained completely. Failure to obtain the gross tank capacity (including the allowance for expansion), to drain the tank completely, to obtain the specified discharge at the discharge nozzle, or evidence of structural failure or noticeable difference in the odor or taste between water entering the tank and water stored for 24 hours shall constitute failure of this test."

Page 63

6.2: Add

"(j) When other than four water supply units are required (see 3.9.13.1)."

Custodian:

Army - ME

Preparing activity:

Army - ME

Project No. 3895-A082

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:26Z
Check the source to verify that this is the current version before use.