MILITARY SPECIFICATION
CONVERTER, TELEPHONE SIGNAL CV-1548( )/G

This amendment forms a part of Military Specification MIL-C-55607A(EL), dated 30 September 1975, and is approved for use by the Communications-Electronics Command, Department of the Army and is available for use by all Departments and Agencies of the Department of Defense

PAGE 1

2.1: Delete "PPP-T-76" and "Tape, Pressure-Sensitive Adhesive Paper, Water Resistant (for Carton Sealing)".

PAGE 2

2.1: Delete title for Military Specification MIL-F-14072 and substitute "Finishes for Ground Electronic Equipment".

Add to Military Specifications "MIL-E-55585 Packaging of Electronic Equipment and Parts"

Add to Military Standards "MIL-STD-726 Packaging Requirements Codes"

PAGE 3

2.1: Delete "SM-B-528523" and "Converter, Telephone Signal, CV-1548A/G Test Requirement" and "SM-B-528731" AND "Power Supply 18A1A, Converter, Test Requirement" and substitute respectively "SM-B-528605" and "Converter, Telephone Signal CV-1548A/G Test Requirement" and "SM-B-528731" and "Power Supply 18A1( ), Converter, Test Requirement".

PAGE 4

3.7: Change "Printed Wiring....type ER(Epoxy)." To "Printed Wiring...type ER (Epoxy) or Type UR (Urthrene Resin)."

PAGE 5

3.8.4.1: Delete "16 Vrms" and substitute "19 Vrms".

PAGE 9

3.11.5.1: Delete title "Vibration (Internal)" and replace with "Vibration (Resonance Search).

FSC 5805

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:41Z
Check the source to verify that this is the current version before use.

3.13: Delete "SM-B-528523" and "18A1A" substitute respectively "SM-B-528605" and "18A1( )."
3.14: Delete title "Operation Inspection" and replace with "Operational Inspection".

3.15: Delete entire paragraph and substitute the following:

3.15: Workmanship: The equipment shall be manufactured and assembled in accordance with Requirement 9 of MIL-STD-454 and the applicable portion of the following:

(1) In MIL-P-11268:

(a) General requirements for plastic material and plastic parts.

(b) Wiring and cabling, including:

Slack
Protection
Splicing
Clearance
Connection, general
Grounding, general
Shielding on wire and cable
Flux and cleaning agent for soldering
General requirements for securing of parts
Cleaning prior to welding
Cleaning after welding
Soldering and brazing
Riveting
Process for welding
Self-tapping screws

(2) In subject specification:

(a) 3.2 Construction
(b) 3.3 Parts, Material and Processes, General
(c) 3.4 Finish
(d) 3.5 Marking
(e) 3.7 Printed Wiring Assemblies"

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:41Z
Check the source to verify that this is the current version before use.

PAGE 11

4.2a: Delete "preparation for delivery" and substitute "packaging."

4.2c: Delete in its entirety and substitute:

"c. Quality conformance inspection of equipment (see 4.5)."

Add new paragraph 4.2d as follows: "d. Packaging inspection (see 4.23)."

PAGE 12

TABLE I: Under Inspections column, delete "Moisture Resistance" and substitute "Humidity."

PAGE 13

4.5: Delete title and substitute "Quality Conformance Inspection of Equipment."

4.5.1: Delete in its entirety and substitute the following:

"4.5.1 Group A Inspection. Each unit on contract or purchase order, and each subassembly and assembly thereof identified in Table II (including spares), shall be inspected for conformance to the inspections specified in Table II.

The order of inspection of the subassemblies and assemblies and units (end equipient) shall be as follows:

a. Prior to their assembly into the end equipment, the assemblies and subassemblies identified in Table II shall be subjected to a 100% visual/mechanical and electrical inspection by the contractor for conformance with the inspection requirements provided in Table II.

b. After completion of the above 100% inspection by the contractor, discrete lots shall be formed from the subassemblies and assemblies which passed 100% inspection and these shall be subjected to sampling inspection by the contractor utilizing the procedures of MIL-STD-105 using general inspection levels and AQL's indicated in Table II (Quality Assurance Verification). Factors of lots composition not defined herein, or in the contract or purchase order, shall be in accordance with MIL-STD-105.

c. Assemblies from the discrete lots which have passed the above Quality Assurance Verification Inspection shall be assembled into the end equipments which shall then be subjected by the contractor to the preconditioning requirements of 3.10 and a 100% visual/mechanical and electrical inspection in accordance with Table II in an order satisfactory to the Government with the Operational Test performed last (See 6.5).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:41Z
Check the source to verify that this is the current version before use.

NOTE: Assemblies are not required to undergo further visual/mechanical and electrical inspection as part of the contractor's 100% Group A Inspection of the end equipment.

d. After completion of the above 100% inspection by the contractor, discrete lots shall be formed from units which passed the 100% inpsection and these shall be subjected to sampling inspection by the contractor utilizing the procedures of MIL-STD-105 using the general inspection levels and AQL's indicated in Table II. Group A electrical inspection of the end equipment shall be performed in accordance with Table II in an order satisfactory to the Government with the Operational Test Performed last (See 6.5)

NOTE: Assemblies and subassemblies are not required to undergo further visual/mechanical and electrical inspection as part of the above contractor's sampling inspection of the end equipment.

4.5.1.1: Delete in its entirety.

PAGE 14

TABLE: Delete and substitute the following:

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:41Z
Check the source to verify that this is the current version before use.

"TABLE II. GROUP A INSPECTION

Inspection	Req Para	Test Par	AQL Major	AQL Minor
Printed Circuit Boards				
Visual-Mechanical				
Case & Covers (Rear, Top and Front)	3.15	4.21	2.5	10.0*
Sub-Assemblies				
Power Supply (18A1( ))	3.15	4.21	1.0	4.0*
Tone Generator (18A2)	3.15	4.21	1.0	4.0*
Channel Unit (18A3B)	3.15	4.21	1.0	4.0*
Converter CV-1548, Final Assy	3.15	4.21	2.5	10.0*
Electrical				
Sub-Assemblies (Electrical Test)				
Power Supply (18A1( ))	3.13	4.10	1%	**
Tone Generator (18A2)	3.13	4.10	1%	**
Channel Unit (18A3B)	3.13	4.10	1%	**
Converter CV-1548	-	-	-	
20 Hz Generator				
Frequency Stability	3.8.2.1	4.8.5		
Power Output	3.8.2.2	4.8.5		
Circuit Protection	3.8.2.3	4.8.5		
1600 Hz Generator				
Frequency Stability	3.8.3.1	4.8.4		
Power Output	3.8.3.2	4.8.4		
20 Hz Detector				
20 Hz Sensitivity	3.8.4.1	4.8.2	1%	**
Circuit Protection	3.8.4.2	4.8.1	For the Group	
1600 Hz Receiver				
Receiving Sensitivity	3.8.5.1	4.8.3		
Frequency Selectivity	3.8.5.2	4.8.3		
Channel Frequency Response				
Four Wire-to-Two Wire Mode	3.8.8.1	4.8.9.1		
Four Wire-to-Four Wire Mode	3.8.8.2	4.8.9.2		
Operational	3.14	4.7	1%	**

*Defects per Hundred Units
**All electrical defects are major

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:41Z
Check the source to verify that this is the current version before use.

PAGE 16

TABLE III: Delete and substitute the following:

TABLE III. GROUP B INSPECTION

Inspection	Req Para	Test Para	AQL
Interchangeability	3.6	4.20	
Dimensional (subassemblies)	3.6	4.20.1	6.5%
Electrical (subassemblies)	3.6	4.20.2	6.5%
Electrical			
Harmonic Distortion	3.8.11	4.8.11	
1600 Hz Receiver			
Guard Circuit	3.8.5.3	4.8.6	
One Way Plug Supervision			
Operating	3.8.12.1	4.8.13a thru e	4.0% For the Group
Originate Current	3.8.12.2	4.8.13f	
Circuit Protection	3.8.12.4	4.8.1	
Idle Condition Two-Wire Termination	3.8.12.3	4.8.7.2	
Hybrid Loss Characteristics			
Transmission	3.8.7.1	4.8.7.1	
Transhybrid	3.8.7.2	4.8.7.2	
Longitudinal Balance	3.8.6	4.8.8	
Signal to Crosstalk Plus Noise	3.8.9	4.8.10	6.5% For the Group
Impedance	3.8.10	4.8.12	
Interface Compatibility	3.9	4.8.14	

PAGE 17

TABLE IV: Under Inspection Column, Sub-Group 1, delete "Moisture Resistance (Humidity)" and substitute "Humidity". Under Inspection Column, Sub-Group 3, delete "Elevation" and substitute "Altitude (Elevation)".

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:41Z
Check the source to verify that this is the current version before use.

PAGE 18

4.6: Delete in its entirety and substitute the following:

"4.6 Preconditioning (See 3.10). Each assembled CV-1548( )/G shall be Bounce Preconditioned and then Electrically Preconditioned (including spare panels and power supplies), prior to submission for Group A, B and C tests."

PAGE 22

*4.8.2b: Delete "16.0 Vrms" and substitute "19.0 Vrms.".

PAGE 30

4.13: Delete title "Low Pressure (Altitude)" and replace with "Altitude (Elevation)"

4.14: Delete title "Rain Test" and replace with "Rain"

PAGE 31

4.15: Delete title "Vibration (Internal)" and replace with "Vibration (Resonance Search)"

PAGE 33

4.20.2: Delete "18A1A" and substitute "18A1( )."

4.21: Delete "3.3 and ".

PAGE 34

4.23: Delete in its entirety and substitute:

"4.23: Packaging inspection. Packaging inspection requirements specified herein are classified as follows:

a. First Article Inspection of Packaging

b. Quality Conformance Inspection of Packaging

4.23.1: First Article Inspection of Packaging. Unless otherwise specified in the contract, First Article Inspection of Packaging shall be in accordance with the Unit Pack Design Validation Requirements of MIL-P-116.

4.23.2 Quality Conformance Inspection of Packaging.

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:41Z
Check the source to verify that this is the currentversion before use.

4.23.2.1 Materials Inspection. All materials to be used in packaging shall be inspected in accordance with the applicable material specification.

4.23.2.2 Preservation Inspection. Inspection of preservation and interior markings shall be in accordance with Group A and B Quality Conformance Inspection Requirements of MIL-P-116. Lot formation and sampling procedures shall be as specified therein.

4.23.2.3 Packing Inspection. Inspection of packing and the marking for shipment and storage shall consist of the examinations specified in Table V "PACKING INSPECTION PROVISIONS." Lot formation shall consist of all packs made of the same materials during an identifiable period and submitted at one time for acceptance. Sampling procedures shall be in accordance with MIL-STD-105, using a single sampling plan and Acceptable Quality Level of 4.0 percent defective."

PAGE 35

"TABLE V.

PACKING INSPECTION PROVISION

NO.	CHARACTERISTIC	METHOD OF INSPEC.
101	Intermediate container not as specified	Visual
102	Improper closure of intermediate container	Visual
103	Shipping containers not in accordance with specification	Visual
104	Excessive cube	Visual
105	Improper blocking and bracing	Visual
106	Closure not in accordance with specification	Visual
107	Weight and size exceed container limitations	Weight & Measure
108	Strapping not in accordance with specification, incorrectly applied, omitted	Visual
109	Marking omitted, incorrect, or illegible	Visual

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:41Z
Check the source to verify that this is the current version before use.

5. Delete in its entirety and substitute:

"5. PACKAGING.

5.1 Preservation. Preservation shall be as specified in MIL-STD-726, coded as follows:

5.1.1 Level A. JR-1-1-ØØ-00-NS-X-ED-Ø-00-A.

5.1.2 Level B. JR-1-1-ØØ-00-NS-X-ED-Ø-00-B.

5.2 Packing and marking Packing and marking shall be in accordance with MIL-E-55585."

Delete "6.2b" and "6.2c" in its entirety and substitute:

"6.2b: Level A or B preservation and packing (see section 5)."

"6.2c: When first article inspection rough handling tests are not required."

Add new paragraph 6.2i as follow:

"When first article packaging inspection test reports require Acquisition Activity approval prior to production unit packing."

Add new paragraph 6.8 and 6.9 as follows:

"6.8 Environmental. Environmental pollution prevention measures are contained in the packaging material specifications referenced herein. Refer to material specifications or preparing activity for recommended disposability methods."

"6.9 Level B Preservation. When Level B preservation is specified, this level of protection will only be used under known favorable conditions during transportation, storage and handling.

PAGE 52

Figure 13: The transmission measuring set is identified as a "Daven 12B".

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:41Z
Check the source to verify that this is the currentversion before use.

PAGE 53

Figure 14: The transmission measuring set is identified as a "Daven 12B."

PAGE 54

Figure 15: The transmission measuring set is identified as a "Daven 12B".

The margins of this amendment are marked with an asterisk or vertical lines to indicate where changes (additions, modifications, corrections, deletions) from the previous amendment were made. This was done as a convenience only, and the government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous amendment.

CUSTODIAN:
ARMY-CR

PREPARING ACTIVITY:
ARMY-CR

(Project 5805-A256)

* U.S. GOVERNMENT PRINTING OFFICE: 1983—705—040/A329

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:41Z
Check the source to verify that this is the current version before use.