MILITARY SPECIFICATION

BOMB, GENERAL PURPOSE, MARK 84, 2000 POUND,
EXPLOSIVE LOADING, ASSEMBLING, AND PACKING

This amendment forms a part of
Military Specification MIL-B-82572
dated 28 February 1969, and is
mandatory for use by all Departments and
Agencies of the Department of Defense.

Page 2

2.1 Delete

"MIL-STD-1314 Safety Precautions for Explosive Loaded Items"

Page 2

2.1 Add

"MANUALS

Department of Defense

4145.26M DOD Contractor's Safety Manual for Ammunition Explosives and Related Dangerous Material"

Page 3

3.5, delete and substitute:

"3.5 Weight of applied asphaltic compound - The total weight of the asphaltic compound on the interior surfaces of the bomb assembly shall be 20.0 ± 4.0 pounds when tested in accordance with 4.4 and 4.6.1."

3.6, add

" (c) No shrinkage cavity is located less than 1.5 inches from the suspension lug area."

Page 4

4.4, delete and substitute:

"4.4. Quality conformance inspection - Each inspection lot shall be sampled in accordance with MIL-STD-105 and 4.5.2. Samples shall be

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:15Z
Check the source to verify that this is the current version before use.

subjected to examination of all the characteristics listed on drawing 1380911 and examination of characteristics listed in 4.5.3. Upon approval of the first article samples, the asphaltic compound weight and radiographic examinations tests as specified in 4.6 shall be conducted as quality conformance tests only in accordance with the following procedure: A minimum of one bomb per week per fill house shall be selected at random and tested as specified in 4.6 for conformance to the requirements of 3.5 and 3.6. If a bomb fails to meet either requirement, the loading line responsible for the failure shall be requalified in accordance with 4.3.1. The asphaltic compound weight and radiographic examination quality conformance tests specified herein shall not be resumed for the loading line until requalification testing provides evidence that control of the asphaltic compound weight and explosive shrinkage cavities have been achieved. Any bomb failing either requirement 3.5 or 3.6 shall be rejected."

Page 6

4.5.5, add

"4.5.5.1. Inspection equipment data. - Inspection equipment lists and detailed drawings for "Supplier Design" inspection equipment shall be prepared and delivered as specified in the contract or purchase order (see 6.3)".

Page 7

4.6.1, delete and substitute:

"4.6.1. Weight of applied asphaltic compound - Prior to application of the asphaltic compound, each bomb selected in accordance with 4.4 shall be weighed with an accuracy of plus or minus 1.0 pound. Record this weight as We. The application of the compound shall be in accordance with drawing 1380911. After all excess compound has been removed, weigh the bomb and record this weight as Wm. The weight of the applied asphaltic compound shall be calculated as the difference in weight, Wm-We, and checked for conformance to the requirements of 3.5."

Page 8

6.1, delete and substitute:

"6.1. Ordering data - Procurement documents should specify the following:

6.1.1 Procurement requirements

(a) Title, number and date of this specification

(b) Explosive composition required (see 3.4 through 3.4.2)

(c) Quantity of bombs

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:15Z
Check the source to verify that this is the current version before use.

(d) When lot size requirements are necessary other than specified (see 4.5.1)

(e) Level of packing and delivery

6.1.2 Contract data requirements. Items of deliverable data required by this specification are cited in the following paragraphs herein:

Paragraph	Data Requirements	Applicable DIDs
4.5.5.1	Inspection equipment data	-
5.3.1	Ammunition data cards	DI-E-2001

DIDs (Data Item Descriptions/DD Forms 1664) for the above data requirements will be documented in the applicable ADL (Authorized Data List).

Such data will be delivered as identified on completed (numbered) DIDs when specified on DD Forms 1423 (Contract Data Requirements Lists) and incorporated into applicable contracts.

6.1.3 Contracts or orders should specify the following provisions for first article inspection.

6.1.3.1 Whether first article inspection is required - When a contractor is in continuous production form contract to contract, consideration should be given to waive the first article inspection. If the first article inspection is required, indicate:

(a) Where the first article inspection is to be conducted the supplier's or Government plant)

(b) That approval of first article samples or the waiving of the first article inspection shall not relieve the supplier of his obligation to fulfill all the other requirements of this specification and contract."

Page 8

6.2 Delete and substitute:

"6.2 Safety Precautions - The supplier shall observe the safety precautions of DOD 4145.26M, as applicable."

Page 9

6.3.1 Delete reference to MIL-D-45608 and substitute MIL-D-1000.

Preparing Activity:
Navy - OS
(Project No. 1325-0157)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:15Z
Check the source to verify that this is the current version before use.