INCH-POUND

MIL-R-53127(ME)
1 April 1992

MILITARY SPECIFICATION

RAKE, MINE CLEARING

This specification is approved for use within the USA Belvoir Research, Development and Engineering Center, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a rake used to clear antitank mines.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. The following specifications and standards form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents shall be those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research, Development, and Engineering Center, ATTN: STRBE-TSE, Fort Belvoir, VA 22060-5606 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 2590

DISTRIBUTION STATEMENT A. Approved for public release, distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:10Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

PPP-T-60 - Tape: Packaging, Waterproof.

MILITARY

MIL-C-104 - Crates, Wood: Lumber and Plywood Sheathed, Nailed and Bolted.
MIL-P-116 - Preservation, Methods of.
MIL-B-121 - Barrier Material, Greaseproofed, Waterproofed, Flexible.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Tables and Procedures for Inspection by Attributes.
MIL-STD-129 - Marking for Shipment and Storage.
MIL-STD-209 - Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment.
MIL-STD-280 - Definitions of Item Levels, Item Exchangeability, Models, and Related Terms.
MIL-STD-810 - Environmental Test Methods and Engineering Guidelines.
MIL-STD-889 - Dissimilar Metals.
MIL-STD-1791 - Designing for Internal Aerial Delivery in Fixed Wing Aircraft.

(Unless otherwise indicated, copies of Federal and military specifications, standards, and handbooks are available from the Standardization Documents Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those in the solicitation.

DRAWINGS

ME

TA13227E0200 - Cleared Lane Marking System (CLAMS).
TA13229E9200 - Rake, Mine Clearing.
13229E9196 - Packaging Requirements, Mine Clearing Rake.
13229E9197 - Accessory Box, Mine Clearing Rake.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:10Z
Check the source to verify that this is the current version before use.

(Copies of drawings required by contractors in connection with specific acquisition functions should be obtained from the USA Belvoir Research, Development, and Engineering Center, ATTN: STRBE-NDM, Fort Belvoir, VA 22060-5606.)

2.2 Non-Government publications. The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Qualification Standard for Welding and Brazing Procedures, Welders, Brazers, and Welding and Brazing Operators.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

AMERICAN WELDING SOCIETY (AWS)

D1.1 - Structural Welding Code - Steel.

(Application for copies should be addressed to the American Welding Society, 550 N.W. LeJeune Road, P.O. Box 351040, Miami, FL 33135.)

ASSOCIATION OF AMERICAN RAILROADS (AAR)

Section 6 - Rules Governing the Loading of Commodities on Open-Top Cars.

(Application for copies should be addressed to the Association of American Railroads, American Railroads Building, 50 F Street, NW, Suite 7702, Washington, DC 20001.)

(Non-Government standards and other publications are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other information services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:10Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Description. The rake shall be in accordance with TA13229E9200 and as specified herein.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviations from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operating of the item. Any data (e.g., shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or the designated representative.

3.2 First article. Unless otherwise specified (see 6.2), a sample shall be subjected to first article inspection (see 6.3) in accordance with 4.3.

3.3 Materials. The materials shall be as specified herein and on the drawing. Materials not specified shall be selected by the contractor and shall be subjected to all provisions of the specification.

3.3.1 Material deterioration prevention and control. The rake shall be fabricated from compatible materials, inherently corrosion resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable operating and storage environments to which the item may be exposed.

3.3.1.1 Dissimilar metals. Dissimilar metals shall not be used in intimate contact with each other unless protected against galvanic corrosion. Dissimilar metals and methods of protection are defined and detailed in MIL-STD-889.

3.3.1.2 Identification of materials and finishes. The contractor shall identify the specific material, material finish, or treatment for use with component and subcomponent and shall make information available upon request to the contracting officer or designated representative.

3.3.2 Recovered materials. For the purpose of this requirement, recovered materials are those materials which have been collected from solid waste and reprocessed to become a source of raw materials, as distinguished from virgin raw materials. The components, pieces, and parts incorporated in the rake may be newly fabricated from recovered materials to the maximum extent practicable, provided the rake

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:10Z
Check the source to verify that this is the current version before use.

produced meets all other requirements of this specification. Used, rebuilt, or remanufactured components, pieces, and parts shall not be incorporated in the rake.

3.4 Design and construction. The rake shall conform to the parts inventory list of TA13227E0200.

3.4.1 Interchangeability. Like units shall be fabricated to be duplicates within the tolerances specified and shall be interchangeable in accordance with MIL-STD-280.

3.5 Material protection. Material protection (treatment and painting, plating, and coating) for the components of the rake shall be as specified in the applicable drawing.

3.6 Identification marking. Identification marking shall be as specified in the applicable drawing.

3.7 Safety. Nonfunctional sharp edges, projecting points, and excessive length of fastening device shall be avoided.

3.8 Workmanship.

3.8.1 Bolted connections. Bolt holes shall be accurately formed and shall have the burrs removed. Washers or lockwashers shall be provided where necessary. Matching thread areas securing bolts or capscrews shall be of sufficient strength to withstand the tensile strength of the bolt. All fasteners shall be correctly torqued and shall have full thread engagement.

3.8.2 Machine work. Tolerances and gages for metal fits shall conform to the limitations specified herein and on the applicable drawings. Tolerances for positioning of holes and parts shall be referenced from one end or side of the member and shall not be cumulative.

3.8.3 Steel fabrication. Steel used in the fabrication of the rake shall be free from laminations, kinks, and sharp bends. Steel shall be cut by shearing, sawing, or flame cutting. Burned surfaces of flame-cut material shall be ground or machined to remove ash and cooling checks. The straightening of material shall be done by methods that will not cause injury to the metal. Precautions shall be taken to avoid overheating and heated metal shall be allowed to cool slowly.

3.8.4 Welders and welding.

3.8.4.1 Welders or welding operator. Before assigning any welder or welding operator to manual welding work covered by this specification, the contractor shall obtain certification that the

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:10Z
Check the source to verify that this is the current version before use.

welder or welding operator has passed qualification tests as prescribed by either AWS D1.1 or the ASME code for the materials joined and the type of welding operation to be performed and that such qualification is effective as defined. Contractors who only make horizontal welds need not qualify welders for "all position welding." The contractor is responsible for determining that automatic welding equipment operators are capable of producing quality welds in accordance with AWS and ASME codes. In the event of evidence of poor welds, the Government reserves the right to require retesting of any welder or welding operator (see 6.6).

3.8.4.2 Welding. The surfaces of parts to be welded shall be free from dirt, scale paint, grease, and other foreign matter. Welding shall be done by the shielded metal-arc (SMA) or gas metal-arc (GMA) processes. All welded parts shall be free from slag, flux, cracks, and other imperfections that may reduce the effectiveness of the part. Work shall be positioned for flat welding when practicable. Before welding over previously deposited weld metal, all traces of slag shall be removed and the deposit and adjoining base metal shall be wire brushed clean. Welding and welds shall be in accordance with either ASME or AWS code.

3.8.4.2.1 Welding jigs. Steel jigs or frames may be used in assembling parts to be welded to prevent distortion and hold the parts in their proper position during welding or stress relieving.

3.9 Transportability. The mine clearing rake shall be capable of being transported by military of commercial trailers, trains, aircraft and must be capable of withstanding the impact forces encountered in shipment, without damage or permanent deformation (see 6.2 and 6.6). The mine clearing rake shall be equipped with tiedown or slinging provisions.

3.9.1 Tiedown provisions. The tiedown provisions shall conform to MIL-STD-209, class 2 or 3, type II equipment, and to MIL-STD-1791 for equipment restraint criteria. The tiedown provisions shall satisfactorily complete the pull testing as specified without weld failure, permanent deformation, cracking, loosening, or breaking of the provision or its connecting structural components.

3.9.2 Slinging provisions. The slinging provisions shall conform to MIL-STD-209, class 1 or 3, type II. The provisions shall enable the complete mine clearing rake to be lifted in the normal operating position. The provisions shall be located so that not less than one-inch clearance is maintained between slings and all exterior parts and shall be fastened to members which will withstand stresses in the amount and direction of pull specified for the provisions without weld failure, permanent deformation, cracking, loosening, or breaking of the provision or its connecting structural components. Slinging provisions may also be used as tiedown provisions when such provisions

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:10Z
Check the source to verify that this is the current version before use.

meet the requirements specified in 3.9.1. All slinging/tiedown provisions shall be labeled "LIFT", "TIEDOWN," or "LIFT TIEDOWN," as appropriate, in 1-inch (2.54 cm) high letters.

3.9.3 Air transportability. The mine clearing rake shall meet the requirements of MIL-STD-1791 for air transport.

3.9.4 Rail transportability. The mine clearing rake shall be rail transportable in CONUS and NATO countries without restrictions. The mine clearing rake shall have a dimensional profile within the Gabarit International de Chargement (GIC) outline diagram, in accordance with AAR outline diagram, when loaded on a 50-inch (127 cm) high rail car. The mine clearing rake shall be capable of withstanding shock loads resulting from rail impact testing in accordance with 4.6.2.6 without failure, damage, or permanent deformation.

3.9.5 Highway transportability. The mine clearing rake, when loaded on a semitrailer/tractor, shall be within the highway permit limits of all states.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items shall meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to accept defective material.

4.1.2 Component and material inspection. The contractor is responsible for ensuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards, as applicable.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:10Z
Check the source to verify that this is the current version before use.

4.2 Classification of inspection. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Inspection comparison (see 4.5).
d. Inspection of packaging (see 4.7).

4.3 First article inspection. The first article inspection shall be performed on one complete rake (see 3.2 and 6.3).

4.3.1 Examination. The first article shall be examined as specified in 4.6.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Tests. The first article shall be tested as specified in 4.6.2. Failure of any test shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for inspection shall be in accordance with MIL-STD-105. Sample size shall be determined by using MIL-STD-105, table I and table IIa. A lot shall be accepted when 0 defects are found and rejected when 1 or more defects are found.

4.4.2 Examination. Samples selected in accordance with 4.4.1 shall be examined as specified in 4.6.1. Presence of one or more defects shall be cause for rejection.

4.4.3 Tests. Samples selected in accordance with 4.4.1 shall be tested as specified in 4.6.2. Failure of any test shall be cause for rejection.

4.5 Inspection comparison. The Government may select rakes at any time during the contract production period and subject these rakes to the examination specified in 4.6.1 and tests specified in 4.6.2. The inspection will be performed by the Government, at a site selected by the Government, on rakes selected at random from those which have been accepted by the Government and will not include the previously inspected first article rake. In addition to any test specified as part of the inspection comparison, the Government reserves the right to conduct any and all other tests contained in this specification as part of the inspection comparison and failure of such additional tests shall have the same effects as failure of those tests specified as inspection comparison.

4.5.1 Inspection failure. Failure of an inspection comparison rake to meet any requirement specified herein during and as a result of the examination specified in 4.6.1 and tests specified in 4.6.2, shall be cause for rejection of the inspection comparison rake and shall be

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:10Z
Check the source to verify that this is the current version before use.

cause for refusal by the Government to continue acceptance of production rakes until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on rakes previously accepted and produced under the contract. Any deficiencies found as a result of the inspection comparison will be considered prima facie evidence that all rakes accepted prior to the completion of the inspection comparison are similarly deficient, unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.6 Inspection procedure.

4.6.1 Examination. The rake shall be examined as specified herein for the following defects:

101. Dimensions not as specified (see 3.1).
102. Materials not as specified (see 3.3).
103. Materials not resistant to corrosion and deterioration, or treated to be resistant to corrosion and deterioration for the applicable storage and operating environments as specified (see 3.3.1).
104. Dissimilar metals as defined in MIL-STD-889 are not effectively insulated from each other as specified (see 3.3.1.1).
105. Used, rebuilt, or remanufactured components, pieces, and parts incorporated in the rake (see 3.3.2).
106. Material protection not as specified (see 3.5).
107. Identification marking not as specified (see 3.6).
108. Safety not as specified (see 3.7).
109. Workmanship not as specified (see 3.8).
110. Welders and welding operators not certified as specified (see 3.8.4.1).
111. Welding not as specified (see 3.8.4.2).
112. Transportability provisions not as specified (see 3.9 - 3.9.5).

4.6.2 Tests.

4.6.2.1 Installation. The mine clearing rake shall be mounted on an M728 Combat Engineer Vehicle using four personnel within one hour. The rake will be installed using tools provided as Basic Issue Items for the Combat Engineer Vehicle plus the tools supplied with the rake. The mine clearing rake shall be removed and remounted at least twice by normal removal (opposite of installation) and twice by emergency (quick disconnect) removal. During the mounting and removal of the mine clearing rake, the operation shall be observed and any interference of the parts noted. Failure of the rake to be mounted to or removed from the moldboard shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:10Z
Check the source to verify that this is the current version before use.

4.6.2.2 Operational. Following installation of the mine clearing rake (see 4.6.2.1), an operational mission test shall be conducted consisting of 5 miles of level cross-country roadability test followed by a - 500 meter raking operation in sandy or loose soil. Following the operational test, the mine clearing rake shall be removed and remounted at least twice each by normal removal and emergency removal. During the mounting and removal of the mine clearing rake, the operation shall be observed and any interference of parts noted. The rake shall also be checked for the following defects: broken welds, straightness of teeth, loose nuts and bolts, turnbuckle adjustments, and damage to the skid shoe or the skid shoe support beam. Presence of one or more defects shall be cause for rejection.

4.6.2.3 Tiedown provisions test. The tiedown provisions shall be tested in accordance with MIL-STD-209 to prove conformance to 3.9.1. Inability to meet the requirements of 3.9.1 shall constitute failure of this demonstration.

4.6.2.4 Slinging provisions test. The slinging provisions shall be tested in accordance with MIL-STD-209 to prove conformance to 3.9.2. Inability to meet the requirements of 3.9.2 shall constitute failure of this demonstration.

4.6.2.5 Air transport test. The mine clearing rake shall be tested in accordance with MIL-STD-1791 to prove conformance to 3.9.3. Inability to meet the requirements of 3.9.3 shall constitute failure of this demonstration.

4.6.2.6 Rail impact test. The first article mine clearing rake shall be tested in accordance with MIL-STD-810 to prove conformance to 3.9.4. Inability to meet the requirements of 3.9.4 shall constitute failure of this demonstration.

4.6.2.7 Highway transport test. The mine clearing rake shall be tested to conform to the requirements of 3.9.5. Nonconformance to 3.9.5 shall constitute failure of this demonstration.

4.7 Inspection of packaging.

4.7.1 First article pack inspection. The first article pack shall be examined for the defects listed in 4.7.2.3. Presence of one or more defects shall be cause for rejection.

4.7.2 Quality conformance inspection of pack.

4.7.2.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:10Z
Check the source to verify that this is the current version before use.

4.7.2.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.7.2.3 Examination. Samples selected in accordance with 4.7.2.2 shall be examined for the following defects. One or more defects shall be cause for rejection.

113. Preservation not as specified for level A or C (see 5.2.1 and 5.2.2).
114. Packing not as specified for level A or C (see 5.3.1 and 5.3.2).
115. Shipping containers not as specified for level A (see 5.3.1).
116. Marking incorrect, illegible, or missing for level A or C (see 5.4).

5. PACKAGING

5.1 First article pack. The contractor shall furnish a first article pack for examination within the time frame specified (see 6.2), to prove, prior to starting production packaging, that the applied preservation, packing, and marking comply with the packaging requirements of this specification. Examination shall be as specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.4). The first article pack may be prepared utilizing either the first article model or a production mine clearing rake. When the first article model is utilized, any preservation and packing shall be removed by the contractor at no expense to the Government, when requested by the Government to facilitate comparison between the first article model and production mine clearing rake.

5.2 Preservation. Preservation shall be level A or C (see 6.2).

5.2.1 Level A. Unpainted or otherwise unprotected surfaces of the mine clearing rake and accessory equipment susceptible to corrosion shall be coated with a preservative in accordance with MIL-P-116. When removal of the preservative can be accomplished without damage to the item or where removal of the preservative is not required, these surfaces shall be coated with P-1 preservative. Surfaces not suitable for coating with P-1 preservative and all machined surfaces shall be coated with P-11 preservative. Machine surfaces shall be wrapped with a barrier material conforming to MIL-B-121, grade A, and secured with tape conforming to PPP-T-60, type IV.

5.2.2 Level C. The mine clearing rake and accessory equipment shall be preserved in accordance with MIL-P-116, method III.

5.3 Packing. Packing shall be level A or C (see 6.2).

5.3.1 Level A. The mine clearing rake and accessory equipment, preserved as specified in 5.2, shall be packed in one or more crates

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:10Z
Check the source to verify that this is the current version before use.

conforming to MIL-C-104, type II, class 2, style a, as shown by the drawing 13229E9196. The exterior size of any crate shall not exceed 16 feet (4.87 m) long by 8 feet (2.43 m) wide by 4.54 feet (1.38 m) high. The accessory equipment shall be packed in an accessory box as shown by drawing 13229E9197.

5.3.2 Level C. The mine clearing rake and all its components, preserved as specified in 5.2, shall be packed in a manner to protect against deterioration and damage from handling and shipment from the contractor to the initial destination.

5.4 Marking. In addition to any special marking specified in the contract or purchase order (see 6.2), marking shall be in accordance with MIL-STD-129.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The mine clearing rake is a bolt-on attachment to the Combat Engineer Vehicle, M728. It is designed to clear both surface-laid and buried antitank mines.

6.2 Acquisition requirements. Acquisition documents must specify the following:

a. Title, number, and date of the specification.
b. Issue of DODISS to be cited in the solicitation and, if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
c. When a first article is required for inspection and approval and the number of units required (see 3.2, 4.3, and 6.3).
d. When data is required for air transportability (see 3.9.3).
e. Time frame required for submission of the first article pack (see 5.1).
f. Level of preservation and level of packing required (see 5.2 and 5.3).
g. Any special marking required (see 5.4).
h. When a transportability report is required (see 6.5).

6.3 First article. When a first article inspection is required, the item(s) should be a preproduction model. The first article should consist of one or more units. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, approval of the first article test results, and disposition of the first articles. Invitation for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:10Z
Check the source to verify that this is the current version before use.

and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract. Bidders should not submit alternate bids unless specifically requested to do so in the solicitation.

6.4 First article pack. Any changes or deviations of production packs from the approved first article pack will be subject to the approval of the contracting officer. Approval of the first article pack will not relieve the contractor of his obligation to preserve, pack, and mark the mine clearing rakes in accordance with this specification.

6.5 Consideration of data requirements. The following data requirements should be considered when this specification is applied on a contract. The applicable Data Item Descriptions (DIDs) should be reviewed in conjunction with the specific acquisition to ensure that only essential data are requested/provided and that the DIDs are tailored to reflect the requirements of the specific acquisition. To ensure correct contractural application of the data requirements, a Contract Data Requirements List (DD Form 1423) must be prepared to obtain the data, except where DoD FAR Supplement 27.475-1 exempts the requirement for a DD Form 1423.

Reference Paragraph	DID Number	DID Title	Suggested Tailoring
3.8.4.1	DI-MISC-80876	Welding Procedure Qualification Test Report	
3.9	DI-PACK-80880	Transportability Report	

The above DIDs were those cleared as of the date of this specification. The current issue of DoD 5010.12-L, Acquisition Management Systems and Data Requirements Control List (AMSDL), must be researched to ensure that only current, cleared DIDs are cited on the DD Form 1423.

6.6 Subject term (key word) listing.

MCR
Plow, mine clearing
Rake, mine clearing

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 2590-A022

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:10Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER MIL-R-53127(ME)	2. DOCUMENT DATE (YYMMDD) 920401

3. DOCUMENT TITLE
Rake, Mine Clearing

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (if applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME Gerry Harlow	b. TELEPHONE (Include Area Code) (1) Commercial (703) 704-3469 (2) AUTOVON 654-3469
c. ADDRESS (Include Zip Code US Army Belvoir RDE Center ATTN: STRBE-TSE Fort Belvoir, VA 22060-5606	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340

DD Form 1426, OCT 89 Previous editions are obsolete

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:10Z
Check the source to verify that this is the current version before use.