MILITARY SPECIFICATION

TENT, PYRAMIDAL, SURVIVAL, 3-4 MAN, SRU-1/P

1. SCOPE

1.1 This specification covers a three to four man pole supported four sided pyramidal tent with a tunnel type entrance.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of the specification to the extent specified herein.

SPECIFICATIONS

Federal

V-T-295	Thread, Nylon
KK-L-162	Leather, Cattlehide, Chrome Tanned For Gloves, Garments And Equipage
TT-I-542	Ink, Marking, Laundry, Black
QQ-C-390	Copper Alloy Castings (Including Cast Bar)
QQ-P-416	Plating, Cadmium (Electrodeposited)
CCC-C-429	Cloth, Osnaburg, Cotton
CCC-C-467	Cloth, Burlap, Jute (Or Kenaf)
PPP-B-636	Box, Fiberboard

Military

MIL-P-116	Preservation, Methods Of
MIL-P-501	Pins, Tent, Metal
MIL-C-3395	Cloth, Netting, Nylon
MIL-C-3953	Cloth, Duck, Nylon
MIL-T-5038	Tape, Textile And Webbing, Textile, Reinforcing, Nylon
MIL-C-5040	Cord, Nylon
MIL-A-8625	Anodic Coatings, For Aluminum And Aluminum Alloys
MIL-F-21840	Fastener Tapes, Hook And Pile, Synthetic
MIL-C-43128	Cloth, Plain Weave, Nylon: Water Repellent, OG-106

STANDARDS

Federal

FED-STD-751	Stitches, Seams, And Stitchings

Source: https://assist.dla.mil -- Downloaded: 20261O-23T09:41Z
Check the source to verify that this is the current version before use.

Military

MIL-STD-105	Sampling Procedures And Tables For Inspection By Attributes
MIL-STD-129	Marking For Shipment And Storage
MIL-STD-130	Identification Marking Of US Military Property
MIL-STD-147	Palletized Unit Loads For 40" X 48" Pallets
MS20230	Grommets, Metallic, Plain And Spur, With Washers, Type I And Type III

DRAWINGS

Air Force

57A3520	Sleeve, Pole Tent
57A3521	Spacer-Sleeve Tent
57A3522	Tubing, Pole Tent
57A3526	Cap, Top, Pole Tent
57A3527	Cap, Bottom Tent
57B3516	Ring, Stabilizer (Upper)
57K3515	Tent-SRU-1/P, Pyramidal Survival, 3 4 Man, Assembly Of

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

Color Association of United States Inc.

TCA Cable Numbers and Colors

(Application for copies should be addressed to the Color Association of United States, 200 Madison Avenue, New York NY 10016.

3. REQUIREMENTS

3.1 First article sample. Unless otherwise specified (see 6.2), before production is commenced, a sample tent covered by this specification shall be submitted or made available to the contracting officer or his authorized representative for approval in accordance with 4.2. The approval of the preproduction sample authorizes the commencement of production, but does not relieve the supplier of responsibility for compliance with all applicable provisions of this specification. The preproduction sample shall be manufactured in the same facilities to be used for the manufacture of the production items.

Source: https://assist.dla.mil -- Downloaded: 202640-23T09:41Z
Check the source to verify that this is the currentversion before use.

3.2 Material and components.

3.2.1 Cloth, plain weave, nylon: Water repellent. The cloth for this tent shall be 3.8-4.5 ounces per square yard, 44 to 45 inches in width, conforming to MIL-C-43128 except the color which shall conform to orange No. 70072 of the Standard Color Card Association of America.

3.2.2 Cloth, duck, nylon. The nylon reinforcement cloth shall be natural color, class I conforming to MIL-C-3953.

3.2.3 Cloth, nylon, netting. The cloth for the tunnel netting shall conform to either Type I or Type II of MIL-C-3395.

3.2.4 Fastener tape, synthetic, hook and pile. The hook and pile fastener tape shall conform to Type II of MIL-F-21840.

3.2.5 Tape, textile and webbing, textile, reinforcing, nylon. The cloth reinforcement tapes shall conform to Type III of MIL-T-5038.

3.2.6 Cord, nylon. All cord shall be 1/8 inch diameter, unbleached nylon conforming to Type III of MIL-C-5040.

3.2.7 Thread, stitching. The thread for stitching shall conform to Type I, Class 2, subclass B, Size E of V-T-295.

3.2.8 Thread, nylon. The thread used to serve the nylon cord connecting the upper stabilizer and the tent panel shall conform to Type I, Size 6 of V-T-295.

3.2.9 Leather, cattlehide. The leather reinforcement patches shall conform to Type III, Class 1, 3/64-4/64 thick of KK-L-162.

3.2.10 Pin, aluminum, 9 inch. The tent pins shall conform to Type I of MIL-P-501. Four tent pins shall be furnished and packed with the tent.

3.2.11 Stabilizer rings, panel rings, tent pole. Stabilizer rings, panel rings, and the tent pole shall conform to the applicable drawing.

3.2.12 Grommets. Grommets shall conform to MS20230 in the following sizes:

Floor grommets - MS20230BS5
Tunnel grommets - MS20230BS1

3.3 Construction. The construction shall conform to Air Force Drawing 57K3515. In cases of conflict between the drawing and this specification, the specification shall govern.

3.3.1 Stitching machine. Unless otherwise specified all stitching shall be Type 301, 7 to 9 stitches per inch, conforming to FED-STD-751.

3.3.1.1 Ends of all stitching shall be backstitched or overstitched one inch minimum except where ends are turned under in a hem or held down by other stitching. Thread tension shall be maintained so that there will be no loose stitching resulting in loose bobbin or top thread or excessively tight stitching resulting in puckering of materials sewn. The lock shall be embedded in the materials sewn.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:41Z
Check the source to verify that this is the current version before use.

3.3.1.1.1 Repair of type 301 stitching. On all stitching, two or more consecutive skipped stitches or run-offs shall be overstitched not less than one inch in each direction beyond the defective stitching area.

3.3.1.2 Stitch margins. Unless otherwise specified, all stitching margins shall be 1/8 ±1/16 inch.

3.3.1.3 Automatic stitching. Automatic machines may be used to perform any of the required stitch patterns provided the requirements for the stitch pattern, stitches per inch, size and type of thread are met, and at least three or more tying, overlapping or back stitches are used to secure the ends of the stitching.

3.3.1.4 Thread ends. All thread ends shall be trimmed.

3.3.1.5 Lubrication of thread. There shall be no lubrication of the thread by any means, prior to, or during sewing operations.

3.3.2 Attachment of tie tapes. Unless otherwise specified, the tunnel and net tie tapes at point of attachment shall be in the center of the tie tape plus or minus one inch.

3.3.3 Piecing seams. Unless otherwise specified, location of seams for piecing end, body and floor panels is optional.

3.3.4 Location marks. Location and notice marks shall not be drilled unless the holes will be covered in the finished assembly of component parts.

3.3.5 Compliance with the cup test. There shall be no seepage of water through the tent stitching when the tent is tested as specified in 4.4. The cup test is intended to insure that nonwicking thread has been used and that no lubrication has been added to the thread during the sewing operation.

3.3.6 Repairs. Any necessary repairs shall be handsewn or machine stitched patches. Patches on holes, cuts or tears not more than 1 inch in diameter or length, using the handsewn or machine stitching method, shall be permitted. A maximum of three cemented patches per tent shall be allowed without prior authorization by the contracting officer. All other repairs shall require contracting officer authorization. All repairs shall comply with the provisions of 3.3.5. Repairs required as a result of failure of the cup test shall be performed by resewing.

3.3.7 Setting of grommets. Holes punched to receive the grommets shall be smaller than the outside diameter of the grommet barrel so that the barrel must be forced through the hole. The grommets shall be securely clinched without cutting the materials.

3.4 Marking.

3.4.1 Identification of product. The tent, survival, 3-4 men shall be marked for identification in accordance with MIL-STD-130 and shall include the following specific information:

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:41Z
Check the source to verify that this is the current version before use.

TENT, PYRAMIDAL, SURVIVAL, 3-4 MAN
Type SRU-1/P
MIL-T-83788(USAF)
Manufacturer's Identification *
Contract or Order No. *
Date of Manufacture *

*The manufacturer shall insert the applicable information.

3.4.1.1 Black ink conforming to TT-I-542 shall be used for identification marking.

3.4.2 Erection instructions. The following erection instructions shall be printed on the outside of the tent floor in such a position as to be visible when the tent is bundled for shipment.

a. Lay the tent out with outside of floor down.

b. Stake out the four corners with the furnished tent pins.

c. Enter through the tunnel and place the small end of the tent pole in the top stabilizing ring. Put the tent pole together and place end in either grommet in the floor.

d. The remaining tent pins will have to be made from material on hand at the using location. In the event nothing is available, consult "Survival Manual 60-5, Dead Man for Tents."

3.4.3 Erection instructions will be stenciled in letters vertically 1/4 inch high, using black ink in accordance with TT-I-542 in the location shown on the applicable drawing.

3.5 Workmanship. The finished tent shall conform to the quality and grade of product established by this specification and the occurrence of defects shall not exceed the applicable acceptable quality levels.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:41Z
Check the source to verify that this is the current version before use.

4.2 First article. Before production is commenced, a completely fabricated Tent, Pyramidal, Survival, 3-4 man type, including pins and poles, shall be available for inspection to determine conformance with drawings; and approval of the contracting officer must be obtained. When the preproduction sample is approved, it shall be retained by the contractor as a guide for subsequent production of the contract. The sample may be included in the quantity for the last shipment.

4.3 Sampling for inspection. Inspection shall be made in accordance with provisions set forth in MIL-STD-105, except where otherwise indicated hereinafter.

4.3.1 Inspection of components. The quality assurance provisions for components and materials, except as otherwise required, shall be in accordance with the applicable specifications and standards referenced. When there is a conflict in quality assurance, this specification shall govern.

4.3.1.1 Certificate of compliance. Components and materials listed below may be accepted on the basis of a contractor's Certification of Compliance for requirements specified in applicable drawings.

Components	Characteristic	Requirements In Drawings No.
Tubing, Spacers, Sleeve, Cap-Toe & Cap Bottom	That they have been anodized in accordance with the requirements in MIL-A-8625, Type I. Also that the equipment and processes employed in anodizing conform to the requirements in MIL-A-8625.	57A3520 57A3521 57A3522 57A3526 57A3527

4.3.1.2 Testing of the intermediate product. Testing of the partially fabricated tent pole assembly, shall be performed in accordance with Table I, for characteristics shown therein. The sample unit shall be one upper stabilizer ring prior to assembly to tent, after cadmium plating.

TABLE I

Characteristic 1/	Rqmt Para	Test Method	Rqmt Apply To: Indiv Unit	Rqmt Apply To: Lot Avg	No. Determ Per Sple Unit	Results Reported As	Inspc Level	AQL
Thickness of Cadmium Plating on Stabilizer Ring	Dwg. No. 57B3516	Para 4.4 QQ-P-416	X	-	2	Average of 2 det.	S-1	6.5

1/ Upper stabilizer ring may be cast from magnanese-bronze alloy conforming to C-1 of QQ-C-390, rendering the required test for cadmium not applicable.

Source: https://assist.dla.mil -- Downloaded: 202610-23T09:41Z
Check the source to verify that this is the current version before use.

4.3.2 Process inspection. Inspection shall be made at any point or during any phase of manufacturing process to determine whether operations or assemblies are in accordance with requirements indicated on drawings. The Government reserves the right to exclude from consideration for acceptance any material or services for which in-process inspection has indicated nonconformance.

4.3.3 Inspection of end item.

4.3.3.1 Examination of end item. The classification of defects found during examination shall be in accordance with list shown in 4.3.3.1.1, 4.3.3.1.2, 4.3.3.1.3 and 4.3.3.1.4. The sample unit for these examinations shall be one completely fabricated tent (including pins and poles when applicable).

4.3.3.1.1 Examination for visual characterisitcs (Canvas Section).

Examine	Defects	Major	Minor A	Minor B
Fabric	Cuts or tears	X		
	Holes:			
	-on walls	X		
	-on floor		X	
	-on apron			X
	Fabric defects:			
	-seriously affecting serviceability	X		
	-affecting serviceability, but not seriously		X	
Screening	Holes, cuts or tears larger than mesh openings, or ruptured strands	X		
Webbing; Tie Tapes	Misplaced, failing to serve intended purpose:			
	-Webbing components or seam reinforcements	X		
	-Tie tapes		X	
	-Finished length less than specified by more than 1/2 inch			X
	-Edges frayed or scalloped; ends of tunnel or netting tapes not seared		X	
Hardware	Broken or malformed; burrs or sharp edges which may damage the item or cause injury in handling	X		
	Finish omitted		X	
Grommets	Size or type not as specified			
	-Seriously affecting serviceability	X		
	-Affecting serviceability, but not seriously		X	
	Improperly set, two or more teeth exposed inside of barrel; clinched loosely, causing grommet to rotate around hole			X
	Clinched excessively tight, cutting fabric, or loosely clinched, i.e., grommet and washer become disengaged	X		

Source: https://assist.dla.mil -- Downloaded: 2022640-23T09:41Z
Check the source to verify that this is the current version before use.

ine	Defects	Major	Minor A	Minor B
	Misplaced:			
	-Seriously affecting serviceability	X		
	-Affecting serviceability, but not seriously		X	
& Guy s	Cuts or abrasions; ends not seared	X		
	Less than specified length by more than 1 inch; insecurely or improperly knotted			X
: See drawings for size (diameter) and type of lines and knots required.				
s and ching				
Seams	Any open seam on deck of tent:			
	-On both rows of stitching at same location	X		
	-On one row of stitching		X	
	On all other seams:			
	-More than 1/4 inch, but not more than 1/2 inch			X
	-More than 1/2 inch		X	
: A seam shall be classified as open when one or more stitches joining a seam are broken, or when two or more consecutive skipped stitches or run-offs occur. On double stitched seams, a seam shall be considered open when either one or both sides of the seam are open.				
Edges	When securely caught in stitching:			
	-More than 1/2 inch, but not more than 1 inch			X
	-More than 1 inch		X	
: Raw edges not securely caught in stitching shall be classified as open seam.				
Offs Open Seams)				
& Stitch	Wrong seam or stitch type:			
	-Seriously affecting serviceability	X		
	-Affecting serviceability, but not seriously		X	
:h Tension	Loose, resulting in a loosely exposed top or bobbin thread; tight, resulting in excessive tightness or puckering of fabric on seams			X

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:41Z
Check the source to verify that this is the current version before use.

Examine	Defects	Major	Minor A	Minor B
Stitches Per Inch	One stitch less than minimum specified			X
	Two or more stitches less than minimum specified		X	
	One stitch in excess of maximum specified			X
	Two or more stitches in excess of maximum specified		X	

NOTE: Variation in the number of stitches per inch, caused by the operator's speeding up the machine and pulling the fabric in order to sew over heavy seams or heavy places or in turning corners, shall be classified as follows:

a. Within the Minor B Defect classification - No Defect.
b. Within the Minor A Defect classification - Minor B Defect.

Stitching Margins; Stitching Gage	Not as specified: -Affecting serviceability or appearance		X	
Thread Breaks	Backstitched less than 1 inch on stitch type 301;			X
	Overstitched less than 3/4 inch on stitch type 301			X

NOTE: Thread breaks not backstitched or not overstitched shall be classified as open seams.

Stitching Ends	Not backstitched or not overstitched (except where ends are held down by other stitching or turned under in a hem)		X	
Components & Assembly	Defects of components or assembly (not specifically classified) -Seriously affecting serviceability	X		
	-Affecting serviceability, but not seriously		X	
	Any required component or part of tent omitted, or not as specified	X		
	Any required operation omitted or not as specified: -Seriously affecting serviceability	X		
	-Affecting serviceability, but not seriously		X	
	Needle chew	X		
	Seams badly pleated or puckered			X

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:41Z
Check the source to verify that this is the current version before use.

Examine	Defects	Major	Minor A	Minor B
Machine Stitching	One or more required rows of stitching omitted	X		
	Type 301 zig zag stitching incomplete: -Two or more stitches omitted; less than specified length by more than 1/8 inch			X
Construction	Any required detail of construction omitted or not as specified: -Seriously affecting serviceability	X		
	-Affecting serviceability, but not seriously		X	
Repairs	Mends, darns or patches, not in accordance with 3.3.6	X		
Hems	Twisted or pleated			X
	Hems required to finish less than 3/4 inch in width less than specified; hems required to finish 3/4 inch or more in width less than specified by more than 1/4 inch			X
	Constructed with partial turnunder when double turnunder is required		X	
Binding	Loosely or improperly applied; ends not finished as specified			X
Reinforcements (Cloth)	Misplaced: -Seriously affecting serviceability	X		
	-Affecting serviceability, but not seriously		X	
	Finished dimension less than specified by more than 1/2 inch			X
	Improperly applied, causing excessive fullness on reinforcements or reinforced parts		X	
Markings	Omitted, incorrect, illegible or misplaced			X
Cleanness	Noticeable grease or oil stains; thread ends not trimmed throughout			X
CONSTRUCTION DETAIL DEFECTS				
Tunnel Body Inner Edge	Tunnel tie tapes set with both ends finished on inside or outside of tent	X		
	Tunnel or tunnel tie tapes not caught in both rows of stitching attaching tunnel to body		X	

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:41Z
Check the source to verify that this is the current version before use.

Examine	Defects	Major	Minor A	Minor B
Outer Edge	Not finished as specified; draw string not inserted in hem or fails to slide freely through hem and grommet	X		
	Seam at top center of tunnel out of alignment with center seam of body section by more than 1/4 inch			X
Tunnel Netting Inner Edge	Not caught in both rows of stitching attaching tunnel to body; tunnel tie tapes not encircling netting	X		
Outer Edge	Draw string not inserted in hem as specified, or fails to slide freely through hem and grommet	X		
Apron	Not securely caught in both rows of stitching attaching reinforcement tape around bottom of tent at location of joining floor to body; free edge not finished as specified		X	
Peg Holes	Not fully reinforced on underside or around opening edges; edge cord not attached as specified; loop openings too small, failing to provide free passage of pins	X		
	Edges of reinforcements around opening uneven with edge of opening by more than 1/8 inch			X
Corners	Not finished as specified; corner cord not attached to corners, loops not formed as indicated in detail "T"; loop opening too small, failing to provide free passage of pins	X		
Rings "A" & "B"	Misplaced, i.e., set off center of panel or section joining seams: -By 1/4 inch or more but not more than 1/2 inch		X	
	-By more than 1/2 inch	X		
Peak	Not constructed as indicated in Section R-R; handworked rings not stitched through body seam, peak reinforcement and ventilator	X		
	Centering guide cord not inserted through rings and ring stabilizer; cord not stitched properly to main panel	X		
Ventilator	Not attached to peak as specified, causing excessive tightness or fullness on peak or ventilator		X	

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:41Z
Check the source to verify that this is the current version before use.

Examine	Defect	Major	Minor A	Minor B
Floor Grommet Reinforcements	Attached to floor on underside instead of floor surface			X
Disposal Opening	Hook (on disposal flap) and pile (on tent floor) are not in alignment. Hook and pile not properly attached.			X
Disposal Flap	Flap fails to cover opening fully when in a closed position.	X		
Outer Edge of Floor & Floor Reinforcement	Not caught in both rows of stitching attaching reinforcement tape		X	

4.3.3.1.2 Examination for dimensions (duck section).

Examine	Defect	Major	Minor A	Minor B
Overall Dimensions	Smaller than nominal dimensions less applicable minus tolerance indicated on drawings	X		
	Larger than nominal dimensions and applicable plus tolerance indicated on drawings			X
Dimensions of Components & Openings (Unless otherwise classified	Smaller than nominal dimensions less applicable minus tolerance indicated on drawings, but not smaller than dimensions less double the tolerance			X
	Smaller than nominal dimensions less double the minus tolerance indicated on drawing		X	
	Larger than nominal dimensions and applicable plus tolerance indicated on drawing			X
Location Dimensions (Unless otherwise classified)	Not within specified tolerance: -Not exceeding twice the applicable tolerance			X
	-Exceeding twice the applicable tolerance		X	

Source: https://assist.dla.mil -- Downloaded: 202610-23T09:41Z
Check the source to verify that this is the current version before use.

4.3.3.1.3 Examination of pole sections and upper stabilizer ring for defects in finish, design, material, construction, workmanship and marking (metal section).

Examine	Defect	Major	Minor
Finish	Not finished or finish is not as specified, e.g., tubing, spacers, sleeve, and caps have not been anodized, or the ring is not cadmium plated	X	
	Finish is not continuous, smooth and uniform		X
	Any powdery areas in anodized finish		X
	Finish is not adherent, i.e., is blistered, peeling or flaking		X
	Cadmium plating is scratched or marred, exposing bare metal		X
	Foreign metal imbedded		X
	Evidence of grease, oil or dirt under plating		X
Material	Any component not fabricated of the specified material	X	
Design	Any characteristic not in accordance with the specified rquirements	X	
Construction & Workmanship General	Any part missing or not specified type or size, e.g., spacers have not been furnished at rivet locations	X	
	Components fractured, split, punctured, dented bowed, sprung, malformed, or otherwise impaired, seriously affecting serviceability	X	
	Damaged or defective affecting serviceability, but not seriously		X
	Sharp edge, burr or sliver that may damage fabric or cause injury to personnel (Drawings permit .010 inch max, check visually, measure when in doubt)	X	

Source: https://assist.dla.mil -- Downloaded: 202610-23T09:41Z
Check the source to verify that this is the current version before use.

Examine	Defect	Major	Minor
Construction & Workmanship General (Cont'd)	Any part e.g., cap or sleeve misplaced, loose or not in proper alignment seriously affecting serviceability, e.g., the sleeve does not protrude 2 inches ±1/16 inch to assure proper assembly	X	
	Any part misplaced, loose or not in proper alignment, affecting serviceability, but not seriously		X
	Any operation omitted or not properly performed, seriously affecting serviceability	X	
	Any operation omitted or not properly performed affecting serviceability, but not seriously		X
	Not connected or joined as specified, or poorly accomplished seriously affecting serviceability	X	
	Not connected or joined as specified, or poorly accomplished affecting serviceability, but not seriously		X
Casting	Blowhole, porosity, shrinkage defect, crack or other defect seriously affecting serviceability	X	
	Defective, affecting serviceability, but not seriously, e.g., slight malformation in noncritical areas that will not reduce strength		X
Rivets	Missing, not specified type, broken, loose, not peened or insufficiently peened, seriously affecting serviceability	X	
	Not specified type, loose, damaged or not sufficiently peened, affecting serviceability, but not seriously		X
Ring, Stabilizer, Upper	Holes not countersunk		X
	Edges not rounded		X
Assembly	Pole sections will not assemble	X	
Marking	Missing, incomplete, not legible, not specified type or size, not in proper location, not affixed in the prescribed manner or not correct color		X

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:41Z
Check the source to verify that this is the current version before use.

4.3.3.1.4 Examination of pole section and upper stabilizer ring for defects in dimensions. Any dimension that is not within the specified tolerances shall be classified as a defect. Unless otherwise specified the tolerance for the overall length of pole shall be ±1/2 inch.

4.3.3.1.5 Acceptable quality levels (AQL's). The acceptable quality levels expressed in defects per hundred units and inspection levels shall be as follows:

	INSPECTION LEVEL		AQL's
For defects applicable to 4.3.3.1.1 & 4.3.3.1.2	I	Major defects	25.0
		Major & Minor A defects combined	65.0
		Totals (Major, Minor A & B defects combined)	150.00
For defects applicable 4.3.3.1.3	I	Major defects	2.5
		Totals (Major & Minor defects)	10.0
For defects applicable to 4.3.3.1.4	S-3	One Class	4.0

4.3.4 Examination of preparation for delivery requirements. An examination shall be made to determine that packaging, packing and marking requirements are in compliance with Section 5 of this specification. Defects shall be scored in accordance with Table II. The sample unit shall be one completely wrapped tent fully prepared for delivery with the exception that it need not be sealed. The lot shall consist of that quantity of tents offered for acceptance at one time. The inspection level shall be S-2 and the AQL shall be 2.5 expressed in terms of defects per hundred units.

TABLE II - Examination of Preparation for Delivery

Examine	Defect
Markings	Omitted, incorrect, illegible, of improper size, location, sequence or method of application
Materials	Any component missing or damaged
Workmanship	Inadequate application of components such as incomplete closure of cloth wrapping and loose stitching
Contents	Not as specified

4.3.5 Testing of the end product. Tent samples shall be tested as specified in 4.4.1 for compliance with 3.3.5. The sample unit shall be one completely fabricated tent. The lot shall consist of all completely fabricated tents offered for inspection and the inspection level shall be S-2. Leakage in any test area of any sample shall be cause for rejection of the lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:41Z
Check the source to verify that this is the current version before use.

4.4 Tests.

4.4.1 Seam leakage test. The tent shall be tested in two areas as follows: Any roof panel joining seam and any corner joining seam.

4.4.1.1 Procedure. Suspend the section of the tent containing the area to be tested between two supports (boxes, wooden horses) so as to allow both sides of the fabric to be viewed. The area to be tested shall then be cupped into a hoop 6 to 7 inches in diameter, e.g., an embroidery hoop, with the seam running through the center of the cupped fabric. Pour into the cupped area approximately one pint of cold tap water. Allow to stand for 5 minutes. At the end of the period, examine the test area for the seepage of water through the thread along the entire portion of the stitching exposed to the cup test.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging shall be level A or C as specified (see 6.2).

5.1.1 Level A. Each tent shall be preserved and packaged in accordance with MIL-P-116, Method III. The tent shall be folded into the smallest configuration possible with the bottom (outside) of the tent floor out and the printed erection instructions visible after the tent has been folded. The pin and pole sections shall be placed in the center of the folded tent in such a way that they are easily accessible when the tent is unfolded.

5.1.1.1 The folded tent shall be wrapped and sewn in one of the following materials:

a. Cotton Osnaburg Cloth conforming to Class B of CCC-C-429.

b. Burlap, 8 ounces per linear yard of 30 or 40 inches in width conforming to CCC-C-467.

5.1.2 Level C. Each tent shall be preserved and packaged in a manner that will provide adequate protection against deterioration and physical damage during shipment from the supply source to the first receiving activity. This may conform to the supplier's commercial practice when it meets the requirements of this level.

5.2 Packing shall be level A, B or C as specified (see 6.2).

5.2.1 Level A. Each tent preserved and packaged as specified in 5.1.1 shall be packed in a weather resistant container conforming to PPP-B-636, Grade W5C. Containers shall be of uniform size and shape and of minimum tare and cube.

5.2.2 Level B. Level B packing shall be the same as Level A except that the containers shall be domestic type.

5.2.3 Level C. Each tent preserved and packaged as specified in 5.1.2 shall be packed in containers that will provide adequate protection during shipment from the supply source to the first receiving activity. Containers shall conform to carrier's rules and regulations as applicable to the mode of transportation.

Source: https://assist.dla.mil -- Downloaded: 20261O-23T09:41Z
Check the source to verify that this is the current version before use.

5.3 Marking. In addition to any special marking required by the contract or order, interior packages and exterior containers shall be marked in accordance with MIL-STD-129.

5.4 Palletization. Packed tents shall be palletized in accordance with Type I load of MIL-STD-147. Strapping and bonding means shall be in accordance with Section 5 of MIL-STD-147. Palletization is not required when physical characteristics or limited quantity procured are not adaptable to palletization.

6. NOTES

6.1 Intended use. The tent is for use as a survival tent.

6.2 Ordering data. Procurement documents should specify the following:

a. Title, number, and date of this specification.

b. Selection of applicable levels of packaging and packing (see 5.1 and 5.2).

c. When First Article sample is not required (see 3.1).

d. When palletization is not required (see 5.4).

6.3 For access to samples, address the procuring office issuing the invitation for bids.

Custodian:
Air Force - 82

Preparing Activity:
Air Force - 82

Project No. 8340-F324

☆ U. S. GOVERNMENT PRINTING OFFICE: 1973-714-917/1279

Source: https://assist.dla.mil -- Downloaded: 202640-23T09:41Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:41Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID

DEPARTMENT OF THE AIR FORCE
DOD 318

OFFICIAL BUSINESS

SAN ANTONIO AIR MATERIEL AREA
SERVICE ENGINEERING DIVISION (MMEOP)
KELLY AFB, TEXAS 78241

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:41Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 68 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:41Z
Check the source to verify that this is the current version before use.