MIL-F-60022 (AR)
31 January 1964
SUPERSEDING
MIL-F-20477 (In Part)
4 December 1951

MILITARY SPECIFICATION

FUZE, MINE, COMBINATION, M10A2
LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the loading, assembling and packing for one type of fuze designated as Fuze, Mine, Combination, Practice, M10A2.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 - Ammunition and Special Weapons; General Specification for
MIL-P-10025 - Packaging, Packing and Marking for Interplant Shipment of Inert Ammunition
MIL-P-12951 - Primer Percussion, M39A1, Loading, Assembling and Packing
MIL-C-13739 - Composition, Delay
MIL-I-45208 - Inspection Requirements, General Specification for
MIL-I-45607 - Inspection Equipment, Supply and Maintenance of

STANDARDS

MILITARY

MIL-STD-105D - Sampling Procedures and Tables for Inspection by Attributes

FSC: 1345

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:04Z
Check the source to verify that this is the current version before use.

MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-129 - Marking for Shipment and Storage
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

ORDNANCE CORPS

8866643 - Fuze, Mine, Combination, M10A2, Assembly.

PUBLICATIONS

ORDNANCE CORPS

IEL-8866643 - Index of Inspection Equipment Lists.

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer).

2.2 Other publications.-The following document forms a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids shall apply.

CODE OF FEDERAL REGULATIONS

49 CFR 71-90 - Interstate Commerce Commission Rules and Regulations for the Transportation of Explosives and Other Dangerous Articles.

(The Interstate Commerce Commission Regulations are now a part of the Code of Federal Regulations (1949 Edition and revisions) available from the Superintendent of Documents, Government Printing Office, Washington 25, D.C. Orders for the above publication should cite "49 CFR 71-90 (latest revisions)".)

3. REQUIREMENTS

3.1 Material.-Materials and parts shall be in accordance with applicable drawings and specifications.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:04Z
Check the source to verify that this is the current version before use.

3.2 Fuze assembly.-The loaded fuze assembly shall comply with all requirements specified on Drawing (dwg.) 8866643 and with all requirements specified in applicable specifications.

3.3 Moisture content of delay composition.-The moisture content of the delay composition at the time of loading shall not exceed 0.04 percent when tested as specified in MIL-C-13739.

3.4 Functioning

3.4.1 Delay time.-The fuze shall function with a delay time of not less than 3.8 second nor more than 4.7 seconds (see 6.4) when tested as specified in 4.4.1.

3.4.2 Visual signal.-The fuze, when assembled to an M8A1 Mine shall produce a yellow smoke cloud when the assembly is functioned as specified in 4.4.1.

3.5 Workmanship.-All parts and assemblies shall be fabricated and loaded in a thorough workmanlike manner. They shall be free of burrs, sharp edges, cracks, dirt, rust and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required markings shall be neat and sharply defined.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified, the supplier may utilize his own or any other inspection facilities and services acceptable to the Government. Inspection records of the examinations and tests shall be kept complete and available to the Government as specified in the contract or order. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL-STD-109 in order to define terms used herein. The provisions of Specification MIL-A-2550 shall apply.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:04Z
Check the source to verify that this is the current version before use.

4.1.1 Contractor quality assurance system.-The contractor shall provide and maintain an effective quality assurance system in compliance with the requirements of Specification MIL-I-45208. The contractor's quality assurance system shall contain a procedure for the reporting of critical defectives found during the course of his inspection and during inspection by the Government. Any critical defect encountered, unless annotated by an asterisk (*) to the right of the characteristic code number (see 6.2), will be reported within 48 hours. A monthly summary report covering those critical defects annotated by an asterisk will be furnished. The agencies to whom the reports will be furnished are identified in paragraph 6.6. The reports shall contain, as a minimum, the following information:

a. Contractor and contract number.
b. Number and revision date of specification.
c. Characteristic code number.
d. Lot or serial number.
e. Number of defectives found.
f. Assignable cause or analysis of occurrence.
g. Corrective action taken or recommended. When the corrective action is beyond the control of the contractor or the scope of the contract, the report shall contain the contractor's recommendation to the Government.

4.1.2 Submission of product.-At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all quality assurance provisions of the approved current written description of the system.
b. Number of units of product inspected.
c. Results obtained for all inspection performed.
d. Drawing, specification number and date, together with an identification and date of changes.
e. Certificates of compliance on all material purchased directly by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.
f. Number of items in the lot.
g. Date submitted.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:04Z
Check the source to verify that this is the current version before use.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.3 Government verification.-Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be in accordance with Specification MIL-I-45208 and will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 Initial production inspection.

4.2.1 Submission.-Prior to normal production the contractor shall submit an initial production sample consisting of (fifty) consecutively produced assemblies (i.e. 50 each of every subassembly), which have been produced by the production process which the contractor will use in fulfilling the contract, to a Government-approved facility designated by the contracting officer. All parts and materials shall be obtained from the same source of supply as will be used in regular production. The initial production sample shall be accompanied by certificates of analyses for all materials. A sample shall also be submitted whenever a change occurs in manufacturing process, material used, drawing, specification, or source of supply such as to significantly affect product uniformity as determined by the Government.

4.2.2 Inspections to be performed.-Each assembly and component shall be inspected by the Government for all the inspections specified in 4.3.2 and 4.3.3 of this specification and for all additional requirements of the applicable drawings.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:04Z
Check the source to verify that this is the current version before use.

4.2.3 Rejection.-If any assembly or component fails to comply with the applicable requirements, the initial production sample shall be rejected. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit new or supplemental quantities until such time as an acceptable sample is submitted, or until otherwise directed by the contracting officer.

4.3 Inspection provisions.

4.3.1 Lot formation.-A lot shall consist of fuze assemblies produced by one manufacturer, in one unchanged process, in accordance with the same drawing, same drawing revision, same specification, and same specification revision. Drawing, specification, and process changes not affecting performance, safety or fit, as determined by the Government, shall not be cause for changing the lot number.

4.3.2 Examination.-Sampling plans and procedures for the following classifications of defects shall be in accordance with Standard MIL-STD-105D except that inspection for critical defects shall be 100 percent. Continuous sampling plans in accordance with Standard MIL-STD-1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.25 percent for each major defect and an AQL of 0.40 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 This section applies to all subassemblies and components not hereinafter specifically listed (see 3.5) and applicable drawings.

Categories	Defects	Method of Inspection
Critical:	None defined	
Major:	AQL 0.25 percent per defect	
101.	Operation missing or improperly performed	Visual
102.	Burr or chip on or at intersection of sliding or other functional surfaces	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:04Z
Check the source to verify that this is the current version before use.

103.	Finish of sliding or other functional surface improper	Visual
104.	Component missing or improperly assembled	Visual
105.	Protective finish inadequate (bare spots)	Visual

Minor: AQL 0.40 percent

201.	Evidence of poor workmanship other than that covered under major category above (see 3.5)	Visual

4.3.2.2 Tube, igniter (see dwg. 8866652 covering a detail of dwg. 8866643).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.25 percent		
101.	Inside diameter	Gage	01001
102.	Total length	Gage	01002
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.5)	Visual	01003

4.3.2.3 Base (see dwg. 8866650 covering a detail of dwg. 8866643).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 1.50 percent		
101.	Diameter of flash hole, minimum (min.)	Gage	02001
102.	Pitch diameter of large thread, maximum (max.)	Gage	02002
103.	Major diameter of large thread, max	Gage	02003
104.	Pitch diameter of small thread, max	Gage	02004

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:04Z
Check the source to verify that this is the current version before use.

105.	Major diameter of small thread, max.	Gage	02005
106.	Diameter of primer cavity, min.	Gage	02006
107.	Depth of primer cavity, min.	Gage	02007
108.	Outside diameter of igniter tube end, max.	Gage	02008
109.	Diameter of delay cavity, min.	Gage	02009
110.	Concentricity between igniter tube end and pitch diameter of large thread.	Gage	02010
111.	Profile of primer cavity.	Gage	02011
112.	Depth of delay cavity.	Gage	02012
Minor:	AQL 4.00 percent		
201.	Total length.	Gage	02013
202.	Diameter of flange.	Gage	02014
203.	Diameter adjacent to small thread.	Gage	02015
204.	Width of undercut below small thread.	Gage	02016
205.	Diameter adjacent to large thread.	Gage	02017
206.	Width of undercut above large thread.	Gage	02018
207.	Length to shoulder below large thread.	Gage	02019
208.	Length to top of shoulder.	Gage	02020
209.	Thickness of flange.	Gage	02021
210.	Diameter of shoulder above igniter tube end.	Gage	02022
211.	Length of igniter tube end.	Gage	02023
212.	Chamfers missing or inadequate.	Visual	02024
213.	Knurl missing or inadequate.	Visual	02025
214.	Radius missing or inadequate.	Visual	02026
215.	Evidence of poor workmanship (see 3.5).	Visual	02027

4.3.2.4 Igniter assembly (see dwg. 8866651 covering a detail of dwg. 8866643).

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	Delay composition missing or inadequate.	Visual	03001
2.	Elements of explosive train exposed.	Visual	03002

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:04Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.65 percent		
101.	Smoke composition missing or inadequate	Visual	03003
102.	Laquer in bore of base	Visual	03004
103.	Percussion primer missing	Visual	03005
104.	Adhesive sealing compound missing or inadequate	Visual	03006
105.	Igniter tube not securely attached to base	Manual	03007
106.	Depth of insertion of base in igniter tube	Gage	03008
107.	Length to shoulder below large thread	Gage	03009
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.5)	Visual	03010

4.3.2.5 Assembly (see dwg. 8866643).

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	Cotter pin missing or leg not bent	Visual	04001
2.	Firing pin safety pin missing or leg not bent	Visual	04002
3.	Elements of explosive train exposed	Visual	04003
Major:	AQL 0.65 percent		
101.	Total length	Gage	04004
102.	Cords missing or damaged	Visual	04005
103.	Gasket missing	Visual	04006
104.	External thread damaged	Visual	04007
105.	Any part dented or distorted	Visual	04008
106.	Prong missing	Visual	04009

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:04Z
Check the source to verify that this is the current version before use.

Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.5).....	Visual	04010

4.3.2.6 Box, packing (see dwg. 8882275).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Evidence of loose contents.....	Manual	05001
102.	Carton damaged so that contents are exposed or liable to become exposed.....	Visual	05002
103.	Closing for shipment improper...	Visual	05003
Minor:	AQL 0.40 percent		
201.	Marking misleading or improper..	Visual	05004

4.3.3 Testing

4.3.3.1 Moisture content of delay composition (see 3.3) - Major defect - Code No. 06001.-The moisture content of the delay composition shall be determined at the time of loading and not less than once for each eight hours of production, or portion thereof. The sample shall be selected just prior to loading and the moisture content determination made as specified in MIL-C-13739. Composite samples shall not be used in this determination. If the moisture content exceeds the specified requirement, the delay composition shall be rejected. If this determination is made after loading has begun components loaded therewith shall be rejected.

4.3.3.2 Functioning (see 3.4) - Major defect - Code No. 04011.-Beginning with the first lot produced and continuing until three consecutive lots have complied with the acceptance criteria specified, the sampling plan for this test shall be in accordance with Standard MIL-STD-105D using code letter K and an AQL of 0.10

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:04Z
Check the source to verify that this is the current version before use.

percent. The test shall be performed as specified in 4.4.1 using equipment in accordance with 4.3.4. Any fuze assembly which fails to comply with 3.4 shall be classed defective. Any fuze which functions in less than 3.0 seconds shall cause the lot to be rejected and testing to cease. Any fuze which fails to function or whose delay time is lost, shall be replaced in order to determine if the lot complies with the delay time requirements.

4.3.3.2.1 Functioning, normal production.-After three consecutive lots have met the criteria of 4.3.3.3, the sampling plan for this test shall be in accordance with Standard MIL-STD-105D using code letter H and an AQL of 0.25 percent.

4.3.3.3 Check test for deterioration of primers (see Military Specification MIL-P-12951) - Major defect.-If the total time between original acceptance of any primer lot and the assembly of that lot into the fuzes exceeds two years, or if the primers have been subjected to adverse conditions, however brief, at any time since previous tests, the primer lot shall be subjected to and must satisfactorily pass the test for functioning specified in Military Specification MIL-P-12951 immediately before the primer lot is assembled into the fuzes. This test shall be performed by the contractor on primers selected by the Government inspector at the facility assembling the primers into the fuzes (see 6.5).

4.3.4 Inspection Equipment.-Index of Inspection Equipment List Number IEL-8866643 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement of parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and wherever inspection equipment drawings are needed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:04Z
Check the source to verify that this is the current version before use.

4.3.4.2 Supply and maintenance.-Supply and maintenance of the equipment listed on the IEL shall be in accordance with Specification MIL-I-45607.

4.3.4.3 Government use of contractor's inspection equipment.-The contractor shall as required make available to the Government all inspection equipment necessary for determining conformance with contract requirements. Operation of the equipment and verification of its accuracy shall be supplied by the contractor, as required by the Government in performance of its examination or test.

4.4 Test methods and procedures.

4.4.1 Functioning.-The fuze assembly shall be assembled to an M8A1 mine. The mine and fuze assembly shall be placed in a hole on a firm foundation so that the release pin ring on the fuze will be just above ground level. The hole shall then be filled up to the mine plastic plug so that the mine is solidly and firmly emplaced. The top of the mine plastic plug shall be free of dirt or rocks. The fuze shall then be functioned and observation made that the delay time is not less than 3.8 seconds nor more than 4.7 seconds to eject the plug from the mine body and produce a yellow smoke cloud as evidence of compliance with 3.4.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.

5.1.1 Level A.

5.1.1.1 Fuze, Mine, M10A2 less Igniter Assembly.-Fuzes shall be packaged in accordance with Drawing 8882273.

5.1.1.2 Igniter Assembly.-Igniters shall be packaged in accordance with Drawing 7548411.

5.1.2 Level C.

5.1.2.1 Fuze, Mine, M10A2 less Igniter Assembly.-Fuzes shall be packaged in accordance with Drawing 8882274 and MIL-P-10025 in such a manner that no damage will result during shipment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:04Z
Check the source to verify that this is the current version before use.

5.1.2.2 Igniter Assembly.-The Igniter Assembly shall be packed in accordance with Drawing 8882275 and ICC Regulations 49 CFR 71-78 in a manner that will provide safe delivery to its destination.

5.2 Marking.

5.2.1 Fuze, Mine, M10A2 less Igniter Assembly.-Unit and exterior containers for Fuzes shall be marked in accordance with MIL-STD-129.

5.2.2 Igniter Assembly.-The Igniter Assembly shall be marked in accordance with the requirements specified in the packing drawings.

5.3 Data cards.-Data card information shall be as specified in Specification MIL-A-2550.

5.4 Shipping.-When component parts from more than one lot are shipped as a carload, each lot must be kept separate and the division between lots clearly indicated to prevent mixing of lots in transit.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment.-The contractor will design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of 6.3.1 through 6.3.7.

6.3.1 Inspection Equipment Lists.-Inspection Equipment Lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (OO Form 1242-3) the numbers of drawings of existing

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:04Z
Check the source to verify that this is the current version before use.

equipment designs or codes as indicated in 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "contractor design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 Inspection Equipment List codes.-The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5, and 6.3.6 will be designated in the Inspection Equipment List by the following codes:

CDOF - Contractor's design responsibility on Ordnance format; ORDM-608-12.
CDCF - Contractor's design responsibility on contractor format.
OD - Ordnance design.
ODMU - Ordnance design, mandatory for use.
CE - Commercial equipment.
SCD - Specification Control Drawing.

6.3.3 Ordnance designs.-Ordnance designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Ordnance design is listed for an item of inspection equipment. Ordnance designs fall into two basic classifications; mandatory and non-mandatory. When an Inspection Equipment List references mandatory Ordnance designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 Specification control drawings -Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic, or pictorial form only and specify the

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:04Z
Check the source to verify that this is the current version before use.

required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 Commercial equipment.-Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and government. Contractors are not required to furnish drawings of commercial inspection equipment but a list of such equipment must be approved by the Government. Lists will be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDOF shall comply with the format and requirements of ORDM 608-12, and, in addition, contain the detail and information specified above.

6.3.7 Submission of contractor designs.-Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:04Z
Check the source to verify that this is the current version before use.

6.4 Delay time.-Delay time is defined as the time between functioning of the firing mechanism and functioning of the smoke composition.

6.5 Cost of check test.-The contracting officer will arrange for the contractor to be reimbursed for the expense incurred in the performance of the check test for deterioration of the primers. The test shall be conducted at Government expense without cost to the contractor who loaded the primers or to the contractor assembling the primers into the fuzes, and shall not constitute a basis for rejection against either contractor except where deterioration has occurred as a direct result of carelessness in handling, storage, etc., permitted while the primer lot was under the jurisdiction of either contractor.

6.6 Submission of critical defect reports.-For U. S. Army Munitions Command procurements, one copy of each critical defect report will be furnished the cognizant Government inspection agency; the Army Ammunition Procurement and Supply Agency, ATTN: SMUAP-RO; Picatinny Arsenal, ATTN: SMUPA-ND.

6.6.1 Reporting to other services.-For other than U. S. Army Munitions Command procurements, critical defect reporting shall be as prescribed by the contracting officer.

Custodian:
Army-AR

Preparing activity:
Army-AR

Project No. 1345-A069

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:04Z
Check the source to verify that this is the current version before use.