M1L-M-46325D(MU)
25 May 1965
SUPERSEDING
MIL-M-46325C(MU)
14 January 1964

MILITARY SPECIFICATION

MOUNT, TELESCOPE: M128

1. SCOPE

1.1 This specification covers performance requirements, related quality assurance provisions, and packaging data for a telescope mount which supports Elbow Telescope: M109 (see 6.1).

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

Military

MIL-F-13926	Fire Control Materiel: General Specification Governing the Manufacture and Inspection of
MIL-P-14232	Parts, Equipment and Tools for Ordnance Materiel, Packaging of
MIL-I-45607	Inspection Equipment, Supply and Maintenance of

STANDARDS

Military

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes
MiL-STD-109	Quality Assurance Terms and Definitions

DRAWINGS

U.S. Army Munitions Command

F8245970	Mount, Telescope: M128
IEL-8245970	List of Inspection Documents for Mount, Telescope: M128

PACKAGING DATA SHEET

MIL-P-14232/P8245970 Packaging of Mount, Telescope: M128

FSC 1240

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:34Z
Check the source to verify that this is the current version before use.

(Copies of specifications, standards, drawings, and packaging data sheets required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Fabrication.- The mount shall be manufactured in accordance with Drawing F8245970 and drawings pertaining thereto.

3.2 General specification.- The contractor shall be esponsible for adherence to the following requirements of MIL-F-13926.

(a) Order of precedence
(b) Dimensions and tolerances
(c) Inorganic protective surface finishes
(d) Part identification and marking
(e) Workmanship

3.3 Environmental service conditions.

3.3.1 Extreme operating temperatures.- The mount shall meet the applicable requirements of 3.11 while exposed to, and thermally stabilized at, ambient temperatures of -40° and +150° Fahrenheit (F).

3.3.2 Standard ambient temPerature.- Unless otherwise speciified, the mount shall meet the following requirements while exposed to, and thermally stabilized at, a standard ambient temperature between +60° and +90°F.

3.3.3 Vibration.- The mount shall withstand a vibration of 30 ± 5 cycles per second (cps) frequency with an amplitude of 1/16 inch (1/8 inch maximum excursion) for a period of 5 minutes ± 15 seconds. Subsequent to vibration the mount shall show no evidence of damage or physical failure, and it shall meet all requirements of this specification.

3.4 Orientation.- The mount shall be positioned as follows to meet the requirements of 3.5 to 3.10.3 inclusive. Where line of sight is specified, the requirement shall be met with the line of sight entering the telescope mounting sleeve from the end adjacent to the angle of site knob.

(a) The flats of the mounting surface in a vertical plane.

(b) A line of sight through the geometric axis of the telescope mounting sleeve parallel to the flats of the mounting surface and horizontal.

(c) The elevation and cross level vial bubbles indicating level within one-half of one graduation.

(d) The coarse angle of site scale index indicating zero within one-half the width of the graduation line.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:34Z
Check the source to verify that this is the current version before use.

(e) The fixed coarse azimuth scale index indicating 3200 mils within one-half the width of the graduation line.

(f) The coarse elevation scale index indicating 800 mils within one-half the width of the graduation line.

(g) The indices for the fixed graduated scales on the angle of site, azimuth, and elevation knobs indicating zero within 0.2 mil.

3.5 Excursion range.

3.5.1 Angle of site.- Rotation of the angle of site knob shall cause the line of sight to elevate and depress a minimum of 200 mils from the position specified in 3.4.

3.5.2 Elevation.- Rotation of the elevation knob shall cause the line of sight to elevate a minimum of 800 mils and depress a - minimum of 1000 mils from the position specified in 3.4.

3.6 Plumb travel.

3.6.1 Angle of site.- Utilizing the angle of site knob, the line of sight shall track a plumb line within 0.5 mil when elevated and depressed through the range specified in 3.5.1 from the position speciried in 3.4. The total lateral spread shall not exceed 0.5 mil.

3.6.2 Elevation.- Utilizing the elevatio nknob, the line of sight shall track a plumb line within 0.5 mil when elevated and depressed through the range specified in 3.5.2 from the position specified in 3.4. The total lateral spread shall not exceed 0.5 mil.

3.7 Lateral and vertical displacement.

3,7.1 Angle of site.- Lateral displacement of the line of sight shall not exceed 0.2 mil when the elevation motion is reversed by means of the angle of site knob.

3.7.2 Elevation.- Lateral displacement of the line of sight shall not exceed 0.2 mil when the elevation motion is reversed by means of the elevation knob.

3.7.3 Azimuth.- Vertical displacement of the line of sight shall not exceed 0.2 mil when the azimuth motion is reversed by means of the azimuth knob.

3.8 Horizontal travel.- The ine of sight shall not vary in elevation in excess of 1.0 mil when rotated 6400 mils in azimuth by means of the azimuth knob.

3.9 Angular accuracy.

3.9.1 Open sight.- The line of sight of the open sight shall be parallel to the line of sight specified in 3.4(b) within 10 mils.

Source: https://assist.dla.mil -- Downloaded: 2026l0-22T05:34Z
Check the source to verify that this is the current version before use.

3.9.2 Angle of site.- The angle os site scales shall indicate elevation angles within 0.7 mil, excluding backlash at each reading, when the line of sight is elevated and depressed through the range specified in 3.5.1. This requirement shall be met with the readings taken at 100 mil increments from the position specified in 3.4.

3.9.3 Elevation.- The elevation scales shall indicate elevation angles within 0.7 mil, excluding backlash at each reading, when the line of sight is elevated and depressed through the range specified in 3.5.2. This requirement shall be met with the readings taken at 200 mil increments from the position specified in 3.4 (see 3.10.2).

3.9.4 Azimuth.- The fixed azimuth scales shall indicate azimuth deflection within 0.5 mi1, excluding backlash at each reading, when the line of sight is rotated through 6400 mils in azimuth. This requirement shall be met with readings taken at 800 mil increments from the position specified in 3.4 (see 3.10.3).

3.10 Backlash.

3.10.1 Angle of site.- Backlash in the angle of sith mechanism shall not exceed 0.5 mil.

3.10.2 Elevation.- When the amount of backhash at each elevation reading, taken in accordance with 3.9.3, is added to the elevation error at that setting, the sum shall not exceed 1.0 mil.

3.10.3 Azimuth.- When the amount of backlash at each azimuth reading, taken in accordance with 3.9.4, is added to the azimuth error at that setting, the sum shall not exceed 1.0 mil.

3.11 Operability.

3.11.1 Telescope clamping mechanism.- The telescope clamping mechanism shall be operable and, when actuated to a locked position, shall prevent movement of a 0.8435-0.0004 inch diameter surface (representative of the telescope body) when a 40 pound-inch torque is applied to the test piece. This requirement shall be met at the standard ambient temperature of 3.3.2 and while the mount is subjected to the extreme operating temperatures of 3.3.1.

3.11.2 Mount locking latch.- The mount locking latch shall be operable at the standard ambient temperature of 3.3.2 and while subjected to the extreme operating temperatures of 3.3.1.

3.11.3 Locking knobs.- Subsequent to rotating the elevation and azimuth locking knobs to a locked position with a 10 pound-inch torque, there shall be no movement in their respective mechanisms when an 8 pound-inch torque is applied to the elevation and azimuth knobs. This requirement shall be met at the standard ambient temperature of 3.3.2 and while the mount is subjected to the extreme operating temperatures of 3.3.1.

Source: https://assist.dla.mil -- Downloaded: 2026l0-22T05:34Z
Check the source to verify that this is the current version before use.

3,11.4 Azimuth slip scales.- The micrometer and coarse azimuth slip scales shall be operable at the standard ambient temperature of 3,3.2 and while subjected to the temperature requirements of 3.3.1.

3.11.5 Torque.- The torque required to rotate the knobs at the standard ambient temperature of 3.3.2 shall be within the values specified in Table I. The torque required while the mount is subjected to the extreme operating temperatures of 3.3,1 shall not exceed the respective value obtained at the standard ambient temperature by more than 50 percent.

TABLE I

TORQUE VALUES IN OUNCE-INCHES

	MINIMUM	MAXIMUM
Angle of site knob	4	32
Elevation knob	32	80
Azimuth knob	32	80

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.- Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1,1 General Provisions.- The component inspection requirements of MIL-F-13926 form a part of the Quality Assurance Provisions of this specification. Definitions of inspectio terms shall be as listed in MIL-STD-109.

4.2 Inspection Provisions.

4.2.1 Submission of Product.- Unless otherwise specified herein, or by the contracting officer, inspection lot size, lot formation and presentation of lots shall be in accordance with “Submission of Product” as specified in MIL-STD-105,

4.2.2 Examination and tests.- compo nents and subassemblies shall be inspected in accordance with the inspection provisions contained in MIL-F-13926 and the Supplementary Quality Assurance Provisions (SQAP) listed in the List of Inspection Documents, IEL 8245970. Examinations and tests related to Section 3 herein shall be performed on a defect (individual characteristic) basis in accordance with the “Classification of Defects” specified in Table II below and the inspection levels and sampling plans specified in MIL-STD-105. Examinations and tests for packaging, packing, and marking shall be in accordance with MIL-P-14232 and Section 5 herein. The tabulated classification of defects shall constitute the minimum inspection to be performed by

Source: https://assist.dla.mil -- Downloaded: 202610-22T05:34Z
Check the source to verify that this is the current version before use.

the supplier prior to Government acceptance or rejection by lot. The Government reserves the right to inspect for any applicable requirement, and to reject individual non-conforming items.

TABLE II. - CLASSIFICATION OF DEFECTS

		REQUIREMENT	TEST PROCEDURES
CRITICAL: NONE			
MAJOR: AQL 1.0%			
101.	Vibration	3.3.3	4.5.3
102.	Angle of site excursion	3.5.1	4.5.5
103.	Elevation excursion	3.5.2	4.5.6
104.	Angle of site plumb travel	3.6.1	4.5.5
105.	Elevation plumb travel	3.6.2	4.5.6
106.	Angle of site displacement	3.7.1	4.5.7
107.	Elevation displacement	3.7.2	4.5.8
108.	Horizontal travel	3.8	4.5.9
109.	Azimuth displacement	3.7.3	4.5.10
110.	Open sight	3.9.1	4.5.11
111.	Angle of site accuracy	3.9.2	4.5.12
112.	Elevation accuracy	3.9.3	4.5.13
113.	Azimuth accuracy	3.9.4	4.5.14
114.	Angle of site backlash	3.10.1	4.5.15
115.	Elevation backlash	3.10.2	4.5.15
116.	Azimuth backlash	3.10.3	4.5.15
117.	Telescope clamping mechanism (60° to 90°F)	3.11.1	4.5.16
MINOR: AQL 2.5%			
		REQUIREMENT	TEST PROCEDURE
201.	Mount locking latch (60° to 90°F)	3.11.2	4.5.17
202.	Locking knobs (60° to 90°F)	3.11.3	4.5.18
203.	Azimuth slip scales (60° to 90°F)	3.11.4	4.5.19
204.	Torque (60° to 90°F)	3.11.5	4.5.20

4.2.3 Acceptance and rejection.- Rejected lots shall be screened for all defective characteristics. Removal or correction of defective units and resubmittance of rejected lots shall be in accordance with "Acceptance and Rejection" as specified in MIL-STD-105.

4.3 Special sampling.

4.3.1 General.- One mount shall be selected at random by a Government representative as a sample from each 100 produced. The sample shall meet the requirements and tests in Table III.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:34Z
Check the source to verify that this is the current version before use.

TABLE III

CHARACTERISTICS	REQUIREMENTS	TEST PROCEDURES
301. Fabrication	3.1	Applicable drawings - visual
302. General specification	3.2	MIL-F-13926 - visual

4.3.2 Environmental.- Three units shall be selected at random by a Government representative as samples from each 50 produced or from each month's production, whichever occurs first. The samples shall have met the requirements and tests in Table 11 and shall then meet the requirements and tests in Table IV.

TABLE IV

CHARACTERISTICS	REQUIREMENTS	TEST PROCEDURES
303. Telescope clamping mechanism	3.11.1	4.5.16
304. Mount locking latch	3.11.2	4.5.17
305. Locking knobs	3.11.3	4.5.18
306. Azimuth slip scales	3.11.4	4.5.19
307. Torque	3.11.5	4.5.20

4.3.3 Failure of sample.- Should any one item of a special sampling fail to meet the specified test requirements, acceptance of the represented inspection lot will be suspended by the Government until necessary corrections have been made by the contractor and the resubmitted samples have been approved (see 4..2.3).

4.4 Inspection equipment.- Except as otherwise provided for by the contract, the contractor shall supply equipment in accordance with the applicable requirements of MIL-I-45607. The Government reserves the right to use the test equipment for its own independent inspections to the extent that such use will not unduly interfere with the contractor's delivery schedule.

4.4.1 Government furnished inspection equipment.- Where the contract provides for Government furnished test equipment, care and maintenance of test equipment shall be in accordance with the applicable requirements specified in MIL-1-45607.

4.4.2 Contractor furnished inspection equipment.

4.4.2.1 Government design.- All inspection equipment required by drawings forming a part of the contract and not provided by the Government shall be supplied by the contractor in accordance with the requirements of 4.4 and the List of Inspection Documents, IEL 8245970.

4.4.2.2 Contractor design.- The contractor shall provide inspection equipment compatible with the "Test methods and procedures" specified in 4.5 and with the "Component inspection" and "Test facili-

Source: https://assist.dla.mil -- Downloaded: 202610-22T05:34Z
Check the source to verify that this is the current version before use.

ties" requirements of MIL-F-13926. Since tolerance of test equipment is normally considered to be within 10% of the product tolerance for which it is intended, this inherent error in the test equipment design must be considered as part of the prescribed product tolerance limit. Thus, concept, construction, materials, dimensions and tolerances used in the design of test equipment shall be so selected and controlled as to insure that the test equipment will reliably indicate acceptability of a product which does not exceed 90% of the prescribed tolerance limit, and permit positive rejection when non-conforming. Construction shall be such as to facilitate routine calibration of test equipment.

4.5 Test methods and procedures.

4.5.1 Extreme operating temperatures.- The temperature cycling for the operability tests of the mounts at the specified temperature extremes shall be conducted in accordance with 3.3.1 and the "Test Facilities" of MIL-F-13926. When the mounts are thermally stabilized at-40° and +150°F, respectively, they shall be subjected to the operability tests specified in 4.5.16 to 4.5.20 inclusive.

4.5.2 Standard ambient temperature.- The mount shall pass the following tests while thermally stabilized at an ambient temperature between +60° and +90°F as specified in 3.3.2 and the "Test facilities" of MIL-F-13926.

4.5.3 Vibration. - Standard vibration equipment capable of providing the amplitude and frequency as specified in 3.3.3 shall be utilized for this test. The mount shall be vibrated in a vertical plane. Unless otherwise specified, the test equipment shall be in conformance with the "Test facilities" of MIL-F-13926.

4.5.3.1 Post vibration.- Subsequent to vibration the mount shall be thoroughly examined for physical defects resulting from poor workmanship and material to determine compliance with 3.3.3 prior to being subjected to the remaining tests specified herein. A visual examination shall be made for missing or damaged parts prior to being subjected to the remaining performance tests. Minimum visual examination shall include the level vials (also use smell test to detect a leaking vial resulting from a broken seal or glass), screws, nuts, etc. A tactile examination shall also be conducted to determine looseness or improper functioning of the elevation, azimuth, and angle of site knobs, the clamping mechanism, mounting latch, locking knobs, and azimuth slip scales. Any one of the possible defects defined above shall be cause to consider a mount defective. Mounts which have passed the above examinations shall be tested for all other requirements of this specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:34Z
Check the source to verify that this is the current version before use.

4.5.4 Orientation. - Orientation in conformance with the requirements of 3.4 is accomplished by using the elevation and cross leveling testing fixture, Drawing D23553. The fixture gage assembly, shown on Drawing D6510966, shall be assembled to the cross leveling fixture. An auxiliary telescope shall be placed on the V's_9 and the cross leveling fixture shall be leveled with a 10-second level for both directions in the horizontal plane. The auxiliary telescope shall be sighted on a wall target or in a target collimator by moving the fixture gage assembly. Place the perpendicularity gage, shown on Drawing D7646979, in the dovetail slot of the fixture gage assembly. Place the auxiliary telescope in the "V" slot and adjust for zero line" of sight in the vertical position. The telescope mount shall now be inserted and the settings adjusted as specified in 3.4.

4.5.5 Angle of site.- Locate a plumb line approximately fifty feet from the elevation fixture, and position the perpendicularity gage in the slot of the elevation fixture that is perpendicular to its axis. Place a collimating telescope of approximately six-power in the "V" slot of the perpendicularity gage. This will establish a line of sight through the telescope mounting sleeve. The mount shall then be placed in the slot as specified in 4.5.4. The angle of site knob shall then be utilized to track the plumb line in accordance with the tolerance specified in 3.6.1 and 3.5.1. A mil block chart located a the top or bottom of the plumb line shall be used to indicate any error. In cases where the plumb line is not long enough for full excursions the elevation fixture can compensate for full travel.

4.5.6 Elevation. - Use the same test equipment and test methods as in 4.5.5, except that the elevation knob shall be actuated instead of the angle of site knob for this test. The line of sight shall track the plumb line in accordance with the tolerances specified in 3.5.2 and 3.6.2.

4.5.7 Angle of site displacement. - This test may also be performied in conjunction with 4.5.5, using the same test equipmetn and setup. Actuate the angle of site knob and note the position of the line of sight to the mil block chart, then reverse the direction. Any lateral displacement of the line of sight shall not exceed the tolerance specified in 3.7.1.

4.5.8 Elevation displacement. - Use the same test equipment and test methods as in 4.5.7, except that the elevation knob shall be used instead of the angle of site knob for this test. Any lateral displacement of the line of sight shall not exceed the tolerance of 3.7.2.

4.5.9 Horizontal travel. - The horizontal travel test is performed with the aid of the azimuth test fixture shown on Drawing F7691596, the collimating telescope, and adapter assembly. The adapter assembly is attached to the mounting plate of the azimuth test fixture and provides a slot for positioning the mount. With the azimuth fix-

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:34Z
Check the source to verify that this is the current version before use.

ture crossleveled, the slot is positioned in a vertical plane with the perpendicularity gage. The test consists of checking the line of sight of the telescope mounting sleeve for deflection at 0,1100, 3200, and 4800 mil settings of the azimuth test fixture during a 6400 mil excursion of the mount in a horizontal plane. The error shall not exceed the requirements of 3.8.

4.5.10 Azimuth displacement.- This test may be combined with 4.5.9 above. A check for any vertical displacement shall be made at the four positions of the azimuth test fixture as described in 4.5.9. Vertical displacement of the line of sight shall not exceed the tolerance as specified in 3.7.3.

4.5.11 Open sight. - The open sight test is made by means of a wall chart located approximately fifty feet from the telescope mount. The chart shall have a mark for the line of sight through the telescope mounting sleeve, and a ten-mil radius circle the center of which will correspond to the center of the open sight. With the aid of the collimator focused on the line of sight mark, the open sight shall read within the limits as specified in 3.9.1.

4.5.12 Angle of site accuracy.- The angle of site accuracy test is made using the same equipment and method as used for the elevation error in 4.5.5. The 100 mil increment requirements of 3.9,2 are equivalent to 5 degrees 37-1/2 minutes as measured on the elevation fixture scale.

4.5.13 Elevation accuracy.- Elevation accuracy is ched using the same set-up as used for the plumb travel test of 4.5.6. In addition, a horizontal zero mark shall be located on a wall chart in back of the plumb line and in a horizontal plane with the line of sight through the telescope mounting sleeve. A mil block located above the line and one below will indicate the error for this test. With the mount located in the dovetail of the fixture, the cross lines of the collimator shall coincide with the zero mark of the wall chart. Elevate the fixture to 11 degrees 15 minutes (200 mils). Then rotate the elevation knob of the mount 200 mils. This should coincide the cross lines of the collimator with the horizontal mark of the wall target. Deviation can be read on the. mil blocks and shall be within the tolerance of 3.9.3. This operation shall be repeated for the entire scale reading at 200 mil increments.

4.5.14 Azimuth accuracy.- The azimuth accuracy test is made with the same set-up employed in the horizontal travel test of 4.5.9. With the mount and azimuth fixture set at zero and in alignment with the target collimator of the fixture, readings are taken in 800 mil increments through 6400 mils of travel and the deviation shall not exceed the requirements of 3.9.4.

4.5.15 Backlash. - Backlash shall be checked at positions where accuracy readings are taken on the targets described for these tests. The backlash test consists of sighting on the target through a collimating telescope installed on the mount, clockwise movement of each

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:34Z
Check the source to verify that this is the current version before use.

micrometer knob without over-travel, and then a counterclockwise movement without over-travel. The difference is readings of each movement shall be considered backlash. The tolerance of these tests shall not exceed the requirements of 3.10.1, 3.10.2, and 3.10.3.

4.5.16 Telescope clamping mechanism.- The telescope clamping mechanism is tested manually for operability at temperatures specified in 3.3.1 and 3.3.2. When clamped, the test piece as specified in 3.11.1 shall be firmly held in all positions when applying the speci fied torque, using a commercial torque wrench. Upon releasing the clamping mechanism, there shall be free movement in all directions.

4.5.17 Mount locking latch.- The locking latch shall be manually operable while subjected to the temperatures specified in 3.3.1 and 3.3.2 to determine compliance with 3.11,2.

4.5.18 Locking knobs. - Locking action of the elevation and azimuth locking knobs shall be checked at the temperatures specified in 3.3.1 and 3.3.2 for compliance with the requirements of 3,11.3, utilizing the commercial torque wrench with an adapter.

4.5.19 Azimuth slip scales. - The micrometer and coarse azimuth slipscales shall be examined by manually slipping the scales while subjected to the temperatures specified in 3.3.1 and 3.3.2 to determine compliance with 3.1,1.4.

4.5.20 Torque. - This test shall be performed using a commercial type inch-ounce torque wrench with adapters to accommodate the knobs. Readings taken with the torque wrench shall be taken in both directions and while in motion. The torque required to rotate the knobs as specified in Table I at standard ambient temperature shall not be exceeded by more than the requirement of 3.11.5 when tested at the extreme operating temperatures of 3.3.1.

5. PREPARATION FOR DELIVERY

5.1 Packaging, packing, and marking. - Packaging, packing, and marking shall be in accordance with MIL-P-14232 and Packaging Data Sheet MIL-P-14232/P245970. The level of protection shall be as specified in the procurement document.

6. NOTES

6.1 Intended use. - Telescope Mount: M128 is a component of SightunitL M53. The mount introduces measured azimuth, elevation, and angle of site readings to Elbow Telescope: M109. The sightunit is mounted on Mount Holder: XM7 and is primarily used to lay the weapon on self-propelled Mortars: T257E2 and XM106 and Multiple Rocket Launcher M91 for indirect fire.

Source: https://assist.dla.mil -- Downloaded: 2026l0-22T05:34Z
Check the source to verify that this is the current version before use.

6.2 Ordering data.- Procurement documents should specify the following:

(a) Title, number, and date of this-specification.
(b) Selection of applicable levels of preservation, packaging, and packing.
(c) Applicable stock number.
(d) Applicable packaging data sheet number (see 5.1).

Custodian:

Army - MU

Preparing activity:

Army - MU

Project No. 1240-A455Y

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:34Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity.

SPECIFICATION

ORGANIZATION	CITY AND STATE

CONTRACT NO.	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT
		$

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)*	DATE

DD FORM 1 OCT 64 1426

Source: https://assist.dla.mil -- Downloaded: 202610-22T05:34Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE ARMY

Frankford Arsenal
Philadelphia, Pa. 19137

OFFICIAL BUSINESS

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY

Commanding Officer
Frankford Arsenal
ATTN: SMUFA-N1100
Philadelphia, Pa. 19137

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:34Z
Check the source to verify that this is the current version before use.