MILITARY SPECIFICATION SHEET
CABLES FOR ATOMIC DEMOLITION CHARGES

W41-1(A)DM-E1 CABLE ASSEMBLY

The complete requirements for procuring the cable assembly described herein shall consist of this document and the latest issue of specification MIL-C-14982(MU).

1. SCOPE

1.1 This specification covers detail requirements, quality assurance provisions and preparation for delivery for production and repair parts for Cable Assembly W41-1(A)DM-E1 Training for use with Training Atomic Demolition Charge.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-C-14982(MU) - Cables for Training Atomic Demolition Charge, General Specification for

STANDARDS

MILITARY

NAS 1081 - Set Screw
NAS 1455 - Chain, Weldless, Flat Type, Link
MS20450 - Rivet
MS25281 - Clamp
MS27183 - Washer
MS87006 - Hooks

FSC 1195

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:18Z
Check the source to verify that this is the current version before use.

DRAWINGS

ORDNANCE CORPS

8838900 - Connector, Plug, Electrical
8838904 - Cap with Chain Dust
8851896 - Box, Set-up for W41-1(A)DM(TNG) Cable Assembly
9216278 - Coupling Ring, Extension
9216955 - Cable Assembly W41-1(A)DM-E1 Training
9217618 - Chemotec, Plastic Sealer
EL-9216955 - Equipment List

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Requirements. Requirements shall be in accordance with MIL-C-14982(MU) and as specified herein.

3.1.1 Deletions and additions to MIL-C-14982(MU). The following deletions and additions shall be made to MIL-C-14982(MU) requirements:

a. 3.8 Vibration. Delete last sentence and substitute: After completion of all testing, the cable assembly shall comply with 3.6 and 3.7.

b. 3.9 High temperature, 3.10 Low temperature and 3.11 Humidity. Delete: and shall comply with 3.6 and 3.7. Add sentence: After completion of all tests, the cable assembly shall comply with 3.6 and 3.7.

3.2 Circuit resistance. The cable assembly circuit resistance shall be in accordance with Table I.

TABLE I

Circuit Resistance (see dwg 9216955)

From	To	
P5-2	Field	Ohms
Connector	Wire	Max
Pin	One wire of each pair	0.2
Shell	Other wire of each pair	0.2

4. QUALITY ASSURANCE PROVISIONS

4.1 Sampling and inspection. Sampling and inspection shall be in accordance with MIL-C-14982(MU) and as specified herein.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:18Z
Check the source to verify that this is the current version before use.

4.1.1 Deletions and additions to MIL-C-14982(MU). The following deletions and additions shall be made to MIL-C-14982(MU) sampling and inspection.

a. 4.2.2 Inspection and testing to be performed. Delete last sentence and substitute: Circuit resistance and insulation resistance tests shall be performed after completion of all other tests and inspections. Otherwise, tests do not have to be performed in the order specified. Table I, Delete: X under contractor's inspection before submission and Non-destructive for circuit and insulation resistance tests. Add: X under Destructive for circuit and insulation resistance tests.

b. Delete: Bag, packing, ammunition for cable assembly (see 4.3.2.1.4).

c. 4.4.1 Circuit resistance (see 3.6). Add sentences at beginning of paragraph: This test shall be performed before molding ends of field wire in production test (see 4.3.3.1). In first article tests, cut off molded ends of field wire and strip ends of wire after completion of all other tests (see 4.2.2).

d. 4.4.2 Insulation resistance (see 3.7). Add sentences at beginning of paragraph: This test shall be performed before molding ends of field wire in production test (see 4.3.3.1). In first article test, cut off molded ends of field wire and strip ends of wire after completion of all other tests (see 4.2.2).

e. 4.4.5 Vibration (see 3.8), High temperature (see 3.9), Low temperature (see 3.10) and Humidity (see 3.11). Delete last sentence and substitute: After completion of all tests, the cable assembly shall comply with 3.6 and 3.7.

4.2 First article inspection.

4.2.1 Quantity to be submitted. In addition to quantities specified in 4.2/MIL-C-14982(MU), 3 sub-assemblies shall be submitted (see dwg. 9216955) cable assembly W41-1(A)DM-E1 before potting and molding.

4.3 Classification of characteristics.

4.3.1 Connector, plug, electrical (see dwg. 8838900); cap with chain, dust (see dwg. 8838904); coupling ring, extension (see dwg. 9216278); chematec, plastic sealer (see dwg. 9217618); set screw (see NAS 1081 C02D2); chain, weldless, flat type, link (see NAS 1455 BO-5); rivet (see MS20450C8AD12); clamp (see MS25281-3); washer (see MS27183-4); hooks (see MS87006-33) covering details of dwg. 9216955.

Categories	Characteristics	Method of Inspection
Critical:	None defined	

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:18Z
Check the source to verify that this is the current version before use.

Major

101. Objective evidence (see 6.3 MIL-C-14982(MU) available for part in accordance with applicable standard or drawing ---------- Visual

Minor

201. Workmanship (see 3.12 MIL-C-14982(MU) ---------- Visual-Manual

4.3.2 Cable assembly W41-1(A)DM-E1 training (see dwg. 9216955) before molding and potting.

Categories	Characteristics	Method of Inspection
Critical:	None defined	
Major		
101.	Length of cable	*Measure
102.	Field wire properly assembled	Visual
103.	Field wire laced correctly	Visual
104.	Knots coated with sealer	Visual
105.	Torque on nut of connector before applying sealer	Gage
106.	Sealer applied to nut	Visual
107.	Torque on set screws	Gage

* Measure with suitable scale

Minor: None defined

4.3.3 Cable assembly W41-1(A)DM-E1 training (see dwg. 9216955).

Categories	Characteristics	Method of Inspection
Critical:	None defined	
Major		
101.	Length to sleeve	*Measure
102.	Length of sleeve	*Measure
103.	Length of chain	*Measure
104.	Length of mold	*Measure
105.	Length from mold to end of molds on field wire	*Measure
106.	Length of molds on field wire	*Measure

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:18Z
Check the source to verify that this is the current version before use.

107.	Diameter of molds on field wire	*Measure
108.	Clamp tight on cable	Manual
109.	Material (see 3.2 MIL-C-14982(MU)	Visual
110.	Marking	Visual

*Measure with suitable scale

Minor

201.	Serialization (see 3.5 MIL-C-14982(MU)	Visual

4.4 Insulation resistance. The cable assembly insulation resistance shall be tested in accordance with Table II.

TABLE II

Insulation Resistance (see dwg. 9216955)

Positive Potential P5-2 Connector Pin	Negative potential to shell, connector pin and all other wires except
	One wire of each pair connected to pin

5. PREPARATION FOR DELIVERY

5.1 Preparation for delivery for production cable assemblies. Preparation for delivery for production cable assemblies shall be in accordance with MIL-C-14982(MU).

5.2 Preparation for delivery for repair cable assemblies.

5.2.1 Preservation and packaging. Preservation and packaging shall be as specified in MIL-C-14982(MU).

5.2.1.1 Level A. The cable assembly shall be packaged in accordance with dwg. 8851896 and 8808362 as specified in MIL-C-14982(MU).

5.2.1.2 Level C. The cable assembly shall be packaged in accordance with dwgs. 8851896 and 8808362 and MIL-C-14982(MU).

5.2.2 Packing.

5.2.2.1 Level A and C. The cable assembly shall be packed in accordance with dwgs. 8851896 and 8808362 and MIL-C-14982(MU).

5.2.3 Marking. Marking shall be as specified in dwgs. 8851896 and 8808362 and MIL-C-14982(MU).

6. NOTES

6.1 Notes. Notes shall be in accordance with MIL-C-14982(MU).

Custodian
Army MU

Preparing activity
Army MU
Project No. 1195-A045

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:18Z
Check the source to verify that this is the current version before use.