MILITARY SPECIFICATION

PROPELLANT M10
FOR 81MM MORTAR M205 PROPELLING CHARGE

This Amendment forms a part of Military Specification MIL-P-48130A(AR), 15 July 1982, and is approved for use by the US Army Armament, Munitions and Chemical Command, and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 4

4.3.1: Delete in its entirety and substitute a new paragraph as follows:

"4.3.1 Submission. The contractor shall submit a preproduction sample as designated by the Contracting Officer for evaluation in accordance with 4.3.2. The preproduction samples shall consist of up to three (3) pilot lots, approximately 100 pounds each, and shall expect to bracket the requirements of these specifications. The contractor shall advise the Procuring Contracting Officer (PCO) when a lapse of 90 days will be exceeded and request a determination for the submission of a new preproduction sample. A new sample, or a portion thereof, as directed by the PCO, shall be submitted whenever a change occurs in manufacturing process, material used, drawing, specification, or source of supply as to significantly affect product uniformity, loadability, or ballistic performance as determined by the Technical Agency (see 6.12)."

4.3.3: Delete in its entirety and substitute a new paragraph as follows:

FSC: 1376

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.

"4.3.3 Rejection. Government engineering, product assurance personnel, and the contractor shall review the pilot lots test data and shall select the granulation which best fits the requirements of these specifications. The Technical Agency shall notify the Contracting Officer of the selected granulation. The Contracting Officer shall designate the chosen pilot lot as accepted preproduction sample and shall authorize the contractor to produce the selected granulation. If none of the pilot lots submitted meets or brackets the requirements of these specifications, a new preproduction sample shall be submitted in accordance with 4.3.1. Until the preproduction sample is accepted, the contractor is in no way authorized by the Government to initiate regular production, unless otherwise directed by the Contracting Officer."

Custodian:
Army-AR

Preparing activity:
Army-AR

(Project 1376-A241)

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:14Z
Check the source to verify that this is the current version before use.

approved by the inspection element of the agency cognizant