MIL-A-11210G
AMENDMENT 2
2 December 1981
SUPERSEDING
INT. AMENDMENT 1(ME)
22 July 1981

MILITARY SPECIFICATION

AIR CONDITIONERS: BASE MOUNTED, SELF-CONTAINED,

MULTIPACKAGE-TYPE, AIR-COOLED, ELECTRIC-MOTOR-DRIVEN,

18,000 - BTU/HR

This amendment forms a part of Military Specification MIL-A-11210G, dated 4 March 1981, and is approved for use by all Departments and Agencies of the Department of Defense.

PAGE 2

STANDARDS, delete "MIL-STD-1474 - Noise Limits for Army Materiel."

PAGE 5

3.9, delete entire paragraph and substitute:

"3.9 Safety. The air conditioner shall have automatic safety controls to protect against overpressure and electrical overcurrent. The safety devices shall perform as described in 3.5.4, 3.12.3 and 3.14."

PAGE 8

3.23, delete entire paragraph.

PAGE 13 and 14

TABLE III, delete entirely and substitute:

FSC 4120

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:44Z
Check the source to verify that this is the current version before use.

"TABLE III. Test Schedule. 1/

Type of Test				Name of test	Inspection Paragraph	Requirement Paragraph
Insp. Seq.	Preprod.	Qual. Conf.	Init. Prod. and Insp. Comp.			
1	2	3	4	5	6	7
1	X	X	X	Examination.	4.6.1	3.1, 3.4, 3.13 3,15, 3.16, 3.18, 3.19, 3.20, and 3.25
2	X	X	-	Refrigerant-system pressure test.	4.6.3.2.1	3.11
3	X	X	-	Controls test.	4.6.3.3	3.12
4	X	X2/	-	Refrigerant moisture content test.	4.6.3.4	3.11
5	X	-	-	Electromagnetic interference.	4.6.3.16	3.17
6	X	X3/	-	Capacity and air flow test.	4.6.3.5	3.5.1, 3.5.3, 3.5.4, 3.5.5
7	X	-	-	Cycling test.	4.6.3.6	3.5.2
8	X	-	-	Evaporator coil frost.	4.6.3.7	3.5.2
9	X	-	-	High temperature operation.	4.6.3.8	3.5.2
10	X	-	-	High temperature storage.	4.6.3.9	3.6
11	X	-	-	Low temperature storage.	4.6.3.10	3.6
12	X	-	X	Rain.	4.6.3.11	3.8
13	X	-	-	Humidity.	4.6.3.12	3.7
14	X	-	-	Salt fog.	4.6.3.13	3.7
15	X	-	X	Controls	4.6.3.3	3.12
16	X	-	X	Motor protection	4.6.3.14	3.14
17	X	X	-	Production run-in.	4.6.3.15	3.10
18	-	-	X	Refrigeration-leakage.	4.6.3.2.2	3.11
19	-	-	X	Reliability (MTBF).	4.6.3.17	3.10
20	-	-	X	Maintenance evaluation.	4.6.3.18	3.22
21	-	-	X	Safety.	4.6.3.20	3.9

1/ Perform inspection marked "X".
2/ Test performed on first production unit. Contractor may certify remaining production units if the method for evacuating, dehydrating, and charging of refrigerant system is identical to first production unit.
3/ Test performed only if the production air conditioner fails test specified in 4.6.3.15."

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:44Z
Check the source to verify that this is the current version before use.

4.6.3.19, delete entire paragraph.

Custodians:
Army - ME
Navy - MC

Review activity:
DLA - GS

User activities:
Army - AT, MI, CR

Preparing activity:
Army - ME

Project 4120-0287

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:44Z
Check the source to verify that this is the current version before use.