MILITARY SPECIFICATION

BALLISTICS COMPUTER SUBASSEMBLY: 10543700
(COMMANDER'S CONTROL UNIT)

This amendment forms a part of Military Specification MIL-B-60598(MU), dated 15 September 1967.

Paragraph 3.5.5, Table I: Delete last line and substitute:

"2S9 .2 ohm 2J2-d 2J2-c"

Paragraph 3.5.6: Delete and substitute:

"3.5.6 Scale factor adjustments.- The scale factor adjustments of Drawing F10543700, Sheet 4 shall be confirmed. 2R4 and 2R9 shall be within ± .0005 of the ratio indicated. 2R10 shall be within ± .0002 of the ratio indicated. 2R3 shall be within ± .0003 of the ratio indicated."

Paragraph 3.5.7, Table II: Delete

"Zero .500000 ±.001388"

and substitute

"Zero .500000 ± .000550"

Paragraph 3.5.8, Table III: Delete and substitute:

TABLE III

"

RANGE KNOB SETTING	RATIO	RATIO TOLERANCE
3975 meters	.955483	± .001262
3000 meters	.721554	± .001262
2500 meters	.600829	± .001262
2000 meters	.480495	± .001262
1500 meters	.360488	± .001262
1200 meters	.288540	± .001262
1000 meters	.240566	± .001262
500 meters	.120485	± .001262
325 meters	.078394	± .001262"

FSC 1220

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:48Z
Check the source to verify that this is the current version before use.

Paragraph 4.2: Delete and substitute:

"4.2 First article (initial production) approval.- The requirement for first article approval and the responsibility (Government or contractor) for first article testing shall be as specified in the contract. The sample for first article approval tests shall consist of three control units plus three each of all items covered by SQAP. The sample shall be manufactured in the same manner, using the same materials, equipment, processes, and procedures as used in regular production. All parts and materials, including packaging and packing, shall be obtained from the same source of supply as used in regular production.

4.2.1 Government testing.- When the Government is responsible for conducting first article approval tests, the contractor, prior to submitting the sample to the Government, shall inspect the sample to insure that it conforms to all the requirements of the contract and submit a record of this inspection with the sample, including certificates of conformance for materials.

4.2.2 Contractor testing.- When the contractor is responsible for conducting first article approval tests, the sample shall be inspected by the contractor for all the requirements of the contract. The sample and a record of this inspection, including certificates of conformance for materials, shall be submitted to the Government for approval. The Government reserves the right to witness the contractor's inspection."

Paragraph 4.4.3: Delete and substitute:

"4.4.3 Failure of sample.- Should any one item of a special sampling fail to meet the specified test requirements, acceptance of the represented inspection lot shall be suspended by the Government until necessary corrections have been made by the contractor and resubmitted items have been approved (see 4.3.3)."

Paragraph 4.5.2.1: Delete and substitute:

"4.5.2.1 Government design.- Unless otherwise specified in the contract, all inspection equipment specified by drawing number in specifications or SQAP forming a part of the contract shall be supplied by the contractor in accordance with technical data listed in the technical data package (TDP)."

Paragraph 4.5.3, Item 5, Description: Delete "1.0% and substitute "3.0%".

Figure 1: Delete "L" on Connector 2J1 and substitute "L"; Delete Ratio Standard terminal designation "1.000000" and substitute ".000000"; Delete Ratio Standard terminal designation ".000000" and substitute "1.000000".

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:48Z
Check the source to verify that this is the current version before use.

Figure 2: Delete "Figure 2" and substitute revised "Figure 2" attached.

Custodian:

Army - MU

Preparing Activity:

Army - MU

Project No. 1220-A145

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:48Z
Check the source to verify that this is the current version before use.