INCH-POUND

MIL-H-62550(AT)
AMENDMENT 1
23 March 1990

MILITARY SPECIFICATION

HEATER ASSEMBLY, COMBUSTION VEHICULAR COMPARTMENT,
30,000 AND 60,000 BTU/HR, GENERAL SPECIFICATION FOR

This amendment forms a part of MIL-H-62550(AT), dated 22 September 1989, and is approved for use by the Tank-Automotive Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

The attached insertable replacement pages listed below are replacements for stipulated pages. When the new pages have been entered in the document, insert the amendment as the cover sheet to the specification.

Replacement page	Page replaced
15	Reprinted without change
16	16

PAGE 4

2.1.1: Add after MIL-STD-45662:

"(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Naval Publications and Forms Center, (ATTN: NPODS), 5801 Tabor Avenue, Philadelphia, PA 19120-5099.)"

PAGE 5

2.3: Delete and substitute:

"2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, (except for related associated detail specifications, specifications, or MS sheets), the text of this documents takes precedence. Nothing in this document however, supersedes applicable laws and regulations unless a specific exemption has been obtained."

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 202610-23T01:48Z
Check the source to verify that this is the current version before use.

PAGE 17

4.5.4: Delete and substitute:

"4.5.4 Failure disposition. Any examination defect shall be cause for the Government to refuse acceptance of the production quantity represented by the sample. Any deficiency found during, or as a result of QCI shall be evidence that all items represented by the sample are similarly deficient unless contrary evidence satisfactory to the Government is furnished by the contractor. Such deficiencies on all items shall be corrected by the contractor."

PAGE 26

6.8: Add:

"6.8 Process average. Sampling may be initiated if the process average value for the first 100 heaters inspected is less than 1% for major defects and less than 4% for minor defects. The process average should be calculated as follows:

$$\text{Process average} = \frac{\text{Number of defects}}{\text{Number of heaters inspected}} \times 100\%"$$

Custodian:
Army - AT

Preparing Activity:
Army - AT

(Project 2540-A018)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:48Z
Check the source to verify that this is the current version before use.

Approval of the first article sample shall not relieve the contractor of his obligation to supply heaters that are fully representative of those inspected as a first article sample. Any changes or deviation of the production units from the first article sample shall be subject to the approval of the contracting officer. Unless otherwise specified, the listing in table V does not imply any particular test sequence. Failure of the first article to meet any of the requirements specified herein will be cause for the Government to refuse to perform surveillance on additional testing until the fault(s) have been identified and corrected to the Government's satisfaction.

4.4.1 In-process inspections. During fabrication of the first sample production heater, an in-process inspection shall be conducted by the contractor under the surveillance of the Government inspector. Inspection shall be made at the contractor's facility prior to application of primer and paint. Processing and welding procedures, quality system, and inspection records shall be reviewed and evaluated during this inspection.

4.4.2 Production sample. After completion of inspection, the first sample production heater shall remain at the manufacturing facility, as a production sample, and be the last heater shipped on the contract, unless otherwise specified herein. The heater may be released sooner at the discretion of the contracting officer. The contractor shall service and maintain the heaters during this period. The heater subject to endurance testing shall not be used to fulfill production quantities of the contract.

4.4.3 First article inspection failure. The procuring agency shall determine whether a particular first article failure shall be treated as major or minor.

a. A major failure is a non-compliance with requirements specified herein by a functioning component, heat exchanger, or when corrective action requires a design change. As a minimum, the endurance or environmental test during which the deficiency surfaced shall be repeated. A complete first article test repeat of any or all units may be necessary at the discretion of the procuring agency.

b. A minor failure, in general, involves a non-compliance caused by a non-functioning component, a minor workmanship deficiency, or when design change is unnecessary. At most, a repeat of the endurance or environmental test which caused the failure shall be required.

c. The Government shall not accept delivery of any production units until all first article requirements have been satisfied.

Reprinted without change

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:48Z
Check the source to verify that this is the current version before use.

4.5 Quality conformance inspections (QCI). QCI shall consist of the examinations of 4.5.2 and the acceptance tests of 4.5.3. Nonconformance with any of the specified requirements in sections 3 and 5 shall be cause for rejection.

4.5.1 Lot formation. An inspection lot shall consist of all the heaters of one type and part number, from an identifiable production period, from one manufacturer, submitted at one time for acceptance.

4.5.1.1 Sampling for examination. Unless otherwise specified (see 6.2), sample size for quality conformance examination shall be determined in accordance with table VI. Before sampling may be initiated, the contractor shall inspect 100% of the first 100 heaters to establish that the process average (see 6.8) falls within the control limits.

TABLE VI. Sampling inspection.

Sampling lot size	Sample size for Majors	Sample size for Minors
2 to 8	*	3
9 to 25	13	3
26 to 50	13	5
51 to 90	13	6
91 to 150	13	7
151 to 280	20	10
281 to 500	29	11
501 to 1200	34	15

* Indicates entire lot must be inspected.
NOTE: The acceptance number in all cases is zero.

4.5.2 Examination. Sample units shall be examined for the defects specified in table VII.

4.5.2.1 Failure disposition. Any examination defect shall be cause for the Government to refuse acceptance of the production quality represented by the sample size.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:48Z
Check the source to verify that this is the current version before use.