INCH - POUND

MIL-PRF-32109(CR)
16 September 2002

PERFORMANCE SPECIFICATION

FLOODLIGHT SET, ELECTRIC, PORTABLE

1. SCOPE

1.1 Scope. This specification covers a floodlight set that provides a minimum of 160,000 mean lumens mounted on an adjustable height floodlight mast.

2. APPLICABLE DOCUMENTS

2.1 General. The documents listed in this section are specified in sections 3 and 4 of this specification. This section does not include documents cited in other sections of this specification or recommended for additional information or as examples. While every effort has been made to ensure the completeness of this list, document users are cautioned that they must meet all specified requirements documents cited in sections 3 and 4 of this specification, whether or not they are listed.

2.2 Government documents.

2.2.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are listed in the issue of the Department of Defense Index of Specifications and Standards (DoDISS) and supplement thereto, cited in the solicitation (see 6.2).

STANDARDS

DEPARTMENT OF DEFENSE

MIL STD-209	-	Slinging and Tie down Provisions for Lifting and Tying Down Military Equipment.
MIL-STD-810	-	Environmental Test Methods and Engineering Guide Lines
MIL STD-1472	-	Department of Defense Design Criteria Standard, Human Engineering

(Unless otherwise indicated, copies of the above specifications, standards are available from the Document Automation and Production Service, Building 4D (DODSSP/ASSIST), 700 Robbins Avenue, Philadelphia, PA 19111-5094).

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Communications-Electronics Command, ATTN: AMSEL-LC-LEO-E-EP, Fort Monmouth, NJ 07703-5023 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC FSC 6230

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T04:47Z
Check the source to verify that this is the current version before use.

2.3 Non-Government publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DoDISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DoDISS are the issues of the documents cited in the solicitation (see 6.2).

ASTM International

ASTM D4169	-	Containers and Systems, Shipping, Performance Testing of

(Application for copies should be addressed to the ASTM International, 100 Barr Harbor Drive, P.O. Box C700, West Conshohocken, PA 19428-2959. Telephone: (610) 832-9585, Fax: (610) 832-9555.)

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

AB 1	-	Molded Case Circuit Breakers.
WD 5	-	Specific- Purpose Wiring Devices.

(Application for copies should be addressed to Global Engineering Documents, 15 Inverness Way East, Englewood, CO 80112. Telephone 1-800-854-7179.)

NATIONAL FIRE PROTECTION ORGANIZATION (NFPA)

NFPA 70	-	National Electrical Code.

(Application for copies should be addressed to NFPA, 1 Batterymarch Park, P.O. Box 9101, Quincy, MA 02269-9101. Telephone (617) 770-3000, Fax (617) 770-0700)

SOCIETY OF AUTOMOTIVE ENGINEERS (SAE)

SAE Aerospace Recommended Practice (ARP) 1328, Rev A

(Application for copies should be addressed to Society of Automotive Engineers, Inc., 400 Commonwealth Drive, Warrendale, PA 15096.)

UNDERWRITERS' LABORATORIES, INC. (UL)

UL 489	-	Molded-Case Circuit Breakers and Circuit-Breaker Enclosures.
UL 498	-	Electrical Attachment Plugs and Receptacles

(Application for copies should be addressed to comm. 2000, 1418 Brook Drive, Downers Grove, IL 60515. Telephone 1-888-853-3503.)

2.4 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T04:47Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Description. The man portable, externally powered floodlight set (hereinafter called "floodlight set") shall consist of a light source(s) that provides a minimum of 160,000 total mean lumens, lights shall be mounted on a mast, provision shall be made for mounting on various soil conditions, including frozen ground, soft mud and sand. All components shall be designed/designated for outdoor use. Floodlight set shall include durable containers for transport and storage of floodlight components. Assembly and operation must be practical for personnel wearing leather work gloves, cold weather gloves, mittens, or MOPP4. Time required to unpack and erect floodlight shall not exceed 1 hour, personnel requirements not to exceed four people. Floodlight shall be operable with both 110 VAC and 220VAC single- phase power sources. Maximum power consumption shall not exceed 3KW. The floodlight set shall be complete with all components and accessories necessary for operation and storage under the conditions specified herein. The contractor shall be responsible for design of the floodlight set. When first article is specified (6.2), sample(s) shall be subject to First Article Inspection (4.2).

3.1.1 Tie down/lift points. Tie down devices shall be provided to allow tie down of containers for transportation. Lifting points shall be provided to allow lifting of the floodlight set containers. Lifting and tie down attachments shall conform to MIL-STD-209, for type I equipment. Lifting and tie down provisions shall be indicated by a plate conforming to the vehicle shipping data plate described in MIL-STD-209. The lift and tie down provisions shall be identified by decals, in letters not less than 1 inch in height.

3.2 First article. The manufacturer shall furnish a sample(s) for first article inspection, test, and approval when specified in the contract or purchase order (see 6.2).

3.3 Operating requirements. The floodlight set shall conform to the following operating requirements:

3.3.1 Weight. The maximum weight of any container shall not exceed 147 lbs. (147 lbs is under the four man lift; and above the one man and three woman lift.) Total weight of all containers shall not exceed 1000 lbs.

3.3.2. Dimensions/volume of all containers. Transport/storage containers shall be man portable and shall be stowable in an M998A1 HMMWV. Acceptable dimensions for transport/storage containers include 40 inches by 50 inches by 32 inches high.

3.3.3 Test of containers. Containers shall be tested as specified in 4.5.2.

3.3.4 Operating Procedure Test. When tested as specified in 4.5.3, the floodlight set shall operate at full capacity, without damage, for not less than 18 hours continuous.

3.3.5 Environmental conditions.

3.3.5.1 Operational conditions. When tested as specified in 4.5, the floodlight set and/or containers shall operate at full capacity without damage under the following conditions:

a. Temperatures from minus 25 degrees F to plus 125 degrees F.
b. Relative humidity up to 100 percent.
c. Rain (spray).
d. Shock to containers (rail impact).
e. Packed container drop – 4 ft. (Note: allows for/exceeds drop from 38 in height of HMMWV cargo deck).
f. Packed container - Vehicle Stacking IAW ASTM D 4169, paragraph 11.2
"F" Factor Assurance Level = 8.
g. Packed container – Vehicle Vibration IAW ASTM D 4169, paragraph 12.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T04:47Z
Check the source to verify that this is the current version before use.

3.3.5.2 Wind (tower strength and floodlight set stability). When tested as specified in 4.5.5, the fully erected floodlight set shall withstand, without damage, 50 miles per hour (mph) winds, and shall not overturn.

3.3.5.3 Ease of maintenance. All components that require servicing or maintenance shall be readily accessible for maintenance, repair, and replacement. Covers or plates that must be removed for component adjustment, repair, replacement, or maintenance shall be equipped with quick-disconnect fasteners. System design shall permit lamp replacement by one person in not more than 15 minutes. Reliability, Availability, Maintainability (RAM): System shall be fully functional at least 90% of operational time (operational time = 1040 hours/year).

3.4. Components.

3.4.1 Lights. Total light output shall be a minimum of 160,000 mean lumens. Each floodlight shall consist of a weatherproof housing and a reflector. Each floodlight shall have a lateral beam spread of not less than 105 degrees and a vertical beam spread of not less than 75 degrees. Each floodlight shall be provided with a keyless lamp holder to accommodate the appropriate bulb . Each floodlight shall rotate through an arc of not less than 120 degrees in the vertical plane, each floodlight shall be adjustable (directly or via mast rotation) to an arc of not less than 360 degrees in the horizontal plane. Identification markings shall be stamped or molded on the floodlight housing to indicate to the using personnel the approximate setting of the floodlight in the vertical plane. Lamp life (rated average life) will exceed 10,000 hours. Each lamp shall be designed to operate in a nominal horizontal position. Only lamps that produce a white light shall be used. Elapsed time for lamp restrike shall not be greater than 20 minutes. Failure of any one bulb shall not affect operation of remaining lamps. Provision shall be made to stow at least one spare bulb in one of the storage/transport containers.

3.4.2 Mast. The mast shall be fabricated such that that when in the vertical (operating) position, it is adjustable from a fully retracted position of not more than 10 feet above the ground, to a minimum of 25 feet above the ground. The mast, with the light source(s) mounted thereon, shall be capable of rotating 360 degrees in either direction when in the upright operating position. The mast shall have components necessary to promote smooth, even tower rotation, extension, and retraction. The mast shall be constructed so that not more than four persons are required to raise or elevate the tower from the horizontal position to the vertical position, lock the tower in the vertical position, and extend the tower to the maximum height in not more 30 minutes, with no more than 30 pounds of force required to operate any control mechanism. The mast shall incorporate safety features to assure that the tower is completely under the control of the operator during elevating, extending and retracting operations. If a hand winch is used to raise and lower the mast, the mast winch mechanism shall be corrosion protected and the cable shall be manufactured from durable corrosion resistant material. The mast shall have structural strength to withstand 50 mph winds from each cardinal direction, with the light source(s) mounted thereon. Mounting means shall be provided for safe and reliable operation of the mast on various soil conditions including: frozen ground, soft mud and sand. If multiple lamps are used, spacing between fixtures shall be sufficient to prevent interference of lamps and associated hardware

3.4.3 Storage/transport containers. Containers shall be man-portable. Containers shall be constructed for one to four person lift. For one-person lift, containers with stored components shall weigh less than 37 lbs. Maximum weight of any one container, including stored components, shall not exceed 147 lbs. Handles and grasp areas shall be IAW MIL-STD-1472. Relation between weight and dimensions shall be IAW MIL STD-1472. Containers shall be designed with internal storage compartments for all components and external tie downs to secure the container(s) to transport vehicles. Each packed container shall be capable of withstanding load and vibration IAW ASTM D 4169. Packed containers shall withstand a four ft drop to each side.

3.4.4 Cables. Cables shall terminate in properly sized weatherproof, grounding and locking type plugs or receptacles conforming to UL 498 and NEMA WD 5. Floodlight design shall incorporate means to prevent entanglement of the power cable when the mast is raised or lowered.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T04:47Z
Check the source to verify that this is the current version before use.

3.4.4.1 Connectors. Connectors if used, shall have locking type cord plugs with weatherproof covers. Any electrical supply ends shall interface with the weatherproof junction box. The cord plug shall conform to UL 498 and NEMA WD 5.

3.4.4.2 Conductors. Conductors for interconnecting wiring if used, shall have a flame-retardant and oil-resistant covering conforming to NFPA No. 70. Extra-flexible conductors shall be used where relative movement between parts may occur. Conductors shall be clamped in a neat manner and protected by grommets or other protection from abrasion where the conductors pass through any wall.

3.4.5 Grounding rod and wire. A grounding rod of not less than 8 feet in length and not less than ½ inch in diameter shall be provided. Driver/puller and tools for couplings shall be provided. A grounding wire of not less than 6 feet in length shall electrically connect the grounding rod to the mast. The grounding rod and mast shall each provide a means for attaching the grounding wire. Grounding rod and wire materials and plating shall safely conduct lightning currents and voltages. There shall be no requirement for special tools for this system.

3.4.6 Power control panel. The power control panel shall include Ground Fault Circuit Interruption (GFCI) circuit breakers and on-off switches of sufficient capacity to safely control lighting loads. The circuit breakers shall conform to NEMA AB 1 and UL 489, and shall have trip ratings as required for the application to protect against overloads, short circuits, and deficient grounds in accordance with NFPA 70. The inside of the control panel compartment shall be protected from dust and rain. The panel shall be mounted on the floodlight set in a readily accessible location (with the operator standing on the ground).

3.5 Ancillary equipment. The floodlight set shall be provided with a ground rod, a ground rod driver/puller, an engineer's 8-pound sledgehammer, 100 foot extension cord and tools required to operate and maintain the floodlight set.

3.6 Fungus and moisture resistance. The electrical circuitry including all components and connections, except as specified below, shall be protected from the effects of fungus growth and moisture by an overall treatment with adequate protective coating:

a. Components or circuit elements that are inherently fungus and moisture resistant or which are hermetically sealed, need not be treated.
b. Components or circuit elements whose functions will be adversely affected by the protective coating shall not be treated.

3.7 Identification marking. An identification plate shall be permanently affixed in a location where the plate will be both visible and legible for the life of the floodlight set. The plate shall include the following information: nomenclature (Floodlight), model number, serial number, manufacturer's name, date of manufacture, contract number, and National Stock Number.

3.8 Instruction plate. The floodlight set shall be equipped with an instruction (operation) plate(s), including warnings and cautions, describing the procedures to be followed in assembling, operating, and operator preventative maintenance checks and services for the floodlight set. Figures may be used in conjunction with the text. The instruction plate(s) shall be permanently affixed to the storage/transport containers in a location where the plate will be both visible and legible. The plate shall be of a material that will last and remain legible for the life of the floodlight set.

3.9 Schematic and wiring diagrams. A legible, permanent schematic and wiring diagram(s) shall be mounted adjacent to the operating instructions. The schematic diagram shall show the complete operational and functional sequence of the circuit for analysis and maintenance of the floodlight set. The wiring diagram shall show the physical location of all wiring interconnections in the same relationship in which they are installed. Identification marking or control devices and connections shall be shown in both diagrams and shall coincide with markings on all items being identified.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T04:47Z
Check the source to verify that this is the current version before use.

3.10 Assembly and operation test. The floodlight set shall be capable of being assembled, raised and operated as specified in 4.5.6.

3.11 Shipping data plate. A shipping data plate shall be supplied, permanently attached to the floodlight containers, to provide transportation data and to identify slinging and tie down provisions. The plate shall contain for each container and for total system, at a minimum, the following information:

a. Gross shipping weight, in pounds.
b. Shipping cube, expressed in cubic feet.
c. Overall length, width, height.
d. Any cautions or warnings that must be observed for transport.

3.12 Technical manual. Unless otherwise specified, commercial type operator/maintainer manuals shall be provided. Commercial manuals shall be authenticated by the Government to ensure that they include appropriate operator and maintenance instructions.

3.13 Treatment and painting. Color shall be specified by contract. External surface shall be protected against environmental conditions as stated in paragraph 4.5.4.

3.13.1 Unpainted surfaces. The Lens of the floodlight housing, and power cables shall not be painted and shall withstand environmental conditions stated in paragraph 4.5.4. Mast assembly sliding portions, if utilized, shall not be painted and shall withstand environmental conditions stated in paragraph 4.5.4.

3.14 Workmanship.

3.14.1 Metal fabrication. The metal used in fabrication shall be free from kinks, sharp bends, and other conditions, which would be deleterious to the finished product.

3.14.2 Bolted connections. Bolt holes, if used, shall be accurately punched or drilled and shall have the burrs removed.

3.14.3 Riveted connections. Rivet holes, if used, shall be accurately punched or drilled and shall have the burrs removed.

3.14.4 Welding. If welding is utilized, the surface of parts to be welded shall be free from rust, scale, paint, grease, or other foreign matter. Welds shall be of sufficient size and shape to develop the full strength of the parts connected by the welds. Welds shall transmit stress without permanent deformation of the parts connected by the welds are subjected to proof and service loadings.

4. VERIFICATION

4.1 Classification of inspection. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.2)
b. Conformance inspection (see 4.3)

4.2 First article inspection.

4.2.1 First article inspection. When specified in the contract, the first article inspection shall be performed on one or more floodlight sets (see 6.2). This inspection shall include (i.) the examination of 4.4, listed in Table I, and (ii.) the tests of 4.5. The first article may be either a first production item(s) or a standard production item(s) from the supplier's current inventory provided the item meets the requirements of the specification and is representative of the design, construction, and manufacturing technique applicable to the remaining items to be furnished under the contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T04:47Z
Check the source to verify that this is the current version before use.

4.3 Conformance inspection. The conformance inspection shall include the examination of 4.4, and the tests of 4.5. This inspection shall be performed on the samples selected in accordance with the contract (see 6.2).

4.4 Examination. Each floodlight shall be examined for compliance with the requirements specified in section 3 of this document. Any redesign or modification of the contractor's standard product to comply with specified requirements, or any other redesign or modification following failure to meet specified requirements shall receive particular attention for adequacy and suitability. This element of inspection shall encompass all visual examinations and dimensional measurements as listed in Table I. Noncompliance with any specified requirements or presence of one or more defects preventing or lessening maximum efficiency shall constitute cause for rejection.

Table I. First article and quality conformance inspection.

Defects	Requirement/Paragraph
Weight not as specified.	3.3.1
Dimensions not as specified.	3.3.2
Ease of maintenance not as specified.	3.3.5.3
Components missing or not as specified.	3.4
Floodlights not as specified.	3.4.1
Mast not as specified.	3.4.2
Containers not as specified.	3.4.3
Wiring not as specified.	3.4.4
Mast / power control panel not as specified electrical cables, plugs, and receptacles not as specified.	3.4.6
Ancillary equipment not as specified	3.5
Fungus and moisture resistance not as specified.	3.6
Identification plate not as specified.	3.7
Instruction plate not as specified.	3.8
Schematic and wiring diagrams not as specified.	3.9
Assembly and operation capability not as specified	3.10
Shipping data plates not as specified.	3.11
Technical manual not furnished as specified.	3.12
Treatment and painting not as specified.	3.13
Unpainted surfaces not cleaned and treated as specified	3.13.1

4.5 Tests. Unless otherwise specified, the first articles floodlight set shall be tested as specified herein. Failure of the floodlight set to meet requirements of the test herein, even though not performing a test directly related to the specific requirement, shall constitute cause for rejection. The contractor is responsible for providing certification or evidence of conformance to all the requirements specified.

4.5.1 Test conditions. Unless otherwise specified in a test, tests shall be performed without shelter under the climatic conditions existing at the place of test, power will be provided by an engine-driven generator set or commercial power, with the floodlight set in the normal operating configuration.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T04:47Z
Check the source to verify that this is the current version before use.

4.5.2 Test of containers. With the floodlight components in their storage/transport containers, perform the following tests:

a. High temperature. The test temperature shall be 125 degrees F, +/_ 5 degrees F, IAW MIL-STD 810, Method 501. Once container temperature stabilization has been achieved, visually inspect the containers for evidence of damage or deformation. Nonconformance to 3.3.5.1 shall constitute failure of this test.

b. Low Temperature. The test temperature shall be minus 25 degrees F, +/_ 5 degrees F, IAW MIL-STD 810, Method 502. Once container temperature stabilization has been achieved, , visually inspect the containers for evidence of damage or deformation. Nonconformance to 3.3.5.1 shall constitute failure of this test.

c. Humidity. The containers shall be subjected to relative humidity as close to 100 percent as possible but not less than 95 percent. The relative humidity shall be maintained for 4 hours. Temperature shall be IAW MIL-STD-810, Method 507. At the end of four hours, visually inspect the containers set for evidence of water penetration and internal condensation. Nonconformance to 3.3.5.1 shall constitute failure of this test.

d. Rain Spray. Spray all the exposed surfaces of the containers with water, of at least 40 pounds per square inch water pressure, for not less than 15 minutes per side. After the 1-hour spray period, visually inspect the containers for evidence of water penetration. Nonconformance to 3.3.5.1 shall constitute failure of this test.

e. Drop test. Containers shall be dropped at least a distance of 4 feet onto hard pavement, drops shall be done at least once to each side, edge and corner of each container. Visually inspect the containers for evidence of damage. Nonconformance to 3.3.5.1 shall constitute failure of this test.

f. Stacking and vibration test on packed containers. Calculations shall be either IAW ASTM D 4169 or IAW MIL-STD-810, method 514.5 Procedure 1 (General Vibration) with test period equal to or greater than 40 minutes. After application of load and vibration to containers, visually inspect containers and contents for damage. Nonconformance to 3.3.5.1 shall constitute failure of this test.

Upon completion of all container tests, the floodlight set shall be operated as specified in 4.5.3 below.

4.5.3 Eighteen-hour Floodlight Set operating test. Perform the following operating procedures:

a. Unpack containers.
b. Assemble set and conduct pre-operations inspections, per manual.
c. Connect to power source.
d. Operate winch, if so equipped, to raise tower to maximum height.
e. Activate lights. Operate the floodlight light set at full capacity i.e. all lights full on for not less than 18 hours continuous. After 18 hours of operation, perform the following shutdown procedures:
f. Disassemble system and repack components in the system transport/storage containers. Nonconformance to 3.3.4 shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T04:47Z
Check the source to verify that this is the current version before use.

4.5.4 Environmental tests. The floodlight set shall be subjected to the following tests:

a. High temperature. The test temperature shall be 125 degrees F, +/_ 5 degrees F, IAW MIL-STD 810, Method 501. Once floodlight set temperature stabilization has been achieved, the set shall be set assembled and operated as specified in 4.5.3 paragraphs c thru f, at full capacity. The floodlights shall be illuminated for a minimum of 2 hours. The test temperature shall be maintained at 125 degrees F, +/_ 5 degrees F during operation of the floodlight set. Nonconformance to 3.3.5.1 shall constitute failure of this test.

b. Low Temperature. The test temperature shall be minus 25 degrees F, +/_ 5 degrees F, IAW MIL-STD-810, Method 502. Once floodlight set temperature stabilization has been achieved, the set shall be assembled and operated as specified in 4.5.3.c thru .f, at full capacity. The floodlights shall be illuminated for a minimum of 2 hours. The test temperature shall be maintained at minus 25 degrees F during operation of the floodlight set. Nonconformance to 3.3.5.1 shall constitute failure of this test.

c. Humidity. The floodlight set shall be subjected to relative humidity as close to 100 percent as possible but not less than 95 percent. IAW MIL-STD-810, Method 507.5: test shall run five 48-hr cycles with the set assembled. Operational testing shall be accomplished at the end of cycle 3 and 5. Nonconformance to 3.3.5.1 shall constitute failure of this test.

d. Rain (spray). Perform test IAW MIL-STD 810, Method 506. With the floodlight set in the operating position, except with all floodlight set switches OFF and the tower vertical but not raised to the maximum height, spray all the exposed surfaces of the floodlight set with water, at 40 pounds per square inch minimum water pressure, for not less than 15 minutes per side. After the 1-hour spray period, visually inspect the floodlight set for evidence of water penetration. Within 30 minutes of the time the spray period ended, operate the floodlight set at full capacity for not less than 1 hour. Nonconformance to 3.3.5.1 shall constitute failure of this test.

4.5.5 Wind test. With the floodlight mast erected and vertical, the mast (with floodlights attached), shall be raised to its maximum height. Readjust as necessary to keep the floodlight set level. While the mast is fully extended, a static horizontal force, of magnitude to simulate a 50 mph wind, shall be applied to the mast to determine conformance to rigidity, construction, and stability requirements. The force shall be directed in each of the four cardinal points and distributed to points spaced over the height of the tower. The force shall consist of the force due to the floodlight surface area (force A), and the force due to the wind load over the height of the mast (force B). Force A shall be applied at the top of the mast , force B shall be distributed to other points on the mast. The force shall be as designated by the test agency for the type and height of the tower, and the type of floodlights used. Wind, Force, Overturn Moment calculations shall be as described by Society of Automotive Engineers (SAE), Aerospace Recommended Practice (ARP) 1328, Rev A (Aug 17, 1999). A Safety Factor of two shall be applied to the wind speed with dimensional/configuration elements (S,H,C) held constant. Two times the fifty mph wind corresponds to a wind speed of 100 mph, i.e. wind forces are calculated and tested for a 100 mph steady state wind condition. The floodlight set shall be tested in each cardinal direction for a total of four tests. The force shall be gradually applied and maintained for five minutes at the required value. After testing in all cardinal directions, the tower shall be lowered and raised. Nonconformance to 3.3.5.2 shall constitute failure of this test

4.5.6 Assembly and operation test. Tests shall be performed to confirm that the floodlight set can be erected and operated on sand, soft mud and hard surface conditions as required in 3.10.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T04:47Z
Check the source to verify that this is the current version before use.

5. PACKAGING

5.1 Packaging. For acquisition purposes, the packaging requirements shall be as specified in the contract or order (see 6.2). When actual packaging of materiel is to be performed by DoD personnel, these personnel need to contact the responsible packaging activity to ascertain requisite packaging requirements. Packaging requirements are maintained by the Inventory Control Point's packaging activity within the Military Department or Defense Agency, or within the Military Department's System Command. Packaging data retrieval is available from the managing Military Department or Defense Agency's automated packaging files, CD-ROM products, or by contacting the responsible packaging activity.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The floodlight set is intended to provide lighting for military police, construction, maintenance, and other combat service and combat service support activities as required.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number and date of the specification.
b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.2 to 2.3).
c. Packaging requirements (see 5.1)
d. When first article inspection is required, the contracting officer should specify which examination and tests will be conducted by the Government and which examination and tests will be Conducted by the contractor (see 4.1 to 4.5.6).

6.3 First article inspection. The first article should consist of at least one unit.

6.4 Definitions. The following definitions apply throughout this specification:

6.4.1 Operational Weight. The operational weight of the floodlight set total weight of all system containers with components packed

6.4.2 Floodlight set operation. Operation of the floodlight set should include the following procedures:

6.4.2.1 Operating procedures.

a. Unpack containers, and assemble/erect floodlight set.
b. Connect to power source
c. Turn power source ON.
d. Turn main circuit breaker, and
floodlights breakers on control panel to ON, allowing 5-second intervals on each floodlight.
e. Operate winch, if so equipped, to raise tower to maximum height.

6.4.2.2 Suggested shutdown procedures.

a. Retract tower to the minimum vertical (operating) height..
b. Set floodlight breakers, and main Circuit breaker on control panel to OFF.
c. Turn power source OFF.
d. Remove floodlights and store in container storage area.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T04:47Z
Check the source to verify that this is the current version before use.

6.4.3 Damage. Damage is deformation, loosening, breakage, change of fit of any component or part, corrosion, water penetration, or any condition resulting in malfunction of the floodlight set or any component part.

6.5 Subject term (key word) listing.

Externally powered
Light source
Mast

Custodians:
Army - CR

Review activity:
DLA – IS

Preparing Activity
Army – CR
(Project 6230-1087)

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T04:47Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.

2. The submitter of this form must complete block1s 4, 5, 6, and 7, and send to preparing activity.

3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	**1. DOCUMENT NUMBER** MIL-PRF-32109(CR)	**2. DOCUMENT DATE** (YYMMDD) 16 September 2002

3. DOCUMENT TITLE Floodlight Set, Electric, Portable

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Incl Area Code) (1) Commercial (2) DSN (If applicable)	7. DATE SUBMITTED (YYYYMMDD)

8. PREPARING ACTIVITY

a. NAME US Army Communications-Electronics Command	b. TELEPHONE (Include Area Code) (1) Commercial (732) 532-9104 (2) DSN 992-9104
c. ADDRESS (Include Zip Code) ATTN: AMSEL-LC-LEO-E-EP Fort Monmouth, NJ 07703-5023	**IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT:** Defense Standardization Program Office (DLSC-LM) 8725 John J. Kingman Road, Suite 2533 Fort Belvoir, Virginia 22060-6221 Telephone (703) 767-6888 DSN 427-6888

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T04:47Z
Check the source to verify that this is the current version before use.