MIL-T-47302A
13 August 1987
Superseding
MIL-T-47302(MI)
20 April 1979

MILITARY SPECIFICATION

TEST SET, ELECTRICAL, MK III

This specification is approved for use within the U.S. Army Missile Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification establishes the requirements for the fabrication, inspection and testing of the MK III Electrical Test Set. The test limits in this specification do not necessarily define maximum capabilities. The MK III Electrical Test Set is a self-contained, multipurpose test set powered by a rechargeable battery. It is used with the HYDRA 70 FFAR system (less rockets) and any other system utilizing the MK I squib or a similar device. This test set shall not be used on any ordnance.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

*2.1.1 Specifications and standards. The following specifications and standards form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of these documents shall be those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commander, U.S. Army Missile Command, ATTN: AMSMI-RD-SE-TD-ST, Redstone Arsenal, AL 35898-5270, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 4927
DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:08Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

MILITARY

MIL-E-17555	Electronic and Electrical Equipment, Accessories, and Provisioned Items (Repair Parts): Packaging of
MIL-T-21200	Test Equipment for use with Electronic and Electrical Equipment, General Specification for

STANDARDS

FEDERAL

* FED-STD-H28	Screw Thread Standards for Federal Service

MILITARY

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-108	Definitions of and Basic Requirements for Enclosures for Electric and Electronic Equipment
MIL-STD-130	Identification Marking of U.S. Military Property
MIL-STD-454	Standard General Requirements for Electronic Equipment
MIL-STD-461	Electromagnetic Emission and Susceptibility Requirements for the Control of Electromagnetic Interference
* MIL-STD-462	Electromagnetic Interface Charactertistics, Measurement of
MIL-STD-781	Reliability Design Qualification and Production Acceptance Tests; Exponential Distribution
MIL-STD-810	Environmental Test Methods and Engineering Guidelines

*2.1.2 Other Government drawings. The following other Government drawing forms a part of this specification to the extent specified herein. Unless otherwise specified, the issue shall be that in effect on the date of the solicitation.

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:08Z
Check the source to verify that this is the currentversion before use.

DRAWINGS

ARMY

11554090 Test Set, MK III

(Copies of specifications, standards and other Government documents required by contractors in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting activity.)

2.2 Other publications. The following document(s) form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of the documents which are DOD adopted shall be those listed in the issue of the DODISS specified in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS shall be the issue of the nongovernment documents which is current on the date of the solicitation.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 3951 Commercial Packaging, Practice for

*(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103).

*(Nongovernment standards and other publications are normally available from the organizations which prepare or which distribute the documents. These documents also may be available in or through libraries or other informational services.)

*2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein (except for associated detail specifications, specification sheets or MS standards), the text of this specification shall take precedence. Nothing in this specification, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 First article. The supplier shall furnish eight complete tests sets for first article inspection. The first article may be either a preproduction model or an initial production item which conforms to the requirements of this specification. The approved first article and the production items shall be identical and in accordance with the terms of the contract. Approval of the first article shall not relieve the supplier of the responsibility to furnish equipment in accordance with the requirements of this specification.

3.2 Design. The test set is designed to ensure proper operation of the intervalometer/launcher combination, and to detect the presence of a ground on the firing lines.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:08Z
Check the source to verify that this is the current version before use.

3.3 Construction. The construction of the MK III electrical test set shall be in accordance with Drawing 11554090 and the requirements specified herein. The applicable requirements of MIL-T-21200 for class 3 equipment shall apply whenever design requirements are not specified in the drawing.

3.3.1 Manufacturing. Unless otherwise specified by the procuring activity, test set drawings or this specification, manufacturing shall conform to the applicable MIL-STD-454 requirements as specified by MIL-T-21200. Responsibility shall be assumed by the contractor for any malfunction, or failure of a part, subassembly, or assembly to pass the tests specified herein (see 4).

3.3.2 Interchangeability. All replaceable parts shall be manufactured to definite tolerances and clearances in order that any such parts of a particular type or model may be replaced or adjusted without requiring modification.

3.3.3 Screw threads. All screw threads shall conform to FED-STD-H28.

3.3.4 Surfaces. Surfaces of all parts shall be cleaned and free from extraneous materials. External surfaces shall be smooth and free from sharp edges. All exterior corners shall be rounded.

3.3.5 Fastening devices. All screws, pins, bolts, and similar parts shall be installed with means for preventing loss of tightness. All such parts when subjected to removal or adjustment shall not be permanently deformed.

3.3.6 Identification of parts. All parts shall be marked in accordance with the applicable requirement of MIL-STD-130.

3.3.7 Dimensions. The MK III electrical test set dimensions shall be in accordance with drawing 11554090.

3.4 Performance characteristics.

3.4.1 Functionals. The MK III electrical test set shall incorporate provisions for performing the following test functions:

3.4.1.1 Firing current. The test set shall function to indicate that a satisfactory firing signal has been received when stimulated with a proper current and time flow. In addition, upon receipt of a correct firing signal the load produced in the test set shall automatically disconnect between 10 and 14 milliseconds. The current firing signal is defined as a current of 0.810 ampere or greater for 10 milliseconds or longer. The test set shall indicate non-satisfactory condition if the stimulating signal is less than 0.810 ampere or its duration is less than 10 milliseconds (see 4.6.2.1).

*3.4.1.2 Ground. The test set shall provide, through the indicator lamp and protection circuit, a current to the test leads. It is essential that the test set shall not, under any conditions, deliver an output current through the external circuit in excess of 40 milliamperes direct current (dc) (see 4.6.2.2).

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:08Z
Check the source to verify that this is the current version before use.

*3.4.1.3 Battery check. The test set shall be capable of performing a self test to ascertain if the battery is sufficiently charged to a voltage above 20 volts direct current (Vdc) (see 4.6.2.3).

*3.4.2 Operating environments. The MK III electrical test set shall comply with requirements of the applicable conditions specified in MIL-T-21200 as listed herein and other conditions specified in table I.

3.4.2.1 Electromagnetic compatibility. The test set shall meet the requirements of MIL-STD-461 with respect to conducted and radiated emissions (see 4.6.3).

3.4.2.2 Temperature altitude. The test set shall operate at all possible combinations of temperature from 0 degrees celsius (C) to +55 degrees C (+32 degrees Fahrenheit (F) to 141 degrees F) and altitudes from 0 to 10,000 feet (0 to 3,048 meters). In addition, the test set shall withstand storage temperatures from -62 degrees C to 85 degrees C (-80 degrees F to 185 degrees F) at altitudes up to 50,000 feet (15,240 meters) (4.6.4.1).

3.4.2.3 Humidity. The test set shall be operable after being subjected to relative humidities of 95 $\pm$ 5% for 10 days (see 4.6.4.2).

3.4.2.4 Salt fog. The test set shall be operable after being exposed to a 5% salt fog solution for a period of 48 hours (see 4.6.4.3).

3.4.2.5 Shock. The test set shall be operable after being exposed to shock levels up to 20 g's (196.133 m/s^2) having a time duration of 11 + 1 milliseconds (see 4.6.4.4).

3.4.2.6 Impact. The test set case shall be operable after being subjected to impacts on a concrete surface from a height of 30 inches (762 millimeters) (see 4.6.4.6).

3.4.2.7 Vibration. The test set shall be operable after being subjected to the vibration requirements for class 3 equipment of MIL-T-21200 (see 4.6.4.5).

3.4.2.8 Watertightness. The test set case shall not leak when subjected to the spraytight requirements of MIL-STD-108 (see 4.6.4.7).

*3.5 Reliability. The test set shall have a specified mean time between failures (MTBF) (O_0) of 1000 hours (see 4.6.4.8).

*3.6 Workmanship. The workmanship of the MK III electrical test set shall conform to Requirement 9 of MIL-STD-454. The standards of workmanship exhibited in the approved first article sample, subject to any qualification stated in the Government's notice of approval, shall determine the requirements of the remainder of the contract relative to workmanship.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:08Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.2 Classification of inspections. The inspections of the MK III electrical test set shall be classified as follows:

a. First article inspection (see 4.4).

b. Quality conformance inspection (see 4.5).

4.3 Inspection conditions. Unless otherwise specified, all inspections shall be performed under the following conditions:

a. Room temperature. Room ambient temperature of 23 ± 10 degrees C (73 ± 18 degrees F) indicated.

b. Test temperature. All parts of the test item shall be stabilized at the specified temperature ± 2.8 degrees C (± 5 degrees F) indicated prior to conducting any operational tests. Unless otherwise specified, temperature stabilization will have been attained when the indicated temperature of the surface of the largest mass of the test item does not change more than ± 2.8 degrees C (± 5 degrees F) per hour.

c. Humidity. Room ambient to 95 percent relative humidity. When humidity testing is required, the tolerance shall be ± 5 percent relative humidity.

4.4 First article inspection. First article inspection shall consist of the test outlined in table I. The procuring activity reserves the right to delete tests and alter the test sequence of table I. First article approval is valid only on the contract or purchase order under which it is granted unless extended by the Government to other contracts or purchase orders.

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:08Z
Check the source to verify that this is the currentversion before use.

Table I. First article inspection - schedule and sequence.

Test No.	Tests	Test Para	Two first article sample A	Two first article sample B
a	Inspection	4.6.1	1	1
b	Functional	4.6.2	2	2
c	Electromagnetic compatibility	4.6.3	3	X
d	Temperature altitude	4.6.4.1	4	X
e	Humidity	4.6.4.2	X	3
f	Salt fog	4.6.4.3	5	X
g	Shock	4.6.4.4	6	X
h	Vibration	4.6.4.5	X	4
i	Impact	4.6.4.6	X	5
j	Watertightness	4.6.4.7	X	6
k	Reliability	4.6.5	(6 units designation C,D,E,F,G,H)	

Note:

1. Under Two F.A. sample A&B, the numbers from one to six are the test requirements and sequences to follow for each unit.

2. The Reliability units C, D, E, F, G, and H are tested to paragraph 4.6.5 only.

4.4.1 Test set samples. First article MK III electrical test set samples shall consist of the first eight test sets manufactured on the contract or purchase order. The test sets shall be permanently labeled for ease of identification and shall have been produced with the equipment and procedures that will be used for the production of all test sets designated in the contract or purchase order. Prior to submission, the contractor shall inspect the samples to the degree necessary to assure that they conform to the requirements, including statements of findings and certificates of conformance for materials and tests a and b of table I. A sample containing known defects shall not be submitted unless specifically authorized by the contracting officer.

4.5 Quality conformance inspection. Quality conformance inspection consists of those tests specified in 4.6.1 and 4.6.2, to be conducted on all MK III Electrical Test Sets, and submitted for acceptance under the contract or purchase order. Acceptance of test sets (4.5.1) shall be on an inspection lot basis.

4.5.1 Acceptance tests.

4.5.1.1 Inspection lots. Each month's production shall be considered a lot for acceptance purposes.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:08Z
Check the source to verify that this is the current version before use.

*4.5.1.2 Sampling. Test sets shall be selected from each inspection lot in accordance with MIL-STD-105, special inspection level S-2, without regard to acceptance quality level, and at the procuring agency's option, be subjected to any of the tests listed in this specification. Failure of any units in a sample to pass any of these tests shall be cause for lot rejection.

4.5.1.3 Resubmission of rejected lots. When a lot is rejected, the contractor, at the discretion of the procuring activity, may have the opportunity of reworking and resubmitting the entire affected lot. The procuring activity shall determine which inspection and tests of this specification are to be performed on the reworked inspection lot samples.

4.6 Inspection and test methods.

4.6.1 Inspection. The test set shall be inspected as follows:

*4.6.1.1 Assembly. The test set shall be inspected to ensure that it has been properly assembled and adjusted, the electrical connections are secure, and the workmanship is as specified herein.

*4.6.1.2 Documentation. The test set shall be thoroughly examined to determine conformance to the requirements of Drawing 11554090 and this specification.

*4.6.1.3 Packaging. The test set shall be examined to ascertain that the packaging conforms to contract requirements (see 5).

4.6.2 Functional. Each test set shall be operated five times in each mode described herein.

*4.6.2.1 Fire current test. This test shall be performed 100 percent. To calibrate the test set, place a 5 ohm resistor in series with an amp meter and connect between terminals A and E, located on face of the test set panel. Connect the 5 pin cable to J4 and J1. Depress the fire switch for 1 to 5 seconds and record the current flow. A minimum of 2 amperes shall be flowing between terminals A and E. To self check the test set, remove the 5 ohm resistor and amp meter from terminals A and E. Connect the one pin cable to J2. Touch the alligator clip end of the cable to the golden post of terminal A and depress the fire switch. The indicator lamp shall illuminate. The calibration and self check verification shall be conducted prior to the fire check conditions. To fire check, connect the test set leads to the test equipment (see 6.4). The test set shall initiate 24 Vdc through the test lead to the test equipment when the fire switch is depressed. The test equipment, upon receipt of the 24 Vdc, will initiate a fire pulse and measure the time and current flow back to the test set. The indicator lamp shall come on during each of the conditions 1 thru 4 below. The output parameters of the fire pulse generated by the test equipment, when connected to a 1 ohm load, shall be as follows:

Condition	Time (milliseconds)	Current (amperes dc)
1	t=16	I=0.90
2	t=16	I-6.0
3	t=5000	I-0.90
4	t=5000	I=6.0

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:08Z
Check the source to verify that this is the current version before use.

The indicator lamp shall not come on when the fire switch is depressed for conditions 5 thru 7 below. The parameters of the fire pulse generated by the test equipment shall be as follows:

Condition	Time (milliseconds)	Current (amperes dc)
5	t=5	I=0.50
6	t=5	I=6.0
7	t=5000	I=0.50

Notes:

1. Tolerance for t= ± 10% and I = ± 10% in conditions 1 thru 7.

2. For conditions 1 thru 4 the load shall disconnect between 10 and 14 milliseconds.

3. For conditions 5 thru 7 the load shall not disconnect from the stimulating signal.

4.6.2.2 Ground test. This test shall be performed 100 percent. The test equipment set shall simulate a condition in which the test set leads are connected together. Current flow through the leads shall be measured and shall not exceed 40 milliamperes dc. The indicator lamp (PL1) shall come on when the ground switch is depressed.

NOTE: The test equipment (see 6.4) shall not increase the resistance of a simulated short circuit connection of the test leads by more than 1 ohm.

4.6.2.3 Battery check. The test equipment (see 6.4) shall check the amount of voltage in the battery when the battery switch is depressed. With the test equipment connected, the indicator lamp shall come on when the battery switch is depressed and a voltage of 20 Vdc or greater is present. The indicator lamp shall not come on if the voltage is below 20 Vdc when the battery switch is depressed.

*4.6.3 Electromagnetic capability. The test set shall be tested in accordance with MIL-STD-462 to the requirements of MIL-STD-461 limits for CE02, CE04, RE01, and RE02.

4.6.4 Environmental tests. The test set shall be subjected to the following environmental tests in accordance with the requirements of MIL-T-21200 and as specified herein:

4.6.4.1 Temperature altitude. The test set shall be subjected to the temperature altitude test of MIL-STD-810, method 504, procedure I except the conditions shall be in accordance with MIL-T-21200, class 3 equipment. While at ambient conditions, the test set shall meet the requirements of 4.6.2. At the completion of testing, the test set shall be visually inspected and tested in accordance with 4.6.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:08Z
Check the source to verify that this is the current version before use.

4.6.4.2 Humidity. The test set shall be subjected to the humidity test of MIL-STD-810, method 507, procedure I. At the completion of testing, the test set shall be visually inspected and tested in accordance with 4.6.2.

4.6.4.3 Salt fog. The test set shall be subjected to the salt fog test of MIL-STD-810, method 509, procedure I. At the completion of testing, the test set shall be visually inspected and tested in accordance with 4.6.2.

4.6.4.4 Shock. The test set shall be subjected to the transit and combination cases shock test in accordance with MIL-T-21200. At the completion of each axis of testing, the test set shall be visually inspected and tested in accordance with 4.6.2.

4.6.4.5 Vibration. The test set shall be subjected to the vibration test in accordance with MIL-T-21200. At the completion of each axis of testing, the test set shall be visually inspected and tested in accordance with 4.6.2.

4.6.4.6 Impact. The test set case shall be subjected to the drop test in accordance with MIL-T-21200.

4.6.4.7 Watertightness. The test set case shall be subjected to the spraytight requirements of MIL-STD-108. Entry of water during the test shall be cause for rejection.

4.6.5 Reliability demonstration. The MTBF of the test set shall be demonstrated according to MIL-STD-781, test plan III C, using O_0 of 1000 hours. Six units shall be used for demonstration. The duty cycle shall be 19 fire checks and 19 ground checks every 5 minutes during operation for the duration of the test. No-go conditions for each function shall be checked every 100 hours of operating time (see table I).

4.6.5.1 Manufacturing run-in. If a manfacturing run-in test or burn-in is performed, it shall be performed in accordance with MIL-STD-781.

5. PACKAGING

5.1 Preservation, Packing, Unitization, and Marking. Level A, B or C Packaging (see 6.2).

5.1.1 Level A or B. Preservation, packing, unitization and marking shall be in accordance with MIL-E-17555.

5.1.2 Level C. Preservation, packing, unitization and marking shall be in accordance with ASTM D 3951.

6. NOTES

6.1 Intended use. The MK III electrical test set is intended for use with the HYDRA 70 FFAR system (less rockets) and any other system utilization the MK I squib or a similar device and is used to perform the following functions:

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:08Z
Check the source to verify that this is the current version before use.

a. To ensure proper operation of the intervalometer/launcher combination.

b. To detect the presence of a ground on the firing lines.

6.1.1 Restriction. This test set shall not be used in the presence of ammunition or explosive devices.

6.2 Ordering data. Procurement documents should specify the following:

a. Title, number and date of this specification.

b. Selection of applicable levels of preservation, packaging, and packing required (see 5.1).

c. Samples subjected to the acceptance tests shall be over and above the quantity procured for delivery to the user.

d. Rework and retest requirements (see 4.5.1) for inspection test samples.

e. Items of data required.

*f. Name and location of Government approved test laboratory if required.

6.3 First article. When a first article inspection is required, the items should be either preproduction models or initial production items. The first article should consist of eight units. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, approval of first article test results and disposition of first articles. Invitations for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract.

6.3.1 First article sample information. Deviation from, or requirements for six first article test sets to do MTBF 1000 hours (3.1) and (3.5) reliability demonstration (4.6.5) will be determined by the Product Assurance Directorate prior to procurement.

6.4 Contractor design. Special calibration and test equipment necessary to accomplish the requirements as stated in 4.6.2.1, 4.6.2.2, 4.6.2.3, and 4.6.5 may be designed and manufactured by the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibrating instructions be properly depicted in accordance with approved practices, to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:08Z
Check the source to verify that this is the current version before use.

procedure, provided such format reflects the detail and information specified above, subject to the following controls: All submitted Contractor designs shall conform to DOD-D-1000, Level 2.

6.5 Submission of contractor design. All submitted designs shall contain a reference to the applicable paragraphs of this specification, and test equipment shall be approved by the procuring activity prior to submission of first article sample. Partial submission of design is permissible. However, the completion date for design review will be based on the date of the final submission. Design review at the procuring activity will be accomplished approximately 30 days after receipt.

*6.6 Changes from previous issue. The margins of this specification are marked with asterisks to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal nations and relationship to the last previous issue.

Custodian:
Army-MI
Air Force-99

Preparing activity:
Army-MI

Project No. 4927-0003

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:08Z
Check the source to verify that this is the currentversion before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER	2. DOCUMENT DATE (YYMMDD)
	MIL-T-47302A(MI)	870813

3. DOCUMENT TITLE
TEST SET, ELECTRICAL, MK III

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION

c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME	b. TELEPHONE (Include Area Code) (1) Commercial	(2) AUTOVON
U.S.. Army Missile Command	(205) 876-6980	746-6980

c. ADDRESS (Include Zip Code)	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT:
Commander, U.S. Army Missile Command, ATTN: AMSMI-RD-SE-TD-ST, Redstone Arsenal, AL 35898-5270	Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:08Z
Check the source to verify that this is the current version before use.